

# PIC16F18015/25/44/45

# PIC16F18015/25/44/45 Full-Featured, 8/14/20-Pin Microcontrollers

# Introduction

The PIC16F180 microcontroller family has a suite of digital and analog peripherals that enable cost-sensitive sensor and real-time control applications. This product family is available from 8 to 44-pin packages in a memory range of 3.5 KB to 28 KB, with speeds up to 32 MHz. The family includes a 10-bit Analog-to-Digital Converter with Computation (ADCC), automated Capacitive Voltage Divider (CVD) techniques for advanced capacitive touch sensing, an 8-bit Digital-to-Analog Converter (DAC) module, and many more waveform control and communication peripherals. This small form factor, feature-rich device is well suited for low-cost sensor and control applications.

# PIC16F180 Family Summary

Table 1. Devices Included in This Data Sheet

Device	Program Flash Memory (bytes)	Data Flash Memory (EEPROM)(bytes)	Data SRAM (bytes)	Memory Access Partition/ Device Information Area	I/O Pins <sup>(1)</sup> / Peripheral Pin Select	8-Bit Timers with HLT/ 16-Bit Timers <sup>(2)</sup>	10-Bit PWM/ CCP	10-Bit ADC Channels (External/Internal)	Charge Pump	l <sup>2</sup> C/SPI	EUSART	NCO	cwg	CLC	FVR	CMP	8-bit DAC	ZCD	SMBus Compatible I/O Pads	External Interrupt Pins	Interrupt-on-Change Pins	Watchdog Timer
PIC16F18015	14k	128	1024	Y/Y	6/Y	3/3	3/2	5/4	1	2	2	1	1	4	2	1	1	1	Υ	1	6	Y
PIC16F18025	14k	128	1024	Y/Y	12/Y	3/3	3/2	11/4	1	2	2	1	1	4	2	1	1	1	Υ	1	12	Υ
PIC16F18044	7k	128	512	Y/Y	18/Y	3/3	3/2	17/4	1	2	2	1	1	4	2	1	1	1	Υ	1	18	Υ
PIC16F18045	14k	128	1024	Y/Y	18/Y	3/3	3/2	17/4	1	2	2	1	1	4	2	1	1	1	Υ	1	18	Υ

Table 2. Devices Not Included in This Data Sheet

Device	Program Flash Memory (bytes)	Data Flash Memory (EEPROM)(bytes)	Data SRAM (bytes)	Memory Access Partition/ Device Information Area	I/O Pins <sup>(1)</sup> / Peripheral Pin Select	8-Bit Timers with HLT/ 16-Bit Timers <sup>(2)</sup>	10-Bit PWM/ CCP	10-Bit ADC Channels (External/Internal)	Charge Pump	MSSP	EUSART	NCO	CWG	CLC	FVR	CMP	8-bit DAC	ZCD	SMBus Compatible I/O Pads	External Interrupt Pins	Interrupt-on-Change Pins	Watchdog Timer
PIC16F18013	3.5k	128	256	Y/Y	6/Y	3/3	3/2	5/4	1	1	1	1	0	4	2	1	1	1	Υ	1	6	Υ
P <b>I</b> C16F18014	7k	128	512	Y/Y	6/Y	3/3	3/2	5/4	1	1	1	1	0	4	2	1	1	1	Υ	1	6	Υ
P <b>I</b> C16F18023	3.5k	128	256	Y/Y	12/Y	3/3	3/2	11/4	1	1	1	1	0	4	2	1	1	1	Υ	1	12	Υ
P <b>I</b> C16F18024	7k	128	512	Y/Y	12/Y	3/3	3/2	11/4	1	1	1	1	0	4	2	1	1	1	Υ	1	12	Υ
P <b>I</b> C16F18026	28k	256	2048	Y/Y	12/Y	3/3	3/2	11/4	1	2	2	1	1	4	2	1	1	1	Υ	1	12	Υ
P <b>I</b> C16F18046	28k	256	2048	Y/Y	18/Y	3/3	3/2	17/4	1	2	2	1	1	4	2	1	1	1	Υ	1	18	Υ
P <b>I</b> C16F18054	7k	128	512	Y/Y	25/Y	3/3	3/2	24/4	1	2	2	1	1	4	2	1	1	1	Υ	1	25	Y
P <b>I</b> C16F18055	14k	128	1024	Y/Y	25/Y	3/3	3/2	24/4	1	2	2	1	1	4	2	1	1	1	Υ	1	25	Y
P <b>I</b> C16F18056	28k	256	2048	Y/Y	25/Y	3/3	3/2	24/4	1	2	2	1	1	4	2	1	1	1	Υ	1	25	Υ
P <b>I</b> C16F18074	7k	128	512	Y/Y	36/Y	3/3	3/2	35/4	1	2	2	1	1	4	2	1	1	1	Υ	1	25	Υ
PIC16F18075	14k	128	1024	Y/Y	36/Y	3/3	3/2	35/4	1	2	2	1	1	4	2	1	1	1	Υ	1	25	Y
PIC16F18076	28k	256	2048	Y/Y	36/Y	3/3	3/2	35/4	1	2	2	1	1	4	2	1	1	1	Υ	1	25	Y

#### Notes:

- 1. Total I/O count includes one input-only pin (MCLR).
- 2. Timer0 can be configured as either an 8 or 16-bit timer.

# **Core Features**

- · C Compiler Optimized RISC Architecture
- Operating Speed:
  - DC 32 MHz clock input
  - 125 ns minimum instruction time
- 16-Level Deep Hardware Stack
- Low-Current Power-on Reset (POR)
- Configurable Power-up Timer (PWRT)
- Brown-out Reset (BOR)
- Watchdog Timer (WDT)

# **Memory**

- Up to 28 KB of Program Flash Memory
- Up to 2 KB of Data SRAM Memory
- Up to 256 Bytes of Data EEPROM Memory

- · Memory Access Partition (MAP) with Program Flash Memory Partitioned into:
  - Application block
  - Boot block
  - Storage Area Flash (SAF) block
- Programmable Code Protection and Write Protection
- · Device Information Area (DIA) Stores:
  - Fixed Voltage Reference (FVR) measurement data
  - Microchip Unique Identifier (MUI)
- Device Characteristics Area (DCI) Stores:
  - Program/erase row sizes
  - Pin count details
- · Direct, Indirect, and Relative Addressing Modes

# **Operating Characteristics**

- · Operating Voltage Range:
  - 1.8V to 5.5V
- · Temperature Range:
  - Industrial: -40°C to 85°C
  - Extended: -40°C to 125°C

# **Power-Saving Functionality**

- Sleep:
  - Reduce device power consumption
  - Reduce system electrical noise while performing ADC conversions
- Low Power Mode Features:
  - Sleep:
    - < 900 nA typical @ 3V/25°C (WDT enabled)</li>
    - < 600 nA typical @ 3V/25°C (WDT disabled)</li>
  - Operating current:
    - 48 µA typical @ 32 kHz, 3V/25°C
    - < 1 mA typical @ 4 MHz, 5V/25°C</li>

# **Digital Peripherals**

- Two Capture/Compare/PWM (CCP) Modules:
  - 16-bit resolution for Capture/Compare modes
  - 10-bit resolution for Pulse-Width Modulator (PWM) mode
- Three Pulse-Width Modulators (PWM):
  - 10-bit resolution
- · Four Configurable Logic Cells (CLC):
  - Integrated combinational and sequential logic
- One Complimentary Waveform Generator (CWG):
  - Rising and falling edge dead-band control
  - Full-bridge, half-bridge, and 1-channel drive
  - Multiple signal sources
  - Programmable dead band
  - Fault-shutdown input

- One Configurable 8/16-Bit Timer (TMR0)
- · Two 16-Bit Timers (TMR1/3) with Gate Control
- Three 8-Bit Timers (TMR2/4/6) with Hardware Limit Timer (HLT)
- One Numerically Controlled Oscillator (NCO):
  - Generates true linear frequency control and increased frequency resolution
  - Input clock up to 64 MHz
- Up to Two Enhanced Universal Synchronous Asynchronous Receiver Transmitters (EUSART):
  - RS-232, RS-485, and LIN compatible
  - Auto wake-up on Start
- Up to Two Host Synchronous Serial Ports (MSSP):
  - Serial Peripheral Interface (SPI) mode:
    - · Client select synchronization
  - Inter-Integrated Circuit (I<sup>2</sup>C) mode:
    - · 7/10-bit Addressing modes
- · Peripheral Pin Select (PPS):
  - Enables pin mapping of digital I/O
- Device I/O Port Features:
  - Up to 35 I/O pins
  - One input-only pin
  - Individual I/O direction, open-drain, input threshold, slew rate, and weak pull-up control
  - Interrupt-on-Change (IOC) on up to 25 pins
  - One external interrupt pin

# **Analog Peripherals**

- Analog-to-Digital Converter with Computation (ADCC):
  - 10-bit resolution
  - Up to 35 external input channels
  - Four internal input channels
  - Internal ADC oscillator (ADCRC)
  - Operates in Sleep
  - Selectable auto-conversion trigger sources
- Charge Pump Module:
  - Improves accuracy of analog modules at low voltages
- 8-Bit Digital-to-Analog Converter (DAC):
  - Output available on one I/O pin
  - Internal connections to ADC and comparators
- One Comparator (CMP):
  - Up to four external inputs
  - Configurable output polarity
  - External output via Peripheral Pin Select
- Zero-Cross Detect (ZCD):
  - Detect when AC signal on pin crosses ground
- · Two Fixed Voltage References (FVR):
  - Selectable 1.024V, 2.048V, and 4.096V output levels
  - FVR1 internally connected to ADC
  - FVR2 internally connected to comparator

# **Clocking Structure**


- High-Precision Internal Oscillator Block (HFINTOSC):
  - Selectable frequencies up to 32 MHz
  - ±2% at calibration
- Internal 31 kHz Oscillator (LFINTOSC)
- External High-Frequency Clock Input:
  - Two External Clock (EC) Power modes
- Secondary Oscillator (SOSC)

# **Programming/Debug Features**

- In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) via Two Pins
- · In-Circuit Debug (ICD) with Three Breakpoints via Two Pins
- · Debug Integrated On-Chip

# **Block Diagram**

Figure 1. PIC16F18015/25/44/45 Block Diagram



# Notes:

- 1. Available on 20-pin devices only.
- 2. Available on 14/20-pin devices only.

# **Table of Contents**

Intro	oduction	1
PIC	16F180 Family Summary	1
Cor	e Features	2
1.	Packages	9
2.	Pin Diagrams	10
3.	Pin Allocation Tables	12
4.	Guidelines for Getting Started with PIC16F180 Microcontrollers	17
5.	Register and Bit Naming Conventions	20
6.	Register Legend	22
7.	Enhanced Mid-Range CPU	23
8.	Device Configuration	25
9.	Memory Organization	35
10.	Resets	70
11.	OSC - Oscillator Module	82
12.	INT - Interrupts	98
13.	Sleep Mode	. 116
14.	WDT - Watchdog Timer	. 118
15.	NVM - Nonvolatile Memory Control	.122
16.	I/O Ports	. 146
17.	IOC - Interrupt-on-Change	162
18.	PPS - Peripheral Pin Select Module	168
19.	TMR0 - Timer0 Module	178
20.	TMR1 - Timer1 Module with Gate Control	.186
21.	TMR2 - Timer2 Module	201
22.	NCO - Numerically Controlled Oscillator Module	. 222
23.	CWG - Complementary Waveform Generator Module	.231
24.	CCP - Capture/Compare/PWM Module	258
25.	Capture, Compare, and PWM Timers Selection	271
26.	PWM - Pulse-Width Modulation	274

27.	PWM Timers Selection	282
28.	CLC - Configurable Logic Cell	285
29.	MSSP - Host Synchronous Serial Port Module	305
30.	EUSART - Enhanced Universal Synchronous Asynchronous Receiver Transmitter	. 366
31.	ADC - Analog-to-Digital Converter with Computation Module	. 395
32.	DAC - Digital-to-Analog Converter Module	. 441
33.	CMP - Comparator Module	. 447
34.	FVR - Fixed Voltage Reference	. 458
35.	Temperature Indicator Module	. 462
36.	ZCD - Zero-Cross Detection Module	467
37.	Charge Pump	474
38.	Instruction Set Summary	478
39.	ICSP <sup>™</sup> - In-Circuit Serial Programming <sup>™</sup>	. 498
40.	Register Summary	. 501
41.	Electrical Specifications	. 509
42.	DC and AC Characteristics Graphs and Tables	537
43.	Packaging Information	. 538
44.	Appendix A: Revision History	567
The	Microchip Website	568
Pro	duct Change Notification Service	568
Cus	tomer Support	568
Pro	duct Identification System	569
Mic	rochip Devices Code Protection Feature	569
Leg	al Notice	. 570
Tra	demarks	. 570
Qua	ality Management System	571
۱۸/۵	ddwide Sales and Service	572

# 1. Packages

# Table 1-1. Packages

Device	8-Pin PDIP	8-Pin SOIC	14-Pin PDIP	14-Pin SOIC	14-Pin TSSOP	16-Pin VQFN	20-Pin PDIP	20-Pin SOIC	20-Pin SSOP	20-Pin QFN
PIC16F18015	•	•								
PIC16F18025			•	•	•	•				
PIC16F18044							•	•	•	•
PIC16F18045							•	•	•	•

# 2. Pin Diagrams

Figure 2-1. 8-Pin PDIP, SOIC



Figure 2-2. 14-Pin PDIP, SOIC, TSSOP





Figure 2-3. 16-Pin VQFN



**Note:** It is recommended that the exposed bottom pad be connected to  $V_{SS}$ , however, it must not be the only  $V_{SS}$  connection to the device.

Figure 2-4. 20-Pin PDIP, SOIC, SSOP





Figure 2-5. 20-Pin QFN



**Note:** It is recommended that the exposed bottom pad be connected to  $V_{SS}$ , however, it must not be the only  $V_{SS}$  connection to the device.

#### 3. **Pin Allocation Tables**

ICSPCLK ICDCLK CLKOUT ICSPDAT ICDDAT sosco MCLR VPP CLKIN Basic SOSCI V<sub>DD</sub> <u>N</u>(1) Ī OCA0 IOCA1 IOCA2 IOCA3 <u>ဗ</u> I CK1(1,3) CK2(1,3,4) DT2(1,3,4) RX2(1,4) RX1<sup>(1)</sup> DT1<sup>(1,3)</sup> TX2(4) DT2(4) X F S SCL2(1,3,4) SCK2(1,3,4) SDA2(1,3,4) SDI2(1,3,4) SCL1(1,3) SCK1(1,3) SDA1(1,3) SDI1(1,3) SS2(1,4) SCL2(4) SCK2(4) SDA2(4) SDO2(4) SS1(1) SDA1 SD01 MSSP SCL1 1 Ī CLCIN1(1) CLCIN0 (1) CLC2OUT CLCIN2(1) CLC3OUT CLC10UT CLC40UT CLCIN3(1) CLC Ī CWG1(1,4) CWG1A(4) CWG1B<sup>(4)</sup> CWG1C<sup>(4)</sup> CWG1D(4) Ī CCP/PWM CCP1 CCP2 PWM3 PWM4 PWM5 T0CKI(1) T1CKI<sup>(1)</sup> T2IN<sup>(1)</sup> T3CKI(1) T3G(1) F4IN(1) T6IN(1) T1G(1) TMR0 ı 1 ZCD1 CCD 1 I C1IN0+ C1IN0-CMP1 1 VREF+ (ADC) DAC1REF0+ DAC10UT1 DAC1REF0ı ANA5 ADACT(1) ADGRDA ADGRDB ANA1 ANA2 ANA4 ADC I 1 8-Pin PDIP SOIC 9 OUT(2) VbD VSS RA0 RA1 RA2 RA4 <u>0</u>

Table 3-1. 8-Pin Allocation Table

This is a PPS remappable input signal. The input function may be moved from the default location shown to any PORTx pin. - 7 E 4

All output signals shown in this row are PPS remappable.

This is a bidirectional signal. For normal operation, user software must map this signal to the same pin via the PPS input and PPS output registers. Only available on the 8-pin PIC16F18015.

VDD

ICSPCLK ICDCLK ICSPDAT ICDDAT CLKOUT sosco INT(1) 1 I I 1 1 IOCA0 IOCA2 IOCA3 IOCA5 IOCC2 10003 10CC4 0000 Ι CK1(1,3) CK2(1,3) DT2(1,3) RX1(1) DT1(1,3) I SDA1(1,3,4) SDI1(1,3,4) SCL1(1,3,4) SCK1(1,3,4) SCL2(1,3,4) SCK2(1,3,4) SDI2(1,3,4) SDA2(1,3,4) SS1(1) SS2(1) MSSP I CLCIN1(1) CLC I CWG1(1) CWG ١ Ī CCP1(1) CCP2(1) CCP I 1 T0CKI(1) T1CKI<sup>(1)</sup> T2IN<sup>(1)</sup> T1G(1) T3G(1) ₹ | E 16 E 1 I ZCD1 ZCD 1 l 1 Τ Comparator C1IN0+ ı VREF+(ADC) DAC1REF0-DAC10UT1 DAC1REF0+ 1 1 Table 3-2, 14/16-Pin Allocation Table ANC2 ADACT<sup>(1)</sup> ANC3 ANA0 ANA5 ANA2 ANA1 ANA4 ANC1 I 16-Pin VQFN 12 9 13 Ξ က 6 ∞ 2 7 9 13 12 9 4 7 VbD RC2 Vss RA0 RA3 RA4 RC0 RC3 RC4 RC5 RC1 RA1

CLKIN

MCLR VPP

Basic

1/O 14-P														
TSSOP	14-Pin         16-Pin           PDIP         VQFN           SOIC         TSSOP	in ADC	Reference	Comparator	ZCD	Timers	CCP	CWG	CLC	MSSP	EUSART	<u> </u>	Interrupt	Basic
OUT(2)		ADGRDB ADGRDB	 	CMP1	I	TMR0	CCP1 CCP2 PWM3 PWM4	CWG1B CWG1B CWG1D	CLC10UT CLC20UT CLC30UT CLC40UT	SCL1 SCK1 SDA1 SCL2 SCK2 SDA2 SDO2	XX	ı	I	I

This is a PPS remappable input signal. The input function may be moved from the default location shown to any PORTx pin.

This is a bidirectional signal. For normal operation, user software must map this signal to the same pin via the PPS input and PPS output registers. 2 8 4

These pins can be configured for I<sup>2</sup>C or SMBus logic levels via the RxyI2C registers. The SCL1/SDA1 signals may be assigned to these pins for expected operation. PPS assignments of these signals to other pins will operate; however, the logic levels will be standard TTL/ST as selected by the INLVL register.

ICSPCLK ICDCLK ICSPDAT ICDDAT CLKOUT sosco CLKIN Basic MCLR VDD Ī Ι 1 Ī Ī Τ 1 IOCA0 IOCC2 10003 10004 10006 10006 IOCA3 IOCB4 10001 IOCB7 <u>၁၀</u> 1 CK1(1,3) CK2(1,3) RX2(1) DT2(1,3) 1 1 1 SDA1(1,3,4) SDI1(1,3,4) SCK2(1,3,4) SCL1(1,3,4) SCK1(1,3,4) SDA2(1,3,4) SDI2(1,3,4) SCL2(1,3,4) SS2(1) MSSP 1 CLCIN3(1) CLCIN1(1) CLCIN2(1) CLC I 1 CWG1(1) CWG 1 Ī Ī 1 1 CCP2(1) CCP1(1) CCP 1 1 T0CKI(1) T1CKI<sup>(1)</sup> T2IN<sup>(1)</sup> T3CKI(1) T3G(1) T6IN(1) T1G(1) T4IN(1) Ī 1 1 ZCD 1 Ī I 1 1 Ī Comparator C1IN0+ C1|N1-1 1 VREF+(ADC) DAC1REF0+ DAC1REF0-DAC10UT1 I ANC2 ADACT(1) ANA0 ANC0 ANC1 ANC3 ANC4 ANC5 ANC6 ANC7 ANA2 ANA5 ANB6 ANB7 ANA4 ANB4 ANA1 ADC 1 20-Pin QFN 16 5 4 20 6 9 6 ω 13 Ξ က 7 2 9 9 20-Pin PDIP SOIC 19 9 17 3 12 10 15 4 20 7 9 2 8 6 က RC4 RC5 RC6 RC6 VDD RA5 RC0 RC1 RA0 RB6 RA4 RB4 RB5 RA1 RB7

Table 3-3, 20-Pin Allocation Table

continued	ntinued														
0/1	20-Pin PDIP	20-Pin QFN	ADC	Reference	Comparator	ZCD	Timers	ССР	CWG	CLC	MSSP	EUSART	<u>8</u>	Interrupt	Basic
	SOIC														
	SSOP														
OUT(2)		ı	ADGRDA	ı	CMP1	1	TMR0	CCP1	CWG1A	CLC10UT	SCL1	TX1	ı	ı	
			ADGRDB					CCP2	CWG1B	CLC2OUT	SCK1	DT1			
								PWM3	CWG1C	CLC3OUT	SDA1	CK 1			
								PWM4	CWG1D	CLC40UT	SD01	TX2			
								PWM5			SCL2	DT2			
											SCK2	CK2			
											SDA2				
											SD02				

1. This is a PPS remappable input signal. The input function may be moved from the default location shown to any PORTx pin.

# 4. Guidelines for Getting Started with PIC16F180 Microcontrollers

### 4.1 Basic Connection Requirements

Getting started with the PIC16F180 family of 8-bit microcontrollers requires attention to a minimal set of device pin connections before proceeding with development.

The following pins must always be connected:

- All V<sub>DD</sub> and V<sub>SS</sub> pins (see 4.2. Power Supply Pins)
- MCLR pin (see 4.3. Master Clear (MCLR) Pin)

These pins must also be connected if they are being used in the end application:


- PGC/PGD pins used for In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) and debugging purposes (see 4.4. In-Circuit Serial Programming (ICSP) Pins)
- · CLKIN pin when an external clock source is used.

Additionally, the following may be required:

V<sub>RFF</sub>+/V<sub>RFF</sub>- pins are used when external voltage reference for analog modules is implemented

The minimum recommended connections are shown in the figure below.

Figure 4-1. Minimum Recommended Connections



Key (all values are recommendations):

C1: 10 nF, 16V ceramic C2: 0.1 µF, 16V ceramic

R1:  $10 \text{ k}\Omega$ R2:  $100\Omega$  to  $470\Omega$ 

# 4.2 Power Supply Pins

#### 4.2.1 Decoupling Capacitors

The use of decoupling capacitors on every pair of power supply pins ( $V_{DD}$  and  $V_{SS}$ ) is required.

Consider the following criteria when using decoupling capacitors:

- Value and type of capacitor: A 0.1 µF (100 nF), 10-25V capacitor is recommended. The capacitor may be a low-ESR device, with a resonance frequency in the range of 200 MHz and higher. Ceramic capacitors are recommended.
- Placement on the printed circuit board: The decoupling capacitors may be placed as close to the pins as possible. It is recommended to place the capacitors on the same side of the board as the device. If space is constricted, the capacitor can be placed on another layer on the PCB using a via; however, ensure that the trace length from the pin to the capacitor is no greater than 0.25 inch (6 mm).

# Guidelines for Getting Started with PIC16F180 Micr...

- Handling high-frequency noise: If the board is experiencing high-frequency noise (upward of tens of MHz), add a second ceramic type capacitor in parallel to the above described decoupling capacitor. The value of the second capacitor can be in the range of 0.01 μF to 0.001 μF. Place this second capacitor next to each primary decoupling capacitor. In high-speed circuit designs, consider implementing a decade pair of capacitances as close to the power and ground pins as possible (e.g., 0.1 μF in parallel with 0.001 μF).
- Maximizing performance: On the board layout from the power supply circuit, run the power and return traces to
  the decoupling capacitors first, and then to the device pins. This ensures that the decoupling capacitors are first
  in the power chain. Equally important is to keep the trace length between the capacitor and the power pins to a
  minimum, thereby reducing PCB trace inductance.

### 4.2.2 Tank Capacitors

With on boards with power traces running longer than six inches in length, it is suggested to use a tank capacitor for integrated circuits, including microcontrollers, to supply a local power source. The value of the tank capacitor may be determined based on the trace resistance that connects the power supply source to the device, and the maximum current drawn by the device in the application. In other words, select the tank capacitor that meets the acceptable voltage sag at the device. Typical values range from  $4.7 \, \mu F$  to  $47 \, \mu F$ .


# 4.3 Master Clear (MCLR) Pin

The  $\overline{MCLR}$  pin provides two specific device functions: Device Reset, and device programming and debugging. If programming and debugging are not required in the end application, a direct connection to  $V_{DD}$  may be all that is required. The addition of other components, to help increase the application's resistance to spurious Resets from voltage sags, may be beneficial. A typical configuration is shown in Figure 4-1. Other circuit designs may be implemented, depending on the application's requirements.

During programming and debugging, the resistance and capacitance that can be added to the pin must be considered. Device programmers and debuggers drive the  $\overline{MCLR}$  pin. Consequently, specific voltage levels (V<sub>IH</sub> and V<sub>IL</sub>) and fast signal transitions must not be adversely affected. Therefore, specific values of R1 and C1 will need to be adjusted based on the application and PCB requirements. For example, it is recommended that the capacitor, C1, be isolated from the  $\overline{MCLR}$  pin during programming and debugging operations by using a jumper (Figure 4-2). The jumper is replaced for normal run-time operations.

Any components associated with the MCLR pin may be placed within 0.25 inch (6 mm) of the pin.

Figure 4-2. Example of MCLR Pin Connections



#### Notes:

- 1. R1 ≤ 10 kΩ is recommended. A suggested starting value is 10 kΩ. Ensure that the  $\overline{MCLR}$  pin V<sub>IH</sub> and V<sub>IL</sub> specifications are met.
- R2 ≤ 470Ω will limit any current flowing into MCLR from the extended capacitor, C1, in the event of MCLR pin breakdown, due to Electrostatic Discharge (ESD) or Electrical Overstress (EOS). Ensure that the MCLR pin V<sub>IH</sub> and V<sub>IL</sub> specifications are met.

# 4.4 In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) Pins

The ICSPCLK and ICSPDAT pins are used for ICSP and debugging purposes. It is recommended to keep the trace length between the ICSP connector and the ICSP pins on the device as short as possible. If the ICSP connector is expected to experience an ESD event, a series resistor is recommended, with the value in the range of a few tens of ohms, not to exceed  $100\Omega$ .

# PIC16F18015/25/44/45

# **Guidelines for Getting Started with PIC16F180 Micr...**

Pull-up resistors, series diodes and capacitors on the ICSPCLK and ICSPDAT pins are not recommended as they can interfere with the programmer/debugger communications to the device. If such discrete components are an application requirement, they may be removed from the circuit during programming and debugging. Alternatively, refer to the AC/DC characteristics and timing requirements information in the respective device Flash programming specification for information on capacitive loading limits, and pin input voltage high  $(V_{IH})$  and input low  $(V_{IL})$  requirements.

For device emulation, ensure that the Communication Channel Select (i.e., ICSPCLK/ICSPDAT pins), programmed into the device, matches the physical connections for the ICSP to the Microchip debugger/emulator tool.

# 4.5 Unused I/Os

Unused I/O pins may be configured as outputs and driven to a Logic Low state. Alternatively, connect a 1 k $\Omega$  to 10 k $\Omega$  resistor to V<sub>SS</sub> on unused pins to drive the output to Logic Low.

# 5. Register and Bit Naming Conventions

# 5.1 Register Names

When there are multiple instances of the same peripheral in a device, the Peripheral Control registers will be depicted as the concatenation of a peripheral identifier, peripheral instance, and control identifier. The Control registers section will show just one instance of all the register names with an 'x' in the place of the peripheral instance number. This naming convention may also be applied to peripherals when there is only one instance of that peripheral in the device to maintain compatibility with other devices in the family that contain more than one.

#### 5.2 Bit Names

There are two variants for bit names:

- · Short name: Bit function abbreviation
- · Long name: Peripheral abbreviation + short name

#### 5.2.1 Short Bit Names

Short bit names are an abbreviation for the bit function. For example, some peripherals are enabled with the EN bit. The bit names shown in the registers are the short name variant.

Short bit names are useful when accessing bits in C programs. The general format for accessing bits by the short name is RegisterNamebits. ShortName. For example, the enable bit, ON, in the ADCON0 register can be set in C programs with the instruction ADCON0bits.ON = 1.

Short names are not useful in assembly programs because the same name may be used by different peripherals in different bit positions. When it occurs, during the include file generation, the short bit name instances are appended with an underscore plus the name of the register where the bit resides, to avoid naming contentions.

### 5.2.2 Long Bit Names

Long bit names are constructed by adding a peripheral abbreviation prefix to the short name. The prefix is unique to the peripheral, thereby making every long bit name unique. The long bit name for the ADC enable bit is the ADC prefix, AD, appended with the enable bit short name, ON, resulting in the unique bit name ADON.

Long bit names are useful in both C and assembly programs. For example, in C the ADCON0 enable bit can be set with the ADON = 1 instruction. In assembly, this bit can be set with the BSF ADCON0, ADON instruction.

#### 5.2.3 Bit Fields

Bit fields are two or more adjacent bits in the same register. Bit fields adhere only to the short bit naming convention. For example, the three Least Significant bits of the ADCON2 register contain the ADC Operating Mode Selection bit. The short name for this field is MD and the long name is ADMD. Bit field access is only possible in C programs. The following example demonstrates a C program instruction for setting the ADC to operate in Accumulate mode:

```
ADCON2bits.MD = 0b001;
```

Individual bits in a bit field can also be accessed with long and short bit names. Each bit is the field name appended with the number of the bit position within the field. For example, the Most Significant MODE bit has the short bit name MD2 and the long bit name is ADMD2. The following two examples demonstrate assembly program sequences for setting the ADC to operate in Accumulate mode:

```
MOVLW ~ (1<<MD2 | 1<<MD1)
ANDWF ADCON2,F
MOVLW 1<<MD0
IORWF ADCON2,F
```

# **Register and Bit Naming Conventions**

BCF ADCON2,ADMD2
BCF ADCON2,ADMD1
BSF ADCON2,ADMD0

# 5.3 Register and Bit Naming Exceptions

# 5.3.1 Status, Interrupt and Mirror Bits

Status, Interrupt enables, Interrupt flags and Mirror bits are contained in registers that span more than one peripheral. In these cases, the bit name shown is unique so there is no prefix or short name variant.

# 6. Register Legend


Table 6-1. Register Legend

Symbol	Definition
R	Readable bit
W	Writable bit
HS	Hardware settable bit
НС	Hardware clearable bit
S	Set only bit
С	Clear only bit
U	Unimplemented bit, read as '0'
<b>'1'</b>	Bit value is set
<b>'</b> 0'	Bit value is cleared
X	Bit value is unknown
u	Bit value is unchanged
q	Bit value depends on condition
m	Bit value is predefined

# 7. Enhanced Mid-Range CPU

This family of devices contains an enhanced mid-range 8-bit CPU core. The CPU has 50 instructions. Interrupt capability includes automatic context saving. The hardware stack is 16-level deep and has overflow and underflow Reset capability. Direct, Indirect, and Relative Addressing modes are available. Two File Select Registers (FSR) provide the ability to read program and data memory.

Figure 7-1. Core Data Path Diagram



# 7.1 Automatic Interrupt Context Saving

During interrupts, certain registers are automatically saved in shadow registers and restored when returning from the interrupt. This saves stack space and user code.

# 7.2 16-Level Stack with Overflow and Underflow

These devices have a hardware stack memory 15 bits wide and 16 words deep. A Stack Overflow or Underflow will set the appropriate bit (STKOVF or STKUNF), and if enabled, will cause a software Reset.

# 7.3 File Select Registers

There are two 16-bit File Select Registers (FSR). FSRs can access all file registers and program memory, which allows one Data Pointer for all memory. When an FSR points to program memory, there is one additional instruction cycle in instructions using INDF to allow the data to be fetched. General purpose memory can also be addressed linearly, providing the ability to access contiguous data larger than 80 bytes.

# 7.4 Instruction Set

There are 50 instructions for the enhanced mid-range CPU to support the features of the CPU. See the "Instruction Set Summary" section for more details.

# 8. Device Configuration

Device configuration consists of the Configuration Words, User ID, Device ID, Device Information Area (DIA) and the Device Configuration Information (DCI) regions.

# 8.1 Configuration Words

There are five Configuration Words that allow the user to select the device oscillator, Reset and memory protection options. These are implemented at addresses 0x8007 - 0x800B.

**Note:** The DEBUG bit in the Configuration Words is managed automatically by device development tools, including debuggers and programmers. For normal device operation, this bit needs to be maintained as a '1'.

#### 8.2 Code Protection

Program memory code protection is controlled using the  $\overline{CP}$  bit while data EEPROM memory code protection is controlled using the  $\overline{CPD}$  bit. When code protection is enabled, all program memory and Data EEPROM locations read as '0'. Further programming is disabled for the program memory and Data EEPROM until a Bulk Erase operation is performed on the configuration memory region. Program memory and Data EEPROM can still be programmed and read during program execution.

The User ID locations and Configuration Bytes can be programmed and read out regardless of the code protection settings.

The only way to disable code protection is to use the Bulk Erase Program Memory command with bit 4 of the payload set to '1'. This will disable code protection and also erase all the memory locations.

# 8.3 Write Protection

Write protection allows the device to be protected from unintended self-writes. Applications, such as bootloader software, can be protected while allowing other regions of the program memory to be modified.

The WRTn Configuration bits determine which of the program memory blocks are protected.

#### 8.4 User ID

Four words in the memory space (8000h-8003h) are designated as ID locations where the user can store checksum or other code identification numbers. These locations are readable and writable during normal execution. See the "NVMREG Access to DIA, DCI, User ID, DEV/REV ID, and Configuration Words" section for more information on accessing these memory locations. See the "Memory Programming Specification" section in the "Electrical Specifications" chapter for information on the electrical parameters required to program these memory locations. For more information on checksum calculation, see the "Family Programming Specification".

#### 8.5 Device ID and Revision ID

The 14-bit Device ID word is located at address 8006h and the 14-bit Revision ID is located at 8005h. These locations are read-only and cannot be erased or modified.


Development tools, such as device programmers and debuggers, may be used to read the Device ID, Revision ID and Configuration Words. Refer to the "**NVM - Nonvolatile Memory Control**" section for more information on accessing these locations.

# 8.6 Register Definitions: Configuration Settings

### 8.6.1 **CONFIG1**

Name: CONFIG1 Offset: 0x8007

Configuration Word 1



# Bit 12 - VDDAR V<sub>DD</sub> Analog Range Calibration Selection

Value	Description
1	Internal analog systems are calibrated for operation between V <sub>DD</sub> = 2.3V-5.5V
0	Internal analog systems are calibrated for operation between V <sub>DD</sub> = 1.8V-3.6V

### Bit 8 - CLKOUTEN Clock Out Enable

Value	Description
1	CLKOUT function is disabled; I/O function on CLKOUT pin
0	CLKOUT function is enabled; F <sub>OSC</sub> /4 clock appears on CLKOUT pin

# Bits 6:4 - RSTOSC[2:0] Power-up Default Value for the COSC bits

Selects the oscillator source used by user software.

Value	Description
111	EXTOSC operating per the FEXTOSC bits
110	HFINTOSC = 1 MHz (FRQ = 1 MHz)
101	LFINTOSC
100	SOSC
011	Reserved
010	Reserved
001	Reserved
000	HFINTOSC = 32 MHz (FRQ = 32 MHz)

# Bits 1:0 - FEXTOSC[1:0] External Oscillator Mode Selection

Value	Description
11	ECH (16 MHz and higher)
10	Reserved
01	ECL (below 16 MHz)
00	Oscillator not enabled

### 8.6.2 **CONFIG2**

Name: CONFIG2 Offset: 0x8008

Configuration Word 2

Bit	15	14	13	12	11	10	9	8
			DEBUG	STVREN	PPS1WAY	ZCD	BORV	DACAUTOEN
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			1	1	1	1	1	1
Bit	7	6	5	4	3	2	1	0
	BORE	N[1:0]		WDT	Ē[1:0]	PWRT	S[1:0]	MCLRE
Access	R/W	R/W		R/W	R/W	R/W	R/W	R/W
Reset	1	1		0	1	1	1	1

# Bit 13 - DEBUG Debugger Enable<sup>(1)</sup>

Value	Description
1	Background debugger disabled
0	Background debugger enabled

#### Bit 12 - STVREN Stack Overflow/Underflow Reset Enable

Value	Description
1	Stack Overflow or Underflow will cause a Reset
0	Stack Overflow or Underflow will not cause a Reset

### Bit 11 - PPS1WAY PPSLOCKED One-Way Set Enable

Value	Description
1	The PPSLOCKED bit can only be set once after an unlocking sequence is executed; once
	PPSLOCKED is set, all future changes to PPS registers are prevented
0	The PPSLOCKED bit can be set and cleared as needed (unlocking sequence is required)

### Bit 10 - ZCD Zero-Cross Detect Disable

Valu	ie	Description
1		ZCD disabled, ZCD can be enabled by setting the ZCDSEN bit of ZCDCON
0		ZCD always enabled, the PMDx [ZCDMD] bit is ignored

### Bit 9 - BORV Brown-Out Reset (BOR) Voltage Selection(2)

		, ,	<del>_</del>
Valu	ue Description		
1	Brown-out Reset vo	oltage (V <sub>B</sub>	<sub>SOR</sub> ) set to 1.9V
0	Brown-out Reset vo	oltage (V <sub>B</sub>	<sub>BOR</sub> ) set to 2.65V

### Bit 8 – DACAUTOEN DAC Buffer Automatic Range Select Enable

Value	Description
1	DAC Buffer reference range is determined by the REFRNG bit of DACxCON
0	DAC Buffer reference range is automatically determined by module hardware

# Bits 7:6 - BOREN[1:0] Brown-Out Reset (BOR) Enable(3)

Value	Description
11	Brown-out Reset enabled, the SBOREN bit is ignored
10	Brown-out Reset enabled while running, disabled in Sleep; the SBOREN bit is ignored
01	Brown-out Reset enabled according to SBOREN
00	Brown-out Reset disabled

### Bits 4:3 - WDTE[1:0] Watchdog Timer (WDT) Enable

# **Device Configuration**

Value	Description
11	WDT enabled regardless of Sleep; the SEN bit of WDTCON is ignored
10	WDT enabled while Sleep = 0, suspended when Sleep = 1; the SEN bit of WDTCON is ignored
01	WDT enabled/disabled by the SEN bit of WDTCON
00	WDT disabled; SEN bit of WDTCON is ignored

### Bits 2:1 - PWRTS[1:0] Power-Up Timer (PWRT) Selection

Value	Description
11	PWRT disabled
10	PWRT is set at 64 ms
01	PWRT is set at 16 ms
00	PWRT is set at 1 ms

# Bit 0 - MCLRE Master Clear (MCLR) Enable

Value	Condition	Description
X	If LVP = 1	MCLR pin is MCLR
1	If LVP = 0	MCLR pin is MCLR
0	If LVP = 0	MCLR pin function is port-defined function

#### Notes:

- 1. The DEBUG bit is managed automatically by device development tools including debuggers and programmers. For normal device operation, this bit needs to be maintained as a '1'.
- 2. The higher voltage selection is recommended for operation at or above 16 MHz.
- 3. When enabled, Brown-out Reset voltage ( $V_{BOR}$ ) is set by the BORV bit.

# PIC16F18015/25/44/45

# **Device Configuration**

# 8.6.3 **CONFIG3**

Name: CONFIG3 Offset: 0x8009 Configuration Word 3

Note: This register is reserved.

Bit	15	14	13	12	11	10	9	8
Access Reset								
Bit	7	6	5	4	3	2	1	0

Access Reset

### 8.6.4 **CONFIG4**

Name: CONFIG4 Offset: 0x800A

Configuration Word 4

Bit	15	14	13	12	11	10	9	8
[			LVP		WRTSAF	WRTD	WRTC	WRTB
Access			R/W		R/W	R/W	R/W	R/W
Reset			1		1	1	1	1
Bit	7	6	5	4	3	2	1	0
	WRTAPP			SAFEN	BBEN		BBSIZE[2:0]	
Access	R/W			R/W	R/W	R/W	R/W	R/W
Reset	1			1	1	1	1	1

# Bit 13 – LVP Low-Voltage Programming Enable<sup>(1)</sup>

Value	Description
1	Low-Voltage Programming is enabled. MCLR/V <sub>PP</sub> pin function is MCLR. The MCLRE bit is ignored.
0	High voltage (HV) on MCLR/V <sub>PP</sub> must be used for programming.

# Bit 11 - WRTSAF Storage Area Flash (SAF) Write Protection<sup>(2, 3)</sup>

Value	Description
1	SAF is not write-protected
0	SAF is write-protected

# Bit 10 - WRTD Data EEPROM Write Protection(2)

Value	Description		
1	Data EEPROM is not write-protected		
0	Data EEPROM is write-protected		

### Bit 9 - WRTC Configuration Registers Write Protection(2)

Value	Description	
1	Configuration registers are not write-protected	
O Configuration registers are write-protected		

# Bit 8 – WRTB Boot Block Write Protection<sup>(2, 4)</sup>

Value Description		
	1	Boot Block is not write-protected
	0	Boot Block is write-protected

# Bit 7 – WRTAPP Application Block Write Protection<sup>(2)</sup>

Value	e Description		
1 Application Block is not write-protected			
0	Application Block is write-protected		

# Bit 4 - SAFEN Storage Area Flash (SAF) Enable<sup>(2)</sup>

Value	Description
1	SAF is disabled
0	SAF is enabled

### Bit 3 - BBEN Boot Block Enable(2)

Value	Description
1	Boot Block is disabled
0	Boot Block is enabled

Bits 2:0 - BBSIZE[2:0] Boot Block Size Selection(5, 6)

Table 8-1. Boot Block Size

BBEN	BBSIZE	End Address of	Boot Block Size (words)		
DDEN		Boot Block	PIC16F180x4	PIC16F180x5	
1	XXX	_	-	-	
0	111	01FFh	5′	12	
0	110	03FFh	10	24	
0	101	07FFh	20	48	
0	100	0FFFh	_(6)	4096	
0	011	1FFFh	_	(6)	
0	010	3FFFh	_	(6)	
0	001	3FFFh	_	(6)	
0	000	3FFFh	_	(6)	


#### Notes:

- 1. The LVP bit cannot be written (to zero) while operating from the LVP programming interface. The purpose of this rule is to prevent the user from dropping out of the LVP mode while programming from LVP mode, or accidentally eliminating the LVP mode from the Configuration state.
- 2. Once protection is enabled through ICSP or a self-write, it can only be reset through a Bulk Erase.
- 3. Applicable only if  $\overline{SAFEN} = 0$ .
- 4. Applicable only if  $\overline{BBEN} = 0$ .
- 5. BBSIZE[2:0] bits can only be changed when  $\overline{BBEN} = 1$ . Once  $\overline{BBEN} = 0$ , BBSIZE[2:0] can only be changed through a Bulk Erase.
- 6. The maximum Boot Block size is half of the user program memory size. Any selection that will exceed half of a device's program memory will default to a maximum Boot Block size of half PFM.

### 8.6.5 **CONFIG5**

Name: CONFIG5 Offset: 0x800B

Configuration Word 5<sup>(1)</sup>



Bit 1 – CPD Data Flash Memory (EEPROM) Code Protection(2)

	Value	e Description	
1 EEPROM code protection is disabled 0 EEPROM code protection is enabled		EEPROM code protection is disabled	
		EEPROM code protection is enabled	

Bit 0 -  $\overline{CP}$  Program Flash Memory (PFM) Code Protection<sup>(2)</sup>

		, ·	,	
Valu	e Description			
1	PFM code prote	ection is disa	oled	
0	PFM code prote	ection is enal	led	

### Notes:

- 1. Since device code protection takes effect immediately, this Configuration Word must be written last.
- 2. Once code protection is enabled, it can only be removed through a Bulk Erase.

# 8.7 Register Definitions: Device ID and Revision ID

# 8.7.1 Device ID

Name: DEVICEID Offset: 0x8006

Device ID Register

Bit	15	14	13	12	11	10	9	8
			Reserved	Reserved		DEV[	11:8]	
Access			R	R	R	R	R	R
Reset			1	1	q	q	q	q
	_	_	_			_		_
Bit	7	6	5	4	3	2	11	0
		DEV[7:0]						
Access	R	R	R	R	R	R	R	R
Reset	q	q	q	q	q	q	q	q

Bit 13 - Reserved Reserved - Read as '1'

Bit 12 - Reserved Reserved - Read as '1'

Bits 11:0 - DEV[11:0] Device ID

Device	Device ID
PIC16F18015	30F5h
PIC16F18025	30F6h
PIC16F18044	30F7h
PIC16F18045	30F8h

# 8.7.2 Revision ID

Name: REVISIONID Offset: 0x8005

Revision ID Register

Bit	15	14	13	12	11	10	9	8
			Reserved	Reserved		MJRRI	EV[5:2]	
Access		•	R	R	R	R	R	R
Reset			1	0	q	q	q	q
Bit	7	6	5	4	2	2	1	0
DIL	/	- V	5		3	Z	ı	
	MJRREV[1:0]			MNRREV[5:0]				
Access	R	R	R	R	R	R	R	R
Reset	q	q	q	q	q	q	q	q

Bit 13 - Reserved Reserved - Read as '1'

Bit 12 - Reserved Reserved - Read as '0'

# Bits 11:6 - MJRREV[5:0] Major Revision ID

These bits are used to identify a major revision (A0, B0, C0, etc.).

# Bits 5:0 - MNRREV[5:0] Minor Revision ID

These bits are used to identify a minor revision.

# 9. Memory Organization

There are three types of memory in PIC16F180 microcontroller devices:

- Program Memory
  - Program Flash Memory
  - Configuration Words
  - Device ID
  - Revision ID
  - User ID
  - Device Information Area (DIA)
  - Device Configuration Information (DCI)
- · Data Memory
  - Core Registers
  - Special Function Registers (FSR)
  - General Purpose RAM (GPR)
  - Common RAM
- Data EEPROM

In Harvard architecture devices, the data and program memories use separate buses that allow for concurrent access of the two memory spaces. The data EEPROM, for practical purposes, can be regarded as a peripheral device, since it is addressed and accessed through a set of control registers.

Additional detailed information on the operation of the Program Flash Memory and data EEPROM memory is provided in the "NVM - Nonvolatile Memory Module" section.

# 9.1 Program Memory Organization

The enhanced mid-range core has a 15-bit Program Counter capable of addressing 32K x 14 program memory space. The table below shows the memory sizes implemented. Accessing a location above these boundaries will cause a wrap-around within the implemented memory space.

The Reset vector is at 0000h and the interrupt vector is at 0004h. Refer to the "Interrupts" chapter for more details.

Table 9-1. Device Sizes and Addresses

Device	Program Memory Size (Words)	Last Program Memory Address
PIC16F18015	8,192	1FFFh
PIC16F18025	8,192	0FFFh
PIC16F18044	4,096	1FFFh
PIC16F18045	8,192	1FFFh

Figure 9-1. Program Memory and Stack (PIC16F180x4)





Figure 9-2. Program Memory and Stack (PIC16F180x5)




## 9.1.1 Reading Program Memory as Data

There are three methods of accessing constants in program memory. The first method is to use tables of RETLW instructions, the second, to set an FSR to point to the program memory, and the third is to use the NVMREG interface to access the program memory.

### 9.1.1.1 RETLW Instruction

The RETLW instruction can be used to provide access to tables of constants. The recommended way to create such a table is shown in the following example.



```
;select data

RETLW DATAO ;Index0 data

RETLW DATA1 ;Index1 data

RETLW DATA2

RETLW DATA3

my_function
;... LOTS OF CODE...

MOVLW DATA_INDEX

call constants
;... THE CONSTANT IS IN W
```

The BRW instruction eases the implementation of this type of table.

### 9.1.1.2 Indirect Read with FSR

The program memory can be accessed as data by setting bit 7 of an FSRxH register and reading the matching INDFx register. The MOVIW instruction will place the lower eight bits of the addressed word in the W register. Writes to the program memory cannot be performed via the INDFx registers. Instructions that read the program memory via the FSR require one extra instruction cycle to complete. The following example demonstrates reading the program memory via an FSR.

The high directive will set bit 7 if a label points to a location in the program memory. This applies to the assembly code shown below.

```
Example 9-2. Read of Program Memory Using FSR Register
 constants
     RETLW DATAO
                         ;Index0 data
     RETLW DATA1
                         ;Index1 data
     RETLW DATA2
     RETLW DATA3
 my function
     ;... LOTS OF CODE...
     MOVLW
              LOW constants
     MOVWF
              FSR1L
     MOVLW
              HIGH constants
     MOVWF
              FSR1H
              2[FSR1]
                            ;DATA2 IS IN W
     WIVOM
```

## 9.1.2 Memory Access Partition (MAP)

User Flash is partitioned into:

- Application Block
- Boot Block
- Storage Area Flash (SAF) Block

The user can allocate the memory usage by setting the BBEN bit, selecting the size of the partition defined by BBSIZE bits and enabling the Storage Area Flash by the SAFEN bit.

### 9.1.2.1 Application Block

Default settings of the Configuration bits ( $\overline{BBEN} = 1$  and  $\overline{SAFEN} = 1$ ) assign all memory in the user Flash area to the application block.

### 9.1.2.2 Boot Block

If BBEN = 1, the Boot Block is enabled and a specific address range is allotted as the Boot Block, based on the value of the BBSIZE bits.

### 9.1.2.3 Storage Area Flash

Storage Area Flash (SAF) is enabled by clearing the SAFEN bit. If enabled, the SAF block is placed at the end of memory and spans 128 words. If the Storage Area Flash (SAF) is enabled, the SAF area is not available for program execution.



**Important:** Storage Area Flash, when enabled, may be used to store variables or other information, often in devices without EEPROM; however, the SAF is accessed in the same manner as other Flash memory areas.

### 9.1.2.4 Memory Write Protection

All the memory blocks have corresponding write protection bits (WRTAPP, WRTB, WRTC, WRTD, and WRTSAF). If write-protected locations are written from NVMCON registers, the memory is not changed and the WRERR bit of the NVMCON1 register is set as explained in the "WRERR Bit" section from the "NVM - Nonvolatile Memory Control" chapter.

### 9.1.2.5 Memory Violation

A Memory Execution Violation Reset occurs while executing an instruction that has been fetched from outside a valid execution area, clearing the  $\overline{\text{MEMV}}$  bit. Refer to the "**Memory Execution Violation**" section in the "**Resets**" chapter for the available valid program execution areas and the PCON1 register definition for  $\overline{\text{MEMV}}$  bit conditions.

Table 9-2. Memory Access Partition

			Part	ition					
REG	Address	BBEN = 1 SAFEN = 1	BBEN = 1 SAFEN = 0	BBEN = 0 SAFEN = 1	BBEN = 0 SAFEN = 0				
	00 0000h Last Block Memory Address			Boot Block <sup>(4)</sup>	Boot Block <sup>(4)</sup>				
PFM	Last Boot Block Memory Address + 1 <sup>(1)</sup> Last Program Memory Address - 80h	Application Block <sup>(4)</sup>	Application Block <sup>(4)</sup>	Application	Application Block <sup>(4)</sup>				
	Last Program Memory Address - 7Fh <sup>(2)</sup> Last Program Memory Address		SAF <sup>(4)</sup>	Block <sup>(4)</sup>	SAF(4)				
CONFIG	Config Memory Address <sup>(3)</sup>		CON	NFIG	_				
EEPROM	F000h-F0FFh	EEPROM							

### Notes:

- Last Boot Block Memory Address is based on the BBSIZE Configuration bits.
- Last Program Memory Address is the Flash size given in the "Program Memory Organization" section in the "NVM - Nonvolatile Memory Control" chapter.
- Config Memory Address are the address locations of the Configuration Words given in the "NVMREG Access
  to DIA, DCI, User ID, DEV/REV ID, and Configuration Words" section in the "NVM Nonvolatile Memory
  Control" chapter.
- 4. Each memory block has a corresponding write protection fuse defined by the WRTAPP, WRTB, WRTC, WRTD, and WRTSAF Configuration bits.

### 9.1.3 Device Information Area (DIA)

The Device Information Area (DIA) is a dedicated region in the Program Flash Memory. The data is mapped from address 8100h to 811Fh. These locations are read-only and cannot be erased or modified. The DIA contains the Microchip Unique Identifier words, Temperature Indicator range data, and the Fixed Voltage Reference (FVR) voltage readings in millivolts (mV). The DIA Table holds the DIA information for the PIC16F180 family of microcontrollers.

Table 9-3. Device Information Area

Address Range	Name of Region	Standard Device Information								
	MUI0									
	MUI1									
	MUI2									
	MUI3									
8100h - 8108h	MUI4	Microchip Unique Identifier (9 Words)								
	MUI5									
	MUI6									
	MUI7									
	MUI8									
8109h	MUI9	Reserved (1 Word)								
	EUI0									
	EUI1									
	EUI2									
04001 04441	EUI3									
810Ah - 8111h	EUI4	Optional External Unique Identifier (8 Words)								
	EUI5									
	EUI6									
	EUI7									
8112h	TSLR1 <sup>(1)</sup>	Gain = $\frac{0.1C \times 256}{count}$ (low range setting)								
8113h	TSLR2 <sup>(1)</sup>	Temperature sensor ADC reading at 90°C (low range setting)								
8114h	TSLR3 <sup>(1)</sup>	Offset (low range setting)								
8115h	TSHR1 <sup>(2)</sup>	Gain = $\frac{0.1C \times 256}{count}$ (high range setting)								
8116h	TSHR2 <sup>(2)</sup>	Temperature sensor ADC reading at 90°C (high range setting)								
8117h	TSHR3 <sup>(2)</sup>	Offset (high range setting)								
8118h	FVRA1X	ADC FVR1 output voltage for 1x setting (in mV)								
8119h	FVRA2X	ADC FVR1 output voltage for 2x setting (in mV)								
811Ah	FVRA4X	ADC FVR1 output voltage for 4x setting (in mV)								
811Bh	FVRC1X	Comparator FVR2 output voltage for 1x setting (in mV)								
811Ch	FVRC2X	Comparator FVR2 output voltage for 2x setting (in mV)								
811Dh	FVRC4X	Comparator FVR2 output voltage for 4x setting (in mV)								
811Eh - 811Fh	Reserved	Reserved (2 Words)								

continued		
Address Range	Name of Region	Standard Device Information
NI 4		

#### Notes:

- TSLR: Addresses 8112h 8114h store the measurements for the low range setting of the temperature sensor at V<sub>DD</sub> = 3.0V, V<sub>REF</sub>+ = 2.048V from FVR1.
- 2. TSHR: Addresses 8115h 8117h store the measurements for the high range setting of the temperature sensor at  $V_{DD} = 3.0V$ ,  $V_{REF}$ + = 2.048V from FVR1.

### 9.1.3.1 Microchip Unique Identifier (MUI)

The PIC16F180 devices are individually encoded during final manufacturing with a Microchip Unique Identifier (MUI). The MUI cannot be erased by a Bulk Erase command or any other user-accessible means. This feature allows for manufacturing traceability of Microchip Technology devices in applications where this is required. It may also be used by the application manufacturer for a number of functions that require unverified unique identification, such as:

- · Tracking the device
- · Unique serial number

The MUI consists of nine program words. When taken together, these fields form a unique identifier. The MUI is stored in read-only locations, located between 8100h to 8108h in the DIA space. The DIA Table lists the addresses of the identifier words.



**Important:** For applications requiring verified unique identification, contact the Microchip Technology sales office to create a serialized quick turn programming option.

### 9.1.3.2 External Unique Identifier (EUI)

The EUI data is stored at locations 810Ah to 8111h in the program memory region. This region is an optional space for placing application specific information. The data is coded per customer requirements during manufacturing. The EUI cannot be erased by a Bulk Erase command.



**Important:** Data is stored in this address range on receiving a request from the customer. The customer may contact the local sales representative or Field Applications Engineer, and provide them the unique identifier information that is required to be stored in this region.

### 9.1.3.3 Standard Parameters for the Temperature Sensor

The purpose of the temperature indicator module is to provide a temperature-dependent voltage that can be measured by an analog module. The DIA Table contains standard parameters for the temperature sensor for low and high range. The values are measured during test and are unique to each device. The calibration data can be used to plot the approximate sensor output voltage,  $V_{TSENSE}$  vs. Temperature curve. The "Temperature Indicator Module" chapter explains the operation of the Temperature Indicator module and defines terms such as the low range and high range settings of the sensor.

## 9.1.3.4 Fixed Voltage Reference Data

The Fixed Voltage Reference (FVR) is a stable voltage reference, independent of  $V_{DD}$ , with 1.024V, 2.048V or 4.096V selectable output levels. The output of the FVR can be configured to supply a reference voltage to the following:

- ADC input channel
- · ADC positive reference
- Comparator positive input
- Digital-to-Analog Converter (DAC)

For more information on the FVR, refer to the "FVR - Fixed Voltage Reference" chapter.

The DIA stores measured FVR voltages for this device in mV for the different buffer settings of 1x, 2x or 4x.

FVRA1X stores the value of ADC FVR1 Output Voltage for 1x setting (in mV)

- FVRA2X stores the value of ADC FVR1 Output Voltage for 2x setting (in mV)
- FVRA4X stores the value of ADC FVR1 Output Voltage for 4x setting (in mV)
- FVRC1X stores the value of Comparator FVR2 Output Voltage for 1x setting (in mV)
- FVRC2X stores the value of Comparator FVR2 Output Voltage for 2x setting (in mV)
- FVRC4X stores the value of Comparator FVR2 Output Voltage for 4x setting (in mV)

## 9.1.4 Device Configuration Information (DCI)

The Device Configuration Information (DCI) is a dedicated region in the memory that holds information about the device, which is useful for programming and bootloader applications. The data stored in this region is read-only and cannot be modified/erased. Refer to the table below for complete DCI table addresses and description.

Table 9-4. Device Configuration Information

Address	Name	Description	Va	lue	Units
Address	INAIIIE	Description	PIC16F180x4	PIC16F180x5	Office
8200h	ERSIZ	Erase Row Size	3	2	Words
8201h	WLSIZ	Number of write latches per row	3	Words	
8202h	URSIZ	Number of user erasable rows	128	256	Rows
8203h	EESIZ	Data EEPROM memory size	12	Bytes	
8204h	PCNT	Pin Count	8/14	Pins	

### 9.1.4.1 DIA and DCI Access

The DIA and DCI data are read-only and cannot be erased or modified. See the "NVMREG Access to DIA, DCI, User ID, DEV/REV ID, and Configuration Words" section in the "NVM - Nonvolatile Memory Control" chapter for more information on accessing these memory locations.

Development tools, such as device programmers and debuggers, may be used to read the DIA and DCI regions, similar to the Device ID and Revision ID.


## 9.2 Data Memory Organization

The data memory is partitioned into up to 64 memory banks with 128 bytes in each bank. Each bank consists of:

- 12 core registers
- Up to 20 Special Function Registers (SFR)
- Up to 80 bytes of General Purpose RAM (GPR)
- 16 bytes of common RAM

Figure 9-3. Banked Memory Partition





### 9.2.1 Bank Selection

The active bank is selected by writing the bank number into the Bank Select Register (BSR). All data memory can be accessed either directly via instructions that use the file registers, or indirectly via the two File Select Registers (FSRs). Data memory uses a 13-bit address. The upper six bits of the address define the Bank Address and the lower seven bits select the registers/RAM in that bank.

## 9.2.2 Core Registers

The core registers contain the registers that directly affect the basic operation. The core registers occupy the first 12 addresses of every data memory bank. These registers are listed in the Core Registers table below.

Table 9-5. Core Registers

Addresses in BANKx	Core Registers
x00h or x80h	INDF0
x01h or x81h	INDF1
x02h or x82h	PCL
x03h or x83h	STATUS
x04h or x84h	FSR0L

continued												
Addresses in BANKx	Core Registers											
x05h or x85h	FSR0H											
x06h or x86h	FSR1L											
x07h or x87h	FSR1H											
x08h or x88h	BSR											
x09h or x89h	WREG											
x0Ah or x8Ah	PCLATH											
x0Bh or x8Bh	INTCON											

## 9.2.3 Special Function Register

The Special Function Registers (SFR) are registers used by the application to control the desired operation of peripheral functions in the device. The SFRs occupy the first 20 bytes of the data banks 0-59 and the first 100 bytes of the data banks 60-63, after the core registers.

The SFRs associated with the operation of the peripherals are described in the appropriate peripheral chapter of this data sheet.

## 9.2.4 General Purpose RAM

There are up to 80 bytes of GPR in each data memory bank. The general purpose RAM can be accessed in a non-banked method via the FSRs. This can simplify access to large memory structures.

Refer to the "Linear Data Memory" section in the "Memory Organization" chapter for details about linear memory accessing.

### 9.2.5 Common RAM

There are 16 bytes of common RAM accessible from all banks.

## 9.2.6 Device Memory Maps

The memory maps for the devices in this data sheet are listed in the following figures.

Figure 9-4. Memory Map Banks 0 - 7

	BANK 0		BANK 1		BANK 2		BANK 3		BANK 4		BANK 5		BANK 6		BANK 7
000h		080h		100h		180h		200h		280h		300h		380h	
	Core Registers		Core Registers		Core Registers		Core Registers		Core Registers		Core Registers		Core Registers		Core Registers
00Bh		08Bh		10Bh		18Bh		20Bh		28Bh		30Bh		38Bh	
00Ch	PORTA	08Ch	PIR0	10Ch		18Ch	WDTCON	20Ch	_	28Ch	TMR1L	30Ch	T2TMR	38Ch	CCPR1L
00Dh	PORTB <sup>(1)</sup>	08Dh	PIR1	10Dh	_	18Dh	BORCON	20Dh	-	28Dh	TMR1H	30Dh	T2PR	38Dh	CCPR1H
00Eh	PORTC <sup>(2)</sup>	08Eh	PIR2	10Eh	_	18Eh	PCON0	20Eh	OSCCON2	28Eh	T1CON	30Eh	T2CON	38Eh	CCP1CON
00Fh	-	08Fh	PIR3	10Fh	-	18Fh	PCON1	20Fh	OSCCON3	28Fh	T1GCON	30Fh	T2HLT	38Fh	CCP1CAP
010h	_	090h	PIR4	110h	_	190h	-	210h	OSCSTAT	290h	T1GATE	310h	T2CLK	390h	CCPR2L
011h	_	091h	_	111h	_	191h	-	211h	OSCEN	291h	T1CLK	311h	T2RST	391h	CCPR2H
012h	TRISA	092h	-	112h	_	192h	_	212h	OSCTUNE	292h	TMR3L	312h	T4TMR	392h	CCP2CON
013h	TRISB <sup>(1)</sup>	093h	_	113h	_	193h	_	213h	OSCFRQ	293h	TMR3H	313h	T4PR	393h	CCP2CAP
014h	TRISC <sup>(2)</sup>	094h	1	114h	1	194h	-	214h	ACTCON	294h	T3CON	314h	T4CON	394h	_
015h	_	095h	_	115h	-	195h	-	215h	-	295h	T3GCON	315h	T4HLT	395h	_
016h	_	096h	PIE0	116h	_	196h	-	216h	-	296h	T3GATE	316h	T4CLK	396h	_
017h	_	097h	PIE1	117h	-	197h	-	217h	-	297h	T3CLK	317h	T4RST	397h	_
018h	LATA	098h	PIE2	118h	-	198h	_	218h	-	298h	1	318h	T6TMR	398h	_
019h	LATB <sup>(1)</sup>	099h	PIE3	119h	-	199h	_	219h	-	299h	-	319h	T6PR	399h	_
01Ah	LATC <sup>(2)</sup>	09Ah	PIE4	11Ah	-	19Ah	-	21Ah	-	29Ah	-	31Ah	T6CON	39Ah	_
01Bh	-	09Bh	-	11Bh	-	19Bh	-	21Bh	-	29Bh	_	31Bh	T6HLT	39Bh	_
01Ch	_	09Ch	1	11Ch	1	19Ch	TMR0L	21Ch	_	29Ch	_	31Ch	T6CLK	39Ch	_
01Dh	_	09Dh	1	11Dh	1	19Dh	TRMOH	21Dh	-	29Dh	-	31Dh	T6RST	39Dh	_
01Eh	_	09Eh	1	11Eh	1	19Eh	T0CON0	21Eh	-	29Eh	-	31Eh	-	39Eh	_
01Fh	-	09Fh	-	11Fh	_	19Fh	T0CON1	21Fh	-	29Fh	-	31Fh	-	39Fh	CCPTMRS0
020h		0A0h		120h		1A0h		220h		2A0h		320h	General	3A0h	
													Purpose		
													Registers		
	General		General		General		General		General		General	32Fh	16 Bytes		General
	Purpose		Purpose		Purpose		Purpose		Purpose		Purpose	330h			Purpose
	Registers		Registers		Registers		Registers		Registers		Registers		General		Registers
	80 Bytes		80 Bytes		80 Bytes		80 Bytes		80 Bytes		80 Bytes		Purpose		80 Bytes <sup>(3)</sup>
													Registers		
													64 Bytes <sup>(3)</sup>		
06Fh		0EFh		16Fh		1EFh		26Fh		2EFh		36Fh		3EFh	L
070h	Common RAM	0F0h	Common RAM	170h	Common RAM	1F0h	Common RAM	270h	Common RAM	2F0h	Common RAM	370h	Common RAM	3F0h	Common RAM
075	(Accesses	OFF	(Accesses	175	(Accesses	155	(Accesses	275	(Accesses	2557	(Accesses	275	(Accesses	3FFh	(Accesses
07Fh	70h-7Fh)	0FFh	70h-7Fh)	17Fh	70h-7Fh)	1FFh	70h-7Fh)	27Fh	70h-7Fh)	2FFh	70h-7Fh)	37Fh	70h-7Fh)	3FFN	70h-7Fh)

1. 20-pin devices only 2. 14/16/20-pin devices only 3. Not available on PIC16F18044

Legend:
Unimplemented data memory locations, read as '0'

Figure 9-5. Memory Map Banks 8 - 15

	BANK 8		BANK 9		BANK 10		BANK 11		BANK 12		BANK 13		BANK 14		BANK 15
400h		480h		500h		580h		600h		680h		700h		780h	
	Core Registers		Core Registers		Core Registers		Core Registers								
40Bh	PWM3DCI	48Bh	NCO1ACCI	50Bh	CWG1CLK	58Bh 58Ch	CLCnCON	60Bh	RC1REG	68Bh	SSP1BUF	70Bh		78Bh	_
40Ch 40Dh	PWM3DCL PWM3DCH	48Ch 48Dh	NCO1ACCL NCO1ACCH	50Ch 50Dh	CWG1CLK	58Ch 58Dh	CLCnCON	60Ch	TX1REG	68Ch 68Dh	SSP1BUF SSP1ADD	70Ch 70Dh	-	78Ch 78Dh	
40Dh 40Eh	PWM3DCH PWM3CON	48Dh 48Eh	NCO1ACCH NCO1ACCU	50Dh	CWG1SM CWG1DBR	58Dh 58Eh	CLCNPOL	60Dh 60Eh	SP1BRGL	68Eh	SSP1ADD SSP1MSK	70Dh 70Eh		78Eh	
40EH	PWM4DCI	48Fh	NCO1NCL	50Fh	CWG1DBR CWG1DBF	58Fh	CLCHSELU CLCnSFL1	60Fh	SP1BRGL SP1BRGH	68Fh	SSP1NISK SSP1STAT	70Fh		78Fh	
40FN 410h	PWM4DCL PWM4DCH	490h	NCO1INCH	510h	CWG1DBF CWG1CON0	590h	CLCnSEL1 CLCnSEL2	610h	RC1STA	690h	SSP1STAT SSP1CON1	70FII 710h		790h	
411h	PWM4CON	491h	NCO1INCU	511h	CWG1CON1	591h	CLCnSEL3	611h	TX1STA	691h	SSP1CON1 SSP1CON2	711h		791h	
411h	PWM5DCL	491h	NCO1CON	511h	CWG1AS0	592h	CLCnGLS0	612h	BAUD1CON	692h	SSP1CON2 SSP1CON3	711h		791h	
413h	PWM5DCH	493h	NCO1CLK	513h	CWG1AS1	593h	CLCnGLS1	613h	-	693h	-	713h	_	793h	_
414h	PWM5CON	494h	-	514h	CWG1STR	594h	CLCnGLS2	614h	_	694h	_	714h	_	794h	_
415h	_	495h		515h	-	595h	CLCnGLS3	615h	_	695h	_	715h	_	795h	_
416h	_	496h	_	516h	_	596h	CLCSELECT	616h	RC2REG	696h	SSP2BUF	716h	_	796h	_
417h	_	497h	_	517h	_	597h	CLCDATA	617h	TX2REG	697h	SSP2ADD	717h	_	797h	_
418h	_	498h	_	518h	_	598h	_	618h	SP2BRGL	698h	SSP2MSK	718h	_	798h	_
419h	_	499h	_	519h	-	599h	_	619h	SP2BRGH	699h	SSP2STAT	719h	_	799h	_
41Ah	_	49Ah	_	51Ah	-	59Ah	_	61Ah	RC2STA	69Ah	SSP2CON1	71Ah	-	79Ah	-
41Bh	_	49Bh	-	51Bh	-	59Bh	_	61Bh	TX2STA	69Bh	SSP2CON2	71Bh	-	79Bh	-
41Ch	_	49Ch	-	51Ch	-	59Ch	_	61Ch	BAUD2CON	69Ch	SSP2CON3	71Ch	-	79Ch	-
41Dh	-	49Dh	-	51Dh	-	59Dh	-	61Dh	-	69Dh	_	71Dh	-	79Dh	-
41Eh	-	49Eh	-	51Eh	-	59Eh	ı	61Eh	-	69Eh	_	71Eh	-	79Eh	_
41Fh	PWMTMRS0	49Fh	-	51Fh	-	59Fh	1	61Fh	_	69Fh	1	71Fh	_	79Fh	_
420h		4A0h		520h		5A0h		620h	General	6A0h		720h		7A0h	
									Purpose						
	General		General		General		General		Registers						
	Purpose		Purpose		Purpose		Purpose	64Fh	48 Bytes <sup>(1)</sup>		Unimplemented		Unimplemented		Unimplemented
	Registers		Registers		Registers		Registers	650h			Read as '0'		Read as '0'		Read as '0'
	80 Bytes <sup>(1)</sup>		Unimplemented												
									Read as '0'						
46Fh		4EFh		56Fh		5EFh		66Fh		6EFh		76Fh		7EFh	
470h	Common RAM	4F0h	Common RAM	570h	Common RAM	5F0h	Common RAM	670h	Common RAM	6F0h	Common RAM	770h	Common RAM	7F0h	Common RAM
	(Accesses		(Accesses		(Accesses		(Accesses								
47Fh	70h-7Fh)	4FFh	70h-7Fh)	57Fh	70h-7Fh)	5FFh	70h-7Fh)	67Fh	70h-7Fh)	6FFh	70h-7Fh)	77Fh	70h-7Fh)	7FFh	70h-7Fh)

Note: 1. Not available on PIC16F18044

Figure 9-6. Memory Map Banks 16 - 23

	BANK 16		BANK 17		BANK 18		BANK 19		BANK 20		BANK 21		BANK 22		BANK 23
800h		880h		900h		980h		A00h		A80h		B00h		B80h	
	Core Registers		Core Registers		Core Registers		Core Registers		Core Registers		Core Registers		Core Registers		Core Registers
80Bh		88Bh		90Bh		98Bh		A0Bh		A8Bh		B0Bh		B8Bh	
80Ch	_	88Ch	_	90Ch	_	98Ch	_	A0Ch	_	A8Ch	-	B0Ch	_	B8Ch	_
80Dh	_	88Dh	_	90Dh	_	98Dh	_	A0Dh	_	A8Dh	_	BODh	_	B8Dh	_
80Eh	_	88Eh	_	90Eh	_	98Eh	_	A0Eh	_	A8Eh	-	B0Eh	_	B8Eh	_
80Fh	_	88Fh	_	90Fh	_	98Fh	_	A0Fh	_	A8Fh	_	B0Fh	_	B8Fh	_
810h	_	890h	_	910h	_	990h	_	A10h	_	A90h	_	B10h	_	B90h	_
811h	_	891h	_	911h	_	991h	_	A11h	_	A91h	_	B11h	_	B91h	_
812h	_	892h		912h	_	992h	_	A12h	_	A92h	_	B12h	_	B92h	_
813h		893h		913h	_	993h		A13h	_	A93h	_	B13h	_	B93h	_
814h	_	894h		914h	_	994h	_	A14h	_	A94h		B14h	_	B94h	_
815h	_	895h		915h	_	995h	_	A15h	_	A95h		B15h	_	B95h	_
816h		896h		916h	_	996h		A16h	_	A96h	_	B16h	_	B96h	_
817h		897h		917h	_	997h	_	A17h	_	A97h		B17h	_	B97h	_
818h	-	898h	_	918h	_	998h	_	A18h	_	A98h	_	B18h	-	B98h	_
819h		899h		919h	_	999h		A19h	_	A99h		B19h	_	B99h	_
81Ah		89Ah		91Ah	_	99Ah	_	A1Ah	_	A9Ah		B1Ah	_	B9Ah	_
81Bh		89Bh		91Bh	_	99Bh	_	A1Bh	_	A9Bh	-	B1Bh	_	B9Bh	_
81Ch		89Ch		91Ch	-	99Ch	_	A1Ch	_	A9Ch	-	B1Ch	_	B9Ch	_
81Dh	-	89Dh	<u> </u>	91Dh	_	99Dh	_	A1Dh	_	A9Dh	-	B1Dh	_	B9Dh	_
81Eh	-	89Eh		91Eh	_	99Eh 99Fh	_	A1Eh	_	A9Eh	-	B1Eh	_	B9Eh	_
81Fh		89Fh	_	91Fh	_		_	A1Fh	_	A9Fh	-	B1Fh	_	B9Fh	_
820h		8A0h		920h		9A0h		A20h		AA0h		B20h		BA0h	
	Unimplemented		Unimplemented		Unimplemented		Unimplemented		Unimplemented		Unimplemented		Unimplemented		Unimplemented
	Read as '0'		Read as '0'		Read as '0'		Read as '0'		Read as '0'		Read as '0'		Read as '0'		Read as '0'
86Fh		8EFh		96Fh		9FFh		A6Fh		AEFh		B6Fh		BEFh	
870h	Common RAM	8F0h	Common RAM	970h	Common RAM	9F0h	Common RAM	A70h	Common RAM	AF0h	Common RAM	B70h	Common RAM	BF0h	Common RAM
27011	(Accesses	2. 0	(Accesses	27011	(Accesses	2.011	(Accesses	, 011	(Accesses	011	(Accesses		(Accesses	2.011	(Accesses
87Fh	70h-7Fh)	8FFh	70h-7Fh)	97Fh	70h-7Fh)	9FFh	70h-7Fh)	A7Fh	70h-7Fh)	AFFh	70h-7Fh)	B7Fh	70h-7Fh)	BFFh	70h-7Fh)
١ ٠٠٠٠٠	, , , , , , , ,	J	, , ,	1 3,	, , , , , , , , , , , , , , , , , , , ,	3	7511 7111,		7011 71117	7	, , , , , , , , , , , , , , , , , , , ,	5,	7011 71117	5	, , , , , , ,

Legend:
Unimplemented data memory locations, read as '0'

Figure 9-7. Memory Map Banks 24 - 31

	BANK 24		BANK 25		BANK 26		BANK 27		BANK 28		BANK 29		BANK 30		BANK 31
C00h	Core Registers	C80h	Core Registers	D00h	Core Registers	D80h	Core Registers	E00h	Core Registers	E80h	Core Registers	F00h	Core Registers	F80h	Core Registers
COBh		C8Bh		DOBh		D8Bh		EOBh		E8Bh		FOBh		F8Bh	
COCh	-	C8Ch	-	D0Ch	-	D8Ch	-	E0Ch	-	E8Ch	-	F0Ch	-	F8Ch	_
CODh	-	C8Dh	-	DODh	_	D8Dh	_	EODh	_	E8Dh	_	FODh	_	F8Dh	_
C0Eh	-	C8Eh	-	D0Eh	_	D8Eh	_	E0Eh	_	E8Eh	-	F0Eh	-	F8Eh	_
C0Fh	-	C8Fh	-	D0Fh	-	D8Fh	-	E0Fh	-	E8Fh	-	F0Fh	-	F8Fh	-
C10h	-	C90h	-	D10h	_	D90h	-	E10h	-	E90h	-	F10h	-	F90h	-
C11h	_	C91h	_	D11h	_	D91h	_	E11h	-	E91h	_	F11h	-	F91h	_
C12h	_	C92h	-	D12h	_	D92h	_	E12h	1	E92h	1	F12h	1	F92h	_
C13h	_	C93h	-	D13h	-	D93h	-	E13h	-	E93h	-	F13h	_	F93h	_
C14h	_	C94h	-	D14h	-	D94h	-	E14h	-	E94h	-	F14h	_	F94h	_
C15h	_	C95h	-	D15h	-	D95h	-	E15h	-	E95h	-	F15h	-	F95h	_
C16h	_	C96h	-	D16h	-	D96h	-	E16h	-	E96h	-	F16h	_	F96h	_
C17h	_	C97h	-	D17h	-	D97h	-	E17h	_	E97h	_	F17h	_	F97h	_
C18h	_	C98h	-	D18h	-	D98h	-	E18h	_	E98h	_	F18h	_	F98h	_
C19h	_	C99h	-	D19h	-	D99h	-	E19h	_	E99h	_	F19h	_	F99h	_
C1Ah	_	C9Ah	_	D1Ah	_	D9Ah	_	E1Ah	_	E9Ah	_	F1Ah	_	F9Ah	_
C1Bh	_	C9Bh	_	D1Bh	_	D9Bh	_	E1Bh	_	E9Bh	_	F1Bh	_	F9Bh	_
C1Ch	_	C9Ch	_	D1Ch	_	D9Ch	_	E1Ch	_	E9Ch	_	F1Ch	_	F9Ch	_
C1Dh	_	C9Dh	_	D1Dh	_	D9Dh	-	E1Dh	_	E9Dh	_	F1Dh	_	F9Dh	_
C1Eh	_	C9Eh	_	D1Eh	_	D9Eh	-	E1Eh	_	E9Eh	_	F1Eh	_	F9Eh	_
C1Fh	_	C9Fh	_	D1Fh	_	D9Fh	_	E1Fh	_	E9Fh	_	F1Fh	_	F9Fh	_
C20h		CA0h		D20h		DA0h		E20h		EA0h		F20h		FA0h	
	Unimplemented	CBFh	Unimplemented		Unimplemented										
	Read as '0'	CC0h	Read as '0'		Read as '0'										
C6Fh		CEEh		D6Fh		DEFh		E6Fh		EEFh		F6Fh		FEFh	
C70h	Common RAM	CF0h	Common RAM	D70h	Common RAM	DF0h	Common RAM	E70h	Common RAM	EF0h	Common RAM	F70h	Common RAM	FF0h	Common RAM
	(Accesses														
C7Fh	70h-7Fh)	CFFh	70h-7Fh)	D7Fh	70h-7Fh)	DFFh	70h-7Fh)	E7Fh	70h-7Fh)	EFFh	70h-7Fh)	F7Fh	70h-7Fh)	FFFh	70h-7Fh)

Figure 9-8. Memory Map Banks 32 - 39

	BANK 32		BANK 33		BANK 34		BANK 35		BANK 36		BANK 37		BANK 38	1	BANK 39
1000h		1080h		1100h		1180h		1200h		1280h		1300h		1380h	
	Core Registers														
100Bh		108Bh		110Bh		118Bh		120Bh		128Bh		130Bh		138Bh	
100Ch	FVRCON	108Ch	CM1CON0	110Ch	DAC1CON0	118Ch	-	120Ch	-	128Ch	_	130Ch	-	138Ch	_
100Dh	CPCON	108Dh	CM1CON1	110Dh	DAC1DATL	118Dh	-	120Dh	-	128Dh	-	130Dh	-	138Dh	_
100Eh	-	108Eh	CM1NCH	110Eh	-	118Eh	-	120Eh	-	128Eh	-	130Eh	-	138Eh	_
100Fh	-	108Fh	CM1PCH	110Fh	-	118Fh	-	120Fh	-	128Fh	-	130Fh	-	138Fh	_
1010h	-	1090h	-	1110h	-	1190h	-	1210h	-	1290h	-	1310h	-	1390h	-
1011h	-	1091h	-	1111h	-	1191h	-	1211h	-	1291h	-	1311h	-	1391h	-
1012h	-	1092h	-	1112h	-	1192h	-	1212h	-	1292h	-	1312h	-	1392h	-
1013h	-	1093h	-	1113h	-	1193h	-	1213h	-	1293h	-	1313h	-	1393h	-
1014h	-	1094h	-	1114h	-	1194h	-	1214h	-	1294h	-	1314h	-	1394h	-
1015h	-	1095h	-	1115h	_	1195h	_	1215h	-	1295h	_	1315h	-	1395h	_
1016h	-	1096h	-	1116h	_	1196h	_	1216h	-	1296h	_	1316h	-	1396h	_
1017h	-	1097h	-	1117h	_	1197h	-	1217h	-	1297h	_	1317h	-	1397h	_
1018h	_	1098h	_	1118h	-	1198h	_	1218h	-	1298h	_	1318h	-	1398h	-
1019h	-	1099h	-	1119h	-	1199h	-	1219h	-	1299h	-	1319h	-	1399h	-
101Ah	-	109Ah	-	111Ah	-	119Ah	-	121Ah	-	129Ah	-	131Ah	-	139Ah	-
101Bh	-	109Bh	-	111Bh	-	119Bh	_	121Bh	-	129Bh	_	131Bh	-	139Bh	_
101Ch	-	109Ch	-	111Ch	-	119Ch	_	121Ch	-	129Ch	_	131Ch	-	139Ch	_
101Dh	-	109Dh	-	111Dh	_	119Dh	-	121Dh	-	129Dh	_	131Dh	-	139Dh	_
101Eh	-	109Eh	-	111Eh	_	119Eh	-	121Eh	-	129Eh	_	131Eh	-	139Eh	_
101Fh	ZCDCON	109Fh	CMOUT	111Fh		119Fh		121Fh	_	129Fh	_	131Fh	_	139Fh	_
1020h		10A0h		1120h		11A0h		1220h		12A0h		1320h		13A0h	
	Unimplemented														
	Read as '0'														
106Fh		10EFh		116Fh		11EFh		126Fh		12EFh		136Fh		13EFh	
1070h	Common RAM	10F0h	Common RAM	1170h	Common RAM	11F0h	Common RAM	1270h	Common RAM	12F0h	Common RAM	1370h	Common RAM	13F0h	Common RAM
	(Accesses														
107Fh	70h-7Fh)	10FFh	70h-7Fh)	117Fh	70h-7Fh)	11FFh	70h-7Fh)	127Fh	70h-7Fh)	12FFh	70h-7Fh)	137Fh	70h-7Fh)	13FFh	70h-7Fh)

Legend:
Unimplemented data memory locations, read as '0'

Figure 9-9. Memory Map Banks 40 - 47

	BANK 40		BANK 41		BANK 42		BANK 43		BANK 44		BANK 45		BANK 46	1	BANK 47
1400h	Core Registers	1480h	Core Registers	1500h	Core Registers	1580h	Core Registers	1600h	Core Registers	1680h	Core Registers	1700h	Core Registers	1780h	Core Registers
140Bh		148Bh		150Bh		158Bh		160Bh		168Bh		170Bh		178Bh	
140Ch	-	148Ch	-	150Ch	-	158Ch	-	160Ch	-	168Ch	_	170Ch	-	178Ch	-
140Dh	_	148Dh	-	150Dh	-	158Dh	-	160Dh	_	168Dh	-	170Dh	-	178Dh	_
140Eh	-	148Eh	-	150Eh	_	158Eh	_	160Eh	_	168Eh	-	170Eh	1	178Eh	_
140Fh	-	148Fh	ı	150Fh	1	158Fh	-	160Fh	ı	168Fh	1	170Fh	-	178Fh	_
1410h	-	1490h	_	1510h	_	1590h	-	1610h	-	1690h	-	1710h	1	1790h	_
1411h	_	1491h	-	1511h	-	1591h	-	1611h	_	1691h	-	1711h	ı	1791h	_
1412h	-	1492h	-	1512h	-	1592h	-	1612h	-	1692h	-	1712h	-	1792h	_
1413h	-	1493h	-	1513h	_	1593h		1613h	-	1693h	_	1713h	-	1793h	_
1414h	_	1494h	_	1514h	_	1594h		1614h	_	1694h	_	1714h	_	1794h	_
1415h	_	1495h	_	1515h	_	1595h		1615h	_	1695h	_	1715h	-	1795h	_
1416h	_	1496h	_	1516h	_	1596h		1616h	_	1696h	_	1716h	-	1796h	_
1417h	_	1497h	_	1517h	_	1597h		1617h	_	1697h	_	1717h	-	1797h	_
1418h	_	1498h	_	1518h	_	1598h		1618h	_	1698h	_	1718h	-	1798h	_
1419h	_	1499h	_	1519h	_	1599h		1619h	_	1699h	_	1719h	-	1799h	_
141Ah	_	149Ah	-	151Ah	_	159Ah		161Ah	_	169Ah	_	171Ah	-	179Ah	_
141Bh		149Bh	_	151Bh	_	159Bh		161Bh	_	169Bh	_	171Bh	-	179Bh	
141Ch		149Ch	_	151Ch	_	159Ch		161Ch	_	169Ch	_	171Ch	_	179Ch	
141Dh		149Dh	_	151Dh	_	159Dh		161Dh	_	169Dh	_	171Dh	_	179Dh	
141Eh		149Eh	_	151Eh		159Eh		161Eh	_	169Eh	_	171Eh	_	179Eh	
141Fh		149Fh	_	151Fh	_	159Fh		161Fh	_	169Fh	_	171Fh	_	179Fh	_
1420h		14A0h		1520h		15A0h		1620h		16A0h		1720h		17A0h	
	Unimplemented Read as '0'														
146Fh		14EFh		156Fh		15EFh		166Fh		16EFh		176Fh		17EFh	
1470h	Common RAM	14F0h	Common RAM	1570h	Common RAM	15F0h	Common RAM	1670h	Common RAM	16F0h	Common RAM	1770h	Common RAM	17F0h	Common RAM
14/011	(Accesses	141011	(Accesses	137011	(Accesses	137011	(Accesses	10/011	(Accesses	101011	(Accesses	177011	(Accesses	1,1011	(Accesses
147Fh	70h-7Fh)	14FFh	70h-7Fh)	157Fh	70h-7Fh)	15FFh	70h-7Fh)	167Fh	70h-7Fh)	16FFh	70h-7Fh)	177Fh	70h-7Fh)	17FFh	70h-7Fh)
14/11	70H-7FH)	TALLU	/UII-/FII)	13/11	/UII-/FII)	TOLLII	/UII-/FII)	10/11	/UII-/FII)	TOFFII	/UII-/FII)	1////	/UII-/FII)	1/11/	/UII=/FII)

Figure 9-10. Memory Map Banks 48 - 55

1800h	Core Registers	1880h		1900h											
			Core Registers	130011	Core Registers	1980h	Core Registers	1A00h	Core Registers	1A80h	Core Registers	1B00h	Core Registers	1B80h	Core Registers
180Bh		188Bh		190Bh		198Bh		1A0Bh		1A8Bh		1B0Bh		1B8Bh	
180Ch	-	188Ch	-	190Ch	_	198Ch	_	1A0Ch	-	1A8Ch	_	1B0Ch	_	1B8Ch	-
180Dh	-	188Dh	_	190Dh	1	198Dh	1	1A0Dh	1	1A8Dh	-	1B0Dh	-	1B8Dh	_
180Eh	-	188Eh	-	190Eh	-	198Eh	-	1A0Eh	-	1A8Eh	-	1B0Eh	-	1B8Eh	_
180Fh	-	188Fh	-	190Fh	-	198Fh	-	1A0Fh	-	1A8Fh	-	1B0Fh	-	1B8Fh	_
1810h	-	1890h	-	1910h	-	1990h	-	1A10h	1	1A90h	1	1B10h	-	1B90h	_
1811h	_	1891h	_	1911h	ı	1991h	-	1A11h	ı	1A91h	1	1B11h	-	1B91h	_
1812h	-	1892h	-	1912h	_	1992h	-	1A12h	-	1A92h	-	1B12h	-	1B92h	_
1813h	_	1893h	-	1913h	_	1993h	_	1A13h	_	1A93h	_	1B13h	_	1B93h	_
1814h	-	1894h	-	1914h	_	1994h	_	1A14h	_	1A94h	_	1B14h	_	1B94h	_
1815h	-	1895h	-	1915h	-	1995h	-	1A15h	-	1A95h	_	1B15h	-	1B95h	_
1816h	-	1896h	-	1916h	-	1996h	-	1A16h	-	1A96h	-	1B16h	-	1B96h	_
1817h	_	1897h	_	1917h	ı	1997h	1	1A17h	ı	1A97h	1	1B17h	1	1B97h	_
1818h	_	1898h	_	1918h	ı	1998h	1	1A18h	ı	1A98h	1	1B18h	1	1B98h	_
1819h	_	1899h	-	1919h	_	1999h	_	1A19h	_	1A99h	_	1B19h	_	1B99h	_
181Ah	_	189Ah	-	191Ah	_	199Ah	_	1A1Ah	_	1A9Ah	_	1B1Ah	_	1B9Ah	_
181Bh	-	189Bh	-	191Bh	_	199Bh	-	1A1Bh	-	1A9Bh	-	1B1Bh	-	1B9Bh	_
181Ch	-	189Ch	-	191Ch	1	199Ch	1	1A1Ch	1	1A9Ch	-	1B1Ch	-	1B9Ch	_
181Dh	_	189Dh	-	191Dh	ı	199Dh	1	1A1Dh	ı	1A9Dh	1	1B1Dh	1	1B9Dh	_
181Eh	_	189Eh	-	191Eh	ı	199Eh	1	1A1Eh	1	1A9Eh	1	1B1Eh	1	1B9Eh	_
181Fh	_	189Fh	_	191Fh	1	199Fh	-	1A1Fh	1	1A9Fh	-	1B1Fh	-	1B9Fh	_
1820h		18A0h		1920h		19A0h		1A20h		1AA0h		1B20h		1BA0h	
	Unimplemented Read as '0'														
186Fh 1870h 187Fh	Common RAM (Accesses 70h-7Fh)	18EFh 18F0h 18FFh	Common RAM (Accesses 70h-7Fh)	196Fh 1970h 197Fh	Common RAM (Accesses 70h-7Fh)	19EFh 19F0h 19FFh	Common RAM (Accesses 70h-7Fh)	1A6Fh 1A70h 1A7Fh	Common RAM (Accesses 70h-7Fh)	1AEFh 1AF0h 1AFFh	Common RAM (Accesses 70h-7Fh)	186Fh 1870h 187Fh	Common RAM (Accesses 70h-7Fh)	1BEFh 1BF0h 1BFFh	Common RAM (Accesses 70h-7Fh)

Legend:

Figure 9-11. Memory Map Banks 56 - 63

	BANK 56		BANK 57		BANK 58		BANK 59		BANK 60		BANK 61		BANK 62		BANK 63
1C00h		1C80h		1D00h		1D80h		1E00h		1E80h		1F00h		1F80h	
	Core Registers		Core Registers	1D0Bh	Core Registers		Core Registers		Core Registers		Core Registers		Core Registers		Core Registers
1C0Bh		1C8Bh		100011		1D8Bh		1E0Bh		1E8Bh		1F0Bh		1F8Bh	
1C0Ch		1C8Ch	NVMADRL	1D0Ch	ADLTHL	1D8Ch	RAOPPS	1E0Ch		1E8Ch		1F0Ch	UMTOAP	1F8Ch	
		1C8Dh	NVMADRH	1D0Dh	ADLTHH	1D8Dh	RA1PPS					1F0Dh	UMTOAL		
		1C8Eh	NVMDATL	1D0Eh	ADUTHL	1D8Eh	RA2PPS					1F0Eh	UMTOAH		
		1C8Fh	NVMDATH	1D0Fh	ADUTHH	1D8Fh	_					1F0Fh			
		1C90h	NVMCON1	1D10h	ADERRL	1D90h	RA4PPS								
		1C91h	NVMCON2	1D11h 1D12h	ADERRH	1D91h	RA5PPS								
		1C92h		1D12h 1D13h	ADSTPTL ADSTPTH	1D92h	Unimplemented								
				1D13h	ADSTETH	1D97h	Read as '0'								
			Unimalamental	1D15h	ADFLTRH	1D98h	RB4PPS <sup>(1)</sup>								
			Unimplemented Read as '0'	1D16h	ADACCL	1D99h	RB5PPS <sup>(1)</sup>								
			Redu as 0	1D17h	ADACCH	1D9Ah	RB6PPS <sup>(1)</sup>	1							
				1D18h	ADACCU	1D9Bh	RB7PPS <sup>(1)</sup>								
		1C99h		1D19h	ADCNT	1D9Ch	RCOPPS <sup>(2)</sup>								
		1C9Ah	CRCDATAL	1D13H	ADRPT	1D9Ch	RC1PPS <sup>(2)</sup>								Unimplemented
		1C9Bh	CRCDATAL	1D1Bh	ADREVL	1D9Eh	RC2PPS <sup>(2)</sup>								Read as '0'
		1C9Ch	CRCDATAU	1D1Ch	ADPREVH	1D9Eh	RC3PPS <sup>(2)</sup>								
		1C9Dh	CRCDATAT	1D1Dh	ADRESL	1DA0h	RC4PPS <sup>(2)</sup>								
		1C9Eh	CRCOUTL	1D1Eh	ADRESH	1DA1h	RC5PPS <sup>(2)</sup>								
	Unimplemented	1C9Fh	CRCOUTH	1D1Fh	ADRESH	1DA111	RC6PPS <sup>(1)</sup>		Con Table 2 for		See Table 3 for				
	Read as '0'	1CA0h	CRCOUTU	1D20h	ADNCH	1DA3h	RC6PPS <sup>(1)</sup>		See Table 2 for register mapping		register mapping				
	neau as u	1CA1h	CRCOUTT	1D21h	ADACQL	1DA3II	RC/PPS17		details		details		Unimplemented		
		1CA1h	CRCCONO	1D21h	ADACQL	1DA4fi			details				Read as '0'		
		1CA3h	CRCCON1	1D23h	ADCAP										
		1CA4h	CRCCON2	1D24h	ADPREL										
		1CA5h		1D25h	ADPREH										
				1D26h	ADCON0										
				1D27h	ADCON1										
				1D28h	ADCON2										
				1D29h	ADCON3									1FE3h	
				1D2Ah 1D2Bh	ADSTAT		Unimplemented							1FE4h	STATUS_SHAD
				1D2Bh	ADREF ADACT		Read as '0'							1FE5h 1FE6h	WREG_SHAD BSR_SHAD
			Unimplemented	1DCDh	ADCLK									1FE7h	PCLATH SHAD
			Read as '0'	1D2Eh	ADCG1A									1FE8h	FSROL_SHAD
				1D2Fh	ADCG1B <sup>(1)</sup>									1FE9h	FSROH SHAD
				1D30h	ADCG1C <sup>(2)</sup>									1FEAh	FSR1L SHAD
				1D31h										1FEBh	FSR1H_SHAD
					Unimplemented									1FECh	_
					Read as '0'									1FEDh	STKPTR
					neau as 0									1FEEh	TOSL
1C6Fh		1CEFh		1D6Fh		1DEFh		1E6Fh		1EEFh		1F6Fh		1FEFh	TOSH
1C70h	Common RAM (Accesses	1CF0h	Common RAM (Accesses	1D70h	Common RAM (Accesses	1DF0h	Common RAM (Accesses	1E70h	Common RAM (Accesses	1EF0h	Common RAM (Accesses	1F70h	Common RAM (Accesses	1FF0h	Common RAM (Accesses
1C7Fh	70h-7Fh)	1CFFh	70h-7Fh)	1D7Fh	70h-7Fh)	1DFFh	70h-7Fh)	1E7Fh	70h-7Fh)	1EFFh	70h-7Fh)	1F7Fh	70h-7Fh)	1FFFh	70h-7Fh)
		[	///	/[											

1. 20-pin devices only 2. 14/16/20-pin devices only

Figure 9-12. Memory Map Bank 61

# **BANK 60**

	DAINK OU		
1E00h		1E3Dh	CLCINOPPS
	Core Registers	1E3Eh	CLCIN1PPS
1E0Bh		1E3Fh	CLCIN2PPS
1E0Ch	PPSLOCK	1E40h	CLCIN3PPS
1E0Dh	INTPPS	1E41h	RX1PPS
1E0Eh	TOCKIPPS	1E42h	CK1PPS
1E0Fh	T1CKIPPS	1E43h	RX2PPS
1E10h	T1GPPS	1E44h	CK2PPS
1E11h	T3CKIPPS	1E45h	_
1E12h	T3GPPS	1E46h	_
1E13h	Unimplemented	1E47h	SSP1CLKPPS
	Read as '0'	1E48h	SSP1DATPPS
1E18h	Redu ds U	1E49h	SSP1SSPPS
1E19h	T2INPPS	1E4Ah	SSP2CLKPPS
1E1Ah	T4INPPS	1E4Bh	SSP2DATPPS
1E1Bh	T6INPPS	1E4Ch	SSP2SSPPS
1E1Ch		1E4Dh	Unimplemented
1E1Dh			Read as '0'
1E1Eh	CCP1PPS	1E4Fh	Neau as U
1E1Fh	CCP2PPS	1E50h	ADACTPPS
1E20h	Unimplemented	1E51h	Unimplemented
	Read as '0'		Read as '0'
1E38h	Neau as U	1E6Fh	ineau as U
1E39h	CWG1PPS	1E70h	Common RAM
1E3Ah	Unimplemented		(Accesses 70h-7Fh
	Read as '0'	1E7Fh	(Accesses /UII-/FII
1E3Ch	Neau as U		

Legend:

Figure 9-13. Memory Map Bank 62

## **BANK 61**

_	DAINKUI		
1E80h		1EA3h	SLRCONC <sup>(2)</sup>
	Core registers	1EA4h	INLVLC <sup>(2)</sup>
1E8Bh		1EA5h	IOCCP <sup>(2)</sup>
1E8Ch	ANSELA	1EA6h	IOCCN <sup>(2)</sup>
1E8Dh	WPUA	1EA7h	IOCCF <sup>(2)</sup>
1E8Eh	ODCONA	1EA8h	Unimplemented
1E8Fh	SLRCONA		Read as '0'
1E90h	INLVLA	1EE0h	
1E91h	IOCAP	1EE1h	RA1I2C <sup>(3)</sup>
1E92h	IOCAN	1EE2h	RA2I2C <sup>(3)</sup>
1E93h	IOCAF	1EE3h	_
1E94h	_	1EE4h	_
1E95h	_	1EE5h	RB4I2C <sup>(1)</sup>
1E96h	ANSELB <sup>(1)</sup>	1EE6h	RB5I2C <sup>(1)</sup>
1E97h	WPUB <sup>(1)</sup>	1EE7h	RB6I2C <sup>(1)</sup>
1E98h	ODCONB <sup>(1)</sup>	1EE8h	RB7I2C <sup>(1)</sup>
1E99h	SLRCONB <sup>(1)</sup>	1EE9h	RC0I2C <sup>(4)</sup>
1E9Ah	INLVLB <sup>(1)</sup>	1EEAh	RC1I2C <sup>(4)</sup>
1E9Bh	IOCBP <sup>(1)</sup>	1EEBh	_
1E9Ch	IOCBN <sup>(1)</sup>	1EECh	RC4I2C <sup>(4)</sup>
1E9Dh	IOCBF <sup>(1)</sup>	1EEDh	RC5I2C <sup>(4)</sup>
1E9Eh	_	1EEEh	_
1E9Fh	_	1EEFh	_
1EA0h	ANSELC <sup>(2)</sup>	1EF0h	Common RAM
1EA1h	WPUC <sup>(2)</sup>		(Accesses
1EA2h	ODCONC <sup>(2)</sup>	1EFFh	70h-7Fh)

Note: 1. 20-pin devices only

2. 14/16/20-pin devices only

3. PIC16F18015 only

4. PIC16F18025 only

## Legend:

Unimplemented data memory locations, read as '0'

# 9.3 STATUS Register

The STATUS register contains:

- · the arithmetic status of the ALU
- · the Reset status

The STATUS register can be the destination for any instruction, like any other register. If the STATUS register is the destination for an instruction that affects the Z, DC or C bits, then writes to these three bits are disabled. These bits

are set or cleared according to the device logic. Furthermore, the  $\overline{\text{TO}}$  and  $\overline{\text{PD}}$  bits are not writable. Therefore, the result of an instruction with the STATUS register as destination may be different than intended.

For example, CLRF STATUS will clear bits [4:3] and [1:0], and set the Z bit. This leaves the STATUS register as '000u uluu' (where u = unchanged).

It is recommended, therefore, that only BCF, BSF, SWAPF and MOVWF instructions are used to alter the STATUS register, because these instructions do not affect any Status bits. For other instructions not affecting any Status bits, refer to the "Instruction Set Summary" chapter.




Important: The C and DC bits operate as Borrow and Digit Borrow out bits, respectively, in subtraction.

## 9.4 PCL and PCLATH

The Program Counter (PC) is 15 bits wide. The low byte comes from the PCL register, which is a readable and writable register. The high byte (PC[14:8]) is not directly readable or writable and comes from PCLATH. On any Reset, the PC is cleared. Loading of PC in Different Situations shows the five situations for the loading of the PC.

Figure 9-14. Loading of PC in Different Situations



## 9.4.1 Modifying PCL

Executing any instruction with the PCL register as the destination simultaneously causes the Program Counter PC[14:8] bits (PCH) to be replaced by the contents of the PCLATH register. This allows the entire contents of the Program Counter to be changed by writing the desired upper seven bits to the PCLATH register. When the lower

eight bits are written to the PCL register, all 15 bits of the Program Counter will change to the values contained in the PCLATH register and those being written to the PCL register.

### 9.4.2 Computed GOTO

A computed GOTO is accomplished by adding an offset to the Program Counter (ADDWF PCL). When performing a table read using a computed GOTO method, care has to be exercised if the table location crosses a PCL memory boundary (each 256-byte block). Refer to application note *AN556*, "Implementing a Table Read" (DS00556).

### 9.4.3 Computed Function Calls

A computed function CALL allows programs to maintain tables of functions and provide another way to execute state machines or Look-up Tables. When performing a table read using a computed function CALL, care has to be exercised if the table location crosses a PCL memory boundary (each 256-byte block).

If using the CALL instruction, the PCH[2:0] and PCL registers are loaded with the operand of the CALL instruction. PCH[6:3] is loaded with PCLATH[6:3].

The CALLW instruction enables computed calls by combining PCLATH and W to form the destination address. A computed CALLW is accomplished by loading the W register with the desired address and executing CALLW. The PCL register is loaded with the value of W and PCH is loaded with PCLATH.

## 9.4.4 Branching

The branching instructions add an offset to the PC. This allows relocatable code and code that crosses page boundaries. There are two forms of branching, BRW and BRA. The PC will have incremented to fetch the next instruction in both cases. When using either branching instruction, a PCL memory boundary may be crossed.

If using BRW, load the W register with the desired unsigned address and execute BRW. The entire PC will be loaded with the address PC + 1 + W.

If using BRA, the entire PC will be loaded with PC + 1 + the signed value of the operand of the BRA instruction.

### 9.5 Stack

All devices have a 16-level by 15-bit wide hardware stack. The stack space is not part of either program or data space. The PC is PUSHed onto the stack when the CALL or CALLW instructions are executed or an interrupt causes a branch. The stack is POPed in the event of a RETURN, RETLW or a RETFIE instruction execution. PCLATH is not affected by a PUSH or POP operation.

The stack operates as a circular buffer if the STVREN Configuration bit is programmed to '0'. This means that after the stack has been PUSHed sixteen times, the seventeenth PUSH overwrites the value that was stored from the first PUSH. The eighteenth PUSH overwrites the second PUSH, and so on. The STKOVF and STKUNF flag bits will be set on an Overflow/Underflow, regardless of whether the Reset is enabled.

If the STVREN bit is programmed to '1', the device will be reset if the stack is PUSHed beyond the sixteenth level or POPed beyond the fist level, setting the appropriate bits (STKOVF or STKUNF, respectively).



**Important:** There are no instructions/mnemonics called PUSH or POP. These are actions that occur from the execution of the CALL, CALLW, RETURN, RETLW and RETFIE instructions or the vectoring to an interrupt address.

### 9.5.1 Accessing the Stack

The stack is accessible through the TOSH, TOSL and STKPTR registers. STKPTR is the current value of the Stack Pointer. The TOSH:TOSL register pair points to the TOP of the stack. Both registers are read/writable. TOS is split into TOSH and TOSL due to the 15-bit size of the PC. To access the stack, adjust the value of STKPTR, which will position TOSH:TOSL, then read/write to TOSH:TOSL. STKPTR also allows the detection of Overflow and Underflow condition.

## PIC16F18015/25/44/45

## **Memory Organization**



Important: Care must be taken when modifying STKPTR while interrupts are enabled.

During normal program operation, CALL, CALLW and interrupts will increment STKPTR, while RETLW, RETURN and RETFIE will decrement STKPTR. STKPTR can be monitored to obtain the value of stack memory left at any given time. STKPTR always points at the currently used place on the stack. Therefore, a CALLW will increment STKPTR and then write the PC, and a return will unload the PC value from the stack and then decrement STKPTR.

Reference the following figures for examples of accessing the stack.

Figure 9-15. Accessing the Stack Example 1

Stack Reset Disabled TOSH:TOSL 0x0F STKPTR = 0x1F (STVREN = 0) 0x0E 0x0D 0x0C 0x0B Initial Stack Configuration: 0x0A After Reset, the stack is empty. The 0x09 empty stack is initialized so the Stack 0x08 Pointer is pointing at 0x1F. If the Stack Overflow/Underflow Reset is enabled, the 0x07 TOSH/TOSL register will return '0'. If the 0x06 Stack Overflow/Underflow Reset is disabled, the TOSH/TOSL register will 0x05 return the contents of stack address 0x04 0x0F. 0x03 0x02 0x01 0x00 Stack Reset Enabled STKPTR = 0x1F TOSH:TOSL 0x1F 0x0000 (STVREN = 1)

Figure 9-16. Accessing the Stack Example 2

Rev. 10-000043B




Figure 9-17. Accessing the Stack Example 3

Rev. 10-000043C 7/30/2013





Figure 9-18. Accessing the Stack Example 4

Rev. 10-000043D 7/30/2013



### 9.5.2 Overflow/Underflow Reset

If the STVREN bit is programmed to '1', the device will be reset if the stack is PUSHed beyond the sixteenth level or POPed beyond the first level, setting the appropriate bits (STKOVF or STKUNF, respectively).


## 9.6 Indirect Addressing

The INDFn registers are not physical registers. Any instruction that accesses an INDFn register actually accesses the register at the address specified by the File Select Registers (FSR). If the FSRn address specifies one of the two INDFn registers, the read will return '0' and the write will not occur (though Status bits may be affected). The FSRn register value is created by the pair FSRnH and FSRnL.

The FSR registers form a 16-bit address that allows an addressing space with 65536 locations. These locations are divided into three memory regions:

- · Traditional/Banked Data Memory
- · Linear Data Memory
- · Program Flash Memory


Figure 9-19. Indirect Addressing



## 9.6.1 Traditional/Banked Data Memory

The traditional or banked data memory is a region from FSR address 0x0000 to FSR address 0x1FFF. The addresses correspond to the absolute addresses of all SFR, GPR and common registers.


Figure 9-20. Traditional/Banked Data Memory Map



## 9.6.2 Linear Data Memory

The linear data memory is the region from FSR address 0x2000 to FSR address 0x2FEF. This region is a virtual region that points back to the 80-byte blocks of GPR memory in all the banks. Refer to Figure 9-21 for the Linear Data Memory Map.

Figure 9-21. Linear Data Memory Map





**Important:** The address range 0x2000 to 0x2FEF represents the complete addressable Linear Data Memory for PIC<sup>®</sup> devices (up to Bank 50). The actual implemented Linear Data Memory will differ from one device to the other in a family.


Unimplemented memory reads as 0x00. Use of the linear data memory region allows buffers to be larger than 80 bytes because incrementing the FSR beyond one bank will go directly to the GPR memory of the next bank.

The 16 bytes of common memory are not included in the linear data memory region.

## 9.6.3 Program Flash Memory

To make constant data access easier, the entire Program Flash Memory is mapped to the upper half of the FSR address space. When the MSB of FSRnH is set, the lower 15 bits are the address in program memory which will be accessed through INDF. Only the lower eight bits of each memory location are accessible via INDF. Writing to the Program Flash Memory cannot be accomplished via the FSR/INDF interface. All instructions that access Program Flash Memory via the FSR/INDF interface will require one additional instruction cycle to complete.

Figure 9-22. Program Flash Memory Map



## 9.6.4 Data EEPROM Memory

The EEPROM memory can be read or written through the NVMCON register interface. However, to make access to the EEPROM easier, read-only access to the EEPROM contents are also available through indirect addressing via an FSR. When the MSP of the FSR (ex: FSRxH) is set to 0x70, the lower 8-bit address value (in FSRxL) determines the EEPROM location that may be read via the INDF register). In other words, the EEPROM address range 0x00-0xFF is mapped into the FSR address space between 0x7000 and 0x70FF. Writing to the EEPROM cannot be accomplished via the FSR/INDF interface. Reads from the EEPROM through the FSR/INDF interface will require one additional instruction cycle to complete.

# 9.7 Register Definitions: Memory Organization

# PIC16F18015/25/44/45

# **Memory Organization**

## 9.7.1 INDF0

Name: INDF0 Offset: 0x0000

Indirect Data Register. This is a virtual register. The GPR/SFR register addressed by the FSR0 register is the target for all operations involving the INDF0 register.

Bit	7	6	5	4	3	2	1	0
[				INDF	0[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

## Bits 7:0 - INDF0[7:0]

Indirect data pointed to by the FSR0 register

# PIC16F18015/25/44/45

# **Memory Organization**

## 9.7.2 INDF1

Name: INDF1 Offset: 0x0001

Indirect Data Register. This is a virtual register. The GPR/SFR register addressed by the FSR1 register is the target for all operations involving the INDF1 register.

Bit	7	6	5	4	3	2	1	0
[				INDF	1[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0


## Bits 7:0 - INDF1[7:0]

Indirect data pointed to by the FSR1 register

## 9.7.3 PCL

Name: PCL Offset: 0x0002

Low byte of the Program Counter



Bits 7:0 - PCL[7:0]

Provides direct read and write access to the Program Counter

## 9.7.4 STATUS

Name: STATUS Offset: 0x0003

Status Register

Bit	7	6	5	4	3	2	1	0
				TO	PD	Z	DC	С
Access		•	•	R	R	R/W	R/W	R/W
Reset				1	1	0	0	0

## Bit 4 - TO Time-Out

Reset States: POR/BOR = 1

All Other Resets = q

	7 III O 11101 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
Value	Description
1	Set at power-up or by execution of CLRWDT or SLEEP instruction
0	A WDT time-out occurred

## Bit 3 – PD Power-Down

Reset States: POR/BOR = 1

All Other Resets = q

Value	Description
1	Set at power-up or by execution of CLRWDT instruction
0	Cleared by execution of the SLEEP instruction

### Bit 2 - Z Zero

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	The result of an arithmetic or logic operation is zero
0	The result of an arithmetic or logic operation is not zero

## Bit 1 – DC Digit Carry/Borrow<sup>(1)</sup>

ADDWF, ADDLW, SUBLW, SUBWF instructions

Reset States: POR/BOR = 0

All Other Resets = u

	7 th Other redeta to
Value	Description
1	A carry-out from the 4th low-order bit of the result occurred
0	No carry-out from the 4th low-order bit of the result

## Bit 0 - C Carry/Borrow(1)

ADDWF, ADDLW, SUBLW, SUBWF instructions

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	A carry-out from the Most Significant bit of the result occurred
0	No carry-out from the Most Significant bit of the result occurred

## Note:


1. For Borrow, the polarity is reversed. A subtraction is executed by adding the two's complement of the second operand. For Rotate (RRCF, RLCF) instructions, this bit is loaded with either the high or low-order bit of the Source register.

## 9.7.5 FSR0

Name: FSR0 Offset: 0x0004

Indirect Address Register

The FSR0 value is the address of the data to which the INDF0 register points.



Bits 15:0 - FSR0[15:0] Address of INDF0 data

**Notes:** The individual bytes in this multibyte register can be accessed with the following register names:

- 1. FSR0H: Accesses the high byte FSR0[15:8].
- 2. FSR0L: Accesses the low byte FSR0[7:0].

## 9.7.6 FSR1

Name: FSR1 Offset: 0x0006 Indirect Address Register

The FSR1 value is the address of the data to which the INDF1 register points.

Bit	15	14	13	12	11	10	9	8
				FSR1	[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
	FSR1[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

### Bits 15:0 - FSR1[15:0] Address of INDF1 data

**Notes:** The individual bytes in this multibyte register can be accessed with the following register names:

- 1. FSR1H: Accesses the high byte FSR1[15:8].
- 2. FSR1L: Accesses the low byte FSR1[7:0].

# PIC16F18015/25/44/45


# **Memory Organization**

## 9.7.7 BSR

Name: BSR Offset: 0x0008

## Bank Select Register

The BSR indicates the data memory bank by writing the bank number into the register. All data memory can be accessed directly via instructions, or indirectly via FSRs.



## Bits 5:0 - BSR[5:0]

Six Most Significant bits of the data memory address

## 9.7.8 WREG

Name: WREG Ox0009

Working Data Register

Bit	7	6	5	4	3	2	1	0
[				WRE	G[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - WREG[7:0]

## 9.7.9 PCLATH

Name: PCLATH Offset: 0x000A

**Program Counter Latches** 

Write Buffer for the upper seven bits of the Program Counter

Bit	7	6	5	4	3	2	1	0
			PCLATH[6:0]					
Access		R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset		0	0	0	0	0	0	0

**Bits 6:0 – PCLATH[6:0]** High PC Latch Register Holding register for Program Counter bits [6:0]

# 9.8 Register Summary - Memory Organization

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00	INDF0	7:0		INDF0[7:0]						
0x01	INDF1	7:0		INDF1[7:0]						
0x02	PCL	7:0		PCL[7:0]						
0x03	STATUS	7:0				TO	PD	Z	DC	С
0x04	FSR0	7:0	FSR0[7:0]							
0004		15:8		FSR0[15:8]						
0x06	FSR1	7:0		FSR1[7:0]						
UXUG	FORT	15:8	FSR1[15:8]							
0x08	BSR	7:0	BSR[5:0]							
0x09	WREG	7:0	WREG[7:0]							
0x0A	PCLATH	7:0	PCLATH[6:0]							

## 10. Resets


There are multiple ways to reset this device:

- Power-on Reset (POR)
- · Brown-out Reset (BOR)
- MCLR Reset
- WDT Reset
- RESET instruction
- Stack Overflow
- · Stack Underflow
- · Programming mode exit

To allow  $V_{DD}$  to stabilize, an optional Power-up Timer can be enabled to extend the Reset time after a BOR or POR event.

A simplified block diagram of the On-Chip Reset Circuit is shown in Figure 10-1.

Figure 10-1. Simplified Block Diagram of On-Chip Reset Circuit



# 10.1 Power-on Reset (POR)

The POR circuit holds the device in Reset until  $V_{DD}$  has reached an acceptable level for minimum operation. Slow rising  $V_{DD}$ , fast operating speeds or analog performance may require greater than minimum  $V_{DD}$ . The PWRT, BOR or  $\overline{MCLR}$  features can be used to extend the start-up period until all device operation conditions have been met.

### 10.1.1 Programming Mode Exit

Upon exit of Programming mode, the device will behave as if a POR had just occurred.

## 10.2 Brown-out Reset (BOR)

The BOR circuit holds the device in Reset when  $V_{DD}$  reaches a selectable minimum level. Between the POR and BOR, complete voltage range coverage for execution protection can be implemented.

The Brown-out Reset module has four operating modes controlled by the BOREN bits. The four operating modes are:

- · BOR is always on
- · BOR is off when in Sleep
- · BOR is controlled by software
- · BOR is always off

Refer to Table 10-1 for more information.

The Brown-out Reset voltage level is selectable by configuring the BORV bits.

A  $V_{DD}$  noise rejection filter prevents the BOR from triggering on small events. If  $V_{DD}$  falls below  $V_{BOR}$  for a duration greater than parameter  $T_{BORDC}$ , the device will reset and the  $\overline{BOR}$  bit will be cleared, indicating the Brown-out Reset condition occurred. See Figure 10-2.

## 10.2.1 BOR is Always On

When the BOREN bits are programmed to '11', the BOR is always on. The device start-up will be delayed until the BOR is ready and  $V_{DD}$  is higher than the BOR threshold.

BOR protection is active during Sleep. The BOR does not delay wake-up from Sleep.

### 10.2.2 BOR Is Off in Sleep

When the BOREN bits are programmed to '10', the BOR is on, except in Sleep. BOR protection is not active during Sleep, but device wake-up will be delayed until the BOR can determine that  $V_{DD}$  is higher than the BOR threshold. The device wake-up will be delayed until the BOR is ready.

## 10.2.3 BOR Controlled by Software

When the BOREN bits of Configuration Words are programmed to '01', the BOR is controlled by the SBOREN bit. The device start-up is not delayed by the BOR Ready condition or the  $V_{DD}$  level.

BOR protection begins as soon as the BOR circuit is ready. The status of the BOR circuit is reflected in the BORRDY bit.

BOR protection is unchanged by Sleep.


Table 10-1. BOR Operating Modes

				Instruction Execution upon:			
BOREN	SBOREN	Device Mode	BOR Mode	Release of POR	Wake-up from Sleep		
11(1)	X	Х	Active	Wait for release of BOR (BORRDY = 1)	Begins immediately		
	Awake		Active	Wait for release of BOR (BORRDY = 1)	N/A		
10	X	Sleep	Hibernate	N/A	Wait for release of BOR (BORRDY = 1)		
01	1	Х	Active	Wait for release of BOR	Begins		
01	0 X Hibernate		(BORRDY = 1)	immediately			
00	X	Х	Disabled	Begins imme	diately		

#### Note:

1. In this specific case, 'Release of POR' and 'Wake-up from Sleep', there is no delay in start-up. The BOR Ready flag (BORRDY = 1) will be set before the CPU is ready to execute instructions because the BOR circuit is forced on by the BOREN bits.

Figure 10-2. Brown-Out Situations



**Note:**  $T_{PWRT}$  delay when the PWRTS bits are enabled ( $\overline{PWRTS} = 00$ ).

### 10.2.4 BOR Is Always Off

When the BOREN bits are programmed to '00', the BOR is always disabled. In the configuration, setting the SBOREN bit will have no affect on BOR operations.

## 10.3 MCLR Reset

The MCLR is an optional external input that can reset the device. The MCLR function is controlled by the MCLRE bit and the LVP bit (see Table 10-2). The RMCLR bit will be set to '0' if a MCLR has occurred.

Table 10-2. MCLR Configuration

MCLRE	LVP	MCLR
х	1	Enabled
1	0	Enabled
0	0	Disabled

### 10.3.1 MCLR Enabled

When  $\overline{MCLR}$  is enabled and the pin is held low, the device is held in Reset. The  $\overline{MCLR}$  pin is connected to  $V_{DD}$  through an internal weak pull-up.

The device has a noise filter in the MCLR Reset path. The filter will detect and ignore small pulses.



**Important:** An internal Reset event (RESET instruction, BOR, WDT, POR, STKOVF, STKUNF) does not drive the MCLR pin low.

#### 10.3.2 MCLR Disabled

When MCLR is disabled, the MCLR becomes input-only and pin functions such as internal weak pull-ups are under software control.

# 10.4 Watchdog Timer (WDT) Reset

The Watchdog Timer generates a Reset if the firmware does not issue a CLRWDT instruction within the time-out period. The TO, PD and RWDT bits are changed to indicate a WDT Reset caused by the timer overflowing.

## 10.5 RESET Instruction

A RESET instruction will cause a device Reset. The  $\overline{RI}$  bit will be set to '0'. See Table 10-4 for default conditions after a RESET instruction has occurred.

#### 10.6 Stack Overflow/Underflow Reset

The device can reset when the Stack Overflows or Underflows. The STKOVF or STKUNF bits indicate the Reset condition. These Resets are enabled by setting the STVREN bit.

# 10.7 Power-Up Timer (PWRT)

The Power-up Timer provides up to a 64 ms time-out period on POR or BOR. The device is held in Reset as long as PWRT is active. The PWRT delay allows additional time for the  $V_{\rm DD}$  to rise to an acceptable level.

The Power-up Timer is controlled by the PWRTS bits. The Power-up Timer starts after the release of the POR and BOR. For additional information, refer to the "Power-up Trouble Shooting" Application Note AN607.


## 10.8 Start-Up Sequence

Upon the release of a POR or BOR, the following must occur before the device will begin executing:

- 1. Power-up Timer runs to completion (if enabled).
- 2. MCLR must be released (if enabled).

The Power-up Timer runs independently of MCLR Reset. If MCLR is kept low long enough, the Power-up Timer will expire. Upon bringing MCLR high, the device will begin execution after 10 F<sub>OSC</sub> cycles (see Figure 10-3). This is useful for testing purposes or for synchronizing more than one device operating in parallel.

Figure 10-3. Reset Start-Up Sequence



#### Note:

1. Code execution begins 10 F<sub>OSC</sub> cycles after the F<sub>OSC</sub> clock is released.

# 10.9 Memory Execution Violation

A memory execution violation Reset occurs if executing an instruction being fetched from outside the valid execution area. The invalid execution areas are:

- Addresses outside implemented program memory. Refer to the "Memory Organization" chapter for details about available Flash size.
- 2. Storage Area Flash (SAF) inside program memory, if enabled.

When a memory execution violation is generated, the device is reset and the MEMV bit is cleared to signal the cause of the Reset. The MEMV bit must be set in the user code after a memory execution violation Reset has occurred to detect further violation Resets.

## 10.10 Determining the Cause of a Reset

Upon any Reset, multiple bits in the STATUS, PCON0 and PCON1 registers are updated to indicate the cause of the Reset. The following tables show the Reset conditions of these registers.

Table 10-3. Reset Status Bits and Their Significance

STKOVF	STKUNF	RWDT	RMCLR	RI	POR	BOR	TO	PD	MEMV	Condition
0	0	1	1	1	0	Х	1	1	1	Power-on Reset
0	0	1	1	1	0	х	0	х	u	Illegal, TO is set on POR
0	0	1	1	1	0	Х	Х	0	u	Illegal, PD is set on POR

con	tinued									
STKOVF	STKUNF	RWDT	RMCLR	RI	POR	BOR	TO	PD	MEMV	Condition
0	0	u	1	1	u	0	1	1	u	Brown-out Reset
u	u	0	u	u	u	u	0	u	u	WDT Reset
u	u	u	u	u	u	u	0	0	u	WDT Wake-up from Sleep
u	u	u	u	u	u	u	1	0	u	Interrupt Wake-up from Sleep
u	u	u	0	u	u	u	u	u	1	MCLR Reset during normal operation
u	u	u	0	u	u	u	1	0	u	MCLR Reset during Sleep
u	u	u	u	0	u	u	u	u	u	RESET Instruction Executed
1	u	u	u	u	u	u	u	u	u	Stack Overflow Reset (STVREN = 1)
u	1	u	u	u	u	u	u	u	u	Stack Underflow Reset (STVREN = 1)
u	u	u	u	u	u	u	u	u	0	Memory Violation Reset

Table 10-4. Reset Conditions for Special Registers

Condition	Program Counter	STATUS Register	PCON0 Register	PCON1 Register
Power-on Reset	0	1 1000	0011 110x	1-
Brown-out Reset	0	1 1000	0011 11u0	u-
MCLR Reset during normal operation	0	-uuu uuuu	uuuu Ouuu	1-
MCLR Reset during Sleep	0	1 Ouuu	uuuu Ouuu	u-
WDT Time-out Reset	0	0 uuuu	uuu0 uuuu	u-
WDT Wake-up from Sleep	PC + 1	0 Ouuu	uuuu uuuu	u-
Interrupt Wake-up from Sleep	PC + 1 <sup>(1)</sup>	1 Ouuu	uuuu uuuu	u-
RESET Instruction Executed	0	u uuuu	uuuu u0uu	u-
Stack Overflow Reset (STVREN = 1)	0	u uuuu	1uuu uuuu	u-
Stack Underflow Reset (STVREN = 1)	0	u uuuu	u1uu uuuu	u-
Memory Violation Reset	0	-uuu uuuu	uuuu uuuu	0-

**Legend:** u = unchanged, x = unknown, — = unimplemented bit, reads as '0'.

#### Note:

1. When the wake-up is due to an interrupt and Global Interrupt Enable (GIE) bit is set, the return address is pushed on the stack and PC is loaded with the interrupt vector (0004h) after execution of PC + 1.

# 10.11 Power Control (PCONx) Register

The Power Control (PCONx) registers contain flag bits to differentiate between a:

- Brown-out Reset (BOR)
- Power-on Reset (POR)
- RESET Instruction Reset (RI)
- MCLR Reset (RMCLR)
- Watchdog Timer Reset (RWDT)
- Stack Underflow Reset (STKUNF)
- Stack Overflow Reset (STKOVF)
- Memory Violation Reset (MEMV)

Hardware will change the corresponding register bit during the Reset process; if the Reset was not caused by the condition, the bit remains unchanged.

Software may reset the bit to the Inactive state after restart (hardware will not reset the bit).

Software may also set any PCONx bit to the Active state, so that user code may be tested, but no Reset action will be generated.

# 10.12 Register Definitions: Power Control

## 10.12.1 BORCON

Name: BORCON Offset: 0x018D

Brown-out Reset Control Register



# Bit 7 - SBOREN Software Brown-Out Reset Enable

Reset States: POR/BOR = 1

All Other Resets = u

Value	Condition	Description
_	If BOREN ≠ 01	SBOREN is read/write, but has no effect on the BOR
1	If BOREN = 01	BOR Enabled
0	If BOREN = 01	BOR Disabled

# Bit 0 - BORRDY Brown-Out Reset Circuit Ready Status

Reset States: POR/BOR = q

All Other Resets = u

Value	Description
1	The Brown-out Reset circuit is active and armed
0	The Brown-out Reset circuit is disabled or is warming up

## 10,12,2 PCON0

Name: PCON0 Offset: 0x018E

Power Control Register 0

Bit	7	6	5	4	3	2	1	0
[	STKOVF	STKUNF		RWDT	RMCLR	RI	POR	BOR
Access	R/W/HS	R/W/HS	•	R/W/HC	R/W/HC	R/W/HC	R/W/HC	R/W/HC
Reset	0	0		1	1	1	0	q

# Bit 7 - STKOVF Stack Overflow Flag

Reset States: POR/BOR = 0

All Other Resets = q

Value	Description
1	A Stack Overflow occurred (more CALLs than fit on the stack)
0	A Stack Overflow has not occurred or set to '0' by firmware

#### Bit 6 - STKUNF Stack Underflow Flag

Reset States: POR/BOR = 0

All Other Resets = q

Value	Description
1	A Stack Underflow occurred (more RETURNS than CALLS)
0	A Stack Underflow has not occurred or set to '0' by firmware

# Bit 4 – RWDT WDT Reset Flag

Reset States: POR/BOR = 1

All Other Resets = q

	7 111 0 11101 1100010 0
Value	Description
1	A WDT Overflow/Time-out Reset has not occurred or set to '1' by firmware
0	A WDT Overflow/Time-out Reset has occurred (set to '0' in hardware when a WDT Reset occurs)

## Bit 3 - RMCLR MCLR Reset Flag

Reset States: POR/BOR = 1

All Other Resets = a

	7 til Othor (Coote q
Value	Description
1	A MCLR Reset has not occurred or set to '1' by firmware
0	A MCLR Reset has occurred (set to '0' in hardware when a MCLR Reset occurs)

## Bit 2 - RI RESET Instruction Flag

Reset States: POR/BOR = 1

All Other Resets = q

Value	Description
1	A RESET instruction has not been executed or set to '1' by firmware
0	A RESET instruction has been executed (set to '0' in hardware upon executing a RESET instruction)

# Bit 1 - POR Power-on Reset Status

Reset States: POR/BOR = 0

All Other Resets = u

	Value	Description
	1	No Power-on Reset occurred or set to '1' by firmware
Ī	0	A Power-on Reset occurred (set to '0' in hardware when a Power-on Reset occurs)

## Bit 0 - BOR Brown-out Reset Status

Reset States: POR/BOR = q

# PIC16F18015/25/44/45


Resets

	All Other Resets = u
Value	Description
1	No Brown-out Reset occurred or set to '1' by firmware
0	A Brown-out Reset occurred (set to '0' in hardware when a Brown-out Reset occurs)

# 10.12.3 PCON1

Name: PCON1 Offset: 0x018F

Power Control Register 1



Bit 1 – MEMV Memory Violation Flag

Reset States: POR/BOR = 1

All Other Resets = u

Value	Description
1	No Memory Violation Reset occurred or set to '1' by firmware
0	A Memory Violation Reset occurred (set to '0' in hardware when a Memory Violation occurs)

# 10.13 Register Summary - Power Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x018C										
0x018D	BORCON	7:0	SBOREN							BORRDY
0x018E	PCON0	7:0	STKOVF	STKUNF		RWDT	RMCLR	RI	POR	BOR
0x018F	PCON1	7:0							MEMV	

# 11. OSC - Oscillator Module

The oscillator module contains multiple clock sources and selection features that allow it to be used in a wide range of applications while maximizing performance and minimizing power consumption.

Clock sources can be supplied either internally or externally. External sources include:

- · External clock oscillators
- Secondary Oscillator (SOSC)

#### Internal sources include:

- High-Frequency Internal Oscillator (HFINTOSC)
- Low-Frequency Internal Oscillator (LFINTOSC)
- · Analog-to-Digital Converter RC Oscillator (ADCRC)

Special features of the oscillator module include:

- Oscillator Start-up Timer (OST): Ensures stability of the Secondary Oscillator's 32.768 kHz crystal oscillator.
- HFINTOSC Frequency Adjustment: Provides the ability to adjust the HFINTOSC frequency.

The Reset Oscillator (RSTOSC) Configuration bits determine the type of oscillator that will be used when the device runs after a Reset, including when the device is first powered up (see the table below).

Table 11-1. RSTOSC Selection Table

RSTOSC	SF	R Reset Values	Clock Source			
K3103C	cosc	OSCFRQ	Glock Source			
111	111		EXTOSC per FEXTOSC			
110	110	000 <b>(1 MHz)</b>	HFINTOSC @ 1 MHz			
101	101	000 <b>(1 MHz)</b>	LFINTOSC			
100	100		SOSC			
011	011	Reserved				
010	010	Reserved				
001	011	Reserved				
000	000	101 (32 MHz) HFINTOSC @ 32 MHz				

If an external clock source is selected by the RSTOSC bits, the External Oscillator Mode Select (FEXTOSC) Configuration bits must be used to select the External Clock mode. These modes include:

- · ECL: External Clock Low Power mode
- · ECH: External Clock High Power mode

The ECH and ECL modes rely on an external logic-level signal as the device clock source. Each mode is optimized for a specific frequency range. The internal oscillator block produces both low-frequency and high-frequency clock signals, designated LFINTOSC and HFINTOSC, respectively. Multiple system operating frequencies may be derived from these clock sources.

The figure below illustrates a block diagram of the oscillator module.




Figure 11-1. Clock Source Block Diagram

# 11.1 Clock Source Types

Clock sources can be classified as external or internal.

External clock sources rely on external circuitry for the clock source to function, such as digital oscillator modules.

Internal clock sources are contained within the oscillator module. The internal oscillator block features two internal oscillators that are used to generate internal system clock sources. The High-Frequency Internal Oscillator (HFINTOSC) can produce a wide range of frequencies which are determined via the HFINTOSC Frequency Selection (OSCFRQ) register. The Low-Frequency Internal Oscillator (LFINTOSC) generates a fixed nominal 31 kHz clock signal. The internal oscillator block also features an RC oscillator which is dedicated to the Analog-to-Digital Converter (ADC).



**Important:** The PIC16F180 microcontroller family does not allow the system clock source to be changed through clock switching. Once the RSTOSC Configuration bits select the oscillator source, the source cannot be changed via software. If the HFINTOSC is selected as the clock source, the HFINTOSC frequency may be changed by modifying the FRQ bits.

The instruction clock ( $F_{OSC}/4$ ) can be routed to the CLKOUT pin when the pin is not in use. The Clock Out Enable ( $\overline{CLKOUTEN}$ ) Configuration bit controls the functionality of the CLKOUT signal. When  $\overline{CLKOUTEN}$  is clear ( $\overline{CLKOUTEN}$  = 0), the CLKOUT signal is routed to the CLKOUT pin. When  $\overline{CLKOUTEN}$  is set ( $\overline{CLKOUTEN}$  = 1), the CLKOUT pin functions as an I/O pin.

#### 11.1.1 External Clock Sources

An external clock source can be used as the device system clock by performing the following actions:

- Program the RSTOSC Configuration bits to select the external clock source (RSTOSC = 111)
- Program the FEXTOSC Configuration bits to select the appropriate External Clock (EC) mode:
  - ECH mode for oscillators operating at or above 16 MHz (FEXTOSC = 11)
  - ECL mode for oscillator operating below 16 MHz (FEXTOSC = 01)

#### 11.1.1.1 EC Mode

The External Clock (EC) mode allows an externally generated logic level signal to be the system clock source. When operating in EC mode, an external clock source is connected to the CLKIN input pin. The CLKOUT pin is available as a general purpose I/O pin or as the CLKOUT signal pin.


EC mode provides two Power mode selections:

- ECH: High Power mode (16 MHz and above)
- ECL: Low Power mode (below 16 MHz)

The Oscillator Start-up Timer (OST) is disabled when EC mode is selected; therefore, there is no delay in operation after a Power-on Reset (POR) or wake-up from Sleep. Because the PIC® MCU design is fully static, stopping the external clock input will have the effect of halting the device while leaving all data intact. Upon restarting the external clock, the device will resume operation as if no time had elapsed.

The figure below shows the pin connections for EC mode.

Figure 11-2. External Clock (EC) Mode Operation



#### Note:

Output depends on the setting of the CLKOUTEN Configuration bit.

#### 11.1.1.2 Secondary Oscillator

The Secondary Oscillator (SOSC) is a separate external oscillator block that can be used as an alternate system clock source or as a Timer clock source. The SOSC is optimized for 32.768 kHz, and can be used with either an external quartz crystal connected to the SOSCI and SOSCO pins, or with an external clock source connected to the SOSCI pin as shown in the figures below.

Figure 11-3. SOSC 32.768 kHz Quartz Crystal Oscillator Operation





Figure 11-4. SOSC 32.768 kHz External Clock Operation



The SOSC can be enabled through one of two methods:

- · Programming the RSTOSC Configuration bits to select the SOSC as the system clock
- · Setting the SOSCEN bit to enable the SOSC for use as a peripheral clock source

Two Power modes are available for the secondary oscillator, and are selected using the Secondary Oscillator Power Mode Select (SOSCPWR) bit. When SOSCPWR is clear (SOSCPWR = 0), the oscillator operates in Low Power mode, which is ideal for crystal oscillators with low drive strength. When SOSCPWR is set (SOSCPWR = 1), the oscillator operates in High Power mode, which is ideal for crystal oscillators with high drive strength or high Equivalent Series Resistance (ESR).



**Important:** The SOSC module must be disabled before changing Power modes. Changes to the Power mode during operation may result in undefined oscillator behavior.

#### 11.1.1.2.1 SOSC Start-Up Timing

The SOSC utilizes the Oscillator Start-up Timer (OST) to ensure that the 32.768 kHz crystal oscillator has started and is available for use. Crystal oscillators do not start immediately and may take a few hundred cycles before achieving stable operation. The oscillations must build up until sufficient amplitude is generated to properly toggle between logic states. The OST counts 1024 oscillation periods from the SOSCI input following a Power-on Reset (POR), Brown-out Reset (BOR), or wake-up from Sleep event to ensure that the oscillator has enough time to reach stable and accurate operation. Once the OST completes its count, module hardware sets the Secondary Oscillator Ready (SOR) bit, indicating that the SOSC is stable and ready to use.

#### 11.1.2 Internal Clock Sources

The internal oscillator block contains two independent oscillators that can produce two internal system clock sources:

- High-Frequency Internal Oscillator (HFINTOSC)
- · Low-Frequency Internal Oscillator (LFINTOSC)

An internal oscillator source can be used as the device system clock by programming the RSTOSC Configuration bits to select one of the INTOSC sources.

In INTOSC mode, the CLKIN and CLKOUT pins are available for use as general purpose I/Os, provided that no external oscillator is connected. The function of the CLKOUT pin is determined by the  $\overline{\text{CLKOUTEN}}$  Configuration bit. When  $\overline{\text{CLKOUTEN}}$  is set  $\overline{\text{CLKOUTEN}} = 1$ ), the pin functions as a general purpose I/O. When  $\overline{\text{CLKOUTEN}}$  is clear  $\overline{\text{CLKOUTEN}} = 0$ ), the system instruction clock (F<sub>OSC</sub>/4) is available as an output signal on the pin.

#### 11.1.2.1 HFINTOSC

The High-Frequency Internal Oscillator (HFINTOSC) is a factory-calibrated, precision digitally-controlled internal clock source that produces a wide range of stable clock frequencies. The HFINTOSC can be enabled by programming the RSTOSC Configuration bits to select one of two HFINTOSC options upon device Reset or power-up.

The HFINTOSC frequency is selected via the HFINTOSC Frequency Selection (FRQ) bits. Fine-tuning of the HFINTOSC is done via the HFINTOSC Frequency Tuning (TUN) bits.

#### 11.1.2.1.1 HFINTOSC Frequency Tuning

The HFINTOSC frequency can be fine-tuned via the HFINTOSC Tuning (OSCTUNE) register. The OSCTUNE register is used by Active Clock Tuning hardware or user software to provide small adjustments to the HFINTOSC nominal frequency.

The OSCTUNE register contains the HFINTOSC Frequency Tuning (TUN) bits. The TUN bits default to a 6-bit, two's compliment value of  $0 \times 00$ , which indicates that the oscillator is operating at the selected frequency. When a value between  $0 \times 01$  and  $0 \times 1F$  is written to the TUN bits, the HFINTOSC frequency is increased. When a value between  $0 \times 3F$  and  $0 \times 20$  is written to the TUN bits, the HFINTOSC frequency is decreased.

When the OSCTUNE register is modified, the oscillator will begin to shift to the new frequency. Code execution continues during this shift. There is no indication that the frequency shift occurred.



Important: OSCTUNE tuning does not affect the LFINTOSC frequency.

#### 11.1.2.2 MFINTOSC

The Medium-Frequency Internal Oscillator (MFINTOSC) generates two constant clock outputs (500 kHz and 31.25 kHz). The MFINTOSC clock signals are created from the HFINTOSC using dynamic divider logic, which provides constant MFINTOSC clock rates regardless of selected HFINTOSC frequency.

The MFINTOSC cannot be used as the system clock, but can be used as a clock source for certain peripherals, such as a Timer.

#### 11.1.2.3 SFINTOSC

The Specified Frequency Internal Oscillator (SFINTOSC) generates a 1 MHz output clock. The SFINTOSC clock signal is created from the HFINTOSC using dynamic divider logic, which provides a constant SFINTOSC clock rate regardless of the selected HFINTOSC frequency.

The SFINTOSC cannot be used as the system clock, but may be selected as a clock source for certain peripherals, such as a Timer.

#### 11.1.2.4 LFINTOSC

The Low-Frequency Internal Oscillator (LFINTOSC) is a factory-calibrated 31 kHz internal clock source.

The LFINTOSC can be used as a system clock source, and may be used by certain peripheral modules as a clock source. Additionally, the LFINTOSC provides a time base for the following:

- Power-up Timer (PWRT)
- Watchdog Timer (WDT)

The LFINTOSC is enabled by programming the RSTOSC Configuration bits to select LFINTOSC.

#### 11.1.2.5 ADCRC

The Analog-to-Digital RC (ADCRC) oscillator is dedicated to the ADC module. This oscillator is also referred to as the FRC clock. The ADCRC operates at a fixed frequency of approximately 600 kHz, and is used as a conversion clock source. The ADCRC allows the ADC module to operate in Sleep mode, which can reduce system noise during the ADC conversion. The ADCRC is automatically enabled when it is selected as the clock source for the ADC module, or when selected as the clock source of any peripheral that may use it. The ADCRC may also be manually enabled via the ADC Oscillator Enable (ADOEN) bit, thereby avoiding start-up delays when this source is used intermittently.

#### 11.1.3 Oscillator Status and Manual Enable

The Oscillator Status (OSCSTAT) register displays the Ready status for each of the following oscillators:

- HFINTOSC
- MFINTOSC
- LFINTOSC
- SOSC
- ADCRC
- SFINTOSC

The HFINTOSC Oscillator Ready (HFOR), MFINTOSC Oscillator Ready (MFOR), LFINTOSC Oscillator Ready (LFOR), ADCRC Oscillator Ready (ADOR), and SFINTOSC Oscillator Ready (SFOR) Status bits indicate whether the respective oscillators are ready for use. These clock sources are available for use at any time, but may require a finite amount of time before they have reached the specified accuracy levels. When the oscillators are ready and have achieved the specified accuracy, module hardware sets the respective bits.

When a new value is loaded into the OSCFRQ register, the HFOR bit is cleared by hardware, and will be set again once the HFINTOSC is ready. During pending OSCFRQ changes, the HFINTOSC will stall at either a high or a low state until the oscillator locks in the new frequency and resumes operation.

The SOSC Oscillator Ready (SOR) Status bit indicates whether the external clock source is ready for use. The SOSC uses the Oscillator Start-Up Timer (OST) to determine when the oscillator is ready. Once the OST has expired, the external oscillator is ready for use, and module hardware sets the SOR bit.

The Oscillator Enable (OSCEN) register can be used to manually enable the following oscillators:

- HFINTOSC
- MFINTOSC
- LFINTOSC
- SOSC
- ADCRC

# 11.2 Active Clock Tuning (ACT)

Many applications, such as those using UART communication, require an oscillator with an accuracy of  $\pm$  1% over the full temperature and voltage range. To meet this level of accuracy, the Active Clock Tuning (ACT) feature utilizes the SOSC frequency of 32.768 kHz to adjust the frequency of the HFINTOSC over voltage and temperature.



**Important:** Active Clock Tuning requires the use of a 32.768 kHz external oscillator connected to the SOSCI/SOSCO pins.


Active Clock Tuning is enabled via the Active Clock Tuning Enable (ACTEN) bit. When ACTEN is set (ACTEN = 1), the ACT module uses the SOSC time base to measure the HFINTOSC frequency, and uses the HFINTOSC Frequency Tuning (TUN) bits to adjust the HFINTOSC frequency. When ACTEN is clear (ACTEN = 0), the ACT feature is disabled, and user software can utilize the TUN bits to adjust the HFINTOSC frequency.



**Important:** When the ACT feature is enabled, the TUN bits are controlled directly through module hardware and become read-only bits to user software. Writes to the TUN bits when the ACT feature is enabled are ignored.

The figure below shows the Active Clock Tuning block diagram.

Figure 11-5. Active Clock Tuning (ACT) Block Diagram



#### 11.2.1 ACT Lock Status

The Active Clock Tuning Lock Status (ACTLOCK) bit can be used to determine when the HFINTOSC has been tuned. When ACTLOCK is set (ACTLOCK = 1), the HFINTOSC frequency has been locked to within  $\pm$  1% of the nominal frequency. When ACTLOCK is clear (ACTLOCK = 0), the following conditions may be true:

- The HFINTOSC frequency has not been locked to within ± 1%
- A device Reset occurred
- · The ACT feature is disabled



**Important**: The ACTLOCK bit is read-only. Writes to ACTLOCK are ignored.

## 11.2.2 ACT Out-Of-Range Status

When Active Clock Tuning is enabled, module hardware uses the TUN bits to achieve high accuracy levels. If the module requires a TUN value outside of its range, the ACT Out-of-Range Status (ACTORS) bit is set by hardware (ACTORS = 1).

The ACTORS bit will be set when:

• The HFINTOSC is tuned to its lowest frequency as determined by the TUN bits, and will require a value lower than the TUN bits can provide to achieve accuracy within ± 1%.

# PIC16F18015/25/44/45

**OSC - Oscillator Module** 

• The HFINTOSC is tuned to its highest frequency as determined by the TUN bits, and will require a value higher than the TUN bits can provide to achieve accuracy within ± 1%.

When an ACT out-of-range event occurs, the HFINTOSC will continue to use the last TUN value until the HFINTOSC frequency returns to the tunable range. Once the HFINTOSC returns to the tunable range, module hardware clears the ACTORS bit.



**Important:** The ACTORS bit is read-only. Writes to ACTORS are ignored.

## 11.2.3 ACT Update Disable

When Active Clock Tuning is enabled, the OSCTUNE register is continuously updated every ACT clock cycle. The ACT Update Disable (ACTUD) bit can be used to suspend updates to the OSCTUNE register. When ACTUD is set (ACTUD = 1), updates to OSCTUNE are suspended, although the module continues to operate. The last value written to OSCTUNE is used for tuning, and the ACTLOCK bit is continually updated for each ACT cycle. When ACTUD is clear (ACTUD = 0), the module updates OSCTUNE register every ACT cycle.

## 11.2.4 ACT Interrupts

When Active Clock Tuning is enabled (ACTEN = 1) and either the ACTLOCK or ACTORS bits change state (e.g., from a Locked to an Unlocked state), the ACT Interrupt Flag (ACTIF) of the PIR registers is set (ACTIF = 1). If the ACT Interrupt Enable (ACTIE) bit is set (ACTIE = 1), an interrupt will be generated when ACTIF becomes set. No interrupts are generated for each OSCTUNE update unless the update results in a change of Lock status or Out-of-Range status.

# 11.3 Register Definitions: Oscillator Module

## 11.3.1 ACTCON

Name: ACTCON Offset: 0x0214

Active Clock Tuning Control Register

Bit	7	6	5	4	3	2	1	0
	ACTEN	ACTUD			ACTLOCK		ACTORS	
Access	R/W	R/W			R		R	
Reset	0	0			0		0	

# Bit 7 - ACTEN Active Clock Tuning Enable

Value	Description
1	ACT enabled: HFINTOSC tuning is controlled by the ACT
0	ACT disabled: HFINTOSC tuning is controlled by the OSCTUNE register via user software

## Bit 6 - ACTUD Active Clock Tuning Update Disable

Value	Condition	Description
1	ACTEN = 1	Updates to the OSCTUNE register from ACT hardware are disabled
0	ACTEN = 1	Updates to the OSCTUNE register from ACT hardware are allowed
1	ACTEN = 0	Updates to the OSCTUNE register through user software are disabled
0	ACTEN = 0	Updates to the OSCTUNE register through user software are allowed

# Bit 3 – ACTLOCK Active Clock Tuning Lock Status

Value	Description
1	Locked: HFINTOSC is within ± 1% of its nominal value
0	Not locked: HFINTOSC may or may not be within ± 1% of its nominal value


# Bit 1 – ACTORS Active Clock Tuning Out-of-Range Status

Value	Description
1	Value required for tuning is outside of the OSCTUNE range
0	Value required for tuning is within the OSCTUNE range

## 11.3.2 OSCCON2

Name: OSCCON2 Offset: 0x020E

Oscillator Control Register 2



Bits 6:4 – COSC[2:0] Current Oscillator Source Select (read-only)<sup>(1)</sup> Indicates the current oscillator source per the RSTOSC Selection Table.

#### Note:

1. The RSTOSC value is the value present when user code execution begins. Refer to the RSTOSC configuration bits or the RSTOSC selection table for the Reset Oscillator selections.

# 11.3.3 OSCCON3

Name: OSCCON3 Offset: 0x020F

Oscillator Control Register 3

Bit	7	6	5	4	3	2	1	0
		SOSCPWR						
Access		R/W		•		•	•	_
Reset		1						


Bit 6 - SOSCPWR Secondary Oscillator Power Mode Select

Value	Description
1	Secondary Oscillator operates in High Power mode
0	Secondary Oscillator operates in Low Power mode

# 11.3.4 OSCTUNE

Name: OSCTUNE Offset: 0x0212

HFINTOSC Frequency Tuning Register




Bits 5:0 - TUN[5:0] HFINTOSC Frequency Tuning

TUN	Condition
01 1111	Maximum frequency
•	•
•	•
•	•
00 0000	Center frequency. Oscillator is operating at the selected nominal frequency. (Default value)
•	•
•	•
•	•
10 0000	Minimum frequency

# 11.3.5 OSCFRQ

Name: OSCFRQ Offset: 0x0213

HFINTOSC Frequency Selection Register



Bits 2:0 - FRQ[2:0] HFINTOSC Frequency Selection

FRQ	Nominal Freq (MHz)
111-110	Reserved
101	32
100	16
011	8
010	4
001	2
000	1

## 11.3.6 OSCSTAT

Name: OSCSTAT Offset: 0x0210

Oscillator Status Register

Bit	7	6	5	4	3	2	1	0
		HFOR	MFOR	LFOR	SOR	ADOR	SFOR	
Access		R	R	R	R	R	R	_
Reset		0	0	0	0	0	0	

## Bit 6 - HFOR HFINTOSC Ready

	Value	e Description	
ſ	1	The HFINTOSC is ready for use	
	0	The HFINTOSC is not enabled, or it is not ready for use	

## Bit 5 - MFOR MFINTOSC Ready

	Value	Description	
1 The MFINTOSC is ready for use		The MFINTOSC is ready for use	
Ī	0	The MFINTOSC is not enabled, or it is not ready for use	

## Bit 4 - LFOR LFINTOSC Ready

Value	Description	
1	The LFINTOSC is ready for use	
0	The LFINTOSC is not enabled, or is not ready for use	

# Bit 3 - SOR Secondary Oscillator (SOSC) Ready

Value	Description
1	The Secondary oscillator is ready for use
0	The Secondary oscillator is not enabled, or is not ready for use

#### Bit 2 - ADOR ADCRC Oscillator Ready

Value	Description		
1	The ADCRC oscillator is ready for use		
0	The ADCRC oscillator is not enabled, or is not ready for use		

# Bit 1 - SFOR SFINTOSC Oscillator Ready

Value	Description
1	The SFINTOSC oscillator is ready for use
0	The SFINTOSC oscillator is not enabled, or is not ready for use

# 11.3.7 OSCEN

Name: OSCEN Offset: 0x0211

Oscillator Enable Register

Bit	7	6	5	4	3	2	1	0
		HFOEN	MFOEN	LFOEN	SOSCEN	ADOEN		
Access		R/W	R/W	R/W	R/W	R/W		
Reset		0	0	0	0	0		

## Bit 6 - HFOEN HFINTOSC Enable

	Value	Description		
		HFINTOSC is explicitly enabled, operating as specified by OSCFRQ		
		HFINTOSC can be enabled by a peripheral request		

#### Bit 5 - MFOEN MFINTOSC Enable

Value	Description	
1	MFINTOSC is explicitly enabled	
0	MFINTOSC can be enabled by a peripheral request	

## Bit 4 - LFOEN LFINTOSC Enable

	√alue	Description	
Γ.	1	LFINTOSC is explicitly enabled	
	)	LFINTOSC can be enabled by a peripheral request	

# Bit 3 - SOSCEN Secondary Oscillator Enable

Value	Description				
1	SOSC is explicitly enabled, operating as specified by SOSCPWR				
0	SOSC can be enabled by a peripheral request				

## Bit 2 - ADOEN ADCRC Oscillator Enable

Value	Description
1	ADCRC is explicitly enabled
0	ADCRC may be enabled by a peripheral request

# 11.4 Register Summary - Oscillator Module

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x020D										
0x020E	OSCCON2	7:0			COSC[2:0]					
0x020F	OSCCON3	7:0		SOSCPWR						
0x0210	OSCSTAT	7:0		HFOR	MFOR	LFOR	SOR	ADOR	SFOR	
0x0211	OSCEN	7:0		HFOEN	MFOEN	LFOEN	SOSCEN	ADOEN		
0x0212	OSCTUNE	7:0					TUN	I[5:0]		
0x0213	OSCFRQ	7:0							FRQ[2:0]	
0x0214	ACTCON	7:0	ACTEN	ACTUD			ACTLOCK		ACTORS	

# 12. INT - Interrupts


## 12.1 Overview

The interrupt feature allows certain events to preempt normal program flow. Firmware is used to determine the source of the interrupt and act accordingly. Some interrupts can be configured to wake the MCU from Sleep mode.

Many peripherals can produce interrupts. Refer to the corresponding chapters for details.

A block diagram of the interrupt logic is shown in Figure 12-1.

Figure 12-1. Interrupt Logic



# 12.2 INTCON Register

The Interrupt Control (INTCON) register is readable and writable, and contains the Global Interrupt Enable (GIE), Peripheral Interrupt Enable (PEIE) and External Interrupt Edge Select (INTEDG) bits.

# 12.3 PIE Registers

The Peripheral Interrupt Enable (PIE) registers contain the individual enable bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are five PIE registers in the PIC16F180 family.

# 12.4 PIR Registers

The Peripheral Interrupt Request (PIR) registers contain the individual flag bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are five PIR registers.

# 12.5 Operation

Interrupts are disabled upon any device Reset. They are enabled by setting the following bits:

- GIE bit
- PEIE bit (if the Interrupt Enable bit of the interrupt event is contained in the PIE registers)

Interrupt Enable bit(s) for the specific interrupt event(s)

The PIR registers record individual interrupts via interrupt flag bits. Interrupt flag bits will be set, regardless of the status of the GIE, PEIE and individual interrupt enable bits.

The following events happen when an interrupt event occurs while the GIE bit is set:

- Current prefetched instruction is flushed
- · GIE bit is cleared
- · Current Program Counter (PC) is pushed onto the stack
- Critical registers are automatically saved to the shadow registers (see the "Automatic Context Saving" section)
- PC is loaded with the interrupt vector 0004h

The firmware within the Interrupt Service Routine (ISR) may determine the source of the interrupt by polling the interrupt flag bits. The interrupt flag bits must be cleared before exiting the ISR to avoid repeated interrupts. Because the GIE bit is cleared, any interrupt that occurs while executing the ISR will be recorded through its interrupt flag, but will not cause the processor to redirect to the interrupt vector.

The RETFIE instruction exits the ISR by popping the previous address from the stack, restoring the saved context from the shadow registers and setting the GIE bit.

For additional information on a specific interrupts operation, refer to its peripheral chapter.




#### Important:

- 1. Individual interrupt flag bits are set, regardless of the state of any other enable bits.
- 2. All interrupts will be ignored while the GIE bit is cleared. Any interrupt occurring while the GIE bit is clear will be serviced when the GIE bit is set again.

# 12.6 Interrupt Latency

Interrupt latency is defined as the time from when the interrupt event occurs to the time code execution at the interrupt vector begins. The interrupt is sampled during Q1 of the instruction cycle. The actual interrupt latency then depends on the instruction that is executing at the time the interrupt is detected. See the following figures for more details.


Figure 12-2. Interrupt Latency



#### Notes:

- 1. An interrupt may occur at any time during the interrupt window.
- 2. Since an interrupt may occur at any time during the interrupt window, the actual latency can vary.

Figure 12-3. INT Pin Interrupt Timing



#### Notes:

- 1. INTF flag is sampled here (every Q1).
- 2. Asynchronous interrupt latency = 3-5 T<sub>CY</sub>. Synchronous latency = 3-4 T<sub>CY</sub>, where T<sub>CY</sub> = instruction cycle time. Latency is the same whether Inst (PC) is a single cycle or a two-cycle instruction.
- 3. For minimum width of INT pulse, refer to AC specifications in the "Electrical Specifications" chapter.
- 4. INTF may be set anytime during the Q4-Q1 cycles.

# 12.7 Interrupts During Sleep

Interrupts can be used to wake from Sleep. To wake from Sleep, the peripheral must be able to operate without the system clock. The interrupt source must have the appropriate Interrupt Enable bit(s) set prior to entering Sleep.

On waking from Sleep, if the GIE bit is also set, the processor will branch to the interrupt vector. Otherwise, the processor will continue executing instructions after the SLEEP instruction. The instruction directly after the SLEEP instruction will always be executed before branching to the ISR.

# 12.8 INT Pin

The INT pin can be used to generate an asynchronous edge-triggered interrupt. This interrupt is enabled by setting the External Interrupt Enable (INTE) bit. The External Interrupt Edge Select (INTEDG) bit determines on which edge the interrupt will occur. When the INTEDG bit is set, the rising edge will cause the interrupt. When the INTEDG bit is clear, the falling edge will cause the interrupt. The External Interrupt Flag (INTF) bit will be set when a valid edge appears on the INT pin. If the GIE and INTE bits are also set, the processor will redirect program execution to the interrupt vector.

# 12.9 Automatic Context Saving

Upon entering an interrupt, the return PC address is saved on the stack. Additionally, the following registers are automatically saved in the shadow registers:

# PIC16F18015/25/44/45

**INT - Interrupts** 

- · WREG register
- STATUS register (except for TO and PD)
- · BSR register
- · FSR registers
- · PCLATH register

Upon exiting the Interrupt Service Routine, these registers are automatically restored. Any modifications to these registers during the ISR will be lost. If modifications to any of these registers are desired, the corresponding shadow register may be modified and the value will be restored when exiting the ISR. The shadow registers are available in Bank 63 and are readable and writable. Depending on the user's application, other registers may also need to be saved.

# 12.10 Register Definitions: Interrupt Control

## 12.10.1 INTCON

Name: INTCON Offset: 0x000B

Interrupt Control Register

Bit	7	6	5	4	3	2	1	0
	GIE	PEIE						INTEDG
Access	R/W	R/W						R/W
Reset	0	0						1

## Bit 7 - GIE Global Interrupt Enable

Value	Description
1	Enables all active interrupts
0	Disables all interrupts

#### Bit 6 - PEIE Peripheral Interrupt Enable

	Value	Description		
1 Enables all active peripheral interrupts				
	0	Disables all peripheral interrupts		

#### Bit 0 - INTEDG External Interrupt Edge Select


Value	Description
1	Interrupt on rising edge of INT pin
0	Interrupt on falling edge of INT pin

**Note:** Interrupt flag bits are set when an Interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable bit. User software may ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows for software polling.

## 12.10.2 PIE0

Name: PIE0 Offset: 0x0096

Peripheral Interrupt Enable Register 0



#### Bit 5 - TMR0IE Timer0 Interrupt Enable

Value	Description
1	TMR0 interrupts are enabled
0	TMR0 interrupts are disabled

#### Bit 4 - IOCIE Interrupt-on-Change Enable

Value	Description
1	IOC interrupts are enabled
0	IOC interrupts are disabled

#### Bit 0 – INTE External Interrupt Enable<sup>(1)</sup>

Value	Description
1	External interrupts are enabled
0	External interrupts are disabled

#### Notes:

- 1. The External Interrupt INT pin is selected by INTPPS.
- 2. Bit PEIE in the INTCON register must be set to enable any peripheral interrupt controlled by registers PIE1 through PIE4. Interrupt sources controlled by the PIE0 register do not require the PEIE bit to be set in order to allow interrupt vectoring (when the GIE bit in the INTCON register is set).

## 12.10.3 PIE1

Name: PIE1 Offset: 0x0097

Peripheral Interrupt Enable Register 1

Bit	7	6	5	4	3	2	1	0
	TMR2IE	TMR3GIE	TMR3IE	TMR1GIE	TMR1IE	ACTIE		NVMIE
Access	R/W	R/W	R/W	R/W	R/W	R/W		R/W
Reset	0	0	0	0	0	0		0

## Bit 7 - TMR2IE TMR2 Interrupt Enable

Value	Description
1	TMR2 interrupts are enabled
0	TMR2 interrupts are disabled

## Bit 6 - TMR3GIE TMR3 Gate Interrupt Enable

Value	Description
1	TMR3 Gate interrupts are enabled
0	TMR3 Gate interrupts are disabled

# Bit 5 - TMR3IE TMR3 Interrupt Enable

Value	Description
1	TMR3 interrupts are enabled
0	TMR3 interrupts are disabled

## Bit 4 - TMR1GIE TMR1 Gate Interrupt Enable

Value	Description
1	TMR1 Gate interrupts are enabled
0	TMR1 Gate interrupts are disabled

#### Bit 3 - TMR1IE TMR1 Interrupt Enable

Val	lue	Description	
1		TMR1 interrupts are enabled	
0		TMR1 interrupts are disabled	

# Bit 2 – ACTIE Active Clock Tuning Interrupt Enable

1	Value	Description
	1	Active Clock Tuning interrupts are enabled
	0	Active Clock Tuning interrupts are disabled

#### Bit 0 - NVMIE NVM Interrupt Enable

Value	Description
1	NVM interrupts are enabled
0	NVM interrupts are disabled

**Note:** Bit PEIE of the INTCON register must be set to enable any peripheral interrupt controlled by registers PIE1 through PIE4.

## 12.10.4 PIE2

Name: PIE2 Offset: 0x0098

Peripheral Interrupt Enable Register 2

Bit	7	6	5	4	3	2	1	0
	CLC2IE	CLC1IE	CWG1IE	NCO1IE	CCP2IE	CCP1IE	TMR6IE	TMR4IE
Access	R/W							
Reset	0	0	0	0	0	0	0	0

# Bit 7 - CLC2IE CLC2 Interrupt Enable

Value	Description
1	CLC2 interrupts are enabled
0	CLC2 interrupts are disabled

## Bit 6 - CLC1IE CLC1 Interrupt Enable

Value	Description
1	CLC1 interrupts are enabled
0	CLC1 interrupts are disabled

## Bit 5 - CWG1IE CWG1 Interrupt Enable

Value	Description
1	CWG1 interrupts are enabled
0	CWG1 interrupts are disabled

#### Bit 4 - NCO1IE NCO1 Interrupt Enable

Value	Description
1	NCO1 interrupts are enabled
0	NCO1 interrupts are disabled

#### Bit 3 - CCP2IE CCP2 Interrupt Enable

Value	Description	
1	CCP2 interrupts are enabled	
0	CCP2 interrupts are disabled	

# Bit 2 - CCP1IE CCP1 Interrupt Enable

Value	Description	
1	CCP1 interrupts are enabled	
0	CCP1 interrupts are disabled	

#### Bit 1 - TMR6IE TMR6 Interrupt Enable

Value Description	
1	TMR6 interrupts are enabled
0	TMR6 interrupts are disabled

## Bit 0 - TMR4IE TMR4 Interrupt Enable

Value	Description	
1	TMR4 interrupts are enabled	
0	TMR4 interrupts are disabled	

**Note:** Bit PEIE of the INTCON register must be set to enable any peripheral interrupt controlled by registers PIE1 through PIE4.

## 12.10.5 PIE3

Name: PIE3 Offset: 0x0099

Peripheral Interrupt Enable Register 3

Bit	7	6	5	4	3	2	1	0
Γ	BCL1IE	SSP1IE	RC2IE	TX2IE	RC1IE	TX1IE	CLC4IE	CLC3IE
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

## Bit 7 - BCL1IE MSSP1 Bus Collision Interrupt Enable

Value	Description
1	MSSP1 Bus Collision interrupts are enabled
0	MSSP1 Bus Collision interrupts are disabled

# Bit 6 - SSP1IE MSSP1 Interrupt Enable

Value	Description		
1	MSSP1 interrupts are enabled		
0	MSSP1 interrupts are disabled		

#### Bit 5 - RC2|E EUSART2 Receive Interrupt Enable

Value	Description		
1	EUSART2 receive interrupts are enabled		
0	EUSART2 receive interrupts are disabled		

#### Bit 4 - TX2IE PWM1 Period Interrupt Enable

Value	Description
1	EUSART2 transmit interrupts are enabled
0	EUSART2 transmit interrupts are disabled

#### Bit 3 - RC1IE EUSART1 Receive Interrupt Enable

Value	Description	
1	EUSART1 receive interrupts are enabled	
0	EUSART1 receive interrupts are disabled	

## Bit 2 - TX1IE EUSART1 Transmit Interrupt Enable

Value	Description		
1	EUSART1 transmit interrupts are enabled		
0	EUSART1 transmit interrupts are disabled		

#### Bit 1 - CLC4IE CLC4 Interrupt Enable

Value	Description
1	CLC4 interrupts are enabled
0	CLC4 interrupts are disabled

#### Bit 0 - CLC3IE CLC3 Interrupt Enable

	2.10 2.20 interrupt 2.100 in		
Value	Description		
1	CLC3 interrupts are enabled		
0	CLC3 interrupts are disabled		

#### Note:

1. Bit PEIE in the INTCON register must be set to enable any peripheral interrupt controlled by registers PIE1 through PIE4.

# 12.10.6 PIE4

Name: PIE4 Offset: 0x009A

Peripheral Interrupt Enable Register 4

Bit	7	6	5	4	3	2	1	0
			ZCDIE	ADTIE	ADIE	CM1IE	BCL2IE	SSP2IE
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			0	0	0	0	0	0

## Bit 5 - ZCDIE Zero-Cross Detect (ZCD) Interrupt Enable

V	alue	Description
1		ZCD interrupts are enabled
0		ZCD interrupts are disabled

## Bit 4 - ADTIE ADC Threshold Interrupt Enable

Value	Description
1	ADC Threshold interrupts are enabled
0	ADC Threshold interrupts are disabled

#### Bit 3 - ADIE ADC Interrupt Enable

Value	Description
1	ADC interrupts are enabled
0	ADC interrupts are disabled

# Bit 2 - CM1IE Comparator 1 Interrupt Enable

Value	Description
1	Comparator 1 interrupts are enabled
0	Comparator 1 interrupts are disabled

#### Bit 1 - BCL2IE MSSP2 Bus Collision Interrupt Enable

Value Description	
1	MSSP2 Bus Collision interrupts are enabled
0	MSSP2 Bus Collision interrupts are disabled

# Bit 0 - SSP2IE MSSP2 Interrupt Enable


Value	Description
1	MSSP2 interrupts are enabled
0	MSSP2 interrupts are disabled

**Note:** Bit PEIE of the INTCON register must be set to enable any peripheral interrupt controlled by registers PIE1 through PIE4.

## 12.10.7 PIR0

Name: PIR0 Offset: 0x008C

Peripheral Interrupt Request Register 0



#### Bit 5 - TMR0IF Timer0 Interrupt Flag

Value	Description
1	TMR0 register has overflowed (must be cleared by software)
0	TMR0 register has not overflowed

## Bit 4 - IOCIF Interrupt-on-Change Flag<sup>(2)</sup>

Value	Description
1	One or more of the IOCAF-IOCEF register bits are currently set, indicating an enabled edge was
	detected by the IOC module
0	None of the IOCAF-IOCEF register bits are currently set

## Bit 0 - INTF External Interrupt Flag<sup>(1)</sup>

	Value	Description
ſ	1	External Interrupt has occurred
	0	External Interrupt has not occurred

#### Notes:

- 1. The External Interrupt INT pin is selected by INTPPS.
- 2. The IOCIF bit is the logical OR of all the IOCAF-IOCEF flags. Therefore, to clear the IOCIF flag, application firmware must clear all of the lower level IOCAF-IOCEF register bits.
- 3. Interrupt flag bits are set when an Interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable (GIE) bit. User software may ensure the appropriate interrupt flag bits are cleared before enabling an interrupt.

## 12.10.8 PIR1

Name: PIR1 Offset: 0x008D

Peripheral Interrupt Request Register 1

Bit	7	6	5	4	3	2	1	0
	TMR2IF	TMR3GIF	TMR3IF	TMR1GIF	TMR1IF	ACTIF		NVMIF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS		R/W/HS
Reset	0	0	0	0	0	0		0

## Bit 7 - TMR2IF TMR2 Interrupt Flag

Va	lue	Description
1		TMR2 interrupt has occurred (must be cleared in software)
0		TMR2 interrupt event has not occurred

## Bit 6 - TMR3GIF TMR3 Gate Interrupt Flag

Value	Description	
1	The TMR3 Gate has gone inactive (must be cleared in software)	
0	TMR3 Gate is active	

## Bit 5 - TMR3IF TMR3 Interrupt Flag

Value	Description
1	TMR3 interrupt has occurred (must be cleared in software)
0	TMR3 interrupt event has not occurred

## Bit 4 - TMR1GIF TMR1 Gate Interrupt Flag

Value	Description
1	The TMR1 Gate has gone inactive (must be cleared in software)
0	TMR1 Gate is active

## Bit 3 - TMR1IF TMR1 Interrupt Flag

Val	ue	Description		
1		TMR1 interrupt has occurred (must be cleared in software)		
0		TMR1 interrupt event has not occurred		

## Bit 2 - ACTIF Active Clock Tuning Interrupt Flag

Value	Description
1	Active Clock Tuning interrupt occurred (must be cleared in software)
0	Active Clock Tuning interrupt event has not occurred

## Bit 0 - NVMIF Nonvolatile Memory (NVM) Interrupt Flag

	<u> </u>
Value	Description
1	The requested NVM operation has completed (must be cleared in software)
0	NVM interrupt event has not occurred

#### Note:

1. Interrupt flag bits are set when an Interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable (GIE) bit. User software may ensure the appropriate interrupt flag bits are cleared before enabling an interrupt.

## 12.10.9 PIR2

Name: PIR2 Offset: 0x008E

Peripheral Interrupt Request Register 2

Bit	7	6	5	4	3	2	1	0
[	CLC2IF	CLC1 <b>I</b> F	CWG1IF	NCO1IF	CCP2IF	CCP1IF	TMR6IF	TMR4IF
Access	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS
Reset	0	0	0	0	0	0	0	0

## Bit 7 - CLC2IF CLC2 Interrupt Flag

Value	Description	
1	CLC2 interrupt has occurred (must be cleared in software)	
0	CLC2 interrupt event has not occurred	

## Bit 6 - CLC1IF CLC1 Interrupt Flag

1	/alue	Description	
1		CLC1 interrupt has occurred (must be cleared in software)	
C	)	CLC1 interrupt event has not occurred	

## Bit 5 - CWG1IF CWG1 Interrupt Flag

Value	Description		
1	CWG1 interrupt has occurred (must be cleared in software)		
0	CWG1 interrupt event has not occurred		

## Bit 4 - NCO1IF NCO1 Interrupt Flag

Value	Description		
1	NCO1 interrupt has occurred (must be cleared in software)		
0	NCO1 interrupt event has not occurred		

## Bit 3 - CCP2IF CCP2 Interrupt Flag

Value	CCP Mode				
value	Capture	Compare	PWM		
1	Capture occurred (must be	Compare match occurred (must be	Output trailing edge occurred (must		
	cleared in software)	cleared in software)	be cleared in software)		
0	Capture did not occur	Compare match did not occur	Output trailing edge did not occur		

## Bit 2 - CCP1IF CCP1 Interrupt Flag

Value		CCP Mode		
value	Capture	Compare	PWM	
1	Capture occurred (must be	Compare match occurred (must be	Output trailing edge occurred (must	
	cleared in software)	cleared in software)	be cleared in software)	
0	Capture did not occur	Compare match did not occur	Output trailing edge did not occur	

## Bit 1 - TMR6IF TMR6 Interrupt Flag

Value	Description	
1	TMR6 interrupt has occurred (must be cleared in software)	
0	TMR6 interrupt event has not occurred	

## Bit 0 - TMR4IF TMR4 Interrupt Flag

Value	Description	
1	TMR4 interrupt has occurred (must be cleared in software)	
0	TMR4 interrupt event has not occurred	

**Note:** Interrupt flag bits are set when an Interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable (GIE) bit. User software may ensure the appropriate interrupt flag bits are cleared before enabling an interrupt.

## 12.10.10 PIR3

Name: PIR3 Offset: 0x008F

Peripheral Interrupt Request Register 3

Bit	7	6	5	4	3	2	1	0
	BCL1IF	SSP1IF	RC2IF	TX2 <b>I</b> F	RC1IF	TX1IF	CLC4 <b>I</b> F	CLC3IF
Access	R/W/HS	R/W/HS	R	R	R	R	R/W/HS	R/W/HS
Reset	0	0	0	0	0	0	0	0

## Bit 7 - BCL1IF MSSP1 Bus Collision Interrupt Flag

Value	Description
1	An MSSP1 Bus Collision was detected (must be cleared in software)
0	No MSSP1 Bus Collision event was detected

## Bit 6 - SSP1IF MSSP1 Interrupt Flag

Value	ıe Description		
1	MSSP1 interrupt has occurred (must be cleared in software)		
0	MSSP1 interrupt event has not occurred		

## Bit 5 - RC2IF EUSART2 Receive Interrupt Flag<sup>(1)</sup>

Value	/alue Description	
1	The EUSART2 receive buffer (RC2REG) is not empty (contains at least one byte)	
0	The EUSART2 receive buffer is empty	

## Bit 4 - TX2IF EUSART2 Transmit Interrupt Flag<sup>(2)</sup>

Value	Description	
1	The EUSART2 transmit buffer (TX2REG) is empty	
0	The EUSART2 transmit buffer is not empty	

## Bit 3 - RC1IF EUSART1 Receive Interrupt Flag<sup>(3)</sup>

Value	Description
1	The EUSART1 receive buffer (RC1REG) is not empty (contains at least one byte)
0	The EUSART1 receive buffer is empty

## Bit 2 – TX1IF EUSART1 Transmit Interrupt Flag<sup>(4)</sup>

Value	Description	
1	The EUSART1 transmit buffer (TX1REG) is empty	
0	The EUSART1 transmit buffer is not empty	

## Bit 1 - CLC4IF CLC4 Interrupt Flag

Valu	e Description	
1	CLC4 interrupt h	has occurred (must be cleared in software)
0	CLC4 interrupt e	event has not occurred

## Bit 0 - CLC3IF CLC3 Interrupt Flag

Value	Description
1	CLC3 interrupt has occurred (must be cleared in software)
0	CLC3 interrupt event has not occurred

# PIC16F18015/25/44/45

**INT - Interrupts** 

#### Notes:

- 1. RC2IF is read-only. User software must read RC2REG to clear RC2IF.
- 2. TX2IF is read-only. User software must load TX2REG to clear TX2IF. TX2IF does not indicate a completed transmission (use TMRT for this purpose instead).
- 3. RC1IF is read-only. User software must read RC1REG to clear RC1IF.
- 4. TX1IF is read-only. User software must load TX1REG to clear TX1IF. TX1IF does not indicate a completed transmission (use TMRT for this purpose instead).
- 5. Interrupt flag bits are set when an Interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable (GIE) bit. User software may ensure the appropriate interrupt flag bits are cleared before enabling an interrupt.

## 12.10.11 PIR4

Name: PIR4 Offset: 0x0090

Peripheral Interrupt Request Register 4

Bit	7	6	5	4	3	2	1	0
			ZCDIF	ADTIF	ADIF	CM1IF	BCL2IF	SSP2IF
Access			R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS	R/W/HS
Reset			0	0	0	0	0	0

## Bit 5 - ZCDIF Zero-Cross Detect (ZCD) Interrupt Flag

Value	Description
1	A ZCD interrupt occurred (must be cleared in software)
0	A ZCD interrupt has not occurred

## Bit 4 - ADTIF ADC Threshold Interrupt Flag

Value	Description
1	ADC Threshold interrupt has occurred (must be cleared in software)
0	ADC Threshold interrupt event has not occurred

#### Bit 3 - ADIF ADC Interrupt Flag

Value	Description
1	ADC interrupt has occurred (must be cleared in software)
0	ADC interrupt event has not occurred

## Bit 2 - CM1IF Comparator 1 Interrupt Flag

Value	Description
1	Comparator 1 interrupt has occurred (must be cleared in software)
0	Comparator 1 interrupt event has not occurred

## Bit 1 - BCL2IF MSSP2 Bus Collision Interrupt Flag

Value	Description
1	An MSSP2 Bus Collision interrupt has occurred (must be cleared in software)
0	No MSSP2 Bus Collision event was detected

## Bit 0 - SSP2IF MSSP2 Interrupt Flag

Value	Description
1	MSSP 2 interrupt has occurred (must be cleared in software)
0	MSSP2 interrupt event has not occurred

## Note:

 Interrupt flag bits are set when an Interrupt condition occurs, regardless of the state of its corresponding enable bit or the Global Enable (GIE) bit. User software may ensure the appropriate interrupt flag bits are cleared before enabling an interrupt.

# 12.11 Register Summary - Interrupt Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x0A										
0x0B	INTCON	7:0	GIE	PEIE						INTEDG
0x0C										
	Reserved									
0x8B										
0x8C	PIR0	7:0			TMR0IF	IOCIF				INTF
0x8D	PIR1	7:0	TMR2IF	TMR3GIF	TMR3IF	TMR1GIF	TMR1IF	ACTIF		NVMIF
0x8E	PIR2	7:0	CLC2IF	CLC1IF	CWG1IF	NCO1IF	CCP2IF	CCP1IF	TMR6IF	TMR4IF
0x8F	PIR3	7:0	BCL1IF	SSP1 <b>I</b> F	RC2IF	TX2IF	RC1IF	TX1IF	CLC4IF	CLC3IF
0x90	PIR4	7:0			ZCDIF	ADTIF	ADIF	CM1IF	BCL2IF	SSP2IF
0x91										
	Reserved									
0x95										
0x96	PIE0	7:0			TMR0IE	IOCIE				INTE
0x97	PIE1	7:0	TMR2IE	TMR3GIE	TMR3IE	TMR1GIE	TMR1IE	ACTIE		NVMIE
0x98	PIE2	7:0	CLC2IE	CLC1IE	CWG1IE	NCO1IE	CCP2IE	CCP1IE	TMR6IE	TMR4IE
0x99	PIE3	7:0	BCL1IE	SSP1IE	RC2IE	TX2IE	RC1IE	TX1IE	CLC4IE	CLC3IE
0x9A	PIE4	7:0			ZCDIE	ADTIE	ADIE	CM1IE	BCL2IE	SSP2IE

# 13. Sleep Mode

## 13.1 Sleep Mode Operation

Sleep mode is entered by executing the SLEEP instruction.

Upon entering Sleep mode, the following conditions exist:

- Resets other than WDT are not affected by Sleep mode; WDT will be cleared but keeps running if enabled for operation during Sleep.
- The PD bit is cleared.
- 3. The  $\overline{TO}$  bit is set.
- The CPU and the System clocks are disabled.
- LFINTOSC and/or HFINTOSC will remain enabled if any peripheral has requested them as a clock source or if the HFOEN, MFOEN or LFOEN bits are set.
- ADC is unaffected if the ADCRC oscillator is selected. When the ADC clock is something other than ADCRC, a SLEEP instruction causes the present conversion to be aborted and the ADC module is turned off, although the ADON bit remains active.
- 7. I/O ports maintain the status they had before SLEEP was executed (driving high, low, or high-impedance) only if no peripheral connected to the I/O port is active.

Refer to individual sections for more details on peripheral operation during Sleep.

To minimize current consumption, the following conditions need to be considered:

- · I/O pins will not be floating
- · External circuitry sinking current from I/O pins
- Internal circuitry sourcing current from I/O pins
- Current draw from pins with internal weak pull-ups
- Modules using any oscillator

I/O pins that are high-impedance inputs need to be pulled to  $V_{DD}$  or  $V_{SS}$  externally to avoid switching currents caused by floating inputs.

#### 13.1.1 Wake-Up from Sleep

The device can wake up from Sleep through one of the following events:

- 1. External Reset input on MCLR pin, if enabled.
- 2. BOR Reset, if enabled.
- 3. POR Reset.
- 4. Watchdog Timer, if enabled.
- 5. Any external interrupt.
- 6. Interrupts by peripherals capable of running during Sleep (see the individual peripheral for more information).

The first three events will cause a device Reset. The last three events are considered a continuation of program execution. To determine whether a device Reset or wake-up event occurred, refer to the "Determining the Cause of a Reset" section in the "Resets" chapter.

When the SLEEP instruction is being executed, the next instruction (PC + 1) is prefetched. For the device to wake up through an interrupt event, the corresponding interrupt enable bit must be enabled. Wake-up will occur regardless of the state of the GIE bit. If the GIE bit is disabled, the device continues execution at the instruction after the SLEEP instruction after the SLEEP instruction and will then call the Interrupt Service Routine. In cases where the execution of the instruction following SLEEP is not desirable, the user needs to have a NOP after the SLEEP instruction.

The WDT is cleared when the device wakes up from Sleep, regardless of the source of wake-up.

## 13.1.2 Wake-Up Using Interrupts

When global interrupts are disabled (GIE cleared) and any interrupt source has both its interrupt enable bit and interrupt flag bit set, one of the following will occur:

- If the interrupt occurs before the execution of a SLEEP instruction:
  - The SLEEP instruction will execute as a NOP
  - The WDT and WDT prescaler will not be cleared
  - The TO bit will not be set
  - The PD bit will not be cleared
- If the interrupt occurs during or after the execution of a SLEEP instruction:
  - The SLEEP instruction will be completely executed
  - The device will immediately wake up from Sleep
  - The WDT and WDT prescaler will be cleared
  - The TO bit will be set
  - The PD bit will be cleared

Even if the flag bits were checked before executing a SLEEP instruction, it may be possible for flag bits to become set before the SLEEP instruction completes. To determine whether a SLEEP instruction executed, test the  $\overline{PD}$  bit. If the  $\overline{PD}$  bit is set, the SLEEP instruction was executed as a NOP.


# 14. WDT - Watchdog Timer

The Watchdog Timer (WDT) is a system timer that generates a Reset event if the firmware does not issue a CLRWDT instruction within the time-out period. The Watchdog Timer is typically used to reset the processor in the event of a software malfunction, but can also be used to wake the device when in Sleep mode.

The WDT has the following features:

- Selectable clock sources
- Multiple operating modes:
  - WDT is always on
  - WDT is off when in Sleep
  - WDT is controlled by software
  - WDT is always off
- Configurable time-out period from 1 ms to 256 seconds (nominal)
- · Multiple Reset conditions
- · Operation during Sleep

Figure 14-1. WDT Block Diagram



## 14.1 Selectable Clock Sources

The WDT can derive its time base from either the 32.768 SOSC or the 31 kHz LFINTOSC as selected by the WDT Clock Source Select (CS) bit.



**Important:** Time intervals detailed in this section are based on a minimum nominal interval of 1 ms generated from the LFINTOSC clock source.

# 14.2 WDT Operating Modes

The WDT module has four operating modes controlled by the Watchdog Timer Enable (WDTE) bits. See Table 14-1.

Table 14-1. WDT Operating Modes

WDTE[1:0]	SEN	Device Mode	WDT Mode
11	Х	Х	Active

continued							
WDTE[1:0]	WDTE[1:0] SEN Device Mode						
10	x	Awake	Active				
10		Sleep	Disabled				
01	1	X	Active				
OI	0	X	Disabled				
00	Х	X	Disabled				

## 14.2.1 WDT is Always On

When the WDTE bits are set to '11', the WDT is always on. The WDT protection is active during Sleep mode.

## 14.2.2 WDT Is Off During Sleep

When the WDTE bits are set to '10', the WDT is on except during Sleep mode. During Sleep mode, the WDT protection is disabled.

## 14.2.3 WDT Controlled by Software

When the WDTE bits are set to '01', the WDT is controlled by the Software Watchdog Timer Enable (SEN) bit. When SEN is set (SEN = 1), WDT protection is active. When SEN is clear (SEN = 0), WDT protection is disabled.

#### 14.2.4 WDT Is Off

When the WDTE bits are set to '00', the WDT is disabled. In this mode, the SEN bit is ignored.

## 14.3 WDT Time-Out Period

The Watchdog Timer Prescale Select (PS) bits set the time-out period from 1 ms to 256 seconds (nominal). After a Reset, the default time-out period is two seconds.

## 14.4 Clearing the WDT

The WDT is cleared when any of the following conditions occur:

- · Any Reset
- Valid CLRWDT instruction is executed
- Device enters Sleep
- · Devices wakes up from Sleep
- · Any write to the WDTCON register

## 14.5 WDT Operation During Sleep

When the WDT enters Sleep, the WDT is cleared. If the WDT is enabled during Sleep, the WDT resumes counting. When the WDT exits Sleep, the WDT is cleared again.

When a WDT time-out occurs while the device is in Sleep, no Reset is generated. Instead, the device wakes up and resumes operation. The Time-Out  $(\overline{TO})$  and Power-Down  $(\overline{PD})$  bits are cleared to indicate the event. Additionally, the Watchdog Timer Reset Flag  $(\overline{RWDT})$  bit is cleared, indicating a WDT Reset event occurred.

## 14.6 Register Definitions: WDT Control

## 14.6.1 WDTCON

Name: WDTCON Offset: 0x018C

Watchdog Timer Control Register

Bit	7	6	5	4	3	2	1	0
	CS				PS[4:0]			SEN
Access	R/W	•	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0		0	0	0	0	0	0

Bit 7 - CS Watchdog Timer Clock Source Selection

Val	ue	Description
1		SOSC (32.768 kHz)
0		LFINTOSC (31 kHz)

Bits 5:1 - PS[4:0] Watchdog Timer Prescale Selection<sup>(1)</sup>

	<u> </u>
Value	Description
11111 -	Reserved. Results in minimum interval (1:32)
10011	
10010	1:8388608 (Interval 256s nominal)
10001	1:4194304 (Interval 128s nominal)
10000	1:2097152 (Interval 64s nominal)
01111	1:1048576 (Interval 32s nominal)
01110	1:524288 (Interval 16s nominal)
	1:262144 (Interval 8s nominal)
01100	1:131072 (Interval 4s nominal)
	1:65536 (Interval 2s nominal) (Reset value)
01010	1:32768 (Interval 1s nominal)
	1:16384 (Interval 512 ms nominal)
01000	1:8192 (Interval 256 ms nominal)
00111	1:4096 (Interval 128 ms nominal)
00110	1:2048 (Interval 64 ms nominal)
	1:1024 (Interval 32 ms nominal)
00100	1:512 (Interval 16 ms nominal)
00011	1:256 (Interval 8 ms nominal)
	1:128 (Interval 4 ms nominal)
	1:64 (Interval 2 ms nominal)
00000	1:32 (Interval 1 ms nominal)

## Bit 0 - SEN Software WDT Enable/Disable

Value	Condition	Description
X	If WDTE[1:0] ≠ 01	This bit is ignored
1	If WDTE[1:0] = 01	WDT is enabled
0	If WDTE[1:0] = 01	WDT is disabled

## Note:

1. Times are approximate and based on the 31 kHz LFINTOSC clock source.

# 14.7 Register Summary - WDT Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x018B										
0x018C	WDTCON	7:0	cs				PS[4:0]	•	•	SEN

## 15. NVM - Nonvolatile Memory Control

The Nonvolatile Memory (NVM) module provides run-time read and write access to the Program Flash Memory (PFM), Data Flash Memory (DFM), and Configuration bits. PFM includes the program memory and user ID space. DFM is also referred to as EEPROM which is accessed one byte at a time and the erase before write is automatic.

NVM is accessible using both FSR and INDF registers, or through the NVMREG register interface (see Table 15-1).

The write time is controlled by an on-chip timer. The write/erase voltages are generated by an on-chip charge pump rated to operate over the operating voltage range of the device.

PFM and DFM can be protected in two ways: code protection and write protection. Code protection (Configuration bits  $\overline{CP}$  (PFM)/ $\overline{CPD}$  (DFM)) disables PFM/DFM read and write access through an external device programmer. Write protection prevents user software writes to NVM areas tagged for protection by the  $\overline{WRTn}$  Configuration bits. Code protection does not affect the self-write and erase functionality, whereas write protection does. Attempts to write a protected location will set the WRERR bit. Code protection and write protection can only be reset on a Bulk Erase performed by an external programmer.

The Bulk Erase command is used to completely erase program memory. The Bulk Erase command can only be issued through an external programmer. There is no run time access for this command.

If the device is code-protected and a Bulk Erase command for the configuration memory is issued; all other memory regions are also erased. Refer to the "**Programming Specifications**" document for more details.

Table 15-1. NVM Organization and Access Information

Main Values				NVMREG Acces	FSR Access			
Memory Function	Memory Type	Program Counter (PC), ICSP <sup>™</sup> Address	NVMREGS bit (NVMCON1)	NVMADR[14:0]	Allowed Operations	FSR Address	FSR Programming Access	
Reset Vector		0x0000	0	0x0000		0x8000		
User Memory		0x0001	0	0x0001		0x8001		
Oser Memory	Program Flash	0x0003	0	0x0003	Read/Write	0x8003	Read-Only	
INT Vector	Memory	0x0004	0	0x0004	ineau/vviile	0x8004	Reau-Only	
Heer Memory		0x0005	0	0x0005		0x8005		
User Memory		0x3FFF <sup>(1)</sup>	U	0x3FFF <sup>(1)</sup>		0xFFFF		
User ID	Program Flash	0x8000	1	0x0000	Read/Write			
Oser ID	Memory	0x8003	1	0x0003	Reau/vviile			
Reserved	_	_	_	0x0004	_			
Revision ID	Hard Coded in	0x8005	1	0x0005				
Device ID	Program Flash Memory	0x8006	1	0x0006	Read			
CONFIG1		0x8007	1	0x0007		No. A		
CONFIG2	]	0x8008	1	0x0008		IN.	o Access	
CONFIG3	Program Flash Memory	0x8009	1	0x0009	Read/Write			
CONFIG4	Wiemory	0x800A	1	0x000A				
CONFIG5		0x800B	1	0x000B				
	Hard Coded in	0x8100	1	0x0100				
DIA and DCI	Program Flash Memory	0x82FF	1	0x02FF	Read			
EEPROM	Data Flash	0xF000	1	0x7000	Read/Write	0x7000	Pead	
LLFROW	Memory	0xF0FF	Τ.	0x70FF	rveau/vviile	0x70FF	Read	

#### Note:

1. The maximum Program Flash Memory address for the PIC16F180 family is 0x3FFF.

## 15.1 Program Flash Memory (PFM)

The Program Flash Memory (PFM) is readable, writable and erasable over the entire V<sub>DD</sub> range.

PFM consists of the following regions:

- User program memory (read/write)
- · Configuration Words (read/write)
- Device ID (read-only)
- Revision ID (read-only)
- User ID (read-write)
- Device Information Area (read-only)
- Device Configuration Information (read-only)

PFM can be read and/or written to through:

- CPU instruction fetch (read-only)
- FSR/INDF indirect access (read-only)
- NVMREG access (read-write)
- In-Circuit Serial Programming<sup>™</sup> (ICSP<sup>™</sup>) (external read-write)

It is important to understand the program memory structure for erase and programming operations. Program memory is arranged in rows. A row consists of 32 14-bit program memory words. A row is the minimum size that can be erased by user software. A Bulk Erase command cannot be issued from user code.

Read operations return a single word of memory. Write and erase operations are done on a row basis. Program memory will erase to a logic '1' and program to a logic '0'.

All or a portion of a row can be programmed. Data to be written into the program memory row is written to 14-bit wide data write latches. These latches are not directly accessible, but may be loaded via sequential writes to the NVMDATH:NVMDATL register pair.



**Important:** To modify only a portion of a previously programmed row, the contents of the entire row must be read. Then, the new data and retained data can be written into the write latches to reprogram the row of program memory. However, any unprogrammed locations can be written without first erasing the row. In this case, it is not necessary to save and rewrite the other previously programmed locations.

Writing or erasing program memory will cease instruction fetches until the operation is complete. The program memory cannot be accessed during the write or erase, so code cannot execute. An internal programming timer controls the write time of program memory writes and erases.

A value written to program memory does not need to be a valid instruction. Executing a program memory location that forms an invalid instruction results in a NOP.

#### 15.1.1 FSR and INDF Access

The File Select (FSR) and INDF registers allow indirect access to the Program Flash Memory. Indirect addressing is a mode in which the memory address in the instruction is determined by another register. The value of the FSR registers is used to determine the memory address location to be accessed.

## 15.1.1.1 FSR Read

The FSRs are used to provide read access to program memory.

Program memory is accessed by loading the FSRxH:FSRxL register pair with the address to be read, and setting bit 7 of the FSRxH register to '1'. When a MOVIW instruction, or any instruction that accesses INDFx, is executed, the value loaded into the FSRx register pair points to the location in program memory to be accessed. If the FSRx register pair points to an INDFx register, the read will return '0'.

Reading from NVM requires one instruction cycle. The CPU operation is suspended during the read and resumes immediately after. Read operations return a single byte of memory.

#### 15.1.1.2 FSR Write

Writing/erasing the NVM through the FSR registers (e.g., the MOVWI instruction) is not supported in the PIC16F180 microcontroller family.

#### 15.1.2 NVMREG Access

The NVMREG interface allows read/write access to all the locations accessible by FSRs, read/write access to the User ID locations, and read-only access to the device identification, revision, and configuration data.

Writing or erasing of NVM via the NVMREG interface is prevented when the device is write-protected.

#### 15.1.2.1 NVMREG Read Operation

To read a NVM location using the NVMREG interface, the user must:


- Clear the NVMREGS bit if the user intends to access program memory locations, or set NMVREGS if the user intends to access User ID or configuration locations.
- 2. Write the desired address into the NVMADRH:NVMADRL register pair.
- 3. Set the RD bit to initiate the read.

Once the read control bit is set, the CPU operation is suspended during the read and resumes immediately after. The data is available in the very next cycle, in the NVMDATH:NVMDATL register pair; therefore, it can be read as two bytes in the following instructions.

The NVMDATH:NVMDATL register pair will hold this value until another read or until it is written to by the user.

Upon completion, the RD bit is cleared by hardware.

Figure 15-1. Program Flash Memory Read Sequence



```
Example 15-1. Program Memory Read

// This code block will read 1 word of program memory

NVMCON1bits.NVMREGS = 0; // Point to PFM

NVMADR = PFM ADDRESS; // Load NVMADRL with PFM address

NVMCON1bits.RD = 1; // Initiate read cycle

PFM DATA_LOW = NVMDATL; // PFM data low byte

PFM_DATA_HIGH = NVMDATH; // PFM data high byte
```

#### 15.1.2.2 NVM Unlock Sequence

The unlock sequence is a mechanism that protects the NVM from unintended self-write programming or erasing. The sequence must be executed and completed without interruption to successfully complete any of the following operations:

- PFM Row Erase
- · Write of PFM write latches to PFM memory
- · Write of PFM write latches to User IDs
- Write to Configuration Words


The unlock sequence consists of the following steps and must be completed in order:

- Write 55h to NVMCON2
- Write AAh to NMVCON2
- Set the WR bit

Once the WR bit is set, the processor will stall internal operations until the operation is complete and then resume with the next instruction.

Since the unlock sequence must not be interrupted, global interrupts must be disabled prior to the unlock sequence and re-enabled after the unlock sequence is completed.

Figure 15-2. NVM Unlock Sequence



```
Example 15-2. NVM Unlock Sequence
 NVMCON1bits.WREN = 1;
                                // Enable write/erase
 INTCONbits.GIE = 0;
                                // Disable global interrupts
 // The next three steps are the required unlock sequence
 NVMCON2 = 0x55;
                               // First unlock code
 NVMCON2 = 0xAA;
                                // Second unlock code
                                // Initiate write/erase cycle
 NVMCON1bits.WR = 1;
 INTCONbits.GIE = 1;
                                // Enable global interrupts
 NVMCON1bits.WREN = 0;
                                // Disable further write/erase cycles
```

## PIC16F18015/25/44/45

## **NVM - Nonvolatile Memory Control**

**Note:** Sequence begins when NVMCON2 is written; the three unlock steps must occur in the cycle-accurate order shown. If the timing of the sequence is corrupted by an interrupt or a debugger Halt, the action will not take place.

## 15.1.2.3 NVMREG Erase of Program Memory

Before writing to program memory, the word(s) to be written must be erased or previously unwritten. Program memory can only be erased one row at a time. No automatic erase occurs upon the initiation of the write to program memory. To erase a program memory row:


- Clear the NVMREGS bit to erase program memory locations, or set the NMVREGS bit to erase User ID locations.
- 2. Write the desired address into the NVMADRH:NVMADRL register pair.
- 3. Set the FREE and WREN bits.
- 4. Perform the unlock sequence as described in the NVM Unlock Sequence section.

If the program memory address is write-protected, the WR bit will be cleared and the erase operation will not take place.

While erasing program memory, the CPU operation is suspended and resumes when the operation is complete. Upon completion, the NVMIF bit is set, and an interrupt will occur if the NVMIE bit is also set.

Write latch data is not affected by erase operations, and WREN will remain unchanged.

Figure 15-3. NVM Erase Sequence



#### Note:

1. See the NVM Unlock Sequence section.

#### Example 15-3. Erasing One Row of Program Flash Memory NVMCON1bits.NVMREGS = 0; // Point to PFM // 14-bit PFM address NVMADR = PFM ADD; NVMCON1bits.FREE = 1; // Specify an erase operation NVMCON1bits.WREN = 1; // Enable write/erase cycle INTCONbits.GIE = 0; // Disable interrupts during unlock sequence //The next three steps are the required unlock sequence // First unlock code NVMCON2 = 0x55;NVMCON2 = 0xAA;// Second unlock code // Initiate write/erase cycle NVMCON1bits.WR = 1; // Enable interrupts

// Disable writes

## 15.1.2.4 NVMREG Write to Program Memory

Program memory is programmed using the following steps:

- Load the address of the row to be programmed into NVMADRH:NVMADRL.
- Load each write latch with data via the NMVDATH:NVMDATL registers. 2.
- 3. Initiate a programming operation.

INTCONbits.GIE = 1;

NVMCON1bits.WREN = 1;

Repeat steps 1 through 3 until all data is written.

Before writing to program memory, the word(s) to be written must be erased or previously unwritten. Program memory can only be erased one row at a time. No automatic erase occurs upon the initiation of the write.

Program memory can be written one or more words at a time. The maximum number of words written at one time is equal to the number of write latches. See Figure 15-4 for more details.

The write latches are aligned to the Flash row address boundary defined by the upper ten bits of NVMADRH:NVMADRL, (NVMADRH[6:0]:NVMADRL[7:5]) with the lower five bits of NVMADRL, (NVMADRL[4:0]) determining the write latch being loaded. Write operations do not cross these boundaries. At the completion of a program memory write operation, the data in the write latches is reset to contain 0x3FFF.

The following steps must be completed to load the write latches and program a row of program memory. These steps are divided into two parts. First, each write latch is loaded with data from the NVMDATH:NVMDATL using the unlock sequence with LWLO = 1. When the last word to be loaded into the write latch is ready, the LWLO bit is cleared and the unlock sequence executed. This initiates the programming operation, writing all the latches into Flash program memory.



Important: The special unlock sequence is required to load a write latch with data or initiate a Flash programming operation. If the unlock sequence is interrupted, writing to the latches or program memory will not be initiated.

- 1. Set the WREN bit.
- 2. Clear the NVMREGS bit.
- Set the LWLO bit. When the LWLO bit is set (LWLO = 1), the write sequence will only load the write latches and will not initiate the write to Program Flash Memory.
- 4. Load the NVMADRH:NVMADRL register pair with the address of the location to be written.
- Load the NVMDATH:NVMDATL register pair with the program memory data to be written.
- Execute the unlock sequence. The write latch is now loaded.
- Increment the NVMADRH:NVMADRL register pair to point to the next location.
- 8. Repeat steps 5 through 7 until all except the last write latch has been loaded.
- Clear the LWLO bit. When the LWLO bit is clear (LWLO = 0), the write sequence will initiate the write to Program Flash Memory.
- Load the NVMDATH:NVMDATL register pair with the program memory data to be written.

11. Execute the unlock sequence. The entire program memory latch content is now written to Flash program memory.



**Important:** The program memory write latches are reset to the Blank state (0x3FFF) at the completion of every write or erase operation. As a result, it is not necessary to load all the program memory write latches. Unloaded latches will remain in the Blank state.

An example of the complete write sequence is shown in Example 15-4. The initial address is loaded into the NVMADRH:NVMADRL register pair; the data is loaded using indirect addressing.

Figure 15-4. NVMREG Writes to Program Flash Memory with 32 Write Latches





Figure 15-5. Program Flash Memory Write Sequence



#### Note:

See the NVM Unlock Sequence section.


```
Example 15-4. Writing to Program Flash Memory
                                      // Disable interrupts
 INTCONbits.GIE = 0;
 // PFM row must be erased before writes can occur
 NVMCON1bits.NVMREGS = 0;  // Point to PFM
NVMADR = PFMStartAddress;  // Must start at beginning of PFM row
NVMCON1bits.FREE = 1;
                                    // Specify an erase operation
// Allow erase cycle
 NVMCON1bits.WREN = 1;
 // Required unlock sequence
 NVMCON2 = 0x55;
 NVMCON2 = 0xAA;
 NVMCON1bits.WR = 1;
 NVMCON1bits.LWLO = 1;
                                      // Load write latches
 // Write to the data latches
 for (i = 0; i < PFM_ROW_SIZE; i++)
                                    // Load starting address
     NVMADR = PFMStartAddress;
                                     // Load data
     NVMDAT = PFM_WRITE_DATA;
     // Required unlock sequence
     NVMCON2 = 0x55;
     NVMCON2 = 0xAA;
     NVMCON1bits.WR = 1;
     PFMStartAddress++;
                                     // Increment address
     if(i = (PFM_ROW_SIZE - 1))
                                      // All latches loaded?
         NVMCON1bits.LWLO = 0;
                                     // Start PFM write
                                      // Disable writes
 NVMCON1bits.WREN = 0;
 INTCONbits.GIE = 1;
                                      // Enable interrupts
```

## 15.1.2.5 Modifying Flash Program Memory

When modifying existing data in a program memory, data within the memory row must be read and saved in a RAM image. Program memory is modified using the following steps:

- 1. Load the starting address of the row to be modified.
- 2. Read the existing data from the row into a RAM image.
- 3. Modify the RAM image to contain the new data to be written into program memory.
- 4. Load the starting address of the row to be rewritten.
- 5. Erase the program memory row.
- 6. Load the write latches with data from the RAM image.
- 7. Initiate a programming operation.

Figure 15-6. Program Flash Memory Modify Sequence



#### Notes:

- 1. See Figure 15-1.
- 2. See Figure 15-3.
- 3. See Figure 15-5.

## 15.1.2.6 NVMREG Access to DIA, DCI, User ID, Device ID, Revision ID, and Configuration Words

NVMREGS can be used to access the following memory regions:

- Device Information Area (DIA)
- Device Configuration Information (DCI)
- User ID region
- · Device ID and Revision ID
- · Configuration Words

The value of NVMREGS is set to '1' to access these regions. The memory regions listed above will be pointed to by PC[15] = 1, but not all addresses reference valid data. Different access may exist for reads and writes. Refer to the table below. When read access is initiated on an address outside the parameters listed in the following table, the NVMDATH: NVMDATL register pair is cleared, reading back '0's.


# Table 15-2. NVMREG Access to DIA, DCI, User ID, Device ID, Revision ID and Configuration Words (NVMREGS = 1)

Address	Function	Read Access	Write Access
0x8000 - 0x8003	User IDs	Yes	Yes
0x8005 - 0x8006	Device ID/Revision ID	Yes	No
0x8007 - 0x800B	Configuration Words 1-5	Yes	Yes
0x8100 - 0x82FF	DIA and DCI	Yes	No
0xF000 - 0xF0FF	EEPROM	Yes	Yes

## 15.1.2.7 Write Verify

It is considered good programming practice to verify that program memory writes agree with the intended value. Since program memory is stored as a full row then the stored program memory contents are compared with the intended data stored in RAM after the last write is complete.

Figure 15-7. Program Flash Memory Write Verify Sequence



#### Note:

1. See Figure 15-1.

#### 15.1.2.8 WRERR Bit

The WRERR bit can be used to determine if a write error occurred. WRERR will be set if one of the following conditions occurs:

- · If WR is set while the NVMADRH:NMVADRL points to a write-protected address
- · A Reset occurs while a self-write operation was in progress
- · An unlock sequence was interrupted

The WRERR bit is normally set by hardware, but can be set by the user for test purposes. Once set, WRERR must be cleared in software.

#### Table 15-3. Actions for PFM When WR = 1

Free	LWLO	Actions for PFM When WR = 1	Comments
1	x	Erase the 32-word row of NVMADRH:NVMADRL location	<ul> <li>If WP is enabled, WR is cleared and WRERR is set</li> <li>All 32 words are erased</li> <li>NVMDATH:NVMDATL is ignored</li> </ul>
0	1	Copy NVMDATH:NVMDATL to the write latch corresponding to NVMADR LSBs	<ul><li>Write protection is ignored</li><li>No memory access occurs</li></ul>
0	0	Write the write-latch data to PFM row	<ul> <li>If WP is enabled, WR is cleared and WRERR is set</li> <li>Write latches are reset to 0x3FFF</li> <li>NVMDATH:NVMDATL is ignored</li> </ul>

## 15.2 Data Flash Memory (DFM)

The Data Flash Memory is a nonvolatile memory array, also referred to as EEPROM. The DFM is mapped above program memory space. The DFM can be accessed using the FSRs or NVM Special Function Registers (SFRs). The DFM is readable and writable during normal operation over the entire  $V_{DD}$  range.

The DFM can only be read and written one byte at a time. When interfacing to the data memory block, the NVMDATL register holds the 8-bit data for read/write and the NVMADR register pair holds the address of the DFM location being accessed.

The DFM is rated for high erase/write cycle endurance. A byte write automatically erases the location and writes the new data (erase-before-write). The write time is controlled by an internal programming timer; it will vary with voltage and temperature as well as from device-to-device. Refer to the data EEPROM memory parameters in the "Electrical Specifications" chapter for more information.

#### 15.2.1 FSR and INDF Access

The File Select (FSR) and INDF registers allow read-only access to the DFM. The value of the FSR registers is used to determine the memory address location to be accessed.

## 15.2.1.1 FSR DFM Read

DFM is accessed by loading the FSRxH:FSRxL register pair with the address to be read, and loading bits [7-4] of the FSRxH register with a value of '0111'. When a MOVIW instruction, or any instruction that accesses INDFx, is executed, the value loaded into the FSRx register pair points to the location in program memory to be accessed. If the FSRx register pair points to an unimplemented address location, the read will return '0'.

## 15.2.1.2 FSR DFM Write

Writing/erasing the DFM through the FSR registers (e.g., the MOVWI instruction) is not supported in the PIC16F180 microcontroller family.

## 15.2.2 NVMREG Access

The NVMREG interface allows read/write access to the DFM.

Writing or erasing of DFM via the NVMREG interface is prevented when the DFM is write-protected (Configuration bit WRTD = '0').

#### 15.2.2.1 NVMREG Read Operation

To read a DFM location using the NVMREG interface, the user must:


- 1. Set the NVMREGS bit.
- 2. Write the desired address into the NVMADRH:NVMADRL register pair.
- 3. Set the RD bit to initiate the read.

Once the read control bit is set, the CPU operation is suspended during the read and resumes immediately after. The data is available in the very next cycle, in the NVMDATL register; therefore, it can be read in the following instructions.

The NVMDATL register will hold this value until another read or until it is written to by the user.

Upon completion, the RD bit is cleared by hardware.

Figure 15-8. Program Flash Memory Read Sequence



#### 15.2.2.2 NVM Unlock Sequence

The unlock sequence is a mechanism that protects the DFM from unintended self-write programming or erasing. The sequence must be executed and completed without interruption to successfully complete an erase or write operation.


The unlock sequence consists of the following steps and must be completed in order:

- Write 55h to NVMCON2
- Write AAh to NMVCON2
- Set the WR bit

Once the WR bit is set, the processor will stall internal operations until the operation is complete and then resume with the next instruction.

Since the unlock sequence must not be interrupted, global interrupts must be disabled prior to the unlock sequence and re-enabled after the unlock sequence is completed.

Figure 15-9. NVM Unlock Sequence



# Example 15-6. NVM Unlock Sequence

**Note:** Sequence begins when NVMCON2 is written; the three unlock steps must occur in the cycle-accurate order shown. If the timing of the sequence is corrupted by an interrupt or a debugger Halt, the action will not take place.

## 15.2.2.3 NVMREG Erase of DFM


DFM can be erased by writing '0xFF' to all locations that need to be erased. To erase a DFM word:

- 1. Set the NVMREGS bit.
- 2. Write the desired address into the NVMADRH:NVMADRL register pair.
- 3. Set the WREN bit.
- 4. Perform the unlock sequence as described in the NVM Unlock Sequence section.
- Set the WR bit.

A single byte (0xFF) is written into the DFM location. The DFM circuitry automatically erases the memory location before performing the write operation. If the DFM address is write-protected, the WR bit will be cleared and the write operation will not take place.

While erasing/writing data memory, CPU operation is suspended and resumes when the operation is complete. Upon completion, hardware clears the WR bit, the NVMIF bit is set, and an interrupt will occur if the NVMIE bit is also set.

Figure 15-10. DFM Erase Sequence



```
Example 15-7. Erasing One Byte of Data Flash Memory

// Code sequence to erase one byte of DFM

NVMCON1bits.NVMREGS = 1; // Point to DFM

NVMADR = DFM_ADDR; // NVMADRH = 0x70, NVMADRL = DFM address

NVMDATL = 0xFF; // Load NVMDATL with 0xFF
```

## **NVM - Nonvolatile Memory Control**

```
NVMCON1bits WREN = 1;
                               // Allows program/erase cycles
INTCONbits.GIE = 0;
                               // Disable interrupts
// Perform required unlock sequence
NVMCON2 = 0x55:
NVMCON2 = 0xAA;
NVMCON1bits.WR = 1;
                               // Begin program/erase cycle
                               // Restore interrupt enable bit value
INTCONbits.GIE = 1;
NVMCON1bits.WREN = 0;
                               // Disable program/erase
   Verify byte erase operation success and call the recovery function if needed
if (NVMCON1bits.WRERR)
    ERASE FAULT RECOVERY();
```

#### 15.2.2.4 NVMREG Write to DFM

DFM is programmed using the following steps:

- 1. Set the NVMREGS bit.
- 2. Load the NVMADRH:NVMADRL registers with the DFM address.
- 3. Load the NVMDATL register with the data byte to be written.
- 4. Set the WREN bit to allow write/erase cycles.
- 5. Disable the GIE bit.
- 6. Perform the NVM Unlock Sequence.
- 7. Set the WR bit.

A single byte (0xFF) is written into the DFM location. The DFM circuitry automatically erases the memory location before performing the write operation. If the DFM address is write-protected, the WR bit will be cleared and the write operation will not take place.

While erasing/writing data memory, the CPU operation is suspended and resumes when the operation is complete. Upon completion, hardware clears the WR bit, the NVMIF bit is set, and an interrupt will occur if the NVMIE bit is also set.

#### 15.2.2.5 WRERR Bit

The WRERR bit can be used to determine if a write error occurred. WRERR will be set if one of the following conditions occurs:

- If WR is set while the NVMADRH:NMVADRL points to a write-protected DFM address
- A Reset occurs while a self-write operation was in progress
- · An unlock sequence was interrupted


The WRERR bit is normally set by hardware, but can be set by the user for test purposes. Once set, WRERR must be cleared in software.

## 15.3 Register Definitions: Nonvolatile Memory Control

## 15.3.1 **NVMADR**

Name: NVMADR Offset: 0x1C8C

Nonvolatile Memory Address Register



Bits 14:0 - NVMADR[14:0] NVM Address Bits

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - NVMADRH: Accesses the high byte NVMADR[15:8]
  - NVMADRL: Accesses the low byte NVMADR[7:0].
- 2. Bit [15] is undefined while WR = 1.

## 15.3.2 NVMDAT

Name: NVMDAT Offset: 0x1C8E

Nonvolatile Memory Data Register

Bit	15	14	13	12	11	10	9	8
					NVMDA	AT[13:8]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			X	X	X	x	x	x
Bit	7	6	5	4	3	2	1	0
			NVMDAT[7:0]					
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	x	x	x	x	x	x	x	x

All Other Resets = uuuuuuuuuuuuu

**Notes:** The individual bytes in this multibyte register can be accessed with the following register names:

- NVMDATH: Accesses the high byte NVMDAT[13:8]
- NVMDATL: Accesses the low byte NVMDAT[7:0]

#### 15,3,3 NVMCON1

Name: NVMCON1 Offset: 0x1C90

Nonvolatile Memory Control 1 Register

Bit	7	6	5	4	3	2	1	0
		NVMREGS	LWLO	FREE	WRERR	WREN	WR	RD
Access		R/W	R/W	R/S/HC	R/W/HS	R/W	R/S/HC	R/S/HC
Reset		0	0	0	0	0	0	0

## Bit 6 - NVMREGS NVM Region Selection

Value	Description
1	Access DFM (EEPROM), DIA, DCI, Configuration, User ID, Revision ID, and Device ID Registers
0	Access Program Flash Memory

## Bit 5 - LWLO Load Write Latches Only

Value	Condition	Description
1	When FREE = 0	The next WR command updates the write latch for this word within the row; no
		memory operation is initiated
0	When FREE = 0	The next WR command writes data or erases
_	Otherwise:	This bit is ignored

## Bit 4 - FREE Program Flash Memory Erase Enable

Value	Description
1	Performs an erase operation with the next WR command; the 32-word pseudo-row containing the
	indicated address is erased (to all 1s) to prepare for writing
0	The next WR command writes without erasing

## Bit 3 – WRERR

Write-Reset Error Flag(1,2,3)

Time Hood End Flag					
Value	Description				
1	A write operation error has occurred				
0	All write operations have completed normally				

## Bit 2 - WREN Program/Erase Enable

Value	Description
1	Allows program/erase cycles
0	Inhibits programming/erasing of program Flash

## Bit 1 - WR Write Control (4,5,6)

Value	Description				
1	Initiates the program/erase operation at the corresponding NVM location				
0	NVM program/erase operation is complete and inactive				

#### Bit 0 - RD Read Control

Va	lue	Description				
1		Initiates a read at address = NVMADR				
0		NVM read operation is complete and inactive				

# PIC16F18015/25/44/45

# **NVM - Nonvolatile Memory Control**

#### Notes:

- 1. Bit is undefined while WR = 1.
- 2. Bit must be cleared by software; hardware will not clear this bit.
- 3. Bit may be written to '1' by the user to implement test sequences.
- 4. This bit can only be set by following the sequence described in the "NVM Unlock Sequence" section.
- 5. Operations are self-timed and the WR bit is cleared by hardware when complete.
- 6. Once a write operation is initiated, setting this bit to zero will have no effect.

## 15.3.4 NVMCON2

Name: NVMCON2 Offset: 0x1C91

Nonvolatile Memory Control 2 Register

Bit	7	6	5	4	3	2	1	0
[	NVMCON2[7:0]							
Access	WO	WO	WO	WO	WO	WO	WO	WO
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - NVMCON2[7:0] Flash Memory Unlock Pattern bits

**Note:** To unlock writes, a 0x55 must be written first followed by an 0xAA before setting the WR bit of the NVMCON1 register. The value written to this register is used to unlock the writes.

# 15.4 Register Summary - NVM Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x1C8B										
0x1C8C	NVMADR	7:0		NVMADR[7:0]						
		15:8		NVMADR[14:8]						
0x1C8E	NVMDAT	7:0		NVMDAT[7:0]						
UXICOE	NVIVIDAT	15:8					NVMDA	AT[13:8]		
0x1C90	NVMCON1	7:0		NVMREGS	LWLO	FREE	WRERR	WREN	WR	RD
0x1C91	NVMCON2	7:0	NVMCON2[7:0]							

## 16. I/O Ports

#### 16.1 Overview

Table 16-1. Port Availability per Device

Device	PORTA	PORTB	PORTC
8-pin devices	•		
14/16-pin devices	•		•
20-pin devices	•	•	•


Each port has eight registers to control the operation. These registers are:

- · PORTx registers (reads the levels on the pins of the device)
- LATx registers (output latch)
- · TRISx registers (data direction)
- ANSELx registers (analog select)
- WPUx registers (weak pull-up)
- INLVLx (input level control)
- · SLRCONx registers (slew rate control)
- ODCONx registers (open-drain control)

In this section, the generic names such as PORTx, LATx, TRISx, etc. can be associated with PORTA, PORTB, PORTC, etc., depending on availability per device.

A simplified model of a generic I/O port, without the interfaces to other peripherals, is shown in the following figure:

Figure 16-1. Generic I/O Port Operation



## 16.2 PORTx - Data Register

PORTx is a bidirectional port, and its corresponding data direction register is TRISx.

Reading the PORTx register reads the status of the pins, whereas writing to it will write to the PORT latch. All write operations are Read-Modify-Write operations. Therefore, a write to a port implies that the PORT pins are read, and this value is modified, then written to the PORT data latch (LATx). The PORT data latch LATx holds the output port data and contains the latest value of a LATx or PORTx write. The example below shows how to initialize PORTA.

```
Example 16-1. Initializing PORTA in Assembly
 ; This code example illustrates initializing the PORTA register.
 ; The other ports are initialized in the same manner.
     BANKSEL
                PORTA
                PORTA
                              ;Clear PORTA
     CLRF
     BANKSEL
                LATA
     CLRF
                LATA
                              ;Clear Data Latch
     BANKSET.
                ANSELA
     CLRF
                ANSELA
                              ;Enable digital drivers
     BANKSEL
                TRISA
     MOVLW
                B'00111000'
                              ;Set RA[5:3] as inputs
     MOVWF
                TRISA
                              ; and set others as outputs
```



**Important:** Most PORT pins share functions with device peripherals, both analog and digital. In general, when a peripheral is enabled on a PORT pin, that pin cannot be used as a general purpose output; however, the pin can still be read.

# 16.3 LATx - Output Latch

The Data Latch (LATx registers) is useful for Read-Modify-Write operations on the value that the I/O pins are driving.

A write operation to the LATx register has the same effect as a write to the corresponding PORTx register. A read of the LATx register reads of the values held in the I/O PORT latches, while a read of the PORTx register reads the actual I/O pin value.



**Important:** As a general rule, output operations to a port must use the LAT register to avoid Read-Modify-Write issues. For example, a bit set or clear operation reads the port, modifies the bit, and writes the result back to the port. When two bit operations are executed in succession, output loading on the changed bit may delay the change at the output in which case the bit will be misread in the second bit operation and written to an unexpected level. The LAT registers are isolated from the port loading and therefore changes are not delayed.

## 16.4 TRISx - Direction Control

The TRISx register controls the PORTx pin output drivers, even when the pins are being used as analog inputs. The user must ensure the bits in the TRISx register are set when using the pins as analog inputs. I/O pins configured as analog inputs always read '0'.

Setting a TRISx bit (TRISx = 1) will make the corresponding PORTx pin an input (i.e., disable the output driver). Clearing a TRISx bit (TRISx = 0) will make the corresponding PORTx pin an output (i.e., it enables output driver and puts the contents of the output latch on the selected pin).

## 16.5 ANSELx - Analog Control

Ports that support analog inputs have an associated ANSELx register. The ANSELx register is used to configure the Input mode of an I/O pin to analog. Setting an ANSELx bit high will disable the digital input buffer associated with that bit and cause the corresponding input value to always read '0', whether the value is read in PORTx register or selected by PPS as a peripheral input.

Disabling the input buffer prevents analog signal levels on the pin between a logic high and low from causing excessive current in the logic input circuitry.

The state of the ANSELx bits has no effect on digital or analog output functions. A pin with TRIS clear and ANSEL set will still operate as a digital output, but the Input mode will be analog. This can cause unexpected behavior when executing Read-Modify-Write instructions on the PORTx register.



**Important:** The ANSELx bits default to the Analog mode after Reset. To use any pins as digital general purpose or peripheral inputs, the corresponding ANSEL bits must be changed to '0' by the user.

## 16.6 WPUx - Weak Pull-Up Control

The WPUx register controls the individual weak pull-ups for each PORT pin. When a WPUx bit is set (WPUx = 1), the weak pull-up will be enabled for the corresponding pin. When a WPUx bit is cleared (WPUx = 0), the weak pull-up will be disabled for the corresponding pin.

#### 16.7 INLVLx - Input Threshold Control

The INLVLx register controls the input voltage threshold for each of the available PORTx input pins. A selection between the Schmitt Trigger CMOS or the TTL compatible thresholds is available. If that feature is enabled, the input threshold is important in determining the value of a read of the PORTx register and also all other peripherals which are connected to the input. Refer to the I/O Ports table in the "Electrical Specifications" chapter for more details on threshold levels.



**Important:** Changing the input threshold selection must be performed while all peripheral modules are disabled. Changing the threshold level during the time a module is active may inadvertently generate a transition associated with an input pin, regardless of the actual voltage level on that pin.

## 16.8 SLRCONx - Slew Rate Control

The SLRCONx register controls the slew rate option for each PORT pin. Slew rate for each PORT pin can be controlled independently. When a SLRCONx bit is set (SLRCONx = 1), the corresponding PORT pin drive is slew

rate limited. When a SLRCONx bit is cleared (SLRCONx = 0), the corresponding PORT pin drive slews at the maximum rate possible.

## 16.9 ODCONx - Open-Drain Control

The ODCONx register controls the open-drain feature of the port. Open-drain operation is independently selected for each pin. When a ODCONx bit is set (ODCONx = 1), the corresponding port output becomes an open-drain driver capable of sinking current only. When a ODCONx bit is cleared (ODCONx = 0), the corresponding port output pin is the standard push-pull drive capable of sourcing and sinking current.



**Important:** It is necessary to set open-drain control when using the pin for I<sup>2</sup>C.

## 16.10 Edge Selectable Interrupt-on-Change

An interrupt can be generated by detecting a signal at the PORT pin that has either a rising edge or a falling edge. Individual pins can be independently configured to generate an interrupt. Refer to the "IOC - Interrupt-on-Change" chapter for more details.

#### 16.11 I<sup>2</sup>C Pad Control

For this family of devices, the I<sup>2</sup>C specific pads are available on RA1 and RA2 (8-pin devices), RB4, RB5, RB6, and RB7 (20-pin devices), and RC0, RC1, RC4, and RC5 (14/16-pin devices) pins. The I<sup>2</sup>C characteristics of each of these pins is controlled by the RxyI2C registers. These characteristics include enabling I<sup>2</sup>C specific slew rate (over standard GPIO slew rate), selecting internal pull-ups for I<sup>2</sup>C pins, and selecting appropriate input threshold as per SMBus specifications.



Important: Any peripheral using the I<sup>2</sup>C pins reads the I<sup>2</sup>C input levels when enabled via Rxyl2C.

#### 16.12 I/O Priorities

Each pin defaults to the data latch after Reset. Other functions are selected with the Peripheral Pin Select logic. Refer to the "PPS - Peripheral Pin Select Module" chapter for more details.

Analog input functions, such as ADC and comparator inputs, are not shown in the Peripheral Pin Select lists. These inputs are active when the I/O pin is set for Analog mode using the ANSELx register. Digital output functions may continue to control the pin when it is in Analog mode.

Analog outputs, when enabled, take priority over digital outputs and force the digital output driver into a High-Impedance state.

The pin function priorities are as follows:

- 1. Port functions determined by the Configuration bits.
- 2. Analog outputs (input buffers must be disabled).
- 3. Analog inputs.
- 4. Port inputs and outputs from PPS.

## 16.13 MCLR/V<sub>PP</sub>/RA3 Pin

The  $\overline{\text{MCLR}}/V_{PP}$  pin is an input-only pin. Its operation is controlled by the MCLRE Configuration bit. When selected as a PORT pin (MCLRE = 0), it functions as a digital input-only pin; as such, it does not have TRISx and LATx bits associated with its operation. Otherwise, it functions as the device's Master Clear input. In either configuration, the  $\overline{\text{MCLR}}/V_{PP}$  pin also functions as the programming voltage input pin during high-voltage programming.

The  $\overline{\text{MCLR}/\text{V}_{PP}}$  pin is a read-only bit and will read '1' when MCLRE = 1 (i.e., Master Clear enabled).



**Important:** On a Power-on Reset (POR), the  $\overline{MCLR}/V_{PP}$  pin is enabled as a digital input-only if Master Clear functionality is disabled.

The  $\overline{\text{MCLR}}/\text{V}_{PP}$  pin has an individually controlled internal weak pull-up. When set, the corresponding WPU bit enables the pull-up. When the  $\overline{\text{MCLR}}/\text{V}_{PP}$  pin is configured as  $\overline{\text{MCLR}}$  (MCLRE = 1 and LVP = 0), or configured for Low-Voltage Programming (MCLRE = x and LVP = 1), the pull-up is always enabled and the WPU bit has no effect.

## 16.14 Register Definitions: Port Control

#### 16,14,1 PORTx

Name: PORTx

PORTx Register

Bit	7	6	5	4	3	2	1	0
	Rx7	Rx6	Rx5	Rx4	Rx3	Rx2	Rx1	Rx0
Access	R/W							
Reset	X	X	X	X	X	X	X	X

#### Bits 0, 1, 2, 3, 4, 5, 6, 7 - Rxn Port I/O Value

Reset States: POR/BOR = xxxxxxxx

All Other Resets = uuuuuuuu

Value	Description
1	PORT pin is ≥ V <sub>IH</sub>
0	PORT pin is ≤ V <sub>IL</sub>



- Writes to PORTx are actually written to the corresponding LATx register. Reads from PORTx register return actual I/O pin values.
- The PORT bit associated with the  $\overline{MCLR}$  pin is read-only and will read '1' when the  $\overline{MCLR}$  function is enabled (LVP = 1 or (LVP = 0 and MCLRE = 1))
- Refer to the "Pin Allocation Table" for details about MCLR pin and pin availability per port
- Unimplemented bits will read back as '0'

#### 16.14.2 LATx

Name: LATx

Output Latch Register

Bit	7	6	5	4	3	2	1	0
[	LATx7	LATx6	LATx5	LATx4	LATx3	LATx2	LATx1	LATx0
Access	R/W							
Reset	Х	Х	X	X	Х	X	X	X

Bits 0, 1, 2, 3, 4, 5, 6, 7 - LATxn Output Latch Value

Reset States: POR/BOR = xxxxxxxx

All Other Resets = uuuuuuuu



- Writes to LATx are equivalent to writes to the corresponding PORTx register. Reads from LATx register return register values, not I/O pin values.
- Refer to the "Pin Allocation Table" for details about pin availability per port
- Unimplemented bits will read back as '0'

## 16,14,3 TRISx

Name: TRISx

Tri-State Control Register

Bit	7	6	5	4	3	2	1	0
	TRISx7	TRISx6	TRISx5	TRISx4	TRISx3	TRISx2	TRISx1	TRISx0
Access	R/W							
Reset	1	1	1	1	1	1	1	1

#### Bits 0, 1, 2, 3, 4, 5, 6, 7 - TRISxn Port I/O Tri-state Control

Value	Description
1	PORTx output driver is disabled. PORTx pin configured as an input (tri-stated)
0	PORTx output driver is enabled. PORTx pin configured as an output



- The TRIS bit associated with the  $\overline{\text{MCLR}}$  pin is read-only and the value is '1'
- Refer to the "Pin Allocation Table" for details about MCLR pin and pin availability per port
- Unimplemented bits will read back as '0'

#### 16.14.4 ANSELx

Name: ANSELx

Analog Select Register

Bit	7	6	5	4	3	2	1	0
Γ	ANSELx7	ANSELx6	ANSELx5	ANSELx4	ANSELx3	ANSELx2	ANSELx1	ANSELx0
Access	R/W							
Reset	1	1	1	1	1	1	1	1

#### Bits 0, 1, 2, 3, 4, 5, 6, 7 - ANSELxn Analog Select on RX Pin

Value	Description
1	Analog input. Pin is assigned as analog input. Digital input buffer disabled.
0	Digital I/O. Pin is assigned to port or digital special function.



- When setting a pin as an analog input, the corresponding TRIS bit must be set to Input mode to allow external control of the voltage on the pin
- Refer to the "Pin Allocation Table" for details about pin availability per port
- Unimplemented bits will read back as '0'

#### 16,14,5 WPUx

Name: WPUx

Weak Pull-Up Register

Bit	7	6	5	4	3	2	1	0
	WPUx7	WPUx6	WPUx5	WPUx4	WPUx3	WPUx2	WPUx1	WPUx0
Access	R/W							
Reset	0	0	0	0	0	0	0	0

#### Bits 0, 1, 2, 3, 4, 5, 6, 7 - WPUxn Weak Pull-up PORTx Control

√alue	Description
1	Weak pull-up enabled
)	Weak pull-up disabled



- The weak pull-up device is automatically disabled if the pin is configured as an output, but this register remains unchanged
- If MCLRE = 1, the weak pull-up on MCLR pin is always enabled and the corresponding WPU bit is not affected
- Refer to the "Pin Allocation Table" for details about pin availability per port
- Unimplemented bits will read back as '0'

## 16.14.6 INLVLx

Name: INLVLx

Input Level Control Register

Bit	7	6	5	4	3	2	1	0
	INLVLx7	INLVLx6	INLVLx5	INLVLx4	INLVLx3	INLVLx2	INLVLx1	INLVLx0
Access	R/W							
Reset	1	1	1	1	1	1	1	1

#### Bits 0. 1. 2. 3. 4. 5. 6. 7 - INLVLxn Input Level Select on RX Pin

Die v, 1, 2, v, 1, v, v, 1 Intervent impact cover collect of 1 v v 1 in									
Value	Description								
1	ST input used for port reads and interrupt-on-change								
0	TTL input used for port reads and interrupt-on-change								



- Refer to the "Pin Allocation Table" for details about pin availability per port
- Unimplemented bits will read back as '0'

#### 16.14.7 SLRCONx

Name: SLRCONx

Slew Rate Control Register

Bit	7	6	5	4	3	2	1	0
Γ	SLRx7	SLRx6	SLRx5	SLRx4	SLRx3	SLRx2	SLRx1	SLRx0
Access	R/W							
Reset	1	1	1	1	1	1	1	1

#### Bits 0, 1, 2, 3, 4, 5, 6, 7 - SLRxn Slew Rate Control on RX Pin

Value	Description
1	PORT pin slew rate is limited
0	PORT pin slews at maximum rate



- Refer to the "Pin Allocation Table" for details about pin availability per port
- Unimplemented bits will read back as '0'

#### 16.14.8 ODCONx

Name: ODCONx

Open-Drain Control Register

Bit	7	6	5	4	3	2	1	0
	ODCx7	ODCx6	ODCx5	ODCx4	ODCx3	ODCx2	ODCx1	ODCx0
Access	R/W							
Reset	0	0	0	0	0	0	0	0

#### Bits 0. 1. 2. 3. 4. 5. 6. 7 - ODCxn Open-Drain Configuration on Rx Pin

, _,	o, i, o, o, i opon brain comigaration of tax in
Value	Description
1	PORT pin operates as open-drain drive (sink current only)
0	PORT pin operates as standard push-pull drive (source and sink current)



- Refer to the "Pin Allocation Table" for details about pin availability per port
- Unimplemented bits will read back as '0'

## 16.14.9 Rxyl2C

Name: Rxyl2C

I<sup>2</sup>C Pad Rxy Control Register

Bit	7	6	5	4	3	2	1	0
		SLEW	PU[	1:0]			TH	[1:0]
Access		R/W	R/W	R/W			R/W	R/W
Reset		0	0	0			0	0

## Bit 6 - SLEW I2C Specific Slew Rate Limiting Control

Value	Description
1	I <sup>2</sup> C specific slew rate limiting is enabled. Standard pad slew limiting is disabled. The SLRxy bit is
	ignored
0	Standard GPIO Slew Rate; enabled/disabled via SLRxy bit

## Bits 5:4 – PU[1:0] I<sup>2</sup>C Pull-Up Selection

Value	Description
11	Reserved
10	10x current of standard weak pull-up
01	2x current of standard weak pull-up
00	Standard GPIO weak pull-up, enabled via the WPUxy bit

## Bits 1:0 - TH[1:0] I<sup>2</sup>C Input Threshold Selection

Value	Description
value	Description
11	SMBus 3.0 (1.35V) input threshold
10	SMBus 2.0 (2.1V) input threshold
01	I <sup>2</sup> C-specific input thresholds
00	Standard GPIO Input pull-up, enabled via the INLVLxy registers



- Refer to the "Pin Allocation Table" for details about pin availability per port
- Unimplemented bits will read back as '0'

# 16.15 Register Summary - IO Ports

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x0B										
0x0C	PORTA	7:0	555	222	RA5	RA4	RA3	RA2	RA1	RA0
0x0D	PORTB	7:0	RB7	RB6	RB5	RB4	200		504	500
0x0E	PORTC	7:0	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0
0x0F	Reserved									
 0x11	Neserveu									
0x11	TRISA	7:0			TRISA5	TRISA4	Reserved	TRISA2	TRISA1	TRISA0
0x13	TRISB	7:0	TRISB7	TRISB6	TRISB5	TRISB4	110001100			
0x14	TRISC	7:0	TRISC7	TRISC6	TRISC5	TRISC4	TRISC3	TRISC2	TRISC1	TRISC0
0x15										
	Reserved									
0x17										
0x18	LATA	7:0			LATA5	LATA4		LATA2	LATA1	LATA0
0x19	LATB	7:0	LATB7	LATB6	LATB5	LATB4				
0x1A	LATC	7:0	LATC7	LATC6	LATC5	LATC4	LATC3	LATC2	LATC1	LATC0
0x1B	_									
	Reserved									
0x1E8B	ANIOE! A	7.0			4105145	ANOE! A 4	111051.10	ANGELAG	41105144	1105110
0x1E8C	ANSELA WPUA	7:0			ANSELA5	ANSELA4	ANSELA3	ANSELA2	ANSELA1	ANSELA0
0x1E8D 0x1E8E	ODCONA	7:0 7:0			WPUA5 ODCA5	WPUA4 ODCA4	WPUA3	WPUA2 ODCA2	WPUA1 ODCA1	WPUA0 ODCA0
0x1E8E	SLRCONA	7:0			SLRA5	SLRA4		SLRA2	SLRA1	SLRA0
0x1E81	INLVLA	7:0			INLVLA5	INLVLA4	INLVLA3	INLVLA2	INLVLA1	INLVLA0
0x1E90	INLVLA	7.0			INLVEAS	INLVLA	INLVEAS	INLVEAZ	INCVERT	INLVEAU
	Reserved									
0x1E95	110001104									
0x1E96	ANSELB	7:0	ANSELB7	ANSELB6	ANSELB5	ANSELB4				
0x1E97	WPUB	7:0	WPUB7	WPUB6	WPUB5	WPUB4				
0x1E98	ODCONB	7:0	ODCB7	ODCB6	ODCB5	ODCB4				
0x1E99	SLRCONB	7:0	SLRB7	SLRB6	SLRB5	SLRB4				
0x1E9A	INLVLB	7:0	INLVLB7	INLVLB6	INLVLB5	INLVLB4				
0x1E9B										
	Reserved									
0x1E9F	ANOFLO	7.0	ANIOELOZ	ANGELOS	ANIOFICE	ANOFIOA	ANGELOS	ANGELOS	ANGELOA	ANOFICO
0x1EA0	ANSELC	7:0	ANSELC7	ANSELC6	ANSELC5	ANSELC4	ANSELC3	ANSELC2	ANSELC1	ANSELCO
0x1EA1 0x1EA2	WPUC ODCONC	7:0 7:0	WPUC7 ODCC7	WPUC6 ODCC6	WPUC5 ODCC5	WPUC4 ODCC4	WPUC3 ODCC3	WPUC2 ODCC2	WPUC1 ODCC1	WPUC0 ODCC0
0x1EA2	SLRCONC	7:0	SLRC7	SLRC6	SLRC5	SLRC4	SLRC3	SLRC2	SLRC1	SLRC0
0x1EA4	INLVLC	7:0	INLVLC7	INLVLC6	INLVLC5	INLVLC4	INLVLC3	INLVLC2	INLVLC1	INLVLC0
0x1EA5		7.5	11121207	11127200	11121200	11,1,1,1,0,1	11127200	11127202	11127201	11,2,200
	Reserved									
0x1EE0										
0x1EE1	RA1I2C	7:0		SLEW	PU[	1:0]			THI	1:0]
0x1EE2	RA2I2C	7:0		SLEW	PU[				TH	1:0]
0x1EE3										
	Reserved									
0x1EE4										
0x1EE5	RB4I2C	7:0		SLEW	PU[					1:0]
0x1EE6	RB5I2C	7:0		SLEW	PU[					1:0]
0x1EE7	RB6I2C	7:0		SLEW	PU[					1:0]
0x1EE7	RB7I2C	7:0		SLEW	PU[	1:0]			TH	[1:0]
0x1EE8	Reserved	7.0		01 = 111		4 . 01				4.01
0x1EE9	RC0I2C	7:0		SLEW	PU[					1:0]
0x1EEA	RC1I2C	7:0		SLEW	PU[	1:0]			ſĦļ	[1:0]

# PIC16F18015/25/44/45

I/O Ports

continued										
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x1EEB	Reserved									
0x1EEC	RC4I2C	7:0		SLEW	PU	[1:0]			TH	[1:0]
0x1EED	RC5I2C	7:0		SLEW	PU	[1:0]			TH	[1:0]

# 17. IOC - Interrupt-on-Change

#### 17.1 Overview

The pins denoted in the table below can be configured to operate as interrupt-on-change (IOC) pins for this device. An interrupt can be generated by detecting a signal that has either a rising edge or a falling edge. Any individual PORT pin, or combination of PORT pins, can be configured to generate an interrupt.

Table 17-1. IOC Pin Availability per Device

Device	PORTA	PORTB	PORTC
8-pin devices	•		
14/16-pin devices	•		•
20-pin devices	•	•	•




**Important:** If MCLRE = 1 or LVP = 1, the  $\overline{\text{MCLR}}$  pin port functionality is disabled and IOC on that pin is not available.

The interrupt-on-change module has the following features:

- · Interrupt-on-change enable (Host Switch)
- · Individual pin configuration
- · Rising and falling edge detection
- · Individual pin interrupt flags

The following figure is a block diagram of the IOC module.

Figure 17-1. Interrupt-on-Change Block Diagram (PORTA Example)



## 17.2 Enabling the Module

For individual PORT pins to generate an interrupt, the IOC Interrupt Enable (IOCIE) bit of the Peripheral Interrupt Enable (PIEx) register must be set. If the IOC Interrupt Enable bit is disabled, the edge detection on the pin will still occur, but an interrupt will not be generated.

## 17.3 Individual Pin Configuration

A rising edge detector and a falling edge detector are present for each PORT pin. To enable a pin to detect a rising edge, the associated bit of the IOCxP register must be set. To enable a pin to detect a falling edge, the associated bit of the IOCxN register must be set. A PORT pin can be configured to detect rising and falling edges simultaneously by setting both associated bits of the IOCxP and IOCxN registers, respectively.


## 17.4 Interrupt Flags

The bits located in the IOCxF registers are status flags that correspond to the interrupt-on-change pins of each port. If an expected edge is detected on an appropriately enabled pin, then the status flag for that pin will be set, and an interrupt will be generated if the IOCIE bit is set. The IOCIF bit located in the corresponding Peripheral Interrupt Request (PIRx) register, is all the IOCxF bits ORd together. The IOCIF bit is read-only. All of the IOCxF Status bits must be cleared to clear the IOCIF bit.

## 17.5 Clearing Interrupt Flags

The individual status flags (IOCxF register bits) will be cleared by resetting them to zero. If another edge is detected during this clearing operation, the associated status flag will be set at the end of the sequence, regardless of the value actually being written.

To ensure that no detected edge is lost while clearing flags, only AND operations masking out known changed bits must be performed. The following sequence is an example of clearing an IOC interrupt flag using this method.



## 17.6 Operation in Sleep

An interrupt-on-change event will wake the device from Sleep mode, if the IOCIE bit is set. If an edge is detected while in Sleep mode, the IOCxF register will be updated prior to the first instruction executed out of Sleep.

# 17.7 Register Definitions: Interrupt-on-Change Control

#### 17.7.1 IOCxF

Name: IOCxF

Interrupt-on-Change Flag Register

Bit	7	6	5	4	3	2	1	0
	IOCxF7	IOCxF6	IOCxF5	IOCxF4	IOCxF3	IOCxF2	IOCxF1	IOCxF0
Access	R/W/HS							
Reset	0	0	0	0	0	0	0	0

Bits 0, 1, 2, 3, 4, 5, 6, 7 – IOCxFn Interrupt-on-Change Flag

Value	Condition	Description
1	IOCxP[n] = 1	A positive edge was detected on the Rx[n] pin
1	IOCxN[n] = 1	A negative edge was detected on the Rx[n] pin
0	IOCxP[n] = x and $IOCxN[n] = x$	No change was detected, or the user cleared the detected change



- If MCLRE = 1 or LVP = 1, the MCLR pin port functionality is disabled and IOC on that pin is not available
- Refer to the "Pin Allocation Table" for details about pins with configurable IOC per port

#### 17.7.2 IOCxN

Name: IOCxN

Interrupt-on-Change Negative Edge Register Example

Bit	7	6	5	4	3	2	1	0
Γ	IOCxN7	IOCxN6	IOCxN5	IOCxN4	IOCxN3	IOCxN2	IOCxN1	IOCxN0
Access	R/W							
Reset	0	0	0	0	0	0	0	0

Bits 0, 1, 2, 3, 4, 5, 6, 7 - IOCxNn Interrupt-on-Change Negative Edge Enable

Value	Description				
1	Interrupt-on-change enabled on the IOCx pin for a negative-going edge. Associated Status bit and				
	interrupt flag will be set upon detecting an edge.				
0	Falling edge interrupt-on-change disabled for the associated pin				



- If MCLRE = 1 or LVP = 1, the MCLR pin port functionality is disabled and IOC on that pin is not available
- Refer to the "Pin Allocation Table" for details about pins with configurable IOC per port

#### 17.7.3 IOCxP

Name: IOCxP

Interrupt-on-Change Positive Edge Register

Bit	7	6	5	4	3	2	1	0
	IOCxP7	IOCxP6	IOCxP5	IOCxP4	IOCxP3	IOCxP2	IOCxP1	IOCxP0
Access	R/W							
Reset	0	0	0	0	0	0	0	0

Bits 0, 1, 2, 3, 4, 5, 6, 7 – IOCxPn Interrupt-on-Change Positive Edge Enable

Value	Description					
1	Interrupt-on-change enabled on the IOCx pin for a positive-going edge. Associated Status bit and					
	interrupt flag will be set upon detecting an edge.					
0	Rising edge interrupt-on-change disabled for the associated pin.					



- If MCLRE = 1 or LVP = 1, the MCLR pin port functionality is disabled and IOC on that pin is not available
- Refer to the "Pin Allocation Table" for details about pins with configurable IOC per port

# 17.8 Register Summary - Interrupt-on-Change

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
 0x1E90	Reserved									
0x1E91	IOCAP	7:0			IOCAP5	IOCAP4	IOCAP3	IOCAP2	IOCAP1	IOCAP0
0x1E92	IOCAN	7:0			IOCAN5	IOCAN4	IOCAN3	IOCAN2	IOCAN1	IOCAN0
0x1E93	IOCAF	7:0			IOCAF5	IOCAF4	IOCAF3	IOCAF2	IOCAF1	IOCAF0
0x1E94  0x1E9A	Reserved									
0x1E9B	IOCBP	7:0	IOCBP7	IOCBP6	IOCBP5	IOCBP4				
0x1E9C	IOCBN	7:0	IOCBN7	IOCBN6	IOCBN5	IOCBN4				
0x1E9D	IOCBF	7:0	IOCBF7	IOCBF6	IOCBF5	IOCBF4				
0x1E9E  0x1EA4	Reserved									
0x1EA5	IOCCP	7:0	IOCCP7	IOCCP6	IOCCP5	IOCCP4	IOCCP3	IOCCP2	IOCCP1	IOCCP0
0x1EA6	IOCCN	7:0	IOCCN7	IOCCN6	IOCCN5	IOCCN4	IOCCN3	IOCCN2	IOCCN1	IOCCN0
0x1EA7	IOCCF	7:0	IOCCF7	IOCCF6	IOCCF5	IOCCF4	IOCCF3	IOCCF2	IOCCF1	IOCCF0

# 18. PPS - Peripheral Pin Select Module

#### 18.1 Overview


The Peripheral Pin Select (PPS) module connects peripheral inputs and outputs to the device I/O pins. Only digital signals are included in the selections.



**Important:** All analog inputs and outputs remain fixed to their assigned pins and cannot be changed through PPS.

Input and output selections are independent as shown in the figure below.

Figure 18-1. PPS Block Diagram



## 18.2 PPS Inputs

Each digital peripheral has a dedicated PPS Peripheral Input Selection (xxxPPS) register with which the input pin to the peripheral is selected. Devices that have 20 leads or less (8/14/16/20) allow PPS routing to any I/O pin, while devices with 28 leads or more allow PPS routing to I/Os contained within two ports (see the table below).



**Important:** The notation "xxx" in the generic register name is a placeholder for the peripheral identifier. For example, xxx = T0CKI for the T0CKIPPS register.

Multiple peripherals can operate from the same source simultaneously. Port reads always return the pin level regardless of peripheral PPS selection. If a pin also has analog functions associated, the ANSEL bit for that pin must be cleared to enable the digital input buffer.

Table 18-1. PPS Input Selection Table

		Regis	ster Reset Value a	at POR	Default Pin Selection at POR		
Peripheral	PPS Input Register	8-Pin Devices	14/16-Pin	20-Pin Devices	8-Pin	14/16-Pin	20-Pin
					Devices	Devices	Devices
External Interrupt	INTPPS		<b>'</b> b000 010			RA2	
Timer0 Clock	T0CKIPPS		<b>'</b> b000 010			RA2	
Timer1 Clock	T1CKIPPS		'b000 101			RA5	
Timer1 Gate	T1GPPS		<b>'</b> b000 100			RA4	
Timer3 Clock	T3CKIPPS	'b000 000d	<b>'</b> b010		RA0	RO	
Timer3 Gate	T3GPPS	'b000 000d'	<b>'</b> b010	100	RA0	RO	C4
Timer2 Input	T2INPPS		<b>'</b> b000 101			RA5	
Timer4 Input	T4INPPS	000 000d'	<b>'</b> b010	001	RA0	RO	21
Timer6 Input	T6INPPS	'b000 001	<b>'</b> b010	010	RA1	RO	22
CCP1	CCP1PPS	'b000 101	<b>'</b> b010	101	RA5	RO	C5
CCP2	CCP2PPS	<b>'</b> b000 101	<b>'</b> b010	011	RA5	RO	23
CWG1	CWG1PPS		'b000 010			RA2	
CLCIN0	CLCIN0PPS	<b>'</b> b000 011	<b>'</b> b010 011	'b000 010	RA3	RC3	RA2
CLCIN1	CLCIN1PPS	<b>'</b> b000 101	<b>'</b> b010 100	'b010 011	RA5	RC4	RC3
CLCIN2	CLCIN2PPS	<b>'</b> b000 001	<b>'</b> b010 001	'b001 100	RA1	RC1	RB4
CLCIN3	CLCIN3PPS	000 000d'	<b>'</b> b000 101	'b001 101	RA0	RA5	RB5
SCL1/SCK1	SSP1CLKPPS(1)	<b>'</b> b000 001	<b>'</b> b010 000	'b001 110	RA1	RC0	RB6
SDA1/SDI1	SSP1DATPPS(1)	<b>'</b> b000 010	<b>'</b> b010 001	'b001 100	RA2	RC1	RB4
SS1	SSP1SSPPS	<b>'</b> b000 011	<b>'</b> b010 011	'b010 110	RA3	RC3	RC6
SCL2/SCK2	SSP2CLKPPS <sup>(1)</sup>	000 000d'	<b>'</b> b010 100	'b001 111	RA0	RC4	RB7
SDA2/SDI2	SSP2DATPPS <sup>(1)</sup>	000 000d'	<b>'</b> b010 101	'b001 101	RA0	RC5	RB5
SS2	SSP2SSPPS	<b>'</b> b00	000 000	'b000 001	R	A0	RA1
RX1/DT1	RX1PPS	'b000 001	<b>'</b> b010 101	'b001 101	RA1	RC5	RB5
CK1	CK1PPS	000 000d'	'b010 100	'b001 111	RA0	RC4	RB7
RX2/DT2	RX2PPS	'b000 001	<b>'</b> b010	001	RA1	RO	21
CK2	CK2PPS	000 000d'	<b>'</b> b010	000	RA0	RO	00
ADC Conversion Trigger	ADACTPPS	<b>'</b> b000 101	<b>'</b> b010	010	RA5	RO	22

#### Note:

1. Bidirectional pin. The corresponding output must select the same pin.

## 18.3 PPS Outputs

Each digital peripheral has a dedicated Pin Rxy Output Source Selection (RxyPPS) register with which the pin output source is selected. With few exceptions, the port TRIS control associated with that pin retains control over the pin output driver. Peripherals that control the pin output driver as part of the peripheral operation will override the TRIS control as needed. The I<sup>2</sup>C module is an example of such a peripheral.



**Important:** The notation 'Rxy' is a placeholder for the pin identifier. The 'x' holds the place of the PORT letter and the 'y' holds the place of the bit number. For example, Rxy = RA0 for the RA0PPS register.

The table below shows the output codes for each peripheral, as well as the available Port selections.

Table 18-2. PPS Output Selection Table

0x1C         ADGRDB           0x1B         ADGRDA           0x1A         NCC1           0x19         TMR0           0x18         SDA2/SDO2(1)           0x17         SCL2/SCK2(1)           0x16         SDA1/SDO1(1)           0x15         SCL1/SCK1(1)           0x14         C1_OUT           0x13         DT2           0x12         Reserved           0x11         TX2/CK2           0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x07         CWG1B           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	RxyPPS	Output Source
0x1B         ADGRDA           0x1A         NCO1           0x19         TMR0           0x18         SDA2/SDO2(1)           0x17         SCL2/SCK2(1)           0x16         SDA1/SDO1(1)           0x15         SCL1/SCK1(1)           0x14         C1_OUT           0x13         DT2           0x12         Reserved           0x11         TX2/CK2           0x10         DT1           0x0F         Reserved           0x10         DT1           0x0F         Reserved           0x1D         PWM5           0x1D         PWM5           0x1D         PWM4           0x1B         PWM3           0x0A         CCP2           0x0B         CCP1           0x0B         CWG1D           0x0B         CWG1D           0x0C         CWG1B           0x0A         CLC4_OUT           0x0A         CLC4_OUT           0x0A         CLC3_OUT           0x0B         CLC3_OUT           0x0C         CLC3_OUT           0x0C         CLC1_OUT		
0x1A         NCO1           0x19         TMR0           0x18         SDA2/SDO2(**)           0x17         SCL2/SCK2(**)           0x16         SDA1/SDO1(**)           0x15         SCL1/SCK1(**)           0x14         C1_OUT           0x13         DT2           0x12         Reserved           0x11         TX2/CK2           0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x07         CWG1A           0x04         CLC4_OUT           0x04         CLC4_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x1B	ADGRDA
0x18         SDA2/SDO2(1)           0x17         SCL2/SCK2(1)           0x16         SDA1/SDO1(1)           0x15         SCL1/SCK1(1)           0x14         C1_OUT           0x13         DT2           0x12         Reserved           0x11         TX2/CK2           0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PVM5           0x1C         PVM4           0x1B         PVM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0×1A	
0x17         SCL2/SCK2(f)           0x16         SDA1/SDO1(f)           0x15         SCL1/SCK1(f)           0x14         C1_OUT           0x13         DT2           0x12         Reserved           0x11         TX2/CK2           0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x07         CWG1B           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x19	TMR0
0x16         SDA1/SDO1(1)           0x15         SCL1/SCK1(1)           0x14         C1_OUT           0x13         DT2           0x12         Reserved           0x11         TX2/CK2           0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM8           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x18	SDA2/SDO2 <sup>(1)</sup>
0x15         SCL1/SCK1(1)           0x14         C1_OUT           0x13         DT2           0x12         Reserved           0x11         TX2/CK2           0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x17	SCL2/SCK2 <sup>(1)</sup>
0x14         C1_OUT           0x13         DT2           0x12         Reserved           0x11         TX2/CK2           0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x16	SDA1/SDO1 <sup>(1)</sup>
0x13         DT2           0x12         Reserved           0x11         TX2/CK2           0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x15	SCL1/SCK1 <sup>(1)</sup>
0x12         Reserved           0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x14	C1_OUT
0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x13	DT2
0x10         DT1           0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x12	Reserved
0x0F         Reserved           0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x11	TX2/CK2
0x1E         TX1/CK1           0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x10	DT1
0x1D         PWM5           0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x0F	Reserved
0x1C         PWM4           0x1B         PWM3           0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x1E	TX1/CK1
0x1B       PWM3         0x0A       CCP2         0x09       CCP1         0x08       CWG1D         0x07       CWG1C         0x06       CWG1B         0x05       CWG1A         0x04       CLC4_OUT         0x03       CLC3_OUT         0x02       CLC2_OUT         0x01       CLC1_OUT	0x1D	PWM5
0x0A         CCP2           0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x1C	PWM4
0x09         CCP1           0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x1B	PWM3
0x08         CWG1D           0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x0A	CCP2
0x07         CWG1C           0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x09	CCP1
0x06         CWG1B           0x05         CWG1A           0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x08	CWG1D
0x05       CWG1A         0x04       CLC4_OUT         0x03       CLC3_OUT         0x02       CLC2_OUT         0x01       CLC1_OUT	0x07	CWG1C
0x04         CLC4_OUT           0x03         CLC3_OUT           0x02         CLC2_OUT           0x01         CLC1_OUT	0x06	CWG1B
0x03       CLC3_OUT         0x02       CLC2_OUT         0x01       CLC1_OUT	0x05	CWG1A
0x02	0x04	CLC4_OUT
0x01 CLC1_OUT	0x03	_
_	0x02	CLC2_OUT
0x00 LATxy	0x01	CLC1_OUT
	0x00	LATxy

#### Note:

1. Bidirectional pin. The corresponding input must select the same pin.

## 18.4 Bidirectional Pins

PPS selections for peripherals with bidirectional signals on a single pin must be made so that the PPS input and PPS output select the same pin. The I<sup>2</sup>C Serial Clock (SCL) and Serial Data (SDA) are examples of such pins.



**Important:** The I<sup>2</sup>C default pins and a limited number of other alternate pins are I<sup>2</sup>C and SMBus compatible. SDA and SCL signals can be routed to any pin; however, pins without I<sup>2</sup>C compatibility will operate at standard TTL/ST logic levels as selected by the port's INLVL register.

#### 18.5 PPS Lock

The PPS module provides an extra layer of protection to prevent inadvertent changes to the PPS selection registers. The PPSLOCKED bit is used in combination with specific code execution blocks to lock/unlock the PPS selection registers.



**Important:** The PPSLOCKED bit is clear by default (PPSLOCKED = 0), which allows the PPS selection registers to be modified without an unlock sequence.

PPS selection registers are locked when the PPSLOCKED bit is set (PPSLOCKED = 1). Setting the PPSLOCKED bit requires a specific lock sequence as shown in the examples below in both C and assembly languages.

PPS selection registers are unlocked when the PPSLOCKED bit is clear (PPSLOCKED = 0). Clearing the PPSLOCKED bit requires a specific unlock sequence as shown in the examples below in both C and assembly languages.



**Important:** All interrupts must be disabled before starting the lock/unlock sequence to ensure proper execution.

## Example 18-1. PPS Lock Sequence (assembly language)

```
; suspend interrupts
BCF INTCONO,GIE
BANKSEL PPSLOCK
; required sequence, next 5 instructions
MOVLW 0x55
MOVWF PPSLOCK
MOVLW 0xAA
MOVWF PPSLOCK
; Set PPSLOCKED bit
BSF PPSLOCK,PPSLOCKED
; restore interrupts
BSF INTCONO,GIE
```

#### Example 18-2. PPS Lock Sequence (C language)

```
INTCONObits.GIE = 0; //Suspend interrupts

PPSLOCK = 0x55; //Required sequence

PPSLOCK = 0xAA; //Required sequence

PPSLOCKbits.PPSLOCKED = 1; //Set PPSLOCKED bit

INTCONObits.GIE = 1; //Restore interrupts
```

#### Example 18-3. PPS Unlock Sequence (assembly language)

```
; suspend interrupts
BCF INTCONO,GIE
BANKSEL PPSLOCK
; required sequence, next 5 instructions
MOVLW 0x55
MOVWF PPSLOCK
MOVLW 0xAA
MOVWF PPSLOCK
; Clear PPSLOCKED bit
BCF PPSLOCK, PPSLOCKED
```

#### 18.5.1 PPS One-Way Lock

The PPS1WAY Configuration bit can also be used to prevent inadvertent modification to the PPS selection registers.

When the PPS1WAY bit is set (PPS1WAY = 1), the PPSLOCKED bit can only be set one time after a device Reset. Once the PPSLOCKED bit has been set, it cannot be cleared again unless a device Reset is executed.

When the PPS1WAY bit is clear (PPS1WAY = 0), the PPSLOCKED bit can be set or cleared as needed; however, the PPS lock/unlock sequences must be executed.

## 18.6 Operation During Sleep

PPS input and output selections are unaffected by Sleep.

### 18.7 Effects of a Reset


A device Power-on Reset (POR) or Brown-out Reset (BOR) returns all PPS input selection registers to their default values and clears all PPS output selection registers. All other Resets leave the selections unchanged. Default input selections are shown in the PPS input register details table. The PPSLOCKED bit is cleared in all Reset conditions.

## 18.8 Register Definitions: Peripheral Pin Select (PPS)

#### 18.8.1 xxxPPS

Name: xxxPPS

Peripheral Input Selection Register



#### Bits 5:3 – PORT[2:0] Peripheral Input PORT Selection<sup>(1)</sup>

See the PPS Input Selection Table for the list of available Ports and default pin locations.

Reset States: POR = mmm

All other Resets = uuu

Value	Description
010	PORTC
001	PORTB
000	PORTA

#### Bits 2:0 – PIN[2:0] Peripheral Input PORT Pin Selection<sup>(2)</sup>

Reset States: POR = mmm

All other Resets = uuu

Value	Description
111	Peripheral input is from PORTx Pin 7 (Rx7)
110	Peripheral input is from PORTx Pin 6 (Rx6)
101	Peripheral input is from PORTx Pin 5 (Rx5)
100	Peripheral input is from PORTx Pin 4 (Rx4)
011	Peripheral input is from PORTx Pin 3 (Rx3)
010	Peripheral input is from PORTx Pin 2 (Rx2)
001	Peripheral input is from PORTx Pin 1 (Rx1)
000	Peripheral input is from PORTx Pin 0 (Rx0)


#### Notes:

- 1. The Reset value 'm' is determined by device default locations for that input.
- 2. Refer to the "Pin Allocation Table" for details about available pins per port.

## 18.8.2 RxyPPS

Name: RxyPPS

Pin Rxy Output Source Selection Register



Bits 5:0 - RxyPPS[5:0] Pin Rxy Output Source Selection

See the PPS Output Selection Table for the list of RxyPPS Output Source codes

Reset States: POR = 000000

All other Resets = uuuuuu

# PIC16F18015/25/44/45

# **PPS - Peripheral Pin Select Module**

## 18.8.3 **PPSLOCK**

Name: PPSLOCK

PPS Lock Register



## Bit 0 - PPSLOCKED PPS Locked

Reset States: POR = 0

All other Resets = 0

	Value	Description
ſ	1	PPS is locked. PPS selections cannot be changed. Writes to any PPS register are ignored.
	0	PPS is not locked. PPS selections can be changed, but may require the PPS lock/unlock sequence.

# 18.9 Register Summary - Peripheral Pin Select Module

December   December	Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
Main	0x00										
Ox108B   Ox108C   RA0PPS   7-0   RA0PPS[5:0]		Reserved									
MATPPS   70   RATPPS   70   RAPPS   70   R											
DATIBOD   DATIPOS   7-0   DATIPOS   0   DA	0x1D8C	RA0PPS	7:0					RA0PI	PS[5:0]	!	-
MATURE   MASPES   7-0   MASPES   7											
DATUBER   RESERVED   RAMPPS   7-0   RAMPPS   7-0											
DATIBOD   RASPPS   7-0   RASPPS											
DAXIDD2   RASPPS   7-0   RASPPS			7:0					RA4PI	PS[5:0]		
DAXIDS2   Reserved   DAXIDS5   RB4PPS   7:0   RB4PPS   5:0   RB4PS   5											
Reserved   Reserved		10.0.1.0							O[0.0]		
BATIDR7		Reserved									
DATIDB8   RBAPPS   7.0   RCAPPS		710001100									
DAT D99   R85PPS   7:0   P81   7:0		RB4PPS	7:0					RB4PI	PS[5:0]		
DATIDAD   R86PPS   7-0   R86PPS   7-0   R87PPS   7-0   P87PS   7-0   P8											
DATIDBB   RBZPPS   7-0   RCOPPS											
Ext DOC   RCOPPS   7:0   RCOPPS 5:0   RCIPPS 5:0   RCIP											
Dot.1090   R.C.1PPS   7:0   R.C.1PPS[5:0]   Dot.109E   R.C.2PPS   7:0   R.C.2PPS[5:0]   R.C.2PPS   7:0   R.C.2PPS[5:0]   R.C.2PPS   7:0   R.C.2PPS[5:0]   R.C.2PPS[5:0]   Dot.1040   R.C.2PPS   7:0   R.C.2PPS[5:0]   R.C.2P						-					
DATIDDE   RC2PPS   7:0   RC3PPS   7:0   RC3PPS[5:0]						-					
Oxt D9F   RC3PPS   7:0   RC3PPS   0     Oxt DAD   RC4PPS   7:0   RC4PPS   0     Oxt DAI   RC5PPS   7:0   RC5PPS   0     Oxt DAI   RC5PPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E0D   INTPPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E0D   TOCKIPPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E0T   TOCKIPPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E0T   TOCKIPPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E0T   TOCKIPPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E11   T3CKIPPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E12   T3C5PPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E13   T2INPPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E14   T4INPPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E15   T5INPPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E16   Reserved   PORT[2:0]   PIN[2:0]     Oxt E17   Reserved   PORT[2:0]   PIN[2:0]     Oxt E18   CCP1PPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E19   Reserved   PORT[2:0]   PIN[2:0]     Oxt E18   CUCIN1PPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E30   CUCIN1PPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E40   CUCIN1PPS   7:0   PORT[2:0]   PIN[2:0]     Oxt E40   CUCIN1PPS   7:0   PORT[2:0]   PIN[2:0]											
Dot.10A0   RC4PPS   7:0   RC5PPS   7:0   RC7PPS   7:0   RC7PPS   7:0   RC7PPS   7:0   RC7PPS   7:0   PORT[2:0]   PIN[2:0]   PIN[2:											
DXIDA1   RCSPPS   7:0   RCSPPS[5:0]   RCSP						-					
DATIDA2   RCGPPS   7:0   RCGPPS[5:0]						-					
OxtDA3											
DX1DA4			-								
Reserved   DXTEOB   PPSLOCK   7:0   PPSLOCKED   PPSLOCKED		RC/PPS	7:0					RC/P	PS[5:0]		
0x1E0B         PPSLOCK         7:0         PPSLOCKED           0x1E0D         INTPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E0E         TOCKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E0F         T1CKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E10         T1GPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E11         T3CKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E12         T3GPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E13         Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E18         T3INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1B         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C         Reserved         PORT[2:0]         PIN[2:0]           0x1E1F         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3A         Reserved         PORT[2:0]         PIN[2:0]           0x1E3B         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN1PPS         7:0         PORT[2:0]		Decembed									
0x1E0C         PPSLOCK         7:0         PPSLOCKED           0x1E0D         INTPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E0F         TOCKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E0F         T1CKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E10         T1CPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E11         T3CKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E13         Reserved         PORT[2:0]         PIN[2:0]           0x1E13         Reserved         PORT[2:0]         PIN[2:0]           0x1E14         T2INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E15         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E16         Reserved         PORT[2:0]         PIN[2:0]           0x1E17         Reserved         PORT[2:0]         PIN[2:0]           0x1E20         Reserved         PORT[2:0]         PIN[2:0]           0x1E23         CWG1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3A         Reserved         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN1PPS		Reserved									
Ox1E0D		DDOLOOK	7.0								DDOL GOVED
0x1E0E         TOCKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E0F         T1CKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E10         T1GPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E11         T3CKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E12         T3GPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E13          Reserved         PORT[2:0]         PIN[2:0]           0x1E18         T4INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E18         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1B         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C          Reserved         PORT[2:0]         PIN[2:0]           0x1E1B         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1F         CCP2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3B         CWG1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3B         CUCINAPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3B         CUCINA							DODT'S SI			DIVID 01	PPSLOCKED
Ox1E0F											
Ox1E10											
0x1E11         T3CKIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E12         T3GPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E13         Reserved         PORT[2:0]         PIN[2:0]           0x1E19         T2INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1A         T4INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1B         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C         Reserved         PORT[2:0]         PIN[2:0]           0x1E1D         PORT[2:0]         PIN[2:0]         PIN[2:0]           0x1E1F         CCP2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3B         CWG1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3A         Reserved         PORT[2:0]         PIN[2:0]           0x1E3C         CLCINOPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3D         CLCINIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCINIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCINIPPS         7:0         PORT[2:0]         PIN[2:0] </td <td></td>											
0x1E12         T3GPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E13         Reserved          PORT[2:0]         PIN[2:0]           0x1E19         T2INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1A         T4INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1B         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C          Reserved         PORT[2:0]         PIN[2:0]           0x1E1B         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C          Reserved         PORT[2:0]         PIN[2:0]           0x1E20          Reserved         PORT[2:0]         PIN[2:0]           0x1E38          Reserved         PORT[2:0]         PIN[2:0]           0x1E3C          PORT[2:0]         PIN[2:0]         PIN[2:0]           0x1E3C          PORT[2:0]         PIN[2:0]         PIN[2:0]           0x1E3F         CLCINIPPS         7:0         PORT[2:0]         PIN[2:0]         PIN[2:0]           0x1E40         CLCINIPPS         7:0         PORT[2:0]         PIN[2:0]         PIN[2:0]											
0x1E13         Reserved           0x1E18         7:0         PORT[2:0]         PIN[2:0]           0x1E19         T2INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1A         T4INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1B         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C         Reserved         PORT[2:0]         PIN[2:0]           0x1E1B         CCP2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C         Reserved         PORT[2:0]         PIN[2:0]           0x1E2D         Reserved         PORT[2:0]         PIN[2:0]           0x1E2O         PORT[2:0]         PIN[2:0]           0x1E3A         PORT[2:0]         PIN[2:0]           0x1E3A         PORT[2:0]         PIN[2:0]           0x1E3D         CLCINOPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3D         CLCINIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3D         CLCINIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCINIPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCINIPPS											
Reserved   PORT[2:0]   PIN[2:0]		T3GPPS	7:0				PORT[2:0]	I		PIN[2:0]	
0x1E18         0x1E19         T2INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1A         T4INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1B         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E1E         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E20          Reserved            0x1E38          PORT[2:0]         PIN[2:0]           0x1E3A          Reserved            0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3C         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]	0x1E13										
0x1E19         T2INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1A         T4INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1B         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E1E         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E20          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E3B         CWG1PPS         7:0         PORT[2:0]         PIN[2:0]         PIN[2:0]           0x1E3C         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]         PIN[2:0]           0x1E3F         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]         PIN[2:0]           0x1E3F         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]         PIN[2:0]		Reserved									
0x1E1A         T4INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1B         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C          Reserved          PORT[2:0]         PIN[2:0]           0x1E1F         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E20          Reserved          PORT[2:0]         PIN[2:0]           0x1E38          Reserved          PORT[2:0]         PIN[2:0]           0x1E3A          Reserved          PORT[2:0]         PIN[2:0]           0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]		Tallippo					DODT'S AL			Divis of	
0x1E1B         T6INPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1C          Reserved          PORT[2:0]         PIN[2:0]           0x1E1E         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1F         CCP2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E20          Reserved          PORT[2:0]         PIN[2:0]           0x1E39         CWG1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3A          Reserved          PORT[2:0]         PIN[2:0]           0x1E3D         CLCINOPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]						-					
0x1E1C          Reserved         PORT[2:0]         PIN[2:0]           0x1E1E         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1F         CCP2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E20          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E3A          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E3D         CLCINOPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]											
Reserved           0x1E1D         7:0         PORT[2:0]         PIN[2:0]           0x1E1F         CCP2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E20          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E38          PORT[2:0]         PIN[2:0]         PIN[2:0]           0x1E3A          Reserved         PORT[2:0]         PIN[2:0]           0x1E3D         CLCINOPPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]		T6INPPS	7:0				PORT[2:0]	1		PIN[2:0]	
0x1E1D         0x1E1E         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1F         CCP2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E20          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E38          PORT[2:0]         PIN[2:0]         PIN[2:0]           0x1E3A          Reserved         PORT[2:0]         PIN[2:0]           0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]	0x1E1C										
0x1E1E         CCP1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E1F         CCP2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E20          Reserved         Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E3A          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]		Reserved									
0x1E1F         CCP2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E20          Reserved         Reserved         Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E3A          Reserved         Reserved         Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]		0001000									
0x1E20          Reserved         PORT[2:0]         PIN[2:0]           0x1E39         CWG1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3A          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]											
Reserved           0x1E38         CWG1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3A          Reserved         Reserved         PORT[2:0]         PIN[2:0]           0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]		CCP2PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E38         0x1E39         CWG1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3A          Reserved          PORT[2:0]         PIN[2:0]           0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]											
0x1E39         CWG1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3A          Reserved		Reserved									
0x1E3A         Reserved           0x1E3C         PORT[2:0]           0x1E3D         CLCIN0PPS           7:0         PORT[2:0]           0x1E3E         CLCIN1PPS           7:0         PORT[2:0]           PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS           7:0         PORT[2:0]           0x1E40         CLCIN3PPS           7:0         PORT[2:0]           PORT[2:0]         PIN[2:0]											
Reserved         PORT[2:0]         PIN[2:0]           0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]		CWG1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E3C         PORT[2:0]         PIN[2:0]           0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]		_									
0x1E3D         CLCIN0PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]		Reserved									
0x1E3E         CLCIN1PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]											
0x1E3F         CLCIN2PPS         7:0         PORT[2:0]         PIN[2:0]           0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]											
0x1E40         CLCIN3PPS         7:0         PORT[2:0]         PIN[2:0]											
0x1E41 RX1PPS 7:0 PORT[2:0] PIN[2:0]											
	0x1E41	RX1PPS	7:0				PORT[2:0]			PIN[2:0]	

# PIC16F18015/25/44/45

# **PPS - Peripheral Pin Select Module**


continued										
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x1E42	CK1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E43	RX2PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E44	CK2PPS	7:0			PORT[2:0]			PIN[2:0]		
0x1E45										
	Reserved									
0x1E46										
0x1E47	SSP1CLKPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E48	SSP1DATPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E49	SSP1SSPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E4A	SSP2CLKPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E4B	SSP2DATPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E4C	SSP2SSPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E4D										
 0x1E4F	Reserved									
0x1E50	ADACTPPS	7:0				PORT[2:0]			PIN[2:0]	


# 19. TMR0 - Timer0 Module


The Timer0 module has the following features:

- · 8-bit timer with programmable period
- 16-bit timer
- · Selectable clock sources
- Synchronous and asynchronous operation
- Programmable prescaler (Independent of Watchdog Timer)
- · Programmable postscaler
- · Interrupt on match or overflow
- · Output on I/O pin (via PPS) or to other peripherals
- · Operation during Sleep

Figure 19-1. Timer0 Block Diagram







## 19.1 Timer0 Operation

Timer0 can operate as either an 8-bit or 16-bit timer. The mode is selected with the MD16 bit.

#### 19.1.1 8-Bit Mode

In this mode, Timer0 increments on the rising edge of the selected clock source. A prescaler on the clock input gives several prescale options (see the prescaler control bits, CKPS). In this mode, as shown in Figure 19-1, a buffered version of TMR0H is maintained.

This is compared with the value of TMR0L on each cycle of the selected clock source. When the two values match, the following events occur:

- TMR0L is reset
- The contents of TMR0H are copied to the TMR0H buffer for next comparison

#### 19.1.2 16-Bit Mode

In this mode, Timer0 increments on the rising edge of the selected clock source. A prescaler on the clock input gives several prescale options (see the prescaler control bits, CKPS). In this mode, TMR0H:TMR0L form the 16-bit timer value. As shown in Figure 19-1, reads and writes of the TMR0H register are buffered. The TMR0H register is updated with the contents of the high byte of Timer0 when the TMR0L register is read. Similarly, writing the TMR0L register causes a transfer of the TMR0H register value to the Timer0 high byte.

This buffering allows all 16 bits of Timer0 to be read and written at the same time. Timer0 rolls over to  $0 \times 0000$  on incrementing past  $0 \times FFFF$ . This makes the timer free-running. While actively operating in 16-bit mode, the Timer0 value can be read but not written.

#### 19.2 Clock Selection

Timer0 has several options for clock source selections, the option to operate synchronously/asynchronously and an available programmable prescaler. The CS bits are used to select the clock source for Timer0.

### 19.2.1 Synchronous Mode

When the ASYNC bit is clear, Timer0 clock is synchronized to the system clock ( $F_{OSC}/4$ ). When operating in Synchronous mode, Timer0 clock frequency cannot exceed  $F_{OSC}/4$ . During Sleep mode, the system clock is not available and Timer0 cannot operate.

#### 19.2.2 Asynchronous Mode

When the ASYNC bit is set, Timer0 increments with each rising edge of the input source (or output of the prescaler, if used). Asynchronous mode allows Timer0 to continue operation during Sleep mode provided the selected clock source operates during Sleep.

#### 19.2.3 Programmable Prescaler

Timer0 has 16 programmable input prescaler options ranging from 1:1 to 1:32768. The prescaler values are selected using the CKPS bits. The prescaler counter is not directly readable or writable. The prescaler counter is cleared on the following events:

- · A write to the TMR0L register
- A write to either the T0CON0 or T0CON1 registers
- Any device Reset

#### 19.2.4 Programmable Postscaler

Timer0 has 16 programmable output postscaler options ranging from 1:1 to 1:16. The postscaler values are selected using the OUTPS bits. The postscaler divides the output of Timer0 by the selected ratio. The postscaler counter is not directly readable or writable. The postscaler counter is cleared on the following events:

- A write to the TMR0L register
- · A write to either the T0CON0 or T0CON1 registers
- Any device Reset

## 19.3 Timer0 Output and Interrupt

### 19.3.1 Timer0 Output

TMR0\_out toggles on every match between TMR0L and TMR0H in 8-bit mode, or when TMR0H:TMR0L rolls over in 16-bit mode. If the output postscaler is used, the output is scaled by the ratio selected. The Timer0 output can be routed to an I/O pin via the RxyPPS output selection register, or internally to a number of Core Independent Peripherals. The Timer0 output can be monitored through software via the OUT output bit.

### 19.3.2 Timer0 Interrupt

The Timer0 Interrupt Flag (TMR0IF) bit is set when the TMR0\_out toggles. If the Timer0 interrupt is enabled (TMR0IE), the CPU will be interrupted when the TMR0IF bit is set. When the postscaler bits (T0OUTPS) are set to 1:1 operation (no division), the T0IF flag bit will be set with every TMR0 match or rollover. In general, the TMR0IF flag bit will be set every T0OUTPS +1 matches or rollovers.

#### 19.3.3 Timer0 Example

Timer0 Configuration:

- Timer0 mode = 16-bit
- Clock Source = F<sub>OSC</sub>/4 (250 kHz)
- · Synchronous operation
- Prescaler = 1:1
- Postscaler = 1:2 (T0OUTPS = 1)

In this case, the TMR0\_out toggles every two rollovers of TMR0H:TMR0L.

i.e., (0xFFFF)\*2\*(1/250 kHz) = 524.28 ms

## 19.4 Operation During Sleep

When operating synchronously, Timer0 will halt when the device enters Sleep mode. When operating asynchronously and the selected clock source is active, Timer0 will continue to increment and wake the device from Sleep mode if the Timer0 interrupt is enabled.

## 19.5 Register Definitions: Timer0 Control

# 19.5.1 T0CON0

Name: T0CON0 Offset: 0x019E

Timer0 Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN		OUT	MD16		OUTF	S[3:0]	
Access	R/W		R	R/W	R/W	R/W	R/W	R/W
Reset	0		0	0	0	0	0	0

# Bit 7 - EN TMR0 Enable

Value Description		
1	The module is enabled and operating	
0	The module is disabled	

# Bit 5 – OUT TMR0 Output

# Bit 4 - MD16 16-Bit Timer Operation Select

Value Description		Description
	1	TMR0 is a 16-bit timer
	0	TMR0 is an 8-bit timer

# Bits 3:0 - OUTPS[3:0] TMR0 Output Postscaler (Divider) Select

Value	Description
1111	1:16 Postscaler
1110	1:15 Postscaler
1101	1:14 Postscaler
1100	1:13 Postscaler
1011	1:12 Postscaler
1010	1:11 Postscaler
1001	1:10 Postscaler
1000	1:9 Postscaler
0111	1:8 Postscaler
0110	1:7 Postscaler
0101	1:6 Postscaler
0100	1:5 Postscaler
0011	1:4 Postscaler
0010	1:3 Postscaler
0001	1:2 Postscaler
0000	1:1 Postscaler

# 19.5.2 T0CON1

Name: T0CON1 Offset: 0x019F

Timer0 Control Register 1

Bit	7	6	5	4	3	2	1	0
	CS[2:0]			ASYNC	CKPS[3:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:5 - CS[2:0] Timer0 Clock Source Select

Value	Description
111	CLC1_OUT
110	SOSC
101	MFINTOSC (500 kHz)
100	LFINTOSC
011	HFINTOSC
010	F <sub>OSC</sub> /4
001	Pin selected by T0CKIPPS (Inverted)
000	Pin selected by T0CKIPPS (Noninverted)

Bit 4 - ASYNC TMR0 Input Asynchronization Enable

Value	Description			
1	The input to the TMR0 counter is not synchronized to system clocks			
0	The input to the TMR0 counter is synchronized to Fosc/4			

# Bits 3:0 - CKPS[3:0] Prescaler Rate Select

Value	Description
1111	1:32768
1110	1:16384
1101	1:8192
1100	1:4096
1011	1:2048
1010	1:1024
1001	1:512
1000	1:256
0111	1:128
0110	1:64
0101	1:32
0100	1:16
0011	1:8
0010	1:4
0001	1:2
0000	1:1

# PIC16F18015/25/44/45

**TMR0 - Timer0 Module** 

# 19.5.3 TMR0H

Name: TMR0H Offset: 0x019D

Timer0 Period/Count High Register

Bit	7	6	5	4	3	2	1	0
[				TMR0	H[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

Bits 7:0 - TMR0H[7:0] TMR0 Most Significant Counter

-	Value	Condition	Description
			8-bit Timer0 Period Value. TMR0L continues counting from 0 when this value is reached.
ı	0 to 255	MD16 = 1	16-bit Timer0 Most Significant Byte

# PIC16F18015/25/44/45

**TMR0 - Timer0 Module** 

# 19.5.4 TMR0L

Name: TMR0L Offset: 0x019C

Timer0 Period/Count Low Register

Bit	7	6	5	4	3	2	1	0
[				TMR	L[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - TMR0L[7:0] TMR0 Least Significant Counter

Value	Condition	Description
0 to 255	MD16 = 0	8-bit Timer0 Counter bits
0 to 255	MD16 = 1	16-bit Timer0 Least Significant Byte

# 19.6 Register Summary - Timer0

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x019B										
0x019C	TMR0L	7:0		•	•	TMR	L[7:0]	:	•	
0x019D	TMR0H	7:0				TMR	H[7:0]			
0x019E	T0CON0	7:0	EN		OUT	MD16		OUTF	PS[3:0]	
0x019F	T0CON1	7:0	CS[2:0]		ASYNC	CKPS[3:0]				

# 20. TMR1 - Timer1 Module with Gate Control


The Timer1 module is a 16-bit timer/counter with the following features:

- 16-bit timer/counter register pair (TMRxH:TMRxL)
- · Programmable internal or external clock source
- · 2-bit prescaler
- Clock source for optional comparator synchronization
- · Multiple Timer1 gate (count enable) sources
- · Interrupt-on-overflow
- Wake-up on overflow (external clock, Asynchronous mode only)
- · 16-bit read/write operation
- Time base for the capture/compare function with the CCP modules
- Special event trigger (with CCP)
- · Selectable gate source polarity
- · Gate Toggle mode
- · Gate Single Pulse mode
- · Gate value status
- · Gate event interrupt



Important: References to the module Timer1 apply to all the odd numbered timers on this device.

Figure 20-1. Timer1 Block Diagram



#### Notes:

- 1. This signal comes from the pin selected by Timer1 PPS register.
- 2. TMRx register increments on rising edge.
- 3. Synchronize does not operate while in Sleep.
- 4. See TxCLK for clock source selections.
- 5. See TxGATE for gate source selections.
- 6. Synchronized comparator output must not be used in conjunction with synchronized input clock.

# 20.1 Timer1 Operation

The Timer1 module is a 16-bit incrementing counter accessed through the TMRx register. Writes to TMRx directly update the counter. When used with an internal clock source, the module is a timer that increments on every instruction cycle. When used with an external clock source, the module can be used as either a timer or counter and increments on every selected edge of the external source.

Timer1 is enabled by configuring the ON and GE bits. Table 20-1 shows the possible Timer1 enable selections.

Table 20-1, Timer1 Enable Selections

ON	GE	Timer1 Operation
1	1	Count enabled
1	0	Always on
0	1	Off
0	0	Off

# 20.2 Clock Source Selection

The CS bits select the clock source for Timer1. These bits allow the selection of several possible synchronous and asynchronous clock sources.

#### 20.2.1 Internal Clock Source

When the internal clock source is selected, the TMRx register will increment on multiples of F<sub>OSC</sub> as determined by the Timer1 prescaler.


When the  $F_{OSC}$  internal clock source is selected, the TMRx register value will increment by four counts every instruction clock cycle. Due to this condition, a two LSB error in resolution will occur when reading the TMRx value. To utilize the full resolution of Timer1, an asynchronous input signal must be used to gate the Timer1 clock input.



**Important:** In Counter mode, a falling edge must be registered by the counter prior to the first incrementing rising edge after any one or more of the following conditions:

- · Timer1 enabled after POR
- · Write to TMRxH or TMRxL
- · Timer1 is disabled
- Timer1 is disabled (ON = 0) when TxCKI is high, then Timer1 is enabled (ON = 1) when TxCKI is low.
   Refer to the figure below.

Figure 20-2. Timer1 Incrementing Edge



#### Notes:

- 1. Arrows indicate counter increments.
- 2. In Counter mode, a falling edge must be registered by the counter prior to the first incrementing rising edge of the clock.

# 20.2.2 External Clock Source

When the external clock source is selected, the TMRx module may work as a timer or a counter. When enabled to count, Timer1 is incremented on the rising edge of the external clock input of the TxCKIPPS pin. This external clock source can be synchronized to the system clock or it can run asynchronously.

# 20.3 Timer1 Prescaler

Timer1 has four prescaler options allowing 1, 2, 4 or 8 divisions of the clock input. The CKPS bits control the prescale counter. The prescale counter is not directly readable or writable; however, the prescaler counter is cleared upon a write to TMRx.

# 20.4 Secondary Oscillator

A secondary low-power 32.768 kHz oscillator circuit is built-in between pins SOSCI (input) and SOSCO (amplifier output). This internal circuit is to be used in conjunction with an external 32.768 kHz crystal. The secondary oscillator is not dedicated only to Timer1; it can also be used by other modules.

The oscillator circuit is enabled by setting the SOSCEN bit of the OSCEN register. This can be used as one of the Timer1 clock sources selected with the CS bits. The oscillator will continue to run during Sleep.



**Important:** The oscillator requires a start-up and stabilization time before use. Thus, the SOSCEN bit of the OSCEN register must be set and a suitable delay observed prior to enabling Timer1. A software check can be performed to confirm if the secondary oscillator is enabled and ready to use. This is done by polling the secondary oscillator ready Status bit. Refer to the "OSC - Oscillator Module (with Fail-Safe Clock Monitor)" chapter for more details.

# 20.5 Timer1 Operation in Asynchronous Counter Mode

When the SYNC Control bit is set, the external clock input is not synchronized. The timer increments asynchronously to the internal phase clocks. If the external clock source is selected, then the timer will continue to run during Sleep and can generate an interrupt on overflow, which will wake up the processor. However, special precautions in software are needed to read/write the timer.



**Important:** When switching from synchronous to asynchronous operation, it is possible to skip an increment. When switching from asynchronous to synchronous operation, it is possible to produce an additional increment.

#### 20.5.1 Reading and Writing TMRx in Asynchronous Counter Mode

Reading TMRxH or TMRxL while the timer is running from an external asynchronous clock will ensure a valid read (taken care of in hardware). However, the user must keep in mind that reading the 16-bit timer in two 8-bit values itself poses certain problems, since there may be a carry-out of TMRxL to TMRxH between the reads.

For writes, it is recommended that the user simply stop the timer and write the desired values. A write contention may occur by writing to the timer registers, while the register is incrementing. This may produce an unpredictable value in the TMRxH:TMRxL register pair.

#### 20.6 Timer1 16-Bit Read/Write Mode


Timer1 can be configured to read and write all 16 bits of data to and from the 8-bit TMRxL and TMRxH registers, simultaneously. The 16-bit read and write operations are enabled by setting the RD16 bit. To accomplish this function, the TMRxH register value is mapped to a buffer register called the TMRxH buffer register. While in 16-bit mode, the TMRxH register is not directly readable or writable and all read and write operations take place through the use of this TMRxH buffer register.

When a read from the TMRxL register is requested, the value of the TMRxH register is simultaneously loaded into the TMRxH buffer register. When a read from the TMRxH register is requested, the value is provided from the TMRxH buffer register instead. This provides the user with the ability to accurately read all 16 bits of the Timer1 value from a

single instance in time (refer to Figure 20-3 for more details). In contrast, when not in 16-bit mode, the user must read each register separately and determine if the values have become invalid due to a rollover that may have occurred between the read operations.

When a write request of the TMRxL register is requested, the TMRxH buffer register is simultaneously updated with the contents of the TMRxH register. The value of TMRxH must be preloaded into the TMRxH buffer register prior to the write request for the TMRxL register. This provides the user with the ability to write all 16 bits to the TMRx register at the same time. Any requests to write to TMRxH directly does not clear the Timer1 prescaler value. The prescaler value is only cleared through write requests to the TMRxL register.

Figure 20-3. Timer1 16-Bit Read/Write Mode Block Diagram



#### 20.7 Timer1 Gate

Timer1 can be configured to count freely or the count can be enabled and disabled using Timer1 gate circuitry. This is also referred to as Timer1 gate enable. Timer1 gate can also be driven by multiple selectable sources.

#### 20.7.1 Timer1 Gate Enable


The Timer1 Gate Enable mode is enabled by setting the GE bit. The polarity of the Timer1 Gate Enable mode is configured using the GPOL bit.

When Timer1 Gate Enable mode is enabled, Timer1 will increment on the rising edge of the Timer1 clock source. When Timer1 Gate signal is inactive, the timer will not increment and hold the current count. Enable mode is disabled, no incrementing will occur and Timer1 will hold the current count. See Figure 20-4 for timing details.

Table 20-2. Timer1 Gate Enable Selections

TMRxCLK	GPOL	TxG	Timer1 Operation
<b>↑</b>	1	1	Counts
<b>↑</b>	1	0	Holds Count
<b>↑</b>	0	1	Holds Count
<b>↑</b>	0	0	Counts





#### 20.7.2 Timer1 Gate Source Selection

The gate source for Timer1 is selected using the GSS bits. The polarity selection for the gate source is controlled by the GPOL bit.

Any of the above mentioned signals can be used to trigger the gate. The output of the CMPx can be synchronized to the Timer1 clock or left asynchronous. For more information refer to the "Comparator Output Synchronization" section.


#### 20.7.3 Timer1 Gate Toggle Mode

When Timer1 Gate Toggle mode is enabled, it is possible to measure the full-cycle length of a Timer1 Gate signal, as opposed to the duration of a single-level pulse. The Timer1 gate source is routed through a flip-flop that changes state on every incrementing edge of the signal. See the figure below for timing details.

Timer1 Gate Toggle mode is enabled by setting the GTM bit. When the GTM bit is cleared, the flip-flop is cleared and held clear. This is necessary to control which edge is measured.




**Important:** Enabling Toggle mode at the same time as changing the gate polarity may result in indeterminate operation.



# 20.7.4 Timer1 Gate Single Pulse Mode


When Timer1 Gate Single Pulse mode is enabled, it is possible to capture a single pulse gate event. Timer1 Gate Single Pulse mode is first enabled by setting the GSPM bit. Next, the GGO/DONE must be set. The Timer1 will be fully enabled on the next incrementing edge. On the next trailing edge of the pulse, the GGO/DONE bit will automatically be cleared. No other gate events will be allowed to increment Timer1 until the GGO/DONE bit is once again set in software.

Figure 20-6. Timer1 Gate Single Pulse Mode



Clearing the GSPM bit will also clear the GGO/DONE bit. See the figure below for timing details. Enabling the Toggle mode and the Single Pulse mode simultaneously will permit both sections to work together. This allows the cycle times on the Timer1 gate source to be measured. See the figure below for timing details.

Figure 20-7. Timer1 Gate Single Pulse and Toggle Combined Mode



# 20.7.5 Timer1 Gate Value Status

When Timer1 gate value status is utilized, it is possible to read the most current level of the gate control value. The value is stored in the GVAL bit in the TxGCON register. The GVAL bit is valid even when the Timer1 gate is not enabled (GE bit is cleared).

#### 20.7.6 Timer1 Gate Event Interrupt

When Timer1 gate event interrupt is enabled, it is possible to generate an interrupt upon the completion of a gate event. When the falling edge of GVAL occurs, the TMRxGIF flag bit in one of the PIR registers will be set. If the TMRxGIE bit in the corresponding PIE register is set, then an interrupt will be recognized.

The TMRxGIF flag bit operates even when the Timer1 gate is not enabled (the GE bit is cleared).

# 20.8 Timer1 Interrupt

The TMRx register increments to FFFFh and rolls over to 0000h. When TMRx rolls over, the Timer1 interrupt flag bit of the PIRx register is set. To enable the interrupt-on-rollover, the following bits must be set:

- · The ON bit of the TxCON register
- The TMRxIE bits of the PIEx register
- Global interrupts must be enabled

The interrupt is cleared by clearing the TMRxIF bit as a task in the Interrupt Service Routine.



Important: The TMRx register and the TMRxIF bit must be cleared before enabling interrupts.

# 20.9 Timer1 Operation During Sleep

Timer1 can only operate during Sleep when configured as an asynchronous counter. In this mode, many clock sources can be used to increment the counter. To set up the timer to wake the device:

- · The ON bit must be set
- · The TMRxIE bit of the PIEx register must be set
- · Global interrupts must be enabled
- · The SYNC bit must be set
- Configure the TxCLK register for using any clock source other than F<sub>OSC</sub> and F<sub>OSC</sub>/4

The device will wake up on an overflow and execute the next instruction. If global interrupts are enabled, the device will call the IRS. The secondary oscillator will continue to operate in Sleep regardless of the SYNC bit setting.

# 20.10 CCP Capture/Compare Time Base

The CCP modules use TMRx as the time base when operating in Capture or Compare mode. In Capture mode, the value in TMRx is copied into the CCPRx register on a capture event. In Compare mode, an event is triggered when the value in the CCPRx register matches the value in TMRx. This event can be a Special Event Trigger.

# 20.11 CCP Special Event Trigger

When any of the CCPs are configured to trigger a special event, the trigger will clear the TMRx register. This special event does not cause a Timer1 interrupt. The CCP module may still be configured to generate a CCP interrupt. In this mode of operation, the CCPRx register becomes the period register for Timer1. Timer1 must be synchronized and  $F_{OSC}/4$  must be selected as the clock source to utilize the Special Event Trigger. Asynchronous operation of Timer1 can cause a Special Event Trigger to be missed. In the event that a write to TMRxH or TMRxL coincides with a Special Event Trigger from the CCP, the write will take precedence.

# 20.12 Peripheral Module Disable

When a peripheral is not used or inactive, the module can be disabled by setting the Module Disable bit in the PMD registers. This will reduce power consumption to an absolute minimum. Setting the PMD bits holds the module in Reset and disconnects the module's clock source. The Module Disable bits for Timer1 (TMR1MD) are in the PMDx register. See the "PMD - Peripheral Module Disable" chapter for more information.

# 20.13 Register Definitions: Timer1 Control

Long bit name prefixes for the Timer registers are shown in the table below, where 'x' refers to the Timer instance number. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 20-3. Timer1 Register Bit Name Prefixes


Peripheral	Bit Name Prefix
Timer1	T1
Timer3	Т3

# 20,13,1 TxCON

Name: TxCON

**Offset:** 0x028E,0x0294

**Timer Control Register** 



# Bits 5:4 - CKPS[1:0] Timer Input Clock Prescaler Select

Reset States: POR/BOR = 00

All Other Resets = uu

Value	Description
11	1:8 Prescaler value
10	1:4 Prescaler value
01	1:2 Prescaler value
00	1:1 Prescaler value

# Bit 2 - SYNC Timer External Clock Input Synchronization Control

Reset States: POR/BOR = 0

All Other Resets = u

Value	Condition	Description
X	CS = F <sub>OSC</sub> /4 or F <sub>OSC</sub>	This bit is ignored. Timer uses the incoming clock as is.
1	All other clock sources	Do not synchronize external clock input
0	All other clock sources	Synchronize external clock input with system clock

# Bit 1 - RD16 16-Bit Read/Write Mode Enable

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Enables register read/write of Timer in one 16-bit operation
0	Enables register read/write of Timer in two 8-bit operations

#### Bit 0 - ON Timer On

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Enables Timer
0	Disables Timer

# 20.13.2 TxGCON

Name: TxGCON Offset: 0x028F,0x0295

Timer Gate Control Register

Bit	7	6	5	4	3	2	1	0
	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL		
Access	R/W	R/W	R/W	R/W	R/W	R		
Reset	0	0	0	0	0	X		

# **Bit 7 – GE** Timer Gate Enable Reset States: POR/BOR = 0

All Other Resets = u

		· · · · · ·
Value	Condition	Description
1	ON = 1	Timer counting is controlled by the Timer gate function
0	ON = 1	Timer is always counting
X	ON = 0	This bit is ignored

# **Bit 6 – GPOL** Timer Gate Polarity Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Timer gate is active-high (Timer counts when gate is high)
0	Timer gate is active-low (Timer counts when gate is low)

#### Bit 5 - GTM Timer Gate Toggle Mode

Timer Gate flip-flop toggles on every rising edge when Toggle mode is enabled.

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Timer Gate Toggle mode is enabled
0	Timer Gate Toggle mode is disabled and Toggle flip-flop is cleared

# Bit 4 - GSPM Timer Gate Single Pulse Mode

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Timer Gate Single Pulse mode is enabled and is controlling Timer gate
0	Timer Gate Single Pulse mode is disabled

# Bit 3 – GGO/DONE Timer Gate Single Pulse Acquisition Status

This bit is automatically cleared when TxGSPM is cleared.

Reset States: POR/BOR = 0

All Other Resets = u

Value	Description
1	Timer Gate Single Pulse Acquisition is ready, waiting for an edge
0	Timer Gate Single Pulse Acquisition has completed or has not been started

#### Bit 2 - GVAL Timer Gate Current State

Indicates the current state of the timer gate that can be provided to TMRxH:TMRxL


Unaffected by the Timer Gate Enable (GE) bit

# 20,13,3 TxCLK

Name: TxCLK

**Offset:** 0x0291,0x0297

Timer Clock Source Selection Register



Bits 4:0 - CS[4:0] Timer Clock Source Selection

# Table 20-4. Timer Clock Sources

CS	Clock	Source
C3	Timer1	Timer3
11111-10001	Rese	erved
10000	CLC4	_OUT
01111	CLC3	_OUT
01110	CLC2	_OUT
01101	CLC1	_OUT
01100	TMR3_overflow	Reserved
01011	Reserved	TMR1_overflow
01010	TMR0_c	overflow
01001	EXT	OSC
01000	SO	SC
00111	MFINTOS	C (32 kHz)
00110	MFINTOSO	C (500 kHz)
00101	SFINTOS	C (1 MHz)
00100	LFIN <sup>-</sup>	TOSC
00011	HFIN'	TOSC
00010	F <sub>C</sub>	DSC
00001	Fos	sc/4
00000	Pin selected by T1CKIPPS	Pin selected by T3CKIPPS

Reset States: POR/BOR = 00000


All Other Resets = uuuuu

# 20.13.4 TxGATE

 Name:
 TxGATE

 Offset:
 0x0290,0x0296

Timer Gate Source Selection Register



Bits 4:0 - GSS[4:0] Timer Gate Source Selection

# **Table 20-5. Timer Gate Sources**

GSS	Gate S	Source
633	Timer1	Timer3
11111-10011	Rese	erved
10010	CLC4	_OUT
10001	CLC3	_OUT
10000	CLC2	_OUT
01111	CLC1	_OUT
01110	ZCD_	OUT
01101	C1_(	OUT
01100	NCO1	_OUT
01011	PWM5	S_OUT
01010	PWM4	I_OUT
01001	PWM3	3_OUT
01000	CCP2	_OUT
00111	CCP1	_OUT
00110	TMR6_Posts	scaled_OUT
00101	TMR4_Posts	scaled_OUT
00100	TMR3_overflow	Reserved
00011	TMR2_Posts	scaled_OUT
00010	Reserved	TMR1_overflow
00001	TMR0_c	overflow
00000	Pin selected by T1GPPS	Pin selected by T3GPPS

# PIC16F18015/25/44/45

# **TMR1 - Timer1 Module with Gate Control**

# 20,13,5 TMRx

Name: TMRx

**Offset:** 0x028C,0x0292

Timer Register

Bit	15	14	13	12	11	10	9	8
[				TMRx	[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
[	TMRx[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 15:0 – TMRx[15:0] Timer Register Value
Reset States: POR/BOR = 000000000000000
All Other Resets = uuuuuuuuuuuuuuuuuu

**Notes:** The individual bytes in this multibyte register can be accessed with the following register names:

- TMRxH: Accesses the high byte TMRx[15:8]
- TMRxL: Accesses the low byte TMRx[7:0]

# 20.14 Register Summary - Timer1

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00  0x028B	Reserved									
0x028C	TMR1	7:0			•	TMR	1[7:0]		•	
000260	BC TWIRT	15:8				TMR	[15:8]			
0x028E	T1CON	7:0			CKP	S[1:0]		SYNC	RD16	ON
0x028F	T1GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL		
0x0290	T1GATE	7:0						GSS[4:0]		
0x0291	T1CLK	7:0						CS[4:0]		
0,,0000	TMD2	7:0		TMR3[7:0]						
0x0292	TMR3	15:8				TMR	B[15:8]			
0x0294	T3CON	7:0			CKP	S[1:0]		SYNC	RD16	ON
0x0295	T3GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL		
0x0296	T3GATE	7:0				GSS[4:0]				
0x0297	T3CLK	7:0				CS[4:0]				

# 21. TMR2 - Timer2 Module

The Timer2 module is an 8-bit timer that incorporates the following features:


- 8-bit timer and period registers
- · Readable and writable
- Software programmable prescaler (1:1 to 1:128)
- Software programmable postscaler (1:1 to 1:16)
- · Interrupt on T2TMR match with T2PR
- · One-shot operation
- · Full asynchronous operation
- Includes Hardware Limit Timer (HLT)
- · Alternate clock sources
- · External timer Reset signal sources
- · Configurable timer Reset operation

See figure below for a block diagram of Timer2.



**Important:** References to module Timer2 apply to all the even numbered timers on this device (Timer2, Timer4, etc.).

Figure 21-1. Timer2 with Hardware Limit Timer (HLT) Block Diagram



#### Notes:

- 1. Signal to the CCP peripheral for PWM pulse trigger in PWM mode.
- 2. See RSEL for external Reset sources.
- 3. See CS for clock source selections.

# 21.1 Timer2 Operation

Timer2 operates in three major modes:

- · Free-Running Period
- One Shot
- Monostable

Within each operating mode, there are several options for starting, stopping and Reset. Table 21-1 lists the options.

In all modes, the T2TMR count register increments on the rising edge of the clock signal from the programmable prescaler. When T2TMR equals T2PR, a high level output to the postscaler counter is generated. T2TMR is cleared on the next clock input.

An external signal from hardware can also be configured to gate the timer operation or force a T2TMR count Reset. In Gate modes, the counter stops when the gate is disabled and resumes when the gate is enabled. In Reset modes, the T2TMR count is reset on either the level or edge from the external source.

The T2TMR and T2PR registers are both directly readable and writable. The T2TMR register is cleared and the T2PR register initializes to 0xFF on any device Reset. Both the prescaler and postscaler counters are cleared on the following events:

- · A write to the T2TMR register
- · A write to the T2CON register
- · Any device Reset
- External Reset source event that resets the timer



**Important:** T2TMR is not cleared when T2CON is written.

# 21.1.1 Free-Running Period Mode

The value of T2TMR is compared to that of the period register, T2PR, on each clock cycle. When the two values match, the comparator resets the value of T2TMR to  $0 \times 00$  on the next cycle and increments the output postscaler counter. When the postscaler count equals the value in the OUTPS bits of the T2CON register then a one clock period wide pulse occurs on the TMR2 postscaled output, and the postscaler count is cleared.

#### 21.1.2 One Shot Mode

The One Shot mode is identical to the Free-Running Period mode except that the ON bit is cleared and the timer is stopped when T2TMR matches T2PR and will not restart until the ON bit is cycled off and on. Postscaler (OUTPS) values other than zero are ignored in this mode because the timer is stopped at the first period event and the postscaler is reset when the timer is restarted.

#### 21.1.3 Monostable Mode

Monostable modes are similar to One Shot modes except that the ON bit is not cleared and the timer can be restarted by an external Reset event.

# 21.2 Timer2 Output

The Timer2 module's primary output is TMR2\_postscaled, which pulses for a single TMR2\_clk period upon each match of the postscaler counter and the OUTPS bits of the T2CON register. The postscaler is incremented each time the T2TMR value matches the T2PR value. This signal can also be selected as an input to other Core Independent Peripherals.

In addition, the Timer2 is also used by the CCP module for pulse generation in PWM mode. See the "PWM Overview" and "PWM Period" sections in the "CCP - Capture/Compare/PWM Module" chapter for more details on setting up Timer2 for use with the CCP and PWM modules.


# 21.3 External Reset Sources

In addition to the clock source, the Timer2 can also be driven by an external Reset source input. This external Reset input is selected for each timer with the corresponding TxRST register. The external Reset input can control starting and stopping of the timer, as well as resetting the timer, depending on the mode used.

# 21.4 Timer2 Interrupt

Timer2 can also generate a device interrupt. The interrupt is generated when the postscaler counter matches the selected postscaler value (OUTPS bits of T2CON register). The interrupt is enabled by setting the TMR2IE interrupt enable bit. Interrupt timing is illustrated in the figure below.

Figure 21-2. Timer2 Prescaler, Postscaler, and Interrupt Timing Diagram



**Notes:** 1. Setting the interrupt flag is synchronized with the instruction clock. Synchronization may take as many as two instruction cycles.

2. Cleared by software.

#### 21.5 PSYNC Bit

Setting the PSYNC bit synchronizes the prescaler output to  $F_{OSC}/4$ . Setting this bit is required for reading the Timer2 counter register while the selected Timer clock is asynchronous to  $F_{OSC}/4$ .

**Note:** Setting PSYNC requires that the output of the prescaler is slower than  $F_{OSC}/4$ . Setting PSYNC when the output of the prescaler is greater than or equal to  $F_{OSC}/4$  may cause unexpected results.

# 21.6 CSYNC Bit

All bits in the Timer2 SFRs are synchronized to  $F_{OSC}/4$ , it is possible for the Timer2 input clock to transition at the same time as the ON bit is set in software, which may cause undesirable behavior and glitches in the counter. Setting the CSYNC bit remedies this problem by synchronizing the ON bit to the Timer2 input clock instead of  $F_{OSC}/4$ . However, as this synchronization uses an edge of the TMR2 input clock, up to one input clock cycle will be consumed and not counted by the Timer2 when CSYNC is set. Conversely, clearing the CSYNC bit synchronizes the ON bit to  $F_{OSC}/4$ , which does not consume any clock edges, but has the previously stated risk of glitches.

# 21.7 Operating Modes

The mode of the timer is controlled by the MODE bits. Edge Triggered modes require six Timer clock periods between external triggers. Level Triggered modes require the triggering level to be at least three Timer clock periods long. External triggers are ignored while in Debug mode.

Table 21-1. Operating Modes Table

Mada	MC	DE	Output	Operation		Timer Control		
Mode	[4:3]	[2:0]	Operation	Operation	Start	Reset	Stop	
		000		Software gate (Figure 21-3)	ON = 1	<del>-</del>	ON = 0	
		001	Period Pulse	Hardware gate, active-high (Figure 21-4)	ON = 1 and TMRx_ers = 1	_	ON = 0 or TMRx_ers = 0	
		010		Hardware gate, active-low	ON = 1 and TMRx_ers = 0	_	ON = 0 or TMRx_ers = 1	
Free-Running Period	00	011		Rising or falling edge Reset		TMRx_ers		
riee-ranning renou		100		Rising edge Reset (Figure 21-5)		TMRx_ers ↑	ON = 0	
		101	Period Pulse	Falling edge Reset		TMRx_ers ↓		
		110	with Hardware Reset	Low-level Reset	<b>ON =</b> 1	TMRx_ers = 0	ON = 0 or TMRx_ers = 0	
		111		High-level Reset (Figure 21-6)		TMRx_ers = 1	ON = 0 or TMRx_ers = 1	
		000	One-shot	Software start (Figure 21-7)	ON = 1	_		
		001	Edge-Triggered Start (Note 1)  Edge-Triggered Start and Hardware Reset (Note 1)	Rising edge start (Figure 21-8)	ON = 1 and TMRx_ers ↑	_		
		010		Falling edge start	ON = 1 and TMRx_ers ↓	_		
		011		Any edge start	ON = 1 and TMRx_ers ↓	_	ON = 0 or	
One Shot	01	100		Rising edge start and Rising edge Reset (Figure 21-9)	ON = 1 and TMRx_ers ↑	TMRx_ers ↑	Next clock after TxTMR = TxPR	
		101		Falling edge start and Falling edge Reset	ON = 1 and TMRx_ers ↓	TMRx_ers↓	(Note 2)	
		110		Rising edge start and Low-level Reset (Figure 21-10)	ON = 1 and TMRx_ers ↑	TMRx_ers = 0		
		111		Falling edge start and High-level Reset	ON = 1 and TMRx_ers ↓	TMRx_ers = 1		

continued								
Mode	MC	DDE	Output	Operation	Timer Control			
Wiode	[4:3]	[2:0]	Operation	Operation	Start	Reset	Stop	
		000		Reserve	ed .			
		001		Rising edge start (Figure 21-11)	ON = 1 and TMRx_ers ↑	_	ON = 0 or	
Monostable		010	Edge-Triggered Start (Note 1)	Falling edge start	ON = 1 and TMRx_ers↓	_	Next clock after	
	10	011		Any edge start	ON = 1 and TMRx_ers ↓	_	(Note 3)	
Reserved		100		Reserve	ed .			
Reserved		101		Reserve	ed .			
One Shot		110	Level-Triggered Start	High-level start and Low-level Reset (Figure 21-12)	ON = 1 and TMRx_ers = 1	TMRx_ers = 0	ON = 0 or Held in Reset	
One Shot		111	Hardware Reset	Low-level start and High-level Reset	ON = 1 and TMRx_ers = 0	TMRx_ers = 1	(Note 2)	
Reserved	11	XXX	Reserved					

#### Notes:

- 1. If ON = 0, then an edge is required to restart the timer after ON = 1.
- 2. When T2TMR = T2PR, the next clock clears ON and stops T2TMR at 00h.
- 3. When T2TMR = T2PR, the next clock stops T2TMR at 00h but does not clear ON.

# 21.8 Operation Examples


Unless otherwise specified, the following notes apply to the following timing diagrams:

- Both the prescaler and postscaler are set to 1:1 (both the CKPS and OUTPS bits).
- The diagrams illustrate any clock except F<sub>OSC</sub>/4 and show clock-sync delays of at least two full cycles for both
  ON and TMRx\_ers. When using F<sub>OSC</sub>/4, the clock-sync delay is at least one instruction period for TMRx\_ers;
  ON applies in the next instruction period.
- ON and TMRx\_ers are somewhat generalized, and clock-sync delays may produce results that are slightly different than illustrated.
- The PWM Duty Cycle and PWM output are illustrated assuming that the timer is used for the PWM function of the CCP module as described in the "PWM Overview" section. The signals are not a part of the Timer2 module.

#### 21.8.1 Software Gate Mode

This mode corresponds to legacy Timer2 operation. The timer increments with each clock input when ON = 1, and does not increment when ON = 0. When the TxTMR count equals the TxPR period count, the timer resets on the next clock and continues counting from zero. Operation with the ON bit software controlled is illustrated in Figure 21-3. With TxPR = 5, the counter advances until TxTMR = 5, and goes to zero with the next clock.

Figure 21-3. Software Gate Mode Timing Diagram (MODE = 'b00000)



Note: 1. BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.


# 21.8.2 Hardware Gate Mode

The Hardware Gate modes operate the same as the Software Gate mode, except the TMRx\_ers external signal can also gate the timer. When used with the CCP, the gating extends the PWM period. If the timer is stopped when the PWM output is high, then the duty cycle is also extended.

When MODE = \b000001, then the timer is stopped when the external signal is high. When MODE = \b000010, then the timer is stopped when the external signal is low.

Figure 21-4 illustrates the Hardware Gating mode for MODE = \bdots000001 in which a high input level starts the counter.

Figure 21-4. Hardware Gate Mode Timing Diagram (MODE = 'b00001)




# 21.8.3 Edge Triggered Hardware Limit Mode

In Hardware Limit mode, the timer can be reset by the TMRx\_ers external signal before the timer reaches the period count. Three types of Resets are possible:

- Reset on rising or falling edge (MODE = 'b00011)
- Reset on rising edge (MODE = 'b00100)
- Reset on falling edge (MODE = `b00101)

When the timer is used in conjunction with the CCP in PWM mode then an early Reset shortens the period and restarts the PWM pulse after a two clock delay. Refer to Figure 21-5.

Figure 21-5. Edge Triggered Hardware Limit Mode Timing Diagram (MODE = 'b00100)



Note: 1. BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.


#### 21.8.4 Level Triggered Hardware Limit Mode

In the Level Triggered Hardware Limit Timer modes the counter is reset by high or low levels of the external signal TMRx\_ers, as shown in Figure 21-6. Selecting MODE = `b00110 will cause the timer to reset on a low-level external signal. Selecting MODE = `b00111 will cause the timer to reset on a high-level external signal. In the example, the counter is reset while TMRx\_ers = 1. ON is controlled by BSF and BCF instructions. When ON = 0, the external signal is ignored.

When the CCP uses the timer as the PWM time base, then the PWM output will be set high when the timer starts counting and then set low only when the timer count matches the CCPRx value. The timer is reset when either the timer count matches the TxPR value or two clock periods after the external Reset signal goes true and stays true.

The timer starts counting, and the PWM output is set high, on either the clock following the TxPR match or two clocks after the external Reset signal relinquishes the Reset. The PWM output will remain high until the timer counts up to match the CCPRx pulse-width value. If the external Reset signal goes true while the PWM output is high, then the PWM output will remain high until the Reset signal is released allowing the timer to count up to match the CCPRx value.

Figure 21-6. Level Triggered Hardware Limit Mode Timing Diagram (MODE = 'b00111)




#### 21.8.5 Software Start One Shot Mode

In One Shot mode, the timer resets and the ON bit is cleared when the timer value matches the TxPR period value. The ON bit must be set by software to start another timer cycle. Setting MODE = <code>\b01000</code> selects One Shot mode which is illustrated in Figure 21-7. In the example, ON is controlled by BSF and BCF instructions. In the first case, a BSF instruction sets ON and the counter runs to completion and clears ON. In the second case, a BSF instruction starts the cycle, the BCF/BSF instructions turn the counter off and on during the cycle, and then it runs to completion.

When One Shot mode is used in conjunction with the CCP PWM operation, the PWM pulse drive starts concurrent with setting the ON bit. Clearing the ON bit while the PWM drive is active will extend the PWM drive. The PWM drive will terminate when the timer value matches the CCPRx pulse-width value. The PWM drive will remain off until the software sets the ON bit to start another cycle. If the software clears the ON bit after the CCPRx match but before the TxPR match, then the PWM drive will be extended by the length of time the ON bit remains cleared. Another timing cycle can only be initiated by setting the ON bit after it has been cleared by a TxPR period count match.

Figure 21-7. Software Start One Shot Mode Timing Diagram (MODE = 'b01000)



Note: 1. BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.

# 21.8.6 Edge Triggered One Shot Mode


The Edge Triggered One Shot modes start the timer on an edge from the external signal input, after the ON bit is set, and clear the ON bit when the timer matches the TxPR period value. The following edges will start the timer:

- Rising edge (MODE = 'b01001)
- Falling edge (MODE = \b01010)
- Rising or Falling edge (MODE = `b01011)

If the timer is halted by clearing the ON bit, then another TMRx\_ers edge is required after the ON bit is set to resume counting. Figure 21-8 illustrates operation in the rising edge One Shot mode.

When Edge Triggered One Shot mode is used in conjunction with the CCP, then the edge-trigger will activate the PWM drive and the PWM drive will deactivate when the timer matches the CCPRx pulse-width value and stay deactivated when the timer halts at the TxPR period count match.

Figure 21-8. Edge Triggered One Shot Mode Timing Diagram (MODE = 'b01001)



#### 21.8.7 Edge Triggered Hardware Limit One Shot Mode


In Edge Triggered Hardware Limit One Shot modes, the timer starts on the first external signal edge after the ON bit is set and resets on all subsequent edges. Only the first edge after the ON bit is set is needed to start the timer. The counter will resume counting automatically two clocks after all subsequent external Reset edges. Edge triggers are as follows:

- Rising edge start and Reset (MODE = 'b01100)
- Falling edge start and Reset (MODE = 'b01101)

The timer resets and clears the ON bit when the timer value matches the TxPR period value. External signal edges will have no effect until after software sets the ON bit. Figure 21-9 illustrates the rising edge hardware limit one-shot operation.

When this mode is used in conjunction with the CCP, then the first starting edge trigger, and all subsequent Reset edges, will activate the PWM drive. The PWM drive will deactivate when the timer matches the CCPRx pulse-width value and stay deactivated until the timer halts at the TxPR period match unless an external signal edge resets the timer before the match occurs.

Figure 21-9. Edge Triggered Hardware Limit One Shot Mode Timing Diagram (MODE = `b01100)



Note: 1. BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.

#### 21,8,8 Level Reset, Edge Triggered Hardware Limit One Shot Modes


In Level Triggered One Shot mode, the timer count is reset on the external signal level and starts counting on the rising/falling edge of the transition from Reset level to the active level while the ON bit is set. Reset levels are selected as follows:

- Low Reset level (MODE = 'b01110)
- High Reset level (MODE = `b01111)

When the timer count matches the TxPR period count, the timer is reset and the ON bit is cleared. When the ON bit is cleared by either a TxPR match or by software control, a new external signal edge is required after the ON bit is set to start the counter.

When Level-Triggered Reset One Shot mode is used in conjunction with the CCP PWM operation, the PWM drive goes active with the external signal edge that starts the timer. The PWM drive goes inactive when the timer count equals the CCPRx pulse-width count. The PWM drive does not go active when the timer count clears at the TxPR period count match.

Figure 21-10. Low Level Reset, Edge Triggered Hardware Limit One Shot Mode Timing Diagram (MODE = \b01110)



Note: 1. BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.

#### 21.8.9 Edge Triggered Monostable Modes

The Edge Triggered Monostable modes start the timer on an edge from the external Reset signal input, after the ON bit is set, and stop incrementing the timer when the timer matches the TxPR period value. The following edges will start the timer:

- Rising edge (MODE = 'b10001)
- Falling edge (MODE = 'b10010)
- Rising or Falling edge (MODE = 'b10011)

When an Edge Triggered Monostable mode is used in conjunction with the CCP PWM operation, the PWM drive goes active with the external Reset signal edge that starts the timer, but will not go active when the timer matches the TxPR value. While the timer is incrementing, additional edges on the external Reset signal will not affect the CCP PWM.

Figure 21-11. Rising Edge Triggered Monostable Mode Timing Diagram (MODE = \b10001)

Note: 1. BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.

# 21.8.10 Level Triggered Hardware Limit One Shot Modes


The Level Triggered Hardware Limit One Shot modes hold the timer in Reset on an external Reset level and start counting when both the ON bit is set and the external signal is not at the Reset level. If one of either the external signal is not in Reset or the ON bit is set, then the other signal being set/made active will start the timer. Reset levels are selected as follows:

- Low Reset level (MODE = 'b10110)
- High Reset level (MODE = `b10111)

When the timer count matches the TxPR period count, the timer is reset and the ON bit is cleared. When the ON bit is cleared by either a TxPR match or by software control, the timer will stay in Reset until both the ON bit is set and the external signal is not at the Reset level.

When Level Triggered Hardware Limit One Shot modes are used in conjunction with the CCP PWM operation, the PWM drive goes active with either the external signal edge or the setting of the ON bit, whichever of the two starts the timer.

Figure 21-12. Level Triggered Hardware Limit One Shot Mode Timing Diagram (MODE = 'b10110)



Note: 1. BSF and BCF represent Bit-Set File and Bit-Clear File instructions executed by the CPU to set or clear the ON bit of TxCON. CPU execution is asynchronous to the timer clock input.

# 21.9 Timer2 Operation During Sleep

When PSYNC = 1, Timer2 cannot be operated while the processor is in Sleep mode. The contents of the T2TMR and T2PR registers will remain unchanged while the processor is in Sleep mode.

When PSYNC = 0, Timer2 will operate in Sleep as long as the clock source selected is also still running. If any internal oscillator is selected as the clock source, it will stay active during Sleep mode.

# 21.10 Register Definitions: Timer2 Control

Long bit name prefixes for the Timer2 peripherals are shown in the table below. Refer to the "Long Bit Names" section of the "Register and Bit Naming Conventions" chapter for more information.

Table 21-2. Timer2 Long Bit Name Prefixes

Peripheral	Bit Name Prefix
Timer2	T2
Timer4	T4
Timer6	T6



**Important:** References to module Timer2 apply to all the even numbered timers on this device (Timer2, Timer4, etc.).

# PIC16F18015/25/44/45

**TMR2 - Timer2 Module** 

# 21.10.1 TxTMR

Name: TxTMR

**Offset:** 0x030C,0x0312,0x0318

Timer Counter Register

Bit	7	6	5	4	3	2	1	0
	TxTMR[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - TxTMR[7:0] Timerx Counter

# PIC16F18015/25/44/45

**TMR2 - Timer2 Module** 

# 21.10.2 TxPR

Name: TxPR

**Offset:** 0x030D,0x0313,0x0319

Timer Period Register

Bit	7	6	5	4	3	2	1	0	
	TxPR[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	1	1	1	1	1	1	1	1	

Bits 7:0 - TxPR[7:0] Timer Period Register

Value	Description
o to 255	The timer restarts at '0' when TxTMR reaches the TxPR value

## 21,10,3 TxCON

Name: TxCON

**Offset:** 0x030E,0x0314,0x031A

Timerx Control Register

Bit	7	6	5	4	3	2	1	0	
	ON CKPS[2:0]			OUTPS[3:0]					
Access	R/W/HC	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	

# Bit 7 - ON Timer On(1)

Value	Description
1	Timer is on
0	Timer is off: All counters and state machines are reset

## Bits 6:4 - CKPS[2:0] Timer Clock Prescale Select

Value	Description
111	1:128 Prescaler
110	1:64 Prescaler
101	1:32 Prescaler
100	1:16 Prescaler
011	1:8 Prescaler
010	1:4 Prescaler
001	1:2 Prescaler
000	1:1 Prescaler

# Bits 3:0 - OUTPS[3:0] Timer Output Postscaler Select

Value	Description
1111	1:16 Postscaler
1110	1:15 Postscaler
1101	1:14 Postscaler
1100	1:13 Postscaler
1011	1:12 Postscaler
1010	1:11 Postscaler
1001	1:10 Postscaler
1000	1:9 Postscaler
0111	1:8 Postscaler
0110	1:7 Postscaler
0101	1:6 Postscaler
0100	1:5 Postscaler
0011	1:4 Postscaler
0010	1:3 Postscaler
0001	1:2 Postscaler
0000	1:1 Postscaler

## Note:

1. In certain modes, the ON bit will be auto-cleared by hardware. See Table 21-1.

## 21.10.4 TxHLT

Name: TxHLT

**Offset:** 0x030F,0x0315,0x031B

Timer Hardware Limit Control Register

Bit	7	6	5	4	3	2	1	0
[	PSYNC	CPOL	CSYNC			MODE[4:0]		
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

## Bit 7 - PSYNC Timer Prescaler Synchronization Enable (1, 2)

Value	Description
1	Timer Prescaler Output is synchronized to F <sub>OSC</sub> /4
0	Timer Prescaler Output is not synchronized to F <sub>OSC</sub> /4

### Bit 6 - CPOL Timer Clock Polarity Selection(3)

Value	Description
1	Falling edge of input clock clocks timer/prescaler
0	Rising edge of input clock clocks timer/prescaler

# Bit 5 - CSYNC Timer Clock Synchronization Enable (4, 5)

Value	Description
1	ON bit is synchronized to timer clock input
0	ON bit is not synchronized to timer clock input

## Bits 4:0 - MODE[4:0] Timer Control Mode Selection<sup>(6, 7)</sup>

Value	Description
00000 to	See Table 21-1
11111	

#### Notes:


- 1. Setting this bit ensures that reading TxTMR will return a valid data value.
- 2. When this bit is '1', the Timer cannot operate in Sleep mode.
- 3. CKPOL must not be changed while ON = 1.
- 4. Setting this bit ensures glitch-free operation when the ON is enabled or disabled.
- 5. When this bit is set, then the timer operation will be delayed by two input clocks after the ON bit is set.
- 6. Unless otherwise indicated, all modes start upon ON = 1 and stop upon ON = 0 (stops occur without affecting the value of TxTMR).
- 7. When TxTMR = TxPR, the next clock clears TxTMR, regardless of the operating mode.

# 21.10.5 TxCLKCON

Name: TxCLKCON

**Offset:** 0x0310,0x0316,0x031C

Timer Clock Source Selection Register



Bits 3:0 - CS[3:0] Timer Clock Source Selection

## Table 21-3. Clock Source Selection


cs		Clock Source	
CS	Timer2	Timer4	Timer6
1111		Reserved	
1110		CLC4_OUT	
1101		CLC3_OUT	
1100		CLC2_OUT	
1011		CLC1_OUT	
1010		ZCD_OUT	
1001		NCO1_OUT	
1000		EXTOSC	
0111		SOSC	
0110		MFINTOSC (32 kHz)	
0101		MFINTOSC (500 kHz)	
0100		LFINTOSC	
0011		HFINTOSC	
0010		F <sub>osc</sub>	
0001		F <sub>OSC</sub> /4	
0000	Pin selected by T2INPPS	Pin selected by T4INPPS	Pin selected by T6INPPS

# 21.10.6 TxRST

Name: TxRST

**Offset:** 0x0311,0x0317,0x031D

Timer External Reset Signal Selection Register



Bits 3:0 - RSEL[3:0] External Reset Source Selection

## Table 21-4. External Reset Sources

RSEL	Reset Source								
KSEL	TMR2	TMR4	TMR6						
1111		Reserved							
1110		CLC4_OUT							
1101		CLC3_OUT							
1100		CLC2_OUT							
1011		CLC1_OUT							
1010		ZCD_OUT							
1001	C1_OUT								
1000		PWM5_OUT							
0111		PWM4_OUT							
0110		PWM3_OUT							
0101		CCP2_OUT							
0100		CCP1_OUT							
0011	TMR6_Post	Reserved							
0010	TMR4_Postscaled_OUT	Reserved	TMR4_Postscaled_OUT						
0001	Reserved	TMR2_Post	scaled_OUT						
0000	Pin selected by T2INPPS	Pin selected by T4INPPS	Pin selected by T6INPPS						

# 21.11 Register Summary - Timer2

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x030B										
0x030C	T2TMR	7:0		:		T2TM	IR[7:0]	-	-	
0x030D	T2PR	7:0				T2PI	R[7:0]			
0x030E	T2CON	7:0	ON		CKPS[2:0]			OUTF	PS[3:0]	
0x030F	T2HLT	7:0	PSYNC	CPOL	CSYNC		•	MODE[4:0]		
0x0310	T2CLKCON	7:0						cs	[3:0]	
0x0311	T2RST	7:0					RSEL[3:0]			
0x0312	T4TMR	7:0		:	•	T4TM	IR[7:0]			
0x0313	T4PR	7:0				T4PI	R[7:0]			
0x0314	T4CON	7:0	ON		CKPS[2:0]			OUTF	PS[3:0]	
0x0315	T4HLT	7:0	PSYNC	CPOL	CSYNC		MODE[4:0]			
0x0316	T4CLKCON	7:0						cs	[3:0]	
0x0317	T4RST	7:0						RSE	L[3:0]	
0x0318	T6TMR	7:0		:	•	T6TM	IR[7:0]			
0x0319	T6PR	7:0				T6PI	R[7:0]			
0x031A	T6CON	7:0	ON		CKPS[2:0]		OUTPS[3:0]			
0x031B	T6HLT	7:0	PSYNC	CPOL	CSYNC		MODE[4:0]			
0x031C	T6CLKCON	7:0					CS[3:0]			
0x031D	T6RST	7:0						RSE	L[3:0]	

# 22. NCO - Numerically Controlled Oscillator Module


The Numerically Controlled Oscillator (NCO) module is a timer that uses overflow from the addition of an increment value to divide the input frequency. The advantage of the addition method over a simple counter driven timer is that the output frequency resolution does not vary with the divider value. The NCO is most useful for applications that require frequency accuracy and fine resolution at a fixed duty cycle.

Features of the NCO include:

- 20-Bit Increment Function
- · Fixed Duty Cycle (FDC) mode
- · Pulse Frequency (PF) mode
- · Output Pulse-Width Control
- · Multiple Clock Input Sources
- · Output Polarity Control
- · Interrupt Capability

The following figure is a simplified block diagram of the NCO module.

Figure 22-1. Numerically Controlled Oscillator Module Simplified Block Diagram



**Note 1:** The increment registers are double-buffered to allow for value changes to be made without first disabling the NCO module. The full increment value is loaded into the buffer registers on the second rising edge of the NCOx\_clk signal that occurs immediately after a write to the NCOxINCL register. The buffers are not user-accessible and are shown here for reference.

# 22.1 NCO Operation

The NCO operates by repeatedly adding a fixed value to an accumulator. Additions occur at the input clock rate. The accumulator will overflow with a carry periodically, which is the raw NCO output (NCO\_overflow). This effectively reduces the input clock by the ratio of the addition value to the maximum accumulator value. See the following equation.

## **Equation 22-1. NCO Overflow Frequency**

$$F_{OVERFLOW} = \frac{NCO\ Clock\ Frequency\ imes\ Increment\ Value}{2^{20}}$$

It is apparent from the equation that there is a linear relationship between the increment value and the overflow frequency. This linear advantage over divide-by-n timers comes at the cost of output jitter. However, the jitter is always plus or minus one NCO clock period that occurs periodically, depending on the division remainder. For example, there is no jitter when there is no division remainder, whereas a division remainder of 0.5 will result in a jitter frequency one half of the overflow frequency.

#### 22.1.1 NCO Clock Sources

The NCO can be clocked from a variety of sources including the system clock, internal timers, and other peripherals. The NCO clock source is selected by configuring the CKS bits.

#### 22.1.2 Accumulator

The accumulator is a 20-bit register. Read and write access to the accumulator is available through three registers:

- NCOxACCL
- NCOxACCH
- NCOxACCU

#### 22.1.3 Adder

The NCO adder is a full adder, which operates synchronously from the source clock. The addition of the previous result and the increment value replaces the accumulator value on the rising edge of each input clock.

## 22.1.4 Increment Registers

The increment value is stored in three registers making up a 20-bit word. In order of LSB to MSB, they are:

- NCOxINCL
- NCOxINCH
- NCOxINCU

The increment registers are readable and writable and are double-buffered to allow value changes to be made without first disabling the NCO module.

When the NCO module is enabled, the NCOxINCU and NCOxINCH registers will be written first, then the NCOxINCL register. Writing to the NCOxINCL register initiates the increment buffer registers to be loaded simultaneously on the second rising edge of the NCO\_clk signal.

When the NCO module is disabled, the increment buffers are loaded immediately after a write to the increment registers.




Important: The increment buffer registers are not user-accessible.

# 22.2 Fixed Duty Cycle Mode

In Fixed Duty Cycle (FDC) mode, every time the accumulator overflows, the output is toggled. This provides a 50% duty cycle at half the F<sub>OVERFLOW</sub> frequency, provided that the increment value remains constant. For more information, see the figure below.

The FDC mode is selected by clearing the PFM bit.

Figure 22-2, FDC Output Mode Timing Diagram



# 22.3 Pulse Frequency Mode

In Pulse Frequency (PF) mode, the output becomes active on the rising clock edge immediately following the overflow event, and goes inactive 1 to 128 clock periods later, determined by the PWS bits. This provides a pulsed output at the  $F_{OVERFLOW}$  frequency. For more information, refer to the figure above.



**Important:** When the selected pulse width is greater than the accumulator overflow time frame, then the NCO output does not toggle.

The level of the Active and Inactive states is determined by the POL bit.

PF mode is selected by setting the PFM bit.

# 22.4 Output Polarity Control

The last stage in the NCO module is the output polarity. The POL bit selects the output polarity. The active level of the Pulse Frequency mode is high true when the POL bit is cleared.

Changing the polarity while the interrupts are enabled will cause an interrupt for the resulting output transition.

The NCO output signal (NCOx out) is available by internal routing to several other peripherals.

# 22.5 Interrupts

When the accumulator overflows, the NCO Interrupt Flag bit, NCOxIF, in the associated PIR register is set. To enable interrupt service on this event, the following bits must be set:

- EN bit
- · NCOxIE bit in the associated PIE register
- · Peripheral and Global Interrupt Enable bits

The interrupt must be cleared by software by clearing the NCOxIF bit in the Interrupt Service Routine.

#### 22.6 Effects of a Reset

All of the NCO registers are cleared to zero as the result of any Reset.

# 22.7 Operation in Sleep

The NCO module operates independently from the system clock and will continue to run during Sleep, provided that the clock source selected remains active.

The HFINTOSC remains active during Sleep when the NCO module is enabled and the HFINTOSC is selected as the clock source, regardless of the system clock source selected.

In other words, if the HFINTOSC is simultaneously selected as the system clock and the NCO clock source, when the NCO is enabled, the CPU will go Idle during Sleep, but the NCO will continue to operate and the HFINTOSC will remain active.

With a clock running, it will have a direct effect on the Sleep mode current.

# 22.8 Register Definitions: NCO


Long bit name prefixes for the NCO peripherals are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 22-1. NCO Long Bit Name Prefixes

Peripheral	Bit Name Prefix		
NCO1	NCO1		

## 22.8.1 NCOxCON

Name: NCOxCON Offset: 0x0492 NCO Control Register



# Bit 7 - EN NCO Enable

Value	Description
1	NCO module is enabled
0	NCO module is disabled

#### Bit 5 – OUT NCO Output

Displays the current logic level of the NCO module output.

## Bit 4 - POL NCO Polarity

Value	Description
1	NCO output signal is inverted
0	NCO output signal is not inverted


# Bit 0 - PFM NCO Pulse Frequency Mode

Value	Description
1	NCO operates in Pulse Frequency mode. Output frequency is F <sub>OVERFLOW</sub> .
0	NCO operates in Fixed Duty Cycle mode. Output frequency is F <sub>OVERFLOW</sub> divided by 2.

## 22.8.2 NCOxCLK

Name: NCOxCLK Offset: 0x0493

NCO Input Clock Control Register



Bits 7:5 - PWS[2:0] NCO Output Pulse-Width Select(1)

Value	Description
111	NCO output is active for 128 input clock periods
110	NCO output is active for 64 input clock periods
101	NCO output is active for 32 input clock periods
100	NCO output is active for 16 input clock periods
011	NCO output is active for 8 input clock periods
010	NCO output is active for 4 input clock periods
001	NCO output is active for 2 input clock periods
000	NCO output is active for 1 input clock periods

Bits 3:0 - CKS[3:0] NCO Clock Source Select

CKS	Clock Source	Active in Sleep		
Value	NCO1	Active in Sleep		
1111-1110	Reserved	-		
1101	CLC4_OUT	No		
1100	CLC3_OUT	No		
1011	CLC2_OUT	No		
1010	CLC1_OUT	-		
1001	TMR6_postscaled_OUT	No		
1000	TMR4_postscaled_OUT	No		
0111	TMR2_postscaled_OUT	No		
0110	EXTOSC	Yes		
0101	SOSC	Yes		
0100	MFINTOSC (32 kHz)	Yes		
0011	MFINTOSC (500 kHz)	Yes		
0010	LFINTOSC	Yes		
0001	HFINTOSC	Yes		
0000	F <sub>osc</sub>	No		


#### Note:

1. PWS applies only when operating in Pulse Frequency mode.

#### 22,8,3 NCOxACC

Name: NCOxACC Offset: 0x048C

NCO Accumulator Register



Bits 19:0 - ACC[19:0] Accumulated sum of NCO additions


#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - NCOxACCU: Accesses the upper byte ACC[23:16]
  - NCOxACCH: Accesses the high byte ACC[15:8]
  - NCOxACCL: Accesses the low byte ACC[7:0].
- 2. The accumulator spans registers NCOxACCU:NCOxACCH:NCOxACCL. The 24 bits are reserved, but not all are used. This register updates in real-time, asynchronously to the CPU; there is no provision to ensure atomic access to this 24-bit space using an 8-bit bus. Writing to this register while the module is operating will produce undefined results.

## **22.8.4 NCOxINC**

Name: NCOxINC Offset: 0x048F

NCO Increment Register



Bits 19:0 - INC[19:0] Value by which the NCOxACC is increased by each NCO clock

#### Notes:

- 1. The individual bytes in this multibyte register can be accessed with the following register names:
  - NCOxINCU: Accesses the upper byte INC[19:16]
  - NCOxINCH: Accesses the high byte INC[15:8]
  - NCOxINCL: Accesses the low byte INC[7:0].
- 2. The logical increment spans NCOxINCU:NCOxINCH:NCOxINCL.
- 3. NCOxINC is double-buffered as INCBUF:
  - INCBUF is updated on the next falling edge of NCOxCLK after writing to NCOxINCL
  - NCOxINCU and NCOxINCH will be written prior to writing NCOxINCL.

# 22.9 Register Summary - NCO

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x048B										
		7:0				ACC	[7:0]			
0x048C	NCO1ACC	15:8	ACC[15:8]							
		23:16						ACC[	19:16]	
		7:0		INC[7:0]						
0x048F	NCO1INC	15:8				INC[	15:8]			
		23:16						INC[1	19:16]	
0x0492	NCO1CON	7:0	EN		OUT	POL				PFM
0x0493	NCO1CLK	7:0		PWS[2:0]				CKS	[3:0]	

# 23. CWG - Complementary Waveform Generator Module

The Complementary Waveform Generator (CWG) produces half-bridge, full-bridge, and steering of PWM waveforms. It is backwards compatible with previous CCP functions.

The CWG has the following features:

- · Six Operating modes:
  - Synchronous Steering mode
  - Asynchronous Steering mode
  - Full Bridge mode, Forward
  - Full Bridge mode, Reverse
  - Half Bridge mode
  - Push-Pull mode
- Output Polarity Control
- · Output Steering
- Independent 6-bit Rising and Falling Event Dead-Band Timers:
  - Clocked dead band
  - Independent rising and falling dead-band enables
- Auto-Shutdown Control with:
  - Selectable shutdown sources
  - Auto-restart option
  - Auto-shutdown pin override control

# 23.1 Fundamental Operation

The CWG generates two output waveforms from the selected input source.

The off-to-on transition of each output can be delayed from the on-to-off transition of the other output, thereby creating a time delay immediately where neither output is driven. This is referred to as dead time and is covered in the Dead-Band Control section.

It may be necessary to guard against the possibility of circuit faults or a feedback event arriving too late or not at all. In this case, the active drive must be terminated before the Fault condition causes damage. This is referred to as auto-shutdown and is covered in the Auto-Shutdown section.

# 23.2 Operating Modes

The CWG module can operate in six different modes, as specified by the MODE bits:

- · Half Bridge mode
- Push-Pull mode
- · Asynchronous Steering mode
- · Synchronous Steering mode
- Full Bridge mode, Forward
- Full Bridge mode, Reverse

All modes accept a single pulse input, and provide up to four outputs as described in the following sections.

All modes include auto-shutdown control as described in the Auto-Shutdown section.



Important: Except as noted for Full Bridge mode, mode changes must only be performed while EN = 0.

# 23.2.1 Half Bridge Mode

In Half Bridge mode, two output signals are generated as true and inverted versions of the input as illustrated in Figure 23-1. A nonoverlap (dead band) time is inserted between the two outputs to prevent shoot-through current in various power supply applications. Dead-band control is described in the Dead-Band Control section. The output steering feature cannot be used in this mode. A basic block diagram of this mode is shown in Figure 23-2.

The unused outputs CWGxC and CWGxD drive similar signals as CWGxA and CWGxB, with polarity independently controlled by the POLC and POLD bits, respectively.

Figure 23-1. CWG Half Bridge Mode Operation





Figure 23-2. Simplified CWG Block Diagram (Half Bridge Mode, MODE = 'b100)



## 23,2,2 Push-Pull Mode

In Push-Pull mode, two output signals are generated, alternating copies of the input as illustrated in Figure 23-3. This alternation creates the Push-Pull effect required for driving some transformer-based power supply designs. Steering modes are not used in Push-Pull mode. A basic block diagram for the Push-Pull mode is shown in Figure 23-4.

The Push-Pull sequencer is reset whenever EN = 0 or if an auto-shutdown event occurs. The sequencer is clocked by the first input pulse, and the first output appears on CWGxA.

The unused outputs CWGxC and CWGxD drive copies of CWGxA and CWGxB, respectively, but with polarity controlled by the POLC and POLD bits, respectively.

Figure 23-3. CWG Push-Pull Mode Operation






Figure 23-4. Simplified CWG Block Diagram (Push-Pull Mode, MODE = 'b101)



# 23.2.3 Full Bridge Mode

In Forward and Reverse Full Bridge modes, three outputs drive static values while the fourth is modulated by the input data signal. The mode selection may be toggled between forward and reverse by toggling the MODE[0] bit of the CWGxCON0 register while keeping the MODE[2:1] bits static, without disabling the CWG module. When connected, as shown in Figure 23-5, the outputs are appropriate for a full-bridge motor driver. Each CWG output signal has independent polarity control, so the circuit can be adapted to high-active and low-active drivers. A simplified block diagram for the Full Bridge modes is shown in Figure 23-6.

Figure 23-5. Example of Full-Bridge Application







Figure 23-6. Simplified CWG Block Diagram (Forward and Reverse Full Bridge Modes)

In Forward Full Bridge mode (MODE = \b010), CWGxA is driven to its Active state, CWGxB and CWGxC are driven to their Inactive state, and CWGxD is modulated by the input signal, as shown in Figure 23-7.

In Reverse Full Bridge mode (MODE = <code>\b011</code>), CWGxC is driven to its Active state, CWGxA and CWGxD are driven to their Inactive states, and CWGxB is modulated by the input signal, as shown in Figure 23-7.

In Full Bridge mode, the dead-band period is used when there is a switch from forward to reverse or vice versa. This dead-band control is described in the Dead-Band Control section, with additional details in the Rising Edge and Reverse Dead Band and Falling Edge and Forward Dead Band sections. Steering modes are not used with either of the Full Bridge modes.

Figure 23-7. Example of Full-Bridge Output



## Notes:

- 1. A rising CWG data input creates a rising event on the modulated output.
- 2. Output signals shown as active-high; all POLy bits are clear.

#### 23.2.3.1 Direction Change in Full Bridge Mode

In Full Bridge mode, changing the MODE[0] bit controls the forward/reverse direction. Direction changes occur on the next rising edge of the modulated input. The sequence, described as follows, is illustrated in Figure 23-8.

- The associated active output CWGxA and the inactive output CWGxC are switched to drive in the opposite direction.
- 2. The previously modulated output CWGxD is switched to the Inactive state, and the previously inactive output CWGxB begins to modulate.
- 3. CWG modulation resumes after the direction-switch dead band has elapsed.




Figure 23-8. Example of PWM Direction Change at Near 100% Duty Cycle

#### 23.2.3.2 Dead-Band Delay in Full Bridge Mode

Dead-band delay is important when either of the following conditions is true:

- The direction of the CWG output changes when the duty cycle of the data input is at or near 100%.
- The turn-off time of the power switch, including the power device and driver circuit, is greater than the turn-on time.

The dead-band delay is inserted only when changing directions, and only the modulated output is affected. The statically-configured outputs (CWGxA and CWGxC) are not afforded dead band, and switch essentially simultaneously.

Figure 23-8 shows an example of the CWG outputs changing directions from forward to reverse, at near 100% duty cycle. In this example, at time t1, the output of CWGxA and CWGxD becomes inactive, while the output of CWGxC becomes active. Since the turn-off time of the power devices is longer than the turn-on time, a shoot-through current will flow through the power devices QC and QD for the duration of 'T'. The same phenomenon will occur to power devices QA and QB for the CWG direction change from reverse to forward.

When changing the CWG direction at high duty cycle is required for an application, two possible solutions for eliminating the shoot-through current are:

- 1. Reduce the CWG duty cycle for one period before changing directions.
- 2. Use switch drivers that can drive the switches off faster than they can drive them on.


# 23.2.4 Steering Modes

In both Synchronous and Asynchronous Steering modes, the CWG Data can be steered to any combination of four CWG outputs. A fixed value will be presented on all the outputs not used for the PWM output. Each output has independent polarity, steering, and shutdown options. Dead-band control is not used in either Steering mode.

For example, when STRA = 0, the corresponding pin is held at the level defined by OVRA. When STRA = 1, the pin is driven by the CWG Data signal. The POLy bits control the signal polarity only when STRy = 1.

The CWG auto-shutdown operation also applies in Steering modes as described in the Auto-Shutdown section. An auto-shutdown event will only affect pins that have STRy = 1.

Figure 23-9. Simplified CWG Block Diagram (Output Steering Modes)




### 23.2.4.1 Synchronous Steering Mode

In Synchronous Steering mode (MODE = <code>\b001</code>), the changes to steering selection registers take effect on the next rising edge of CWG Data (see the figure below). In Synchronous Steering mode, the output will always produce a complete waveform.



**Important:** Only the STRx bits are synchronized; the OVRx bits are not synchronized.


Figure 23-10. Example of Synchronous Steering (MODE = 'b001)



### 23.2.4.2 Asynchronous Steering Mode

In Asynchronous mode (MODE = \b000), steering takes effect at the end of the instruction cycle that writes to STRx. In Asynchronous Steering mode, the output signal may be an incomplete waveform (see the figure below). This operation may be useful when the user firmware needs to immediately remove a signal from the output pin.

Figure 23-11. Example of Asynchronous Steering (MODE = 'b000)



#### 23.2.4.3 Start-Up Considerations

The application hardware must use the proper external pull-up and/or pull-down resistors on the CWG output pins. This is required because all I/O pins are forced to high-impedance at Reset.

The Polarity Control (POLy) bits allow the user to choose whether the output signals are active-high or active-low.

#### 23.3 Clock Source

The clock source is used to drive the dead-band timing circuits. The CWG module allows the following clock sources to be selected:

- F<sub>OSC</sub> (system clock)
- HFINTOSC

When the HFINTOSC is selected, the HFINTOSC will be kept running during Sleep. Therefore, the CWG modes requiring dead band can operate in Sleep, provided that the CWG data input is also active during Sleep. The clock sources are selected using the CS bit. The system clock F<sub>OSC</sub> is disabled in Sleep and thus dead-band control cannot be used.

# 23.4 Selectable Input Sources

The CWG generates the output waveforms from the input sources which are selected with the ISM bits. Refer to the CWGxISM register for more details.

# 23.5 Output Control

#### 23.5.1 CWG Output

Each CWG output can be routed to a Peripheral Pin Select (PPS) output via the RxyPPS register. Refer to the "PPS - Peripheral Pin Select Module" chapter for more details.

# 23.5.2 Polarity Control

The polarity of each CWG output can be selected independently. When the output polarity bit is set, the corresponding output is active-high. Clearing the output polarity bit configures the corresponding output as active-low. However, polarity does not affect the override levels. Output polarity is selected with the POLy bits. Auto-shutdown and steering options are unaffected by polarity.

#### 23.6 Dead-Band Control

The dead-band control provides nonoverlapping complementary outputs to prevent shoot-through current when the outputs switch. Dead-band operation is employed for Half Bridge and Full Bridge modes. The CWG contains two 6-bit dead-band counters. One is used for the rising edge of the input source control in Half Bridge mode or for reverse direction change dead band in Full Bridge mode. The other is used for the falling edge of the input source control in Half Bridge mode or for forward direction change dead band in Full Bridge mode.

Dead band is timed by counting CWG clock periods from zero up to the value in the rising or falling dead-band counter registers.

#### 23.6.1 Dead-Band Functionality in Half Bridge Mode

In Half Bridge mode, the dead-band counters dictate the delay between the falling edge of the normal output and the rising edge of the inverted output. This can be seen in Figure 23-1.

#### 23.6.2 Dead-Band Functionality in Full Bridge Mode


In Full Bridge mode, the dead-band counters are used when undergoing a direction change. The MODE[0] bit can be set or cleared while the CWG is running, allowing for changes from Forward to Reverse mode. The CWGxA and CWGxC signals will change immediately upon the first rising input edge following a direction change, but the modulated signals (CWGxB or CWGxD, depending on the direction of the change) will experience a delay dictated by the dead-band counters.

# 23.7 Rising Edge and Reverse Dead Band

In Half Bridge mode, the rising edge dead band delays the turn-on of the CWGxA output after the rising edge of the CWG data input. In Full Bridge mode, the reverse dead-band delay is only inserted when changing directions from Forward mode to Reverse mode, and only the modulated output, CWGxB, is affected.

The CWGxDBR register determines the duration of the dead-band interval on the rising edge of the input source signal. This duration is from 0 to 64 periods of the CWG clock. The following figure illustrates different dead-band delays for rising and falling CWG Data events.

Figure 23-12. Dead-Band Operation, CWGxDBR = 0x01, CWGxDBF = 0x02



Dead band is always initiated on the edge of the input source signal. A count of zero indicates that no dead band is present.

If the input source signal reverses polarity before the dead-band count is completed, then no signal will be seen on the respective output.

The CWGxDBR register value is double-buffered. When EN = 0, the buffer is loaded when CWGxDBR is written. When EN = 1, the buffer will be loaded at the rising edge following the first falling edge of the CWG Data, after the LD bit is set.

# 23.8 Falling Edge and Forward Dead Band


In Half Bridge mode, the falling edge dead band delays the turn-on of the CWGxB output at the falling edge of the CWG data input. In Full Bridge mode, the forward dead-band delay is only inserted when changing directions from Reverse mode to Forward mode, and only the modulated output, CWGxD, is affected.

The CWGxDBF register determines the duration of the dead-band interval on the falling edge of the input source signal. This duration is from 0 to 64 periods of the CWG clock.

Dead-band delay is always initiated on the edge of the input source signal. A count of zero indicates that no dead band is present.

If the input source signal reverses polarity before the dead-band count is completed, then no signal will be seen on the respective output.

Figure 23-13. Dead-Band Operation, CWGxDBR = 0x03, CWGxDBF = 0x06, Source Shorter Than Dead Band



The CWGxDBF register value is double-buffered. When EN = 0, the buffer is loaded when CWGxDBF is written. When EN = 1, the buffer will be loaded at the rising edge following the first falling edge of the data input after the LD bit is set.

#### 23.9 Dead-Band Jitter

When the rising and falling edges of the input source are asynchronous to the CWG clock, it creates jitter in the dead-band time delay. The maximum jitter is equal to one CWG clock period. Refer to the equations below for more details.

## Equation 23-1. Dead-Band Delay Time Calculation

$$\begin{split} T_{DEAD-BAND\_MIN} &= \frac{1}{F_{CWG\_CLOCK}} \bullet DBx \\ T_{DEAD-BAND\_MAX} &= \frac{1}{F_{CWG\_CLOCK}} \bullet (DBx+1) \\ T_{IITTER} &= T_{DEAD-BAND\_MAX} - T_{DEAD-BAND\_MIN} \end{split}$$

$$T_{JITTER} = \frac{1}{F_{CWG,CLOCK}}$$

$$T_{DEAD-BAND\_MAX} = T_{DEAD-BAND\_MIN} + T_{JITTER}$$


#### **Dead-Band Delay Example Calculation**

$$DBx = 0x0A = 10$$
  
 $F_{CWG\_CLOCK} = 8 \, MHz$   
 $T_{JITTER} = \frac{1}{8 \, MHz} = 125 \, ns$   
 $T_{DEAD} - B_{AND\_MIN} = 125 \, ns \bullet 10 = 1.25 \, \mu s$   
 $T_{DEAD} - B_{AND\_MAX} = 1.25 \, \mu s + 0.125 \, \mu s = 1.37 \, \mu s$ 

## 23.10 Auto-Shutdown

Auto-shutdown is a method to immediately override the CWG output levels with specific overrides that allow for safe shutdown of the circuit. The Shutdown state can be either cleared automatically or held until cleared by software. The auto-shutdown circuit is illustrated in the following figure.

#### Figure 23-14. CWG Shutdown Block Diagram



#### 23.10.1 Shutdown

The Shutdown state can be entered by either of the following two methods:

- · Software Generated
- · External Input

#### 23.10.2 Software Generated Shutdown

Setting the SHUTDOWN bit will force the CWG into the Shutdown state.

When the auto-restart is disabled, the Shutdown state will persist as long as the SHUTDOWN bit is set.

When auto-restart is enabled, the SHUTDOWN bit will clear automatically and resume operation on the next rising edge event. The SHUTDOWN bit indicates when a Shutdown condition exists. The bit may be set or cleared in software or by hardware.

# 23.10.3 External Input Source

External shutdown inputs provide the fastest way to safely suspend CWG operation in the event of a Fault condition. When any of the selected shutdown inputs goes active, the CWG outputs will immediately go to the selected override levels without software delay. The override levels are selected by the LSBD and LSAC bits. Several input sources can be selected to cause a Shutdown condition. All input sources are active-low. The shutdown input sources are individually enabled by the ASyE bits.



**Important:** Shutdown inputs are level sensitive, not edge sensitive. The Shutdown state cannot be cleared, except by disabling auto-shutdown, as long as the shutdown input level persists.

#### 23.10.4 Pin Override Levels

The levels driven to the CWG outputs during an auto-shutdown event are controlled by the LSBD and LSAC bits. The LSBD bits control CWGxB/D output levels, while the LSAC bits control the CWGxA/C output levels.

## 23.10.5 Auto-Shutdown Interrupts

When an auto-shutdown event occurs, either by software or hardware setting SHUTDOWN, the CWGxIF flag bit of the PIRx register is set.

### 23.11 Auto-Shutdown Restart

After an auto-shutdown event has occurred, there are two ways to resume operation:

- · Software controlled
- Auto-restart

In either case, the shutdown source must be cleared before the restart can take place. That is, either the Shutdown condition must be removed, or the corresponding ASyE bit must be cleared.

#### 23.11.1 Software-Controlled Restart


When the REN bit is clear (REN = 0), the CWG module must be restarted after an auto-shutdown event through software.

Once all auto-shutdown sources are removed, the software must clear the SHUTDOWN bit. Once SHUTDOWN is cleared, the CWG module will resume operation upon the first rising edge of the CWG data input.



**Important**: The SHUTDOWN bit cannot be cleared in software if the Auto-Shutdown condition is still present.

Figure 23-15. Shutdown Functionality, Auto-Restart Disabled (REN = 0, LSAC = 'b01, LSBD = 'b01)



#### 23.11,2 Auto-Restart

When the REN bit is set (REN = 1), the CWG module will restart from the Shutdown state automatically.


# **CWG - Complementary Waveform Generator Mod...**

Once all Auto-Shutdown conditions are removed, the hardware will automatically clear the SHUTDOWN bit. Once SHUTDOWN is cleared, the CWG module will resume operation upon the first rising edge of the CWG data input.



**Important:** The SHUTDOWN bit cannot be cleared in software if the Auto-Shutdown condition is still present.

Figure 23-16. Shutdown Functionality, Auto-Restart Enabled (REN = 1, LSAC = 'b01, LSBD = 'b01)



# 23.12 Operation During Sleep

The CWG module operates independently from the system clock and will continue to run during Sleep, provided that the clock and input sources selected remain active.

The HFINTOSC remains active during Sleep when all the following conditions are met:

- · CWG module is enabled
- · Input source is active
- HFINTOSC is selected as the clock source, regardless of the system clock source selected.

In other words, if the HFINTOSC is simultaneously selected as the system clock and the CWG clock source, when the CWG is enabled and the input source is active, then the CPU will go Idle during Sleep, but the HFINTOSC will remain active and the CWG will continue to operate. This will have a direct effect on the Sleep mode current.

# 23.13 Configuring the CWG

- Ensure that the TRIS control bits corresponding to CWG outputs are set so that all are configured as inputs, ensuring that the outputs are inactive during setup. External hardware must ensure that pin levels are held to safe levels.
- 2. Clear the EN bit, if not already cleared.
- 3. Configure the MODE bits to set the output operating mode.
- 4. Configure the POLy bits to set the output polarities.
- 5. Configure the ISM bits to select the data input source.
- 6. If a Steering mode is selected, configure the STRy bits to select the desired output on the CWG outputs.
- 7. Configure the LSBD and LSAC bits to select the Auto-Shutdown Output Override states (this is necessary even if not using auto-shutdown, because start-up will be from a Shutdown state).
- 8. If auto-restart is desired, set the REN bit.
- 9. If auto-shutdown is desired, configure the ASyE bits to select the shutdown source.
- Set the desired rising and falling dead-band times with the CWGxDBR and CWGxDBF registers.
- 11. Select the clock source with the CS bit.

# **CWG - Complementary Waveform Generator Mod...**

- 12. Set the EN bit to enable the module.
- 13. Clear the TRIS bits that correspond to the CWG outputs to set them as outputs.

If auto-restart is to be used, set the REN bit and the SHUTDOWN bit will be cleared automatically. Otherwise, clear the SHUTDOWN bit in software to start the CWG.

# 23.14 Register Definitions: CWG Control

Long bit name prefixes for the CWG peripherals are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 23-1. CWG Long Bit Name Prefixes

Peripheral	Bit Name Prefix		
CWG1	CWG1		

## 23.14.1 CWGxCON0

Name: CWGxCON0 Offset: 0x0510

CWG Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN	LD					MODE[2:0]	
Access	R/W	R/W/HC				R/W	R/W	R/W
Reset	0	0				0	0	0

## Bit 7 - EN CWG Enable

Value	Description
1	Module is enabled
0	Module is disabled

## Bit 6 - LD CWG1 Load Buffers(1)

Value	Description
1	Dead-band count buffers to be loaded on CWG data rising edge, following first falling edge after this bit
	is set
0	Buffers remain unchanged

# Bits 2:0 - MODE[2:0] CWG Mode

DIG 2.0 - I	Bits 2.0 - MODE[2.0] OVIO Mode					
Value	Description					
111	Reserved					
110	Reserved					
101	CWG outputs operate in Push-Pull mode					
100	CWG outputs operate in Half Bridge mode					
011	CWG outputs operate in Reverse Full Bridge mode					
010	CWG outputs operate in Forward Full Bridge mode					
001	CWG outputs operate in Synchronous Steering mode					
000	CWG outputs operate in Asynchronous Steering mode					

#### Note:

1. This bit can only be set after EN = 1; it cannot be set in the same cycle when EN is set.

## 23.14.2 CWGxCON1

Name: CWGxCON1 Offset: 0x0511

CWG Control Register 1

Bit	7	6	5	4	3	2	1	0
			IN		POLD	POLC	POLB	POLA
Access			R		R/W	R/W	R/W	R/W
Reset			x		0	0	0	0

# Bit 5 – IN CWG Input Value (read-only)

V	alue	Description
1		CWG data input is a logic '1'
0		CWG data input is a logic '0'

# Bits 0, 1, 2, 3 - POLy CWG Output 'y' Polarity

	Value Description		
1 Sign		Signal output is inverted polarity	
	0	Signal output is normal polarity	

# 23.14.3 CWGxCLK

Name: CWGxCLK Offset: 0x050C

CWG Clock Input Selection Register




Bit 0 - CS CWG Clock Source Selection Select

Value	Description		
1	HFINTOSC (remains operating during Sleep)		
0	Fosc		

# 23.14.4 CWGxISM

Name: CWGxISM Offset: 0x050D

CWGx Input Selection Register



Bits 3:0 - ISM[3:0] CWG Data Input Source Select

ISM	Input Selection			
ISIVI	CWG1			
1111-1100	Reserved			
1011	CLC4_OUT			
1010	CLC3_OUT			
1001	CLC2_OUT			
1000	CLC1_OUT			
0111	C1_OUT			
0110	NCO1_OUT			
0101	PWM5_OUT			
0100	PWM4_OUT			
0011	PWM3_OUT			
0010	CCP2_OUT			
0001	CCP1_OUT			
0000	Pin selected by CWG1PPS			

## 23.14.5 CWGxSTR

Name: CWGxSTR Offset: 0x0514

CWG Steering Control Register<sup>(1)</sup>

Bit	7	6	5	4	3	2	1	0
	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA
Access	R/W							
Reset	0	0	0	0	0	0	0	0

#### Bits 4. 5. 6. 7 - OVRv Steering Data OVR'v'

Value	Condition	Description		
x STRy = 1		CWGx'y' output has the CWG data input waveform with polarity control from		
		POLy bit		
1	STRy = $0$ and POLy = $\times$	CWGx'y' output is high		
0	STRy = $0$ and POLy = $x$	CWGx'y' output is low		

## Bits 0, 1, 2, 3 – STRy STR'y' Steering Enable<sup>(2)</sup>

Value	Description	า		
1	CWGx'y' ou	tput has	the CWG dat	ta input waveform with polarity control from the POLy bit
0	CWGx'y' ou	tput is a	ssigned to val	lue of the OVRy bit

#### Notes:

- 1. The bits in this register apply only when MODE = `b00x (CWGxCON0, Steering modes).
- 2. This bit is double-buffered when MODE = 'b001.

#### 23.14.6 CWGxAS0

Name: CWGxAS0 Offset: 0x0512

CWG Auto-Shutdown Control Register 0

Bit	7	6	5	4	3	2	1	0
	SHUTDOWN	REN	LSBD[1:0]		LSAC[1:0]			
Access	R/W/HS/HC	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	1	0	1		

## Bit 7 – SHUTDOWN Auto-Shutdown Event Status<sup>(1,2)</sup>

Va	alue	Description
1		An Auto-Shutdown state is in effect
0		No auto-shutdown event has occurred

#### Bit 6 - REN Auto-Restart Enable

Value	Description
1	Auto-restart is enabled
0	Auto-restart is disabled

#### Bits 5:4 - LSBD[1:0] CWGxB and CWGxD Auto-Shutdown State Control

Value	Description
11	A logic '1' is placed on CWGxB/D when an auto-shutdown event occurs
10	A logic '0' is placed on CWGxB/D when an auto-shutdown event occurs
01	Pin is tri-stated on CWGxB/D when an auto-shutdown event occurs
00	The Inactive state of the pin, including polarity, is placed on CWGxB/D after the required dead-band
	interval when an auto-shutdown event occurs

#### Bits 3:2 - LSAC[1:0] CWGxA and CWGxC Auto-Shutdown State Control

Value	Description
11	A logic '1' is placed on CWGxA/C when an auto-shutdown event occurs
10	A logic '0' is placed on CWGxA/C when an auto-shutdown event occurs
01	Pin is tri-stated on CWGxA/C when an auto-shutdown event occurs
00	The Inactive state of the pin, including polarity, is placed on CWGxA/C after the required dead-band
	interval when an auto-shutdown event occurs


#### Notes:

- 1. This bit may be written while EN = 0, to place the outputs into the shutdown configuration.
- The outputs will remain in Auto-Shutdown state until the next rising edge of the CWG data input after this bit is cleared.

#### 23.14.7 CWGxAS1

Name: CWGxAS1 Offset: 0x0513

CWG Auto-Shutdown Control Register 1



Bits 0, 1, 2, 3, 4, 5, 6, 7 – ASyE CWG Auto-Shutdown Source Enable<sup>(1,2)</sup>

ASyE	Auto-Shutdown Source
ASYL	CWG1
AS7E	CLC3_OUT
AS6E	CLC2_OUT
AS5E	CLC1_OUT
AS4E	C1_OUT
AS3E	TMR6_Postscaled_OUT
AS2E	TMR4_Postscaled_OUT
AS1E	TMR2_Postscaled_OUT
AS0E	Pin selected by CWG1PPS


#### Notes:

- 1. This bit may be written while EN = 0, to place the outputs into the shutdown configuration.
- 2. The outputs will remain in Auto-Shutdown state until the next rising edge of the CWG data input after this bit is cleared.

#### 23,14,8 CWGxDBR

Name: CWGxDBR Offset: 0x050E

CWG Rising Dead-Band Count Register



Bits 5:0 - DBR[5:0] CWG Rising Edge-Triggered Dead-Band Count

Reset States: POR/BOR = xxxxxx


All Other Resets = uuuuuu

Valu	e Description	
n	Dead band is	active no less than n and no more than n+1 CWG clock periods after the rising edge
0	0 CWG clock	periods. Dead-band generation is bypassed.

#### 23.14.9 CWGxDBF

Name: CWGxDBF Offset: 0x050F

CWG Falling Dead-Band Count Register



Bits 5:0 - DBF[5:0] CWG Falling Edge-Triggered Dead-Band Count

Reset States: POR/BOR = xxxxxx

All Other Resets = uuuuuu

Value	Description
n	Dead band is active no less than n and no more than n+1 CWG clock periods after the falling edge
0	0 CWG clock periods. Dead-band generation is bypassed.

# 23.15 Register Summary - CWG

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x050B										
0x050C	CWG1CLK	7:0								CS
0x050D	CWG1ISM	7:0			ISM[3:0]					
0x050E	CWG1DBR	7:0					DBR	R[5:0]		
0x050F	CWG1DBF	7:0					DBF	[5:0]		
0x0510	CWG1CON0	7:0	EN	LD					MODE[2:0]	
0x0511	CWG1CON1	7:0			IN		POLD	POLC	POLB	POLA
0x0512	CWG1AS0	7:0	SHUTDOWN	REN	LSBD[1:0] LSAC[1:0]					
0x0513	CWG1AS1	7:0	AS7E	AS6E	AS5E	AS4E	AS3E	AS2E	AS1E	AS0E
0x0514	CWG1STR	7:0	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA

## 24. CCP - Capture/Compare/PWM Module

The Capture/Compare/PWM module is a peripheral that allows the user to time and control different events, and to generate Pulse-Width Modulation (PWM) signals. In Capture mode, the peripheral allows the timing of the duration of an event. The Compare mode allows the user to trigger an external event when a predetermined amount of time has expired. The PWM mode can generate Pulse-Width Modulated signals of varying frequency and duty cycle.

Each individual CCP module can select the timer source that controls the module. The default timer selection is Timer1 when using Capture/Compare mode and Timer2 when using PWM mode in the CCPx module.

Note that the Capture/Compare mode operation is described with respect to Timer1 and the PWM mode operation is described with respect to Timer2 in the following sections.

The Capture and Compare functions are identical for all CCP modules.



**Important:** In devices with more than one CCP module, it is very important to pay close attention to the register names used. Throughout this section, the prefix "CCPx" is used as a generic replacement for specific numbering. A number placed where the "x" is in the prefix is used to distinguish between separate modules. For example, CCP1CON and CCP2CON control the same operational aspects of two completely different CCP modules.

## 24.1 CCP Module Configuration

Each Capture/Compare/PWM module is associated with a control register (CCPxCON), a capture input selection register (CCPxCAP) and a data register (CCPRx). The data register, in turn, is comprised of two 8-bit registers: CCPRxL (low byte) and CCPRxH (high byte).

### 24.1.1 CCP Modules and Timer Resources

The CCP modules utilize Timers 1 through 6 that vary with the selected mode. Various timers are available to the CCP modules in Capture, Compare or PWM modes, as shown in the table below.

Table 24-1. CCP Mode - Timer Resources

CCP Mode	Timer Resource					
Capture	Timer1, Timer3					
Compare	Timeri, Timers					
PWM	Timer2, Timer4, Timer6					

The assignment of a particular timer to a module is selected as shown in the "Capture, Compare, and PWM Timers Selection" chapter. All of the modules may be active at once and may share the same timer resource if they are configured to operate in the same mode (Capture/Compare or PWM) at the same time.

#### 24.1.2 Open-Drain Output Option

When operating in Output mode (the Compare or PWM modes), the drivers for the CCPx pins can be optionally configured as open-drain outputs. This feature allows the voltage level on the pin to be pulled to a higher level through an external pull-up resistor and allows the output to communicate with external circuits without the need for additional level shifters.

## 24.2 Capture Mode

Capture mode makes use of the 16-bit odd numbered timer resources (Timer1, Timer3, etc.). When an event occurs on the capture source, the 16-bit CCPRx register captures and stores the 16-bit value of the TMRx register. An event is defined as one of the following and is configured by the MODE bits:


- · Every falling edge of CCPx input
- · Every rising edge of CCPx input
- Every 4<sup>th</sup> rising edge of CCPx input
- Every 16<sup>th</sup> rising edge of CCPx input
- Every edge of CCPx input (rising or falling)

When a capture is made, the Interrupt Request Flag bit CCPxIF of the PIRx register is set. The interrupt flag must be cleared in software. If another capture occurs before the value in the CCPRx register is read, the old captured value is overwritten by the new captured value. The following figure shows a simplified diagram of the capture operation.



**Important:** If an event occurs during a 2-byte read, the high and low-byte data will be from different events. It is recommended while reading the CCPRx register pair to either disable the module or read the register pair twice for data integrity.

Figure 24-1. Capture Mode Operation Block Diagram



### 24.2.1 Capture Sources

The capture source is selected with the CTS bits.

In Capture mode, the CCPx pin must be configured as an input by setting the associated TRIS control bit.



**Important:** If the CCPx pin is configured as an output, a write to the port can cause a capture event.

#### 24.2.2 Timer1 Mode for Capture

Timer1 must be running in Timer mode or Synchronized Counter mode for the CCP module to use the capture feature. In Asynchronous Counter mode, the capture operation may not work.

See the "TMR1 - Timer1 Module with Gate Control" chapter for more information on configuring Timer1.

#### 24.2.3 Software Interrupt Mode

When the Capture mode is changed, a false capture interrupt may be generated. The user will keep the CCPxIE Interrupt Enable bit of the PIEx register clear to avoid false interrupts. Additionally, the user will clear the CCPxIF Interrupt Flag bit of the PIRx register following any change in Operating mode.

## **CCP - Capture/Compare/PWM Module**



**Important:** Clocking Timer1 from the system clock ( $F_{OSC}$ ) must not be used in Capture mode. For Capture mode to recognize the trigger event on the CCPx pin, Timer1 must be clocked from the instruction clock ( $F_{OSC}/4$ ) or from an external clock source.

#### 24.2.4 CCP Prescaler

There are four prescaler settings specified by the MODE bits. Whenever the CCP module is turned off, or the CCP module is not in Capture mode, the prescaler counter is cleared. Any Reset will clear the prescaler counter.

Switching from one capture prescaler to another does not clear the prescaler and may generate a false interrupt. To avoid this unexpected operation, turn the module off by clearing the CCPxCON register before changing the prescaler. The example below demonstrates the code to perform this function.

# Example 24-1. Changing between Capture Prescalers

BANKSEL CCP1CON ; only needed when CCP1CON is not in ACCESS space CLRF CCP1CON ; Turn CCP module off
MOVLW NEW\_CAPT\_PS ;CCP ON and Prescaler select → W
MOVWF CCP1CON ;Load CCP1CON with this value

## 24.2.5 Capture During Sleep

Capture mode depends upon the Timer1 module for proper operation. There are two options for driving the Timer1 module in Capture mode. It can be driven by the instruction clock (F<sub>OSC</sub>/4), or by an external clock source.

When Timer1 is clocked by  $F_{OSC}/4$ , Timer1 will not increment during Sleep. When the device wakes from Sleep, Timer1 will continue from its previous state.

Capture mode will operate during Sleep when Timer1 is clocked by an external clock source.

### 24.3 Compare Mode

The Compare mode function described in this section is available and identical for all CCP modules.

Compare mode makes use of the 16-bit odd numbered Timer resources (Timer1, Timer3, etc.). The 16-bit value of the CCPRx register is constantly compared against the 16-bit value of the TMRx register. When a match occurs, one of the following events can occur:


- · Toggle the CCPx output and clear TMRx
- Toggle the CCPx output without clearing TMRx
- · Set the CCPx output
- Clear the CCPx output
- Generate a Pulse output
- Generate a Pulse output and clear TMRx

The action on the pin is based on the value of the MODE control bits.

All Compare modes can generate an interrupt. When MODE = `b0001 or `b1011, the CCP resets the TMRx register.

The following figure shows a simplified diagram of the compare operation.

Figure 24-2. Compare Mode Operation Block Diagram



## 24.3.1 CCPx Pin Configuration

The CCPx pin must be configured as an output in software by clearing the associated TRIS bit and defining the appropriate output pin through the RxyPPS registers. See the "PPS - Peripheral Pin Select Module" section for more details.

The CCP output can also be used as an input for other peripherals.



**Important:** Clearing the CCPxCON register will force the CCPx compare output latch to the default low level. This is not the PORT I/O data latch.

#### 24.3.2 Timer1 Mode for Compare

In Compare mode, Timer1 must be running in either Timer mode or Synchronized Counter mode. The compare operation may not work in Asynchronous Counter mode.

See the "TMR1 - Timer1 Module with Gate Control" section for more information on configuring Timer1.



**Important:** Clocking Timer1 from the system clock ( $F_{OSC}$ ) must not be used in Compare mode. For Compare mode to recognize the trigger event on the CCPx pin, Timer1 must be clocked from the instruction clock ( $F_{OSC}$ /4) or from an external clock source.

### 24.3.3 Compare During Sleep

Since  $F_{OSC}$  is shut down during Sleep mode, the Compare mode will not function properly during Sleep, unless the timer is running. The device will wake on interrupt (if enabled).


### 24.4 PWM Overview

Pulse-Width Modulation (PWM) is a scheme that controls power to a load by switching quickly between fully ON and fully OFF states. The PWM signal resembles a square wave where the high portion of the signal is considered the ON state and the low portion of the signal is considered the OFF state. The high portion, also known as the pulse width, can vary in time and is defined in steps. A larger number of steps applied, which lengthens the pulse width, also supplies more power to the load. Lowering the number of steps applied, which shortens the pulse width, supplies less power. The PWM period is defined as the duration of one complete cycle or the total amount of ON and OFF time combined.

PWM resolution defines the maximum number of steps that can be present in a single PWM period. A higher resolution allows for more precise control of the power applied to the load.

The term duty cycle describes the proportion of the ON time to the OFF time and is expressed in percentages, where 0% is fully OFF and 100% is fully ON. A lower duty cycle corresponds to less power applied and a higher duty cycle corresponds to more power applied. The figure below shows a typical waveform of the PWM signal.

Figure 24-3, CCP PWM Output Signal




#### 24.4.1 Standard PWM Operation

The standard PWM function described in this section is available and identical for all CCP modules. It generates a Pulse-Width Modulation (PWM) signal on the CCPx pin with up to ten bits of resolution. The period, duty cycle, and resolution are controlled by the following registers:

- Even numbered TxPR registers (T2PR, T4PR, etc.)
- · Even numbered TxCON registers (T2CON, T4CON, etc.)
- · 16-bit CCPRx registers
- · CCPxCON registers

It is required to have  $F_{OSC}/4$  as the clock input to TxTMR for correct PWM operation. The following figure shows a simplified block diagram of the PWM operation.

Figure 24-4. Simplified PWM Block Diagram



Notes

- An 8-bit timer is concatenated with two bits generated by Fosc or two bits of the internal prescaler to create 10-bit time base.
- 2. The alignment of the 10 bits from the CCPR register is determined by the CCPxFMT bit.



Important: The corresponding TRIS bit must be cleared to enable the PWM output on the CCPx pin.

#### 24.4.2 Setup for PWM Operation

The following steps illustrate how to configure the CCP module for standard PWM operation:

- 1. Select the desired output pin with the RxyPPS control to select CCPx as the source. Disable the selected pin output driver by setting the associated TRIS bit. The output will be enabled later at the end of the PWM setup.
- 2. Load the selected timer TxPR period register with the PWM period value.
- 3. Configure the CCP module for the PWM mode by loading the CCPxCON register with the appropriate values.
- 4. Load the CCPRx register with the PWM duty cycle value and configure the FMT bit to set the proper register alignment.
- 5. Configure and start the selected timer:
  - Clear the TMRxIF Interrupt Flag bit of the PIRx register. See the Note below.
  - Select the timer clock source to be as F<sub>OSC</sub>/4. This is required for correct operation of the PWM module.
  - Configure the TxCKPS bits of the TxCON register with the desired timer prescale value.
  - Enable the timer by setting the TxON bit.
- 6. Enable the PWM output:
  - Wait until the timer overflows and the TMRxIF bit of the PIRx register is set. See the Note below.
  - Enable the CCPx pin output driver by clearing the associated TRIS bit.



**Important:** To send a complete duty cycle and period on the first PWM output, the above steps must be included in the setup sequence. If it is not critical to start with a complete PWM signal on the first output, then step 6 may be ignored.

#### 24.4.3 Timer2 Timer Resource

The PWM Standard mode makes use of the 8-bit Timer2 timer resources to specify the PWM period.

#### 24.4.4 PWM Period

The PWM period is specified by the T2PR register of Timer2. The PWM period can be calculated using the formula in the equation below.

#### Equation 24-1. PWM Period

 $PWM\ Period = [(T2PR + 1)] \cdot 4 \cdot T_{OSC} \cdot (TMR2\ Prescale\ Value)$ 

where  $T_{OSC} = 1/F_{OSC}$ 

When T2TMR is equal to T2PR, the following three events occur on the next increment event:

- · T2TMR is cleared
- The CCPx pin is set (Exception: If the PWM duty cycle = 0%, the pin will not be set)
- The PWM duty cycle is transferred from the CCPRx register into a 10-bit buffer




**Important:** The Timer postscaler (see the "Timer2 Interrupt" section) is not used in the determination of the PWM frequency.

#### 24.4.5 PWM Duty Cycle

The PWM duty cycle is specified by writing a 10-bit value to the CCPRx register. The alignment of the 10-bit value is determined by the FMT bit (see Figure 24-5). The CCPRx register can be written to at any time. However, the duty cycle value is not latched onto the 10-bit buffer until after a match between T2PR and T2TMR.

The equations below are used to calculate the PWM pulse width and the PWM duty cycle ratio.

#### Figure 24-5. PWM 10-Bit Alignment



#### Equation 24-2. Pulse Width

 $Pulse\ Width = (CCPRxH: CCPRxL\ register\ value) \bullet T_{OSC} \bullet (TMR2\ Prescale\ Value)$ 

#### Equation 24-3. Duty Cycle

$$DutyCycleRatio = \frac{(CCPRxH:CCPRxL register value)}{4(T2PR + 1)}$$

The CCPRx register is used to double buffer the PWM duty cycle. This double buffering is essential for glitchless PWM operation.

The 8-bit timer T2TMR register is concatenated with either the 2-bit internal system clock (F<sub>OSC</sub>), or two bits of the prescaler, to create the 10-bit time base. The system clock is used if the Timer2 prescaler is set to 1:1.

When the 10-bit time base matches the CCPRx register, then the CCPx pin is cleared (see Figure 24-4).

#### 24.4.6 PWM Resolution

The resolution determines the number of available duty cycles for a given period. For example, a 10-bit resolution will result in 1024 discrete duty cycles, whereas an 8-bit resolution will result in 256 discrete duty cycles.

The maximum PWM resolution is 10 bits when T2PR is <code>0xff</code>. The resolution is a function of the T2PR register value, as shown below.

#### Equation 24-4. PWM Resolution

$$Resolution = \frac{\log[4(T2PR + 1)]}{\log(2)}bits$$



**Important:** If the pulse-width value is greater than the period, the assigned PWM pin(s) will remain unchanged.

Table 24-2. Example PWM Frequencies and Resolutions ( $F_{OSC} = 20 \text{ MHz}$ )

PWM Frequency	1.22 kHz	4.88 kHz	19.53 kHz	78.12 kHz	156.3 kHz	208.3 kHz
Timer Prescale	16	4	1	1	1	1
T2PR Value	0xFF	0xFF	0xFF	0x3F	0x1F	0x17
Maximum Resolution (bits)	10	10	10	8	7	6.6

Table 24-3. Example PWM Frequencies and Resolutions ( $F_{OSC} = 8 \text{ MHz}$ )

PWM Frequency	1.22 kHz	4.90 kHz	19.61 kHz	76.92 kHz	153.85 kHz	200.0 kHz
Timer Prescale	16	4	1	1	1	1
T2PR Value	0x65	0x65	0x65	0x19	0x0C	0x09
Maximum Resolution (bits)	8	8	8	6	5	5

#### 24.4.7 Operation in Sleep Mode

In Sleep mode, the T2TMR register will not increment and the state of the module will not change. If the CCPx pin is driving a value, it will continue to drive that value. When the device wakes up, T2TMR will continue from the previous state.

#### 24.4.8 Changes in System Clock Frequency

The PWM frequency is derived from the system clock frequency. Any changes in the system clock frequency will result in changes to the PWM frequency. See the "OSC - Oscillator Module (with Fail-Safe Clock Monitor)" chapter for additional details.

#### 24.4.9 Effects of Reset

Any Reset will force all ports to Input mode and the CCP registers to their Reset states.

#### 24.5 Register Definitions: CCP Control

Long bit name prefixes for the CCP peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

# PIC16F18015/25/44/45

# **CCP - Capture/Compare/PWM Module**

## Table 24-4. CCP Long Bit Name Prefixes

Peripheral	Bit Name Prefix
CCP1	CCP1
CCP2	CCP2

#### 24.5.1 CCPxCON

Name: CCPxCON Offset: 0x038E,0x0392

**CCP Control Register** 

Bit	7	6	5	4	3	2	1	0	
	EN		OUT	FMT	MODE[3:0]				
Access	R/W		R	R/W	R/W	R/W	R/W	R/W	
Reset	0		X	0	0	0	0	0	

#### Bit 7 - EN CCP Module Enable

1	/alue	Description
	-	CCP is enabled
(	)	CCP is disabled

## Bit 5 – OUT CCP Output Data (read-only)

#### Bit 4 – FMT CCPxRH:L Value Alignment (PWM mode)

Value	Condition	Description
Х	Capture mode	Not used
Х	Compare mode	Not used
1	PWM mode	Left aligned format
0	PWM mode	Right aligned format

#### Bits 3:0 - MODE[3:0] CCP Mode Select

#### Table 24-5, CCPx Mode Select

MODE Value	Operating Mode	Operation	Set CCPxIF
11xx	PWM	PWM operation	Yes
1011		Pulse output; clear TMR1 <sup>(2)</sup>	Yes
1010	Compare	Pulse output	Yes
1001	Compare	Clear output <sup>(1)</sup>	Yes
1000	_	Set output <sup>(1)</sup>	Yes
0111		Every 16th rising edge of CCPx input	Yes
0110		Every 4 <sup>th</sup> rising edge of CCPx input	Yes
0101	Capture	Every rising edge of CCPx input	Yes
0100		Every falling edge of CCPx input	Yes
0011		Every edge of CCPx input	Yes
0010	Compare	Toggle output	Yes
0001	Compare	Toggle output; clear TMR1 <sup>(2)</sup>	Yes
0000	Disabled		_

#### Notes:

- 1. The set and clear operations of the Compare mode are reset by setting MODE = \b00000 or EN = 0.
- 2. When MODE = \b00001 or \b1011, then the timer associated with the CCP module is cleared. TMR1 is the default selection for the CCP module, so it is used for indication purposes only.

## 24.5.2 CCPxCAP

Name: CCPxCAP Offset: 0x038F,0x0393

Capture Trigger Input Selection Register



Bits 3:0 - CTS[3:0] Capture Trigger Input Selection

## **Table 24-6. Capture Trigger Sources**

CTS Value	Source
1111-0111	Reserved
0110	CLC4_OUT
0101	CLC3_OUT
0100	CLC2_OUT
0011	CLC1_OUT
0010	IOC Interrupt
0001	C1_OUT
0000	Pin selected by CCPxPPS

#### 24,5,3 CCPRx

Name: CCPRx

**Offset:** 0x038C,0x0390

Capture/Compare/Pulse-Width Register

Bit	15	14	13	12	11	10	9	8					
	CCPR[15:8]												
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W					
Reset	x	X	x	x	x	x	x	X					
Bit	7	6	5	4	3	2	1	0					
				CCPI	₹[7:0]								
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W					
Reset	X	x	x	x	X	x	x	X					

Bits 15:0 - CCPR[15:0] Capture/Compare/Pulse-Width

All other Resets = uuuuuuuuuuuuuuu

Notes: The individual bytes in this multibyte register can be accessed with the following register names:

- When MODE = Capture or Compare
  - CCPRxH: Accesses the high byte CCPR[15:8]
  - CCPRxL: Accesses the low byte CCPR[7:0]
- When MODE = PWM and FMT = 0
  - CCPRx[15:10]: Not used
  - CCPRxH[1:0]: Accesses the two Most Significant bits CCPR[9:8]
  - CCPRxL: Accesses the eight Least Significant bits CCPR[7:0]
- When MODE = PWM and FMT = 1
  - CCPRxH: Accesses the eight Most Significant bits CCPR[9:2]
  - CCPRxL[7:6]: Accesses the two Least Significant bits CCPR[1:0]
  - CCPRx[5:0]: Not used

# 24.6 Register Summary - CCP Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0		
0x00												
	Reserved											
0x038B												
0x038C	CCPR1	7:0				CCP	R[7:0]					
UXUSOC	CCPRI	15:8		CCPR[15:8]								
0x038E	CCP1CON	7:0	EN		OUT	FMT		MOD	E[3:0]			
0x038F	CCP1CAP	7:0						CTS	[3:0]			
0x0390	CCPR2	7:0		•		CCP	R[7:0]					
0x0390	COPRZ	15:8				CCPR[15:8]						
0x0392	CCP2CON	7:0	EN		OUT	FMT MODE[3:0]						
0x0393	CCP2CAP	7:0		CTS[3:0]								

## 25. Capture, Compare, and PWM Timers Selection


Each of these modules has an independent timer selection which can be accessed using the timer selection register. The default timer selection is Timer1 for capture or compare functions and Timer2 for PWM functions.

25.1 Register Definitions: Capture, Compare, and PWM Timers Selection

## 25.1.1 CCPTMRS0

Name: CCPTMRS0 Offset: 0x039F

**CCP Timers Selection Register** 



Bits 0:1, 2:3 - CnTSEL CCPn Timer Selection

CnTSEL Value	Capture/Compare	PWM
11	Reserved	Timer6
10	Timer3	Timer4
01	Timer1	Timer2
00	Reserved	

# 25.2 Register Summary - Capture, Compare, and PWM Timers Selection

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x039E										
0x039F	CCPTMRS0	7:0					C2TS	EL[1:0]	C1TSI	EL[1:0]

## 26. PWM - Pulse-Width Modulation

The PWM module generates a Pulse-Width Modulated signal determined by the duty cycle, period, and resolution that are configured by the following registers:

- TxPR
- TxCON
- PWMxDC
- PWMxCON




Important: The corresponding TRIS bit must be cleared to enable the PWM output on the PWMx pin.

Each PWM module uses the same timer source, Timer2, to control each module.

Figure 26-1 shows a simplified block diagram of PWM operation.

Figure 26-2 shows a typical waveform of the PWM signal.


Figure 26-1. Simplified PWM Block Diagram



#### Note:

 8-bit timer is concatenated with two bits generated by F<sub>OSC</sub> or two bits of the internal prescaler to create 10-bit time base.

Figure 26-2. PWM Output



For a step-by-step procedure on how to set up this module for PWM operation, refer to 26.9. Setup for PWM Operation Using PWMx Output Pins.

## 26.1 Fundamental Operation

The PWM module produces a 10-bit resolution output. The timer selection for PWMx is TMRx. TxTMR and TxPR set the period of the PWM. The PWMxDCL and PWMxDCH registers configure the duty cycle. The period is common to all PWM modules, whereas the duty cycle is independently controlled.



**Important**: The Timerx postscaler is not used in the determination of the PWM frequency. The postscaler might be used to have a servo update rate at a different frequency than the PWM output.

All PWM outputs associated with Timerx are set when TxTMR is cleared. Each PWMx is cleared when TxTMR is equal to the value specified in the corresponding PWMxDCH (8 MSb) and PWMxDCL[7:6] (2 LSb) registers. When the value is greater than or equal to TxPR, the PWM output is never cleared (100% duty cycle).



**Important:** The PWMxDCH and PWMxDCL registers are double-buffered. The buffers are updated when TxTMR matches TxPR. Care has to be taken to update both registers before the timer match occurs.

## 26.2 PWM Output Polarity

The output polarity is inverted by setting the POL bit.

#### 26.3 PWM Period

The PWM period is specified by the TxPR register. The PWM period can be calculated using the formula of Equation 26-1. It is required to have  $F_{OSC}/4$  as the selected clock input to the timer for correct PWM operation.

### Equation 26-1. PWM Period

 $PWM\ Period = [(T2PR) + 1] \bullet 4 \bullet Tosc \bullet (TMR2\ Prescale\ Value)$ 

Note:  $T_{OSC} = 1/F_{OSC}$ 

When TxTMR is equal to TxPR, the following three events occur on the next increment cycle:

TxTMR is cleared

- The PWM output is active (Exception: When the PWM duty cycle = 0%, the PWM output will remain inactive)
- The PWMxDCH and PWMxDCL register values are latched into the buffers



**Important**: The Timer2 postscaler has no effect on the PWM operation.

## 26.4 PWM Duty Cycle

The PWM duty cycle is specified by writing a 10-bit value to the PWMxDCH and PWMxDCL register pair. The PWMxDCH register contains the eight MSbs and the two LSbs, PWMxDCL[7:6]. The PWMxDCH and PWMxDCL registers can be written to at any time.

The equations below are used to calculate the PWM pulse width and the PWM duty cycle ratio.

#### Equation 26-2. Pulse Width

 $Pulse\ Width = (PWMxDCH: PWMxDCL[7:6]) \bullet Tosc \bullet (TMR2\ Prescale\ Value)$ 

Note:  $T_{OSC} = 1/F_{OSC}$ 

### Equation 26-3. Duty Cycle Ratio

$$DutyCycleRatio = \frac{(PWMxDCH: PWMxDCL[7:6])}{4(T2PR+1)}$$

The 8-bit timer T2TMR register is concatenated with the two Least Significant bits of  $1/F_{OSC}$ , adjusted by the Timer2 prescaler to create the 10-bit time base. The system clock is used if the Timer2 prescaler is set to 1:1.

### 26.5 PWM Resolution

The resolution determines the number of available duty cycles for a given period. For example, a 10-bit resolution will result in 1024 discrete duty cycles, whereas an 8-bit resolution will result in 256 discrete duty cycles.

The maximum PWM resolution is 10 bits when T2PR is 255. The resolution is a function of the T2PR register value as shown below.

#### Equation 26-4. PWM Resolution

$$Resolution = \frac{\log[4(T2PR + 1)]}{\log(2)}bits$$



**Important:** If the pulse-width value is greater than the period, the assigned PWM pin(s) will remain unchanged.

#### Table 26-1. Example PWM Frequencies and Resolutions (F<sub>OSC</sub> = 20 MHz)

PWM Frequency	0.31 kHz	4.88 kHz	19.53 kHz	78.12 kHz	156.3 kHz	208.3 kHz
Timer Prescale	64	4	1	1	1	1
T2PR Value	0xFF	0xFF	0xFF	0x3F	0x1F	0x17
Maximum Resolution (bits)	10	10	10	8	7	6.6

Table 26-2. Example PWM Frequencies and Resolutions ( $F_{OSC} = 8 \text{ MHz}$ )

PWM Frequency	0.31 kHz	4.90 kHz	19.61 kHz	76.92 kHz	153.85 kHz	200.0 kHz
Timer Prescale	64	4	1	1	1	1
T2PR Value	0x65	0x65	0x65	0x19	0x0C	0x09
Maximum Resolution (bits)	8	8	8	6	5	5

#### **Operation in Sleep Mode** 26.6

In Sleep mode, the T2TMR register will not increment and the state of the module will not change. If the PWMx pin is driving a value, it will continue to drive that value. When the device wakes up, T2TMR will continue from its previous state.

#### 26.7 **Changes in System Clock Frequency**

The PWM frequency is derived from the system clock frequency (F<sub>OSC</sub>). Any changes in the system clock frequency will result in changes to the PWM frequency.

#### 26.8 Effects of Reset

Any Reset will force all ports to Input mode and the PWM registers to their Reset states.

#### 26.9 Setup for PWM Operation Using PWMx Output Pins

Follow the next steps when configuring the module for PWM operation using the PWMx pins:

- Disable the PWMx pin output driver(s) by setting the associated TRIS bit(s).
- 2. Clear the PWMxCON register.
- 3 Load the TxPR register with the PWM period value.
- Load the PWMxDCH register and bits [7:6] of the PWMxDCL register with the PWM duty cycle value.
- Configure and start Timerx:
  - Clear the TMRxIF Interrupt Flag bit of the PIRx register.<sup>(1)</sup>
  - Select the timer clock source to be as F<sub>OSC</sub>/4 using the TxCLKCON register. This is required for correct operation of the PWM module.
  - Configure the CKPS bits of the TxCON register with the Timerx prescale value.
  - Enable Timerx by setting the ON bit of the TxCON register.
- Enable the PWM output pin and wait until Timerx overflows; the TMRxIF bit of the PIRx register is set. (2)
- Enable the PWMx pin output driver(s) by clearing the associated TRIS bit(s) and setting the desired pin PPS control bits.
- 8. Configure the PWM module by loading the PWMxCON register with the appropriate values.

#### Notes:

- To send a complete duty cycle and period on the first PWM output, the above steps must be followed in the given order. If it is not critical to start with a complete PWM signal, then move step 8 to replace step 4.
- 2. For operation with other peripherals only, disable PWMx pin outputs.

#### 26.9.1 **PWMx Pin Configuration**

All PWM outputs are multiplexed with the PORT data latch. The user must configure the pins as outputs by clearing the associated TRIS bits.

## 26.10 Setup for PWM Operation to Other Device Peripherals

Follow the next steps when configuring the module for PWM operation to be used by other device peripherals:

- 1. Disable the PWMx pin output driver(s) by setting the associated TRIS bit(s).
- 2. Clear the PWMxCON register.
- 3. Load the TxPR register with the PWM period value.
- 4. Load the PWMxDCH register and bits [7:6] of the PWMxDCL register with the PWM duty cycle value.
- Configure and start Timerx:
  - Clear the TMRxIF Interrupt Flag bit of the PIRx register.<sup>(1)</sup>
  - Select the timer clock source to be as F<sub>OSC</sub>/4 using the TxCLKCON register. This is required for correct operation of the PWM module.
  - Configure the CKPS bits of the TxCON register with the Timerx prescale value.
  - Enable Timerx by setting the ON bit of the TxCON register.
- 6. Wait until Timerx overflows; the TMRxIF bit of the PIRx register is set. (1)
- 7. Configure the PWM module by loading the PWMxCON register with the appropriate values.

#### Note:

1. To send a complete duty cycle and period on the first PWM output, the above steps must be included in the setup sequence. If it is not critical to start with a complete PWM signal on the first output, then step 6 may be ignored.

## 26.11 Register Definitions: PWM Control

Long bit name prefixes for the PWM peripherals are shown in the table below. Refer to the "Long Bit Names" section for more information.

Table 26-3. PWM Bit Name Prefixes

Peripheral	Bit Name Prefix
PWM3	PWM3
PWM4	PWM4
PWM5	PWM5

## 26.11.1 PWMxCON

Name: PWMxCON

**Offset:** 0x40E,0x0411,0x0414

**PWM Control Register** 

Bit	7	6	5	4	3	2	1	0
	EN		OUT	POL				
Access	R/W		R	R/W				
Reset	0		0	0				

## Bit 7 - EN PWM Module Enable bit

	Value	Description
ſ	1	PWM module is enabled
	0	PWM module is disabled

# Bit 5 – OUT PWM Module Output Level

Indicates PWM module output level when bit is read

### Bit 4 – POL PWM Output Polarity Select bit

N	/alue	Description
1		PWM output is inverted
C	)	PWM output is normal

#### 26.11.2 PWMxDC

Reset

Name: PWMxDC

**Offset:** 0x040C,0x040F,0x0412

PWM Duty Cycle Register

Bit	15	14	13	12	11	10	9	8
				DCH	I[7:0]			
Access Reset								_
Reset	x	x	x	x	x	x	x	x
Bit	7	6	5	4	3	2	1	0
	DCL	[1:0]						
Access			-		•			

Bits 15:8 - DCH[7:0] PWM Duty Cycle Most Significant bits

These bits are the MSbs of the PWM duty cycle.

Х

Reset States: POR/BOR = xxxxxxxx

All Other Resets = uuuuuuuu

Bits 7:6 - DCL[1:0] PWM Duty Cycle Least Significant bits

These bits are the LSbs of the PWM duty cycle.

Reset States: POR/BOR = xx

All Other Resets = uu

# 26.12 Register Summary - PWM

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x040B										
0x040C	PWM3DC	7:0	DCL	.[1:0]						
000400	PVVIVISDC	15:8				DCF	I[7:0]	•	•	
0x040E	PWM3CON	7:0	EN		OUT	POL				
0x040F	PWM4DC	7:0	DCL	[1:0]						
000406	P VVIVI4DC	15:8			•	DCF	I[7:0]	•	•	
0x0411	PWM4CON	7:0	EN		OUT	POL				
0x0412	PWM5DC	7:0	DCL	[1:0]						
0x0412	15:8				DCH[7:0]			•		
0x0414	PWM5CON	7:0	EN		OUT	POL				

## 27. PWM Timers Selection


Each of the PWM modules has an independent timer selection which can be accessed using the timer selection register. The default timer selection is Timer2 for PWM functions.

27.1 Register Definitions: Capture, Compare, and PWM Timers Selection

## 27.1.1 PWMTMRS0

Name: PWMTMRS0 Offset: 0x041F

PWM Timers Selection Register



Bits 0:1, 2:3, 4:5 - PnTSEL PWMn Timer Selection

PnTSEL Value	PWM
11	Timer6
10	Timer4
01	Timer2
00	Reserved

# 27.2 Register Summary - Capture, Compare, and PWM Timers Selection

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x041E										
0x041F	PWMTMRS0	7:0			P5TSE	EL[1:0]	P4TSI	EL[1:0]	P3TSE	EL[1:0]

## 28. CLC - Configurable Logic Cell

The Configurable Logic Cell (CLC) module provides programmable logic that operates outside the speed limitations of software execution. The logic cell takes up to 256 input signals and, through the use of configurable gates, reduces those inputs to four logic lines that drive one of eight selectable single-output logic functions.

Input sources are a combination of the following:


- I/O pins
- Internal clocks
- Peripherals
- · Register bits

The output can be directed internally to peripherals and to an output pin.

The following figure is a simplified diagram showing signal flow through the CLC. Possible configurations include:

- · Combinatorial Logic
  - AND
  - NAND
  - AND-OR
  - AND-OR-INVERT
  - OR-XOR
  - OR-XNOR
- Latches
  - SR
  - Clocked D with Set and Reset
  - Transparent D with Set and Reset

Figure 28-1. CLC Simplified Block Diagram



#### Notes:

- 1. See Figure 28-2 for input data selection and gating.
- 2. See Figure 28-3 for programmable logic functions.

## 28.1 CLC Setup

Programming the CLC module is performed by configuring the four stages in the logic signal flow. The four stages are:

- Data selection
- Data gating
- Logic function selection
- · Output polarity

Each stage is set up at run time by writing to the corresponding CLC Special Function Registers. This has the added advantage of permitting logic reconfiguration on-the-fly during program execution.

#### 28.1.1 Data Selection

Data inputs are selected with CLCnSEL0 through CLCnSEL3 registers.



**Important**: Data selections are undefined at power-up.

Depending on the number of bits implemented in the CLCnSELy registers, there can be as many as 256 sources available as inputs to the configurable logic. Four multiplexers are used to independently select these inputs to pass on to the next stage as indicated on the left side of the following diagram.

Data inputs in the figure are identified by a generic numbered input name.




Figure 28-2. Input Data Selection and Gating

Note: All controls are undefined at power-up.

The CLC Input Selection table correlates the generic input name to the actual signal for each CLC module. The table column labeled 'DyS Value' indicates the MUX selection code for the selected data input. DyS is an abbreviation for the MUX select input codes, D1S through D4S, where 'y' is the gate number.

### 28.1.2 Data Gating

Outputs from the input multiplexers are directed to the desired logic function input through the data gating stage. Each data gate can direct any combination of the four selected inputs.

The gate stage is more than just signal direction. The gate can be configured to direct each input signal as inverted or noninverted data. Directed signals are ANDed together in each gate. The output of each gate can be inverted before going on to the logic function stage.

The gating is in essence a 1-to-4 input AND/NAND/OR/NOR gate. When every input is inverted and the output is inverted, the gate is an AND of all enabled data inputs. When the inputs and output are not inverted, the gate is an OR or all enabled inputs.

Table 28-1 summarizes the basic logic that can be obtained in gate 1 by using the gate logic select bits. The table shows the logic of four input variables, but each gate can be configured to use less than four. If no inputs are selected, the output will be '0' or '1', depending on the gate output polarity bit.

Table 28-1. Data Gating Logic

CLCnGLSy	GyPOL	Gate Logic
0x55	1	AND
0x55	0	NAND
0xAA	1	NOR
0xAA	0	OR
0x00	0	Logic '0'
0x00	1	Logic '1'

It is possible (but not recommended) to select both the true and negated values of an input. When this is done, the gate output is '0', regardless of the other inputs, but may emit logic glitches (transient-induced pulses). If the output of the channel must be '0' or '1', the recommended method is to set all gate bits to '0' and use the gate polarity bit to set the desired level.

Data gating is configured with the logic gate select registers as follows:

- · Gate 1: CLCnGLS0
- · Gate 2: CLCnGLS1
- Gate 3: CLCnGLS2
- Gate 4: CLCnGLS3

**Note:** Register number suffixes are different than the gate numbers because other variations of this module have multiple gate selections in the same register.

Data gating is indicated in the right side of Figure 28-2. Only one gate is shown in detail. The remaining three gates are configured identically, except when the data enables correspond to the enables for that gate.

## 28.1.3 Logic Function


There are eight available logic functions including:

- · AND-OR
- OR-XOR
- AND
- SR Latch
- · D Flip-Flop with Set and Reset
- D Flip-Flop with Reset
- · J-K Flip-Flop with Reset
- · Transparent Latch with Set and Reset

Logic functions are shown in the following diagram. Each logic function has four inputs and one output. The four inputs are the four data gate outputs of the previous stage. The output is fed to the inversion stage and from there to other peripherals, an output pin, and back to the CLC itself.

Figure 28-3. Programmable Logic Functions

Rev. 10-000122B 9/13/2016



## 28.1.4 Output Polarity

The last stage in the Configurable Logic Cell is the output polarity. Setting the POL bit inverts the output signal from the logic stage. Changing the polarity while the interrupts are enabled will cause an interrupt for the resulting output transition.

## 28.2 CLC Interrupts

An interrupt will be generated upon a change in the output value of the CLCx when the appropriate interrupt enables are set. A rising edge detector and a falling edge detector are present in each CLC for this purpose.

The CLCxIF bit of the associated PIR register will be set when either edge detector is triggered and its associated enable bit is set. The INTP bit enables rising edge interrupts and the INTN bit enables falling edge interrupts.

To fully enable the interrupt, set the following bits:

- The CLCxIE bit of the respective PIE register
- The INTP bit (for a rising edge detection)
- The INTN bit (for a falling edge detection)

If priority interrupts are not used:

- Clear the IPEN bit of the INTCON register.
- Set the GIE bit of the INTCON register.
- Set the GIEL bit of the INTCON register.

If the CLC is a high-priority interrupt:

- Set the IPEN bit of the INTCON register.
- 2. Set the CLCxIP bit of the respective IPR register.
- 3. Set the GIEH bit of the INTCON register.

If the CLC is a low-priority interrupt:

- 1. Set the IPEN bit of the INTCON register.
- Clear the CLCxIP bit of the respective IPR register.
- Set the GIEL bit of the INTCON register.

The CLCxIF bit of the respective PIR register must be cleared in software as part of the interrupt service. If another edge is detected while this flag is being cleared, the flag will still be set at the end of the sequence.

#### 28.3 Effects of a Reset

The CLCnCON register is cleared to '0' as the result of a Reset. All other selection and gating values remain unchanged.

## 28.4 Output Mirror Copies

Mirror copies of all CLCxOUT bits are contained in the CLCDATA register. Reading this register reads the outputs of all CLCs simultaneously. This prevents any reading skew introduced by testing or reading the OUT bits in the individual CLCnCON registers.

## 28.5 Operation During Sleep

The CLC module operates independently from the system clock and will continue to run during Sleep, provided that the input sources selected remain Active.

The HFINTOSC remains Active during Sleep when the CLC module is enabled and the HFINTOSC is selected as an input source, regardless of the system clock source selected.

In other words, if the HFINTOSC is simultaneously selected as both the system clock and as a CLC input source then, when the CLC is enabled, the CPU will go Idle during Sleep, but the CLC will continue to operate and the HFINTOSC will remain Active. This will have a direct effect on the Sleep mode current.

## 28.6 CLC Setup Steps

These steps need to be followed when setting up the CLC:

- 1. Disable the CLC by clearing the EN bit.
- Select the desired inputs using the CLCnSEL0 through CLCnSEL3 registers.
- Clear any ANSEL bits associated with CLC input pins.
- 4. Set all TRIS bits associated with inputs. However, a CLC input will also operate if the pin is configured as an output, in which case the TRIS bits must be cleared.

## **CLC - Configurable Logic Cell**

- 5. Enable the chosen inputs through the four gates using the CLCnGLS0 through CLCnGLS3 registers.
- 6. Select the gate output polarities with the GyPOL bits.
- 7. Select the desired logic function with the MODE bits.
- Select the desired polarity of the logic output with the POL bit (this step may be combined with the previous gate output polarity step).
- If driving a device pin, configure the associated pin PPS control register and also clear the TRIS bit corresponding to that output.
- 10. Configure the interrupts (optional). See the CLC Interrupts section.
- 11. Enable the CLC by setting the EN bit.

## 28.7 Register Overlay

All CLCs in this device share the same set of registers. Only one CLC instance is accessible at a time. The value in the CLCSELECT register is one less than the selected CLC instance. For example, a CLCSELECT value of '0' selects CLC1.


## 28.8 Register Definitions: Configurable Logic Cell

## **28.8.1 CLCSELECT**

Name: CLCSELECT Offset: 0x0596

**CLC Instance Selection Register** 

Selects which CLC instance is accessed by the CLC registers



Bits 2:0 - SLCT[2:0] CLC instance selection

Value	Description
n	Shared CLC registers of instance n+1 are selected for read and write operations

## 28.8.2 CLCnCON

Name: CLCnCON Offset: 0x058C

Configurable Logic Cell Control Register

Bit	7	6	5	4	3	2	1	0
	EN		OUT	INTP	INTN		MODE[2:0]	
Access	R/W		R	R/W	R/W	R/W	R/W	R/W
Reset	0		0	0	0	0	0	0

## Bit 7 - EN CLC Enable

Value	Description
1	Configurable logic cell is enabled and mixing signals
0	Configurable logic cell is disabled and has logic zero output

Bit 5 - OUT Logic cell output data, after LCPOL. Sampled from CLCxOUT.

Bit 4 – INTP Configurable Logic Cell Positive Edge Going Interrupt Enable

Value	Description
1	CLCxIF will be set when a rising edge occurs on CLCxOUT
0	Rising edges on CLCxOUT have no effect on CLCxIF

Bit 3 – INTN Configurable Logic Cell Negative Edge Going Interrupt Enable

Value	Description
1	CLCxIF will be set when a falling edge occurs on CLCxOUT
0	Falling edges on CLCxOUT have no effect on CLCxIF

Bits 2:0 - MODE[2:0] Configurable Logic Cell Functional Mode Selection

Value	Description
111	Cell is 1-input transparent latch with Set and Reset
110	Cell is J-K flip-flop with Reset
101	Cell is 2-input D flip-flop with Reset
100	Cell is 1-input D flip-flop with Set and Reset
011	Cell is SR latch
010	Cell is 4-input AND
001	Cell is OR-XOR
000	Cell is AND-OR

## 28.8.3 CLCnPOL

Name: CLCnPOL Offset: 0x058D

Signal Polarity Control Register

Bit	7	6	5	4	3	2	1	0
	POL				G4POL	G3POL	G2POL	G1POL
Access	R/W				R/W	R/W	R/W	R/W
Reset	0				X	X	X	X

Bit 7 - POL CLCxOUT Output Polarity Control

Value	Description
1	The output of the logic cell is inverted
0	The output of the logic cell is not inverted

Bits 0, 1, 2, 3 – GyPOL Gate Output Polarity Control

Reset States: POR/BOR = xxxx

Value	Description
1	The gate output is inverted when applied to the logic cell
0	The output of the gate is not inverted

## 28,8,4 CLCnSEL0

Name: CLCnSEL0 Offset: 0x058E

Generic CLCn Data 1 Select Register



Bits 5:0 - D1S[5:0] CLCn Data1 Input Selection

## Table 28-2. CLC Input Selection

DyS	Input Source	DyS (cont.)	Input Source (cont.)	
[0] 0000 0000	CLCINOPPS	<b>[21]</b> 0001 0101	PWM3_OUT	
[1] 0000 0001	CLCIN1PPS	[22] 0001 0110	PWM4_OUT	
[2] 0000 0010	CLCIN2PPS	[23] 0001 0111	PWM5_OUT	
[3] 0000 0011	CLCIN3PPS	[24] 0001 1000	NCO1_OUT	
[4] 0000 0100	Fosc	[25] 0001 1001	C1_OUT	
<b>[5]</b> 0000 0101	HFINTOSC	[26] 0001 1010	ZCD_OUT	
<b>[6]</b> 0000 0110	LFINTOSC	[27] 0001 1011	IOC	
[7] 0000 0111	MFINTOSC (500 kHz)	[28] 0001 1100	CLC1_OUT	
[8] 0000 1000	MFINTOSC (32 kHz)	[29] 0001 1101	CLC2_OUT	
<b>[9]</b> 0000 1001	SFINTOSC (1 MHz)	[30] 0001 1110	CLC3_OUT	
[10] 0000 1010	SOSC	[31] 0001 1111	CLC4_OUT	
[11] 0000 1011	EXTOSC	[32] 0010 0000	TX1/CK1	
[12] 0000 1100	ADCRC	[33] 0010 0001	TX2/CK2	
[13] 0000 1101	TMR0_overflow	<b>[34]</b> 0010 0010	SDA1/SDO1	
[14] 0000 1110	TMR1_overflow	<b>[35]</b> 0010 0011	SCL1/SCK1	
[15] 0000 1111	TMR2_Postscaled_OUT	<b>[36]</b> 0010 0100	SDA2/SDO2	
[16] 0001 0000	TMR3_overflow	[37] 0010 0101	SCL2/SCK2	
[17] 0001 0001	TMR4_Postscaled_OUT	[38] 0010 0110	CWG1A_OUT	
[18] 0001 0010	TMR6_Postscaled_OUT	<b>[39]</b> 0010 0111	CWG1B_OUT	
[19] 0001 0011	CCP1_OUT	[40] 0010 1000 [62] 0011 1444	Decembed	
[20] 0001 0100	CCP2_OUT	[40] 0010 1000 - [63] 0011 1111	Reserved	


Reset States: POR/BOR = xxxxxx

All Other Resets = uuuuuu

## 28,8,5 CLCnSEL1

Name: CLCnSEL1 Offset: 0x058F

Generic CLCn Data 1 Select Register



Bits 5:0 - D2S[5:0] CLCn Data2 Input Selection

Reset States: POR/BOR = xxxxxx

Value	Description
n	Refer to the CLC Input Selection table for input selections

## 28,8,6 CLCnSEL2

Name: CLCnSEL2 Offset: 0x0590

Generic CLCn Data 1 Select Register

Bit	7	6	5	4	3	2	1	0
[					D3S	[5:0]		
Access			R/W	R/W	R/W	R/W	R/W	R/W
Reset			X	X	X	X	X	X

Bits 5:0 - D3S[5:0] CLCn Data3 Input Selection

Reset States: POR/BOR = xxxxxx

Value	Description
n	Refer to the CLC Input Selection table for input selections

## 28.8.7 CLCnSEL3

Name: CLCnSEL3 Offset: 0x0591

Generic CLCn Data 4 Select Register



Bits 5:0 - D4S[5:0] CLCn Data4 Input Selection

Reset States: POR/BOR = xxxxxx

Value	Description
n	Refer to the CLC Input Selection table for input selections

## 28.8.8 CLCnGLS0

Name: CLCnGLS0 Offset: 0x0592

CLCn Gate1 Logic Select Register

Bit	7	6	5	4	3	2	1	0
	G1D4T	G1D4N	G1D3T	G1D3N	G1D2T	G1D2N	G1D1T	G1D1N
Access	R/W							
Reset	x	x	x	x	x	x	x	x

## Bits 1, 3, 5, 7 – G1DyT dyT: Gate1 Data 'y' True (noninverted)

Reset States: POR/BOR = xxxx

All Other Resets = uuuu

Value	Description
1	dyT is gated into g1
0	dyT is not gated into g1

## Bits 0, 2, 4, 6 – G1DyN dyN: Gate1 Data 'y' Negated (inverted)

Reset States: POR/BOR = xxxx

Value	Description
1	dyN is gated into g1
0	dyN is not gated into g1

## 28,8,9 CLCnGLS1

Name: CLCnGLS1 Offset: 0x0593

CLCn Gate2 Logic Select Register

Bit	7	6	5	4	3	2	1	0
	G2D4T	G2D4N	G2D3T	G2D3N	G2D2T	G2D2N	G2D1T	G2D1N
Access	R/W							
Reset	X	X	X	X	X	X	X	X

## Bits 1, 3, 5, 7 – G2DyT dyT: Gate2 Data 'y' True (noninverted)

Reset States: POR/BOR = xxxx

All Other Resets = uuuu

Value	Description
1	dyT is gated into g2
0	dyT is not gated into g2

## Bits 0, 2, 4, 6 – G2DyN dyN: Gate2 Data 'y' Negated (inverted)

Reset States: POR/BOR = xxxx

Value	Description
1	dyN is gated into g2
0	dyN is not gated into g2

## 28.8.10 CLCnGLS2

Name: CLCnGLS2 Offset: 0x0594

CLCn Gate3 Logic Select Register

Bit	7	6	5	4	3	2	1	0
	G3D4T	G3D4N	G3D3T	G3D3N	G3D2T	G3D2N	G3D1T	G3D1N
Access	R/W							
Reset	x	x	x	x	x	x	x	x

## Bits 1, 3, 5, 7 – G3DyT dyT: Gate3 Data 'y' True (noninverted)

Reset States: POR/BOR = xxxx

All Other Resets = uuuu

Value	Description
1	dyT is gated into g3
0	dyT is not gated into g3

## Bits 0, 2, 4, 6 – G3DyN dyN: Gate3 Data 'y' Negated (inverted)

Reset States: POR/BOR = xxxx

Value	Description
1	dyN is gated into g3
0	dyN is not gated into g3

## 28.8.11 CLCnGLS3

Name: CLCnGLS3 Offset: 0x0595

CLCn Gate4 Logic Select Register

Bit	7	6	5	4	3	2	1	0
	G4D4T	G4D4N	G4D3T	G4D3N	G4D2T	G4D2N	G4D1T	G4D1N
Access	R/W							
Reset	X	X	X	X	X	X	X	X

## Bits 1, 3, 5, 7 – G4DyT dyT: Gate4 Data 'y' True (noninverted)

Reset States: POR/BOR = xxxx

All Other Resets = uuuu

Value	Description
1	dyT is gated into g4
0	dyT is not gated into g4

## Bits 0, 2, 4, 6 – G4DyN dyN: Gate4 Data 'y' Negated (inverted)

Reset States: POR/BOR = xxxx

Value	Description
1	dyN is gated into g4
0	dyN is not gated into g4

## 28.8.12 CLCDATA

Name: CLCDATA
Offset: 0x0597
CLC Data Output Register

Mirror copy of CLC outputs

Bit	7	6	5	4	3	2	1	0
					CLC4OUT	CLC3OUT	CLC2OUT	CLC1OUT
Access					R/W	R/W	R/W	R/W
Reset					0	0	0	0

Bits 0, 1, 2, 3 - CLCxOUT Mirror copy of CLCx\_out

Value	Description
1	CLCx_out is 1
0	CLCx_out is 0

# 28.9 Register Summary - CLC Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00  0x058B	Reserved									
0x058C	CLCnCON	7:0	EN		OUT	INTP	INTN		MODE[2:0]	
0x058D	CLCnPOL	7:0	POL				G4POL	G3POL	G2POL	G1POL
0x058E	CLCnSEL0	7:0			D1S[5:0]					
0x058F	CLCnSEL1	7:0			D2S[5:0]					
0x0590	CLCnSEL2	7:0			D3S[5:0]					
0x0591	CLCnSEL3	7:0			D4S[5:0]					
0x0592	CLCnGLS0	7:0	G1D4T	G1D4N	G1D3T	G1D3N	G1D2T	G1D2N	G1D1T	G1D1N
0x0593	CLCnGLS1	7:0	G2D4T	G2D4N	G2D3T	G2D3N	G2D2T	G2D2N	G2D1T	G2D1N
0x0594	CLCnGLS2	7:0	G3D4T	G3D4N	G3D3T	G3D3N	G3D2T	G3D2N	G3D1T	G3D1N
0x0595	CLCnGLS3	7:0	G4D4T	G4D4N	G4D3T	G4D3N	G4D2T	G4D2N	G4D1T	G4D1N
0x0596	CLCSELECT	7:0			SLCT[2:0]					
0x0597	CLCDATA	7:0					CLC4OUT	CLC3OUT	CLC2OUT	CLC1OUT

## 29. MSSP - Host Synchronous Serial Port Module

The Host Synchronous Serial Port (MSSP) module is a serial interface useful for communicating with other peripheral or microcontroller devices. These peripheral devices may be serial EEPROMs, shift registers, display drivers, A/D converters, etc. The MSSP module can operate in one of two modes:

- · Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I<sup>2</sup>C)

The SPI interface can operate in Host or Client mode and supports the following features:

- Selectable clock parity
- Client select synchronization (Client mode only)
- · Daisy-chain connection of client devices

The I<sup>2</sup>C interface can operate in Host or Client mode and supports the following modes and features:

- · Byte NACKing (Client mode)
- · Limited multi-host support
- · 7-bit and 10-bit addressing
- Start and stop interrupts
- Interrupt masking
- Clock stretching
- · Bus collision detection
- · General call address matching
- · Address masking
- · Address Hold and Data Hold modes
- · Selectable SDA hold times

### 29.1 SPI Mode Overview


The Serial Peripheral Interface (SPI) is a synchronous serial data communication bus that operates in Full Duplex mode. Devices communicate in a host/client environment where the host device initiates the communication. A client device is selected for communication using the Client Select feature.

The SPI bus specifies four signal connections:

- Serial Clock (SCK)
- Serial Data Out (SDO)
- Serial Data In (SDI)
- Client Select (SS)

Figure 29-1 shows the block diagram of the MSSP module when operating in SPI mode.

Figure 29-1. MSSP Block Diagram (SPI Mode)




Notes: 1. Output selection for Host mode.

2. Input selection for Client and Host modes.

The SPI bus operates with a single host device and one or more client devices. When multiple client devices are used, an independent Client Select connection is required from the host device to each client device. The host selects only one client at a time. Most client devices have tri-state outputs, so their output signal appears disconnected from the bus when they are not selected.

Figure 29-2 shows a typical connection between a host device and multiple client devices.


Figure 29-2. SPI Host and Multiple Client Connection



Transmissions involve two shift registers, eight bits in size: One in the host and one in the client. Data is always shifted out one bit at a time, with the Most Significant bit (MSb) shifted out first. At the same time, a new Least Significant bit (LSb) is shifted into the same register.

Figure 29-3 shows a typical connection between two processors configured as host and client devices.

Figure 29-3. SPI Host/Client Connection



Data is shifted out of both shift registers on the programmed clock edge and latched on the opposite edge of the clock.

The host device transmits information out on its SDO output pin, which is connected to and received by the client's SDI input pin. The client device transmits information out on its SDO output pin, which is connected to and received by the host's SDI input pin.

To begin communication, the host device transmits both the MSb from its shift register and the clock signal. Both the host and client devices need to be configured for the same clock polarity. During each SPI clock cycle, a full-duplex data transmission occurs. This means that while the host device is sending out the MSb from its shift register (on its SDO pin) and the client device is reading this bit and saving it as the LSb of its shift register, the client device is also sending out the MSb from its shift register (on its SDO pin) and the host device is reading this bit and saving it as the LSb of its shift register.

After eight bits have been shifted out, the host and client have exchanged register values. If there is more data to exchange, the shift registers are loaded with new data and the process repeats itself.

Whether the data is meaningful or not (dummy data) depends on the application software. This leads to three scenarios for data transmission:

- · Host sends useful data and client sends dummy data.
- · Host sends useful data and client sends useful data.
- · Host sends dummy data and client sends useful data.

Transmissions must be performed in multiples of eight clock cycles. When there is no more data to be transmitted, the host stops sending the clock signal and it deselects the client.

Every client device connected to the bus that has not been selected through its Client Select line must disregard the clock and transmission signals and must not transmit out any data of its own.

#### 29.1.1 SPI Mode Registers

The MSSP module has six registers for SPI mode operation. They are:

- MSSP Status Register (SSPxSTAT)
- MSSP Control Register 1 (SSPxCON1)
- MSSP Control Register 3 (SSPxCON3)
- MSSP Data Buffer Register (SSPxBUF)

## **MSSP - Host Synchronous Serial Port Module**

- MSSP Address Register (SSPxADD)
- MSSP Shift (SSPSR) register (not directly accessible)

SSPxCON1 and SSPxSTAT are the control and status registers for SPI mode operation. The SSPxCON1 register is readable and writable. The lower six bits of the SSPxSTAT are read-only. The upper two bits of the SSPxSTAT are read/write.

One of the five SPI Host modes uses the SSPxADD value to determine the Baud Rate Generator clock frequency. More information on the Baud Rate Generator is available in 29.3. Baud Rate Generator.

SSPSR is the shift register used for shifting data in and out. SSPxBUF provides indirect access to the SSPSR register. SSPxBUF is the buffer register to which data bytes are written, and from which data bytes are read.

In receive operations, SSPSR and SSPxBUF together create a buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPxBUF and the SSPxIF interrupt is set.

During transmission, the SSPxBUF is not buffered. A write to SSPxBUF will write to both SSPxBUF and SSPSR.

#### 29.1.2 SPI Mode Operation

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits (SSPxCON1[5:0] and SSPxSTAT[7:6]). These control bits allow the following to be specified:

- Host mode (SCK is the clock output)
- · Client mode (SCK is the clock input)
- Clock Polarity (Idle state of SCK)
- · Data Input Sample Phase (middle or end of data output time)
- · Clock Edge (output data on rising/falling edge of SCK)
- Clock Rate (Host mode only)
- · Client Select mode (Client mode only)

To enable the serial port, the SSP Enable (SSPEN) bit must be set. To reset or reconfigure SPI mode, clear the SSPEN bit, re-initialize the SSPxCONy registers and then set the SSPEN bit. The SDI, SDO, SCK and SS serial port pins are selected with the PPS controls. For the pins to behave as the serial port function, some must have their data direction bits (in the TRIS register) appropriately programmed as follows:

- · SDI must have the corresponding TRIS bit set
- SDO must have the corresponding TRIS bit cleared
- · SCK (Host mode) must have the corresponding TRIS bit cleared
- · SCK (Client mode) must have the corresponding TRIS bit set
- The RxyPPS and SSPxCLKPPS controls must select the same pin
- SS must have the corresponding TRIS bit set

Any serial port function that is not desired may be overridden by programming the corresponding data direction (TRIS) register to the opposite value.

The MSSP consists of a Transmit/Receive Shift Register (SSPSR) and a buffer register (SSPxBUF). The SSPSR shifts the data in and out of the device, MSb first. The SSPxBUF holds the data that was written to the SSPSR until the received data is ready. Once the eight bits of data have been received, that byte is moved to the SSPxBUF register. Then, the Buffer Full Status (BF) bit and the MSSP Interrupt Flag (SSPxIF) bit are set. This double-buffering of the received data allows the next byte to start reception before reading the data that was just received. Any write to the SSPxBUF register during transmission/reception of data will be ignored and the Write Collision Detect (WCOL) bit will be set. User software must clear the WCOL bit to allow the following write(s) to the SSPxBUF register to complete successfully.

When the application software is expecting to receive valid data, the SSPxBUF must be read before the next byte of data to be transferred is written to the SSPxBUF. The BF bit indicates when SSPxBUF has been loaded with the received data (transmission is complete). When the SSPxBUF is read, the BF bit is cleared. This data may be irrelevant if the SPI is only a transmitter. The MSSP interrupt is used to determine when the transmission/reception has completed. If the interrupt method is not going to be used, then software polling can be done to ensure that a write collision does not occur.

## **MSSP - Host Synchronous Serial Port Module**



**Important:** The SSPSR is not directly readable or writable and can only be accessed by addressing the SSPxBUF register.

#### 29.1.2.1 SPI Host Mode

The Host can initiate the data transfer at any time because it controls the SCK line. The Host determines when the client (Processor 2, Figure 29-3) is to broadcast data by the software protocol.

In Host mode, the data is transmitted/received as soon as the SSPxBUF register is written to. If the SPI is only going to receive, the SDO output may be disabled (programmed as an input). The SSPSR register will continue to shift in the signal present on the SDI pin at the programmed clock rate. As each byte is received, it will be loaded into the SSPxBUF register (interrupts and Status bits appropriately set).

The clock polarity is selected by appropriately programming the Clock Polarity Select (CKP) and SPI Clock Edge Select (CKE) bits. Figure 29-4 shows the four clocking configurations. When the CKE bit is set, the SDO data is valid one half of a clock cycle before a clock edge appears on SCK, and transmission occurs on the transition from the Active to Idle clock state. When CKE is clear, the SDO data is valid at the same time as the clock edge appears on SCK, and transmission occurs on the transition from the Idle to Active clock states.

The SPI Data Input Sample (SMP) bit determines when the SDI input is sampled. When SMP is set, input data is sampled at the end of the data output time. When SMP is clear, input data is sampled at the middle of the data output time.

The SPI clock rate (bit rate) is user-programmable to be one of the following:

- F<sub>OSC</sub>/4 (or T<sub>CY</sub>)
- F<sub>OSC</sub>/16 (or 4 \* T<sub>CY</sub>)
- F<sub>OSC</sub>/64 (or 16 \* T<sub>CY</sub>)
- · Timer2 output/2
- F<sub>OSC</sub>/(4 \* (SSPxADD + 1))



**Important:** In Host mode, the clock signal output to the SCK pin is also the clock signal input to the peripheral. The pin selected for output with the RxyPPS register must also be selected as the peripheral input with the SSPxCLKPPS register.




Figure 29-4. SPI Mode Waveform (Host Mode)

#### 29.1.2.2 SPI Client Mode

In Client mode, the data is transmitted and received as external clock pulses appear on SCK. When the last bit is latched, the SSPxIF Interrupt Flag bit is set.

Before enabling the module in SPI Client mode, the clock line must match the proper Idle state. The clock line can be observed by reading the SCK pin. The Idle state is determined by the CKP bit.

While in Client mode, the external clock is supplied by the external clock source on the SCK pin. This external clock must meet the minimum high and low times as specified in Electrical Specifications.

While in Sleep mode, the client can transmit/receive data. The shift register is clocked from the SCK pin input and when a byte is received, the device will generate an interrupt. If enabled, the device will wake up from Sleep.


#### 29.1.2.3 Daisy-Chain Configuration

The SPI bus can sometimes be connected in a daisy-chain configuration. The first client output is connected to the second client input, the second client output is connected to the third client input, and so on. The final client output is connected to the host input. Each client sends out, during a second group of clock pulses, an exact copy of what was received during the first group of clock pulses. The whole chain acts as one large communication shift register. The daisy-chain feature only requires a single Client Select line from the host device.

In a daisy-chain configuration, only the most recent byte on the bus is required by the client. Setting the Buffer Overwrite Enable (BOEN) bit will enable writes to the SSPxBUF register, even if the previous byte has not been read. This allows the software to ignore data that may not apply to it.

Figure 29-5 shows the block diagram of a typical daisy-chain connection when operating in SPI mode.

Figure 29-5. SPI Daisy-Chain Connection



## 29.1.2.4 Client Select Synchronization

The Client Select can also be used to synchronize communication (see Figure 29-6). The Client Select line is held high until the host device is ready to communicate. When the Client Select line is pulled low, the client knows that a new transmission is starting.

If the client fails to receive the communication properly, it will be reset at the end of the transmission, when the Client Select line returns to a High state. The client is then ready to receive a new transmission when the Client Select line is pulled low again. If the Client Select line is not used, there is a risk that the client will eventually become out of sync with the host. If the client misses a bit, it will always be one bit off in future transmissions. Use of the Client Select line allows the client and host to align themselves at the beginning of each transmission.

The  $\overline{SS}$  pin allows a Synchronous Client mode. The SPI must be in Client mode with  $\overline{SS}$  pin control enabled (MSSP Mode Select (SSPM) bits = 0100).

When the SS pin is low, transmission and reception are enabled and the SDO pin is driven.

When the  $\overline{SS}$  pin goes high, the SDO pin is no longer driven, even if in the middle of a transmitted byte, and becomes a floating output. External pull-up/pull-down resistors may be desirable depending on the application.


When the SPI module resets, the bit counter is forced to '0'. This can be done by either forcing the  $\overline{SS}$  pin to a high level or clearing the SSPEN bit.




#### Important:

- 1. When the SPI is in Client mode with  $\overline{SS}$  pin control enabled (SSPM = 0100), the SPI module will reset if the  $\overline{SS}$  pin is set to  $V_{DD}$ .
- 2. When the SPI is used in Client mode with CKE set, the user must enable  $\overline{SS}$  pin control (see Figure 29-8). If CKE is clear,  $\overline{SS}$  pin control is optional (see Figure 29-7).
- 3. While operated in SPI Client mode, the SMP bit must remain clear.

Figure 29-6. Client Select Synchronous Waveform









Figure 29-8. SPI Mode Waveform (Client Mode with CKE = 1)



## 29.1.2.5 SPI Operation in Sleep Mode


In SPI Host mode, when the Sleep mode is selected, all module clocks are halted and the transmission/reception will remain in that state until the device wakes. After the device returns to Run mode, the module will resume transmitting and receiving data.

In SPI Client mode, the SPI Transmit/Receive Shift register operates asynchronously to the device. This allows the device to be placed in Sleep mode and data to be shifted into the SPI Transmit/Receive Shift register. When all eight bits have been received, the MSSP Interrupt Flag bit will be set and if enabled, will wake the device.

## 29.2 I<sup>2</sup>C Mode Overview

The Inter-Integrated Circuit (I<sup>2</sup>C) bus is a multi-host serial data communication bus. Devices communicate in a host/client environment where the host devices initiate the communication. A client device is controlled through addressing. Figure 29-9 and Figure 29-10 show block diagrams of the I<sup>2</sup>C Host and Client modes, respectively.


Figure 29-9. MSSP Block Diagram (I<sup>2</sup>C Host Mode)



Notes: 1. SDA pin selections must be the same for input and output.

SCL pin selections must be the same for input and output.

Figure 29-10. MSSP Block Diagram (I<sup>2</sup>C Client Mode)



Notes: 1.SDA pin selections must be the same for input and output.

2. SCL pin selections must be the same for input and output.


The I<sup>2</sup>C bus specifies two signal connections:

- · Serial Clock (SCL)
- Serial Data (SDA)

Both the SCL and SDA connections are bidirectional open-drain lines, each requiring pull-up resistors for the supply voltage. Pulling the line to ground is considered a logical zero and letting the line float is considered a logical one.

Figure 29-11 shows a typical connection between two processors configured as host and client devices.

Figure 29-11. I<sup>2</sup>C Host/Client Connection



The I<sup>2</sup>C bus can operate with one or more host devices and one or more client devices.

There are four potential modes of operation for a given device:

- Host Transmit mode (host is transmitting data to a client)
- Host Receive mode (host is receiving data from a client)
- Client Transmit mode (client is transmitting data to a host)
- Client Receive mode (client is receiving data from the host)

To begin communication, the host device transmits a Start condition followed by the address byte of the client it intends to communicate with. A Start condition is indicated by a high-to-low transition of the SDA line while the SCL

## **MSSP - Host Synchronous Serial Port Module**

line is held high. Address and data bytes are sent out, MSb first. This is followed by a single Read/Write Information  $(R/\overline{W})$  bit, which determines whether the host intends to transmit to or receive data from the client device. The  $R/\overline{W}$  bit is sent out as a logical one when the host intends to read data from the client, and is sent out as a logical zero when it intends to write data to the client.

If the requested client exists on the bus, it will respond with an Acknowledge sequence, otherwise known as an  $\overline{ACK}$ . The Acknowledge sequence is an active-low signal, which holds the SDA line low to indicate to the transmitter that the client device has received the transmitted data and is ready to receive more. The host then continues to either transmit to or receive data from the client.

The transition of a data bit is always performed while the SCL line is held low. Transitions that occur while the SCL line is held high are used to indicate Start and Stop conditions.

If the host intends to write to the client, then it repeatedly sends out a byte of data, with the client responding after each byte with an  $\overline{\mathsf{ACK}}$  sequence. In this example, the host device is in Host Transmit mode and the client is in Client Receive mode.

If the host intends to read from the client, then it repeatedly receives a byte of data from the client, and responds after each byte with an  $\overline{\mathsf{ACK}}$  sequence. In this example, the host device is in Host Receive mode and the client is in Client Transmit mode.

On the last byte of data communicated, the host device may end the transmission by sending a Stop condition. If the host device is in Receive mode, it sends the Stop condition in place of the last  $\overline{ACK}$  sequence. A Stop condition is indicated by a low-to-high transition of the SDA line while the SCL line is held high.

In some cases, the host may want to maintain control of the bus and re-initiate another transmission. If so, the host device may send a Restart condition in place of the Stop condition or last  $\overline{ACK}$  sequence when it is in Receive mode.

The I<sup>2</sup>C bus specifies three message protocols:

- · Single message where a host writes data to a client.
- · Single message where a host reads data from a client.
- Combined message where a host initiates a minimum of two writes, or two reads, or a combination of writes and reads, to one or more clients.

## 29.2.1 I<sup>2</sup>C Mode Registers

The MSSP module has eight registers for I<sup>2</sup>C operation.

#### These are:

- MSSP Status Register (SSPxSTAT)
- MSSP Control 1 Register (SSPxCON1)
- MSSP Control 2 Register (SSPxCON2)
- MSSP Control 3 Register (SSPxCON3)
- Serial Receive/Transmit Buffer Register (SSPxBUF)
- MSSP Address Register (SSPxADD)
- I<sup>2</sup>C Client Address Mask Register (SSPxMSK)
- MSSP Shift (SSPSR) register not directly accessible

SSPxCON1, SSPxCON2, SSPxCON3 and SSPxSTAT are the Control and Status registers in I<sup>2</sup>C mode operation. The SSPxCON1, SSPxCON2 and SSPxCON3 registers are readable and writable. The lower six bits of the SSPxSTAT are read-only. The upper two bits of the SSPxSTAT are read/write. SSPxMSK holds the client address mask value used in address comparison. SSPxADD contains the client device address when the MSSP is configured in I<sup>2</sup>C Client mode. When the MSSP is configured in Host mode, SSPxADD acts as the Baud Rate Generator reload value.

SSPSR is the shift register used for shifting data in or out. SSPxBUF is the buffer register to which data bytes are written to or read from. In receive operations, SSPSR and SSPxBUF together, create a double-buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPxBUF and the SSPxIF interrupt is set. During transmission, the SSPxBUF is not double-buffered. A write to SSPxBUF will write to both SSPxBUF and SSPSR.

## 29.2.2 I<sup>2</sup>C Mode Operation

All MSSP I<sup>2</sup>C communication is byte oriented and shifted out MSb first. Eight SFR registers and two interrupt flags interface the module with the PIC<sup>®</sup> microcontroller and user software. Two pins, SDA and SCL, are exercised by the module to communicate with other external I<sup>2</sup>C devices.

## 29.2.2.1 Definition of I<sup>2</sup>C Terminology

There is language and terminology in the description of I<sup>2</sup>C communication that have definitions specific to I<sup>2</sup>C. That word usage is defined below and may be used in the rest of this document without explanation. This table was adapted from the Philips/NXP I<sup>2</sup>C Specification.

Table 29-1. I<sup>2</sup>C Terminology

Term	Description						
Transmitter	The device that shifts data out onto the bus						
Receiver	The device that shifts data in from the bus						
Host	The device that initiates a transfer, generates clock signals, and terminates a transfer						
Client The device addressed by the host							
Multi-Host	A bus with more than one device that can initiate data transfers						
Arbitration	Procedure to ensure that only one host at a time controls the bus. Winning arbitration ensures that the message is not corrupted.						
Synchronization Procedure to synchronize the clocks of two or more devices on the bus							
Idle No host is controlling the bus, and both SDA and SCL lines are high							
Active	Any time one or more host devices are controlling the bus						
Addressed Client	Client device that has received a matching address and is actively being clocked by a host						
Matching Address	Address byte that is clocked into a client that matches the value stored in SSPxADD						
Write Request	Client receives a matching address with the R/W bit clear, and is ready to clock in data						
Read Request	Host sends an address byte with the $R/\overline{W}$ bit set, indicating that it wishes to clock data out of the client. This data is the next and all following bytes until a Restart or Stop.						
Clock Stretching	When a device on the bus hold SCL low to stall communication						
Bus Collision	Any time the SDA line is sampled low by the module while it is outputting and expected High state						

## **29.2.2.2** Byte Format

All communication in  $I^2C$  is done in 9-bit segments. A byte is sent from a host to a client or vice versa, followed by an Acknowledge sequence sent back. After the eighth falling edge of the SCL line, the device outputting data on the SDA changes that pin to an input and reads the Acknowledge value on the next clock pulse.

The clock signal, SCL, is provided by the host. Data is valid to change while the SCL signal is low, and sampled on the rising edge of the clock. Changes on the SDA line while the SCL line is high define special conditions on the bus, such as a Start or Stop condition.

#### 29.2.2.3 SDA and SCL Pins

Selection of any I<sup>2</sup>C mode with the SSPEN bit set forces the SCL and SDA pins to be open-drain. These pins must be configured as inputs by setting the appropriate TRIS bits.

## **MSSP - Host Synchronous Serial Port Module**



**Important:** Any device pin can be selected for SDA and SCL functions with the PPS peripheral. These functions are bidirectional. The SDA input is selected with the SSPxDATPPS registers. The SCL input is selected with the SSPxCLKPPS registers. Outputs are selected with the RxyPPS registers. It is the user's responsibility to make the selections so that both the input and the output for each function is on the same pin.

#### 29.2.2.4 SDA Hold Time

The hold time of the SDA pin is selected by the SDA Hold Time Selection (SDAHT) bit. Hold time is the time SDA is held valid after the falling edge of SCL. Setting the SDAHT bit selects a longer 300 ns minimum hold time and may help buses with large capacitance.

#### 29.2.2.5 Clock Stretching

Clock stretching occurs when a device on the bus holds the SCL line low, effectively pausing communication. The client may stretch the clock to allow more time to handle data or prepare a response for the host device. A host device is not concerned with stretching as anytime it is active on the bus and not transferring data it is stretching. Any stretching done by a client is invisible to the host software and handled by the hardware that generates SCL.

The CKP bit is used to control stretching in software. Any time the CKP bit is cleared, the module will wait for the SCL line to go low and then hold it. Setting CKP will release SCL and allow more communication.

## 29.2.2.6 Arbitration

Each host device must monitor the bus for Start and Stop conditions. If the device detects that the bus is busy, it cannot begin a new message until the bus returns to an Idle state.

However, two host devices may try to initiate a transmission on or about the same time. When this occurs, the process of arbitration begins. Each transmitter checks the level of the SDA data line and compares it to the level that it expects to find. The first transmitter to observe that the two levels do not match, loses arbitration, and must stop transmitting on the SDA line.

For example, if one transmitter holds the SDA line to a logical one (lets SDA float) and a second transmitter holds it to a logical zero (pulls SDA low), the result is that the SDA line will be low. The first transmitter then observes that the level of the line is different than expected and concludes that another transmitter is communicating.

The first transmitter to notice this difference is the one that loses arbitration and must stop driving the SDA line. If this transmitter is also a host device, it also must stop driving the SCL line. It then can monitor the lines for a Stop condition before trying to reissue its transmission. In the meantime, the other device that has not noticed any difference between the expected and actual levels on the SDA line continues with its original transmission. It can do so without any complications, because so far, the transmission appears exactly as expected with no other transmitter disturbing the message.

Client Transmit mode can also be arbitrated, when a host addresses multiple clients, but this is less common.

#### 29.2.2.7 Start Condition

The I<sup>2</sup>C Specification defines a Start condition as a transition of SDA from a High to a Low state while SCL line is high. A Start condition is always generated by the host and signifies the transition of the bus from an Idle to an Active state. Figure 29-12 shows wave forms for Start and Stop conditions.

A bus collision can occur on a Start condition if the module samples the SDA line low before asserting it low. This does not conform to the I<sup>2</sup>C Specification that states no bus collision can occur on a Start.


#### 29.2.2.8 Stop Condition

A Stop condition is a transition of the SDA line from Low-to-High state while the SCL line is high.



**Important:** At least one SCL low time must appear before a Stop is valid, therefore, if the SDA line goes low then high again while the SCL line stays high, only the Start condition is detected.

Figure 29-12. I<sup>2</sup>C Start and Stop Conditions



#### 29.2.2.9 Start/Stop Condition Interrupt Masking


The Start Condition Interrupt Enable (SCIE) and Stop Condition Interrupt Enable (PCIE) bits can enable the generation of an interrupt in Client modes that do not typically support this function. These bits will have no effect in Client modes where interrupt on Start and Stop detect are already enabled.

#### 29.2.2.10 Restart Condition

A Restart condition is valid any time that a Stop is valid. A host can issue a Restart if it wishes to hold the bus after terminating the current transfer. A Restart has the same effect on the client that a Start would, resetting all client logic and preparing it to clock in an address. The host may want to address the same or another client. Figure 29-13 shows the waveform for a Restart condition.

In 10-bit Addressing Client mode, a Restart is required for the host to clock data out of the addressed client. Once a client has been fully addressed, matching both high and low address bytes, the host can issue a Restart and the high address byte with the R/W bit set. The client logic will then hold the clock and prepare to clock out data.

Figure 29-13, I<sup>2</sup>C Restart Condition



#### 29.2.2.11 Acknowledge Sequence

The ninth SCL pulse for any transferred byte in  $I^2C$  is dedicated as an Acknowledge sequence ( $\overline{ACK}$ ). It allows receiving devices to respond back to the transmitter by pulling the SDA line low. The transmitter must release control of the line during this time to shift in the response. The Acknowledge ( $\overline{ACK}$ ) is an active-low signal, pulling the SDA line low indicates to the transmitter that the device has received the transmitted data and is ready to receive more.

The result of an ACK is placed in the Acknowledge Status (ACKSTAT) bit.

The client software, when the Address Hold Enable (AHEN) and Data Hold Enable (DHEN) bits are set, allows the user to select the  $\overline{ACK}$  value sent back to the transmitter. The Acknowledge Data (ACKDT) bit is set/cleared to determine the response.

The client hardware will generate an  $\overline{ACK}$  response under most circumstances. However, if the BF bit or the Receive Overflow Indicator (SSPOV) bit are set when a byte is received then the  $\overline{ACK}$  will not be sent by the client.

## **MSSP - Host Synchronous Serial Port Module**

When the module is addressed, after the eighth falling edge of SCL on the bus, the Acknowledge Time Status (ACKTIM) bit is set. The ACKTIM bit indicates the acknowledge time of the active bus. The ACKTIM bit is only active when either the AHEN bit or DHEN bit is enabled.

### 29.2.3 I<sup>2</sup>C Client Mode Operation

The MSSP Client mode operates in one of four modes selected by the MSSP Mode Select (SSPM) bits. The modes can be divided into 7-bit and 10-bit Addressing mode. 10-bit Addressing modes operate the same as 7-bit with some additional overhead for handling the larger addresses.

Modes with Start and Stop condition interrupts operate the same as the other modes with SSPxIF additionally getting set upon detection of a Start, Restart, or Stop condition.

#### 29.2.3.1 Client Mode Addresses

The SSPxADD register contains the Client mode address. The first byte received after a Start or Restart condition is compared against the value stored in this register. If the byte matches, the value is loaded into the SSPxBUF register and an interrupt is generated. If the value does not match, the module goes Idle and no indication is given to the software that anything happened.

The SSPxMSK register affects the address matching process. See 29.2.3.5. SSP Mask Register for more information.

#### 29.2.3.1.1 I<sup>2</sup>C Client 7-Bit Addressing Mode

In 7-bit Addressing mode, the LSb of the received data byte is ignored when determining if there is an address match.

### 29.2.3.1.2 I<sup>2</sup>C Client 10-Bit Addressing Mode

In 10-bit Addressing mode, the first received byte is compared to the binary value of '1 1 1 1 0 A9 A8 0'. A9 and A8 are the two MSbs of the 10-bit address and stored in bits 2 and 1 of the SSPxADD register.

After the acknowledge of the high byte the Update Address (UA) bit is set and SCL is held low until the user updates SSPxADD with the low address. The low address byte is clocked in and all eight bits are compared to the low address value in SSPxADD. Even if there is not an address match; SSPxIF and UA are set, and SCL is held low until SSPxADD is updated to receive a high byte again. When SSPxADD is updated the UA bit is cleared. This ensures the module is ready to receive the high address byte on the next communication.

A high and low address match as a write request is required at the start of all 10-bit addressing communication. A transmission can be initiated by issuing a Restart once the client is addressed and clocking in the high address with the R/W bit set. The client hardware will then acknowledge the read request and prepare to clock out data. This is only valid for a client after it has received a complete high and low address byte match.

## 29.2.3.2 Clock Stretching

Clock stretching occurs when a device on the bus holds the SCL line low, effectively pausing communication. The client may stretch the clock to allow more time to handle data or prepare a response for the host device. A host device is not concerned with stretching as anytime it is active on the bus and not transferring data it is stretching. Any stretching done by a client is invisible to the host software and handled by the hardware that generates SCL.

The CKP bit is used to control stretching in software. Any time the CKP bit is cleared, the module will wait for the SCL line to go low and then hold it. Setting CKP will release SCL and allow more communication.

#### 29.2.3.2.1 Normal Clock Stretching

Following an  $\overline{ACK}$  if the R/W bit is set (a read request), the client hardware will clear CKP. This allows the client time to update SSPxBUF with data to transfer to the host. If the Stretch Enable (SEN) bit is set, the client hardware will always stretch the clock after the  $\overline{ACK}$  sequence. Once the client is ready; CKP is set by software and communication resumes.

#### 29.2.3.2.2 10-Bit Addressing Mode

In 10-bit Addressing mode, when the UA bit is set, the clock is always stretched. This is the only time the SCL is stretched without CKP being cleared. SCL is released immediately after a write to SSPxADD.

#### 29.2.3.2.3 Byte NACKing

When the AHEN bit is set, CKP is cleared by hardware after the eighth falling edge of SCL for a received matching address byte. When the DHEN bit is set, CKP is cleared after the eighth falling edge of SCL for received data.

## **MSSP - Host Synchronous Serial Port Module**

Stretching after the eighth falling edge of SCL allows the client to look at the received address or data and decide if it wants to acknowledge (ACK) the received address or data, or not acknowledge (NACK) the address or data.

#### 29.2.3.3 Clock Synchronization and the CKP Bit


Any time the CKP bit is cleared, the module will wait for the SCL line to go low and then hold it. However, clearing the CKP bit will not assert the SCL output low until the SCL output is already sampled low. Therefore, the CKP bit will not assert the SCL line until an external I<sup>2</sup>C host device has already asserted the SCL line. The SCL output will remain low until the CKP bit is set and all other devices on the I<sup>2</sup>C bus have released SCL.

#### 29.2.3.4 General Call Address Support

The addressing procedure for the  $I^2C$  bus is such that the first byte after the Start condition usually determines which device will be the client addressed by the host device. The exception is the General Call address that can address all devices. When this address is used, all devices must, in theory, respond with an  $\overline{ACK}$ .

The general call address is a reserved address in the  $I^2C$  protocol, defined as address 0x00. When the General Call Enable (GCEN) bit is set, the client module will automatically  $\overline{ACK}$  the reception of this address regardless of the value stored in SSPxADD. After the client clocks in an address of all zeros with the  $R/\overline{W}$  bit clear, an interrupt is generated and client software can read SSPxBUF and respond. Figure 29-14 shows a General Call reception sequence.

Figure 29-14. Client Mode General Call Address Sequence



In 10-bit Address mode, the UA bit will not be set on the reception of the general call address. The client will prepare to receive the second byte as data, just as it would in 7-bit mode.

If the AHEN bit is set, just as with any other address reception, the client hardware will stretch the clock after the eighth falling edge of SCL. The client must then set its Acknowledge Sequence Enable (ACKEN) bit and release the clock.

### 29.2.3.5 SSP Mask Register

The MSSP Mask (SSPxMSK) register is available in I<sup>2</sup>C Client mode as a mask for the value held in the SSPSR register during an address comparison operation. A zero ('0') bit in the SSPxMSK register has the effect of making the corresponding bit of the received address a "don't care".

This register is reset to all '1's upon any Reset condition and, therefore, has no effect on standard MSSP operation until written with a mask value.

SSPxMSK is active during:

- 7-bit Address mode: Address compare of A[7:1]
- 10-bit Address mode: Address compare of A[7:0] only. The MSSP mask has no effect during the reception of the first (high) byte of the address.

#### 29.2.3.6 Client Reception

When the R/ $\overline{W}$  bit of a matching received address byte is clear, the R/ $\overline{W}$  bit is cleared. The received address is loaded into the SSPxBUF register and acknowledged.

When the Overflow condition exists for a received address, a Not Acknowledge (NACK) is transmitted and the Receive Overflow Indicator (SSPOV) bit is set. The Buffer Override Enable (BOEN) bit modifies this operation.

## PIC16F18015/25/44/45

## **MSSP - Host Synchronous Serial Port Module**

An MSSP interrupt is generated for each transferred data byte. The SSPxIF flag bit must be cleared by software.

When the SEN bit is set, SCL will be held low (clock stretch) following each received byte. The clock must be released by setting the CKP bit, except sometimes in 10-bit mode. See 29.2.3.2.2. 10-Bit Addressing Mode for more details.

#### 29.2.3.6.1 7-Bit Addressing Reception

This section describes a standard sequence of events for the MSSP module configured as an I<sup>2</sup>C client in 7-bit Addressing mode. Figure 29-15 and Figure 29-16 are used as a visual reference for this description.

This is a step by step process of what typically must be done to accomplish I<sup>2</sup>C communication.

- 1. Start condition detected.
- 2. The Start (S) bit is set; SSPxIF is set if the Start Condition Interrupt Enable (SCIE) bit is set.
- 3. Matching address with R/W bit clear is received.
- 4. The client pulls SDA low, sending an ACK to the host, and sets SSPxIF bit.
- 5. Software clears the SSPxIF bit.
- 6. Software reads received address from SSPxBUF, clearing the BF flag.
- 7. If SEN = 1; Client software sets the CKP bit to release the SCL line.
- 8. The host clocks out a data byte.
- 9. Client drives SDA low, sending an ACK to the host, and sets SSPxIF bit.
- 10. Software clears SSPxIF.
- 11. Software reads the received byte from SSPxBUF, clearing BF.
- 12. Steps 8-12 are repeated for all received bytes from the host.
- 13. Host sends Stop condition, setting the Stop (P) bit, and the bus goes Idle.




Figure 29-15. I<sup>2</sup>C Client, 7-Bit Address, Reception (SEN = 0, AHEN = 0, DHEN = 0)




Figure 29-16. I<sup>2</sup>C Client, 7-Bit Address, Reception (SEN = 1, AHEN = 0, DHEN = 0)

### 29.2.3.6.2 7-Bit Reception with AHEN and DHEN

Client device reception with AHEN and DHEN set operate the same as without these options with extra interrupts and clock stretching added after the eighth falling edge of SCL. These additional interrupts allow the client software to decide whether it wants to  $\overline{\mathsf{ACK}}$  the receive address or data byte, rather than the hardware. This functionality adds support for PMBus<sup>™</sup> that was not present on previous versions of this module.

This list describes the steps that need to be taken by client software to use these options for I<sup>2</sup>C communication. Figure 29-17 displays a module using both address and data holding. Figure 29-18 includes the operation with the SEN bit set.

- The Start (S) bit is set; SSPxIF is set if SCIE is set.
- 2. Matching address with the R/W bit clear is clocked in. SSPxIF is set and CKP cleared after the eighth falling edge of SCL.
- 3. Software clears the SSPxIF.
- 4. Client can look at the ACKTIM bit to determine if the SSPxIF was after or before the ACK.
- 5. Client reads the address value from SSPxBUF, clearing the BF flag.
- 6. Client transmits an ACK to the host by clearing ACKDT.
- 7. Client releases the clock by setting CKP.
- 8. SSPxIF is set after an ACK, not after a NACK.
- 9. If SEN = 1, the client hardware will stretch the clock after the  $\overline{ACK}$ .
- 10. Client clears SSPxIF.



**Important:** SSPxIF is still set after the ninth falling edge of SCL even if there is no clock stretching and BF has been cleared. Only if a NACK is sent to the host is SSPxIF not set.

- 11. SSPxIF is set and CKP cleared after eighth falling edge of SCL for a received data byte.
- 12. Client looks at the ACKTIM bit to determine the source of the interrupt.
- 13. Client reads the received data from SSPxBUF, clearing BF.
- 14. Steps 7-14 are the same for each received data byte.
- 15. Communication is ended by either the client sending a NACK, or the host sending a Stop condition. If a Stop is sent and the Stop Condition Interrupt Enable (PCIE) bit is clear, the client will only know by polling the Stop (P) bit.




Figure 29-17. I<sup>2</sup>C Client, 7-Bit Address, Reception (SEN = 0, AHEN = 1, DHEN = 1)




Figure 29-18. I<sup>2</sup>C Client, 7-Bit Address, Reception (SEN = 1, AHEN = 1, DHEN = 1)

## 29.2.3.6.3 Client Mode 10-Bit Address Reception

This section describes a standard sequence of events for the MSSP module configured as an I<sup>2</sup>C client in 10-bit Addressing mode. Figure 29-19 shows a standard waveform for a client receiver in 10-bit Addressing mode with clock stretching enabled.

This is a step-by-step process of what must be done by the client software to accomplish I<sup>2</sup>C communication.

- Bus starts Idle.
- 2. Host sends Start condition; S bit is set; SSPxIF is set if SCIE is set.
- 3. Host sends matching high address with the R/W bit clear; the UA bit is set.
- 4. Client sends ACK and SSPxIF is set.
- Software clears the SSPxIF bit.
- 6. Software reads received address from SSPxBUF, clearing the BF flag.
- 7. Client loads low address into SSPxADD, releasing SCL.
- 8. Host sends matching low address byte to the client; UA bit is set.



Important: Updates to the SSPxADD register are not allowed until after the ACK sequence.

Client sends ACK and SSPxIF is set.



**Important:** If the low address does not match, SSPxIF and UA are still set so that the client software can set SSPxADD back to the high address. BF is not set because there is no match. CKP is unaffected.

- 10. Client clears SSPxIF.
- 11. Client reads the received matching address from SSPxBUF, clearing BF.
- 12. Client loads high address into SSPxADD.
- 13. Host clocks a data byte to the client and clocks out the client ACK on the ninth SCL pulse; SSPxIF is set.
- 14. If the SEN bit is set, CKP is cleared by hardware and the clock is stretched.
- 15. Client clears SSPxIF.
- 16. Client reads the received byte from SSPxBUF, clearing BF.
- 17. If SEN is set the client software sets CKP to release the SCL.
- 18. Steps 13-17 repeat for each received byte.
- 19. Host sends Stop to end the transmission.




Figure 29-19. I<sup>2</sup>C Client, 10-Bit Address, Reception (SEN = 1, AHEN = 0, DHEN = 0)


# PIC16F18015/25/44/45


# **MSSP - Host Synchronous Serial Port Module**

# 29.2.3.6.4 10-Bit Addressing with Address or Data Hold

Reception using 10-bit addressing with AHEN or DHEN set is the same as with 7-bit modes. The only difference is the need to update the SSPxADD register using the UA bit. All functionality, specifically when the CKP bit is cleared and SCL line is held low, are the same. Figure 29-20 can be used as a reference of a client in 10-bit addressing with AHEN set.

Figure 29-21 shows a standard waveform for a client transmitter in 10-bit Addressing mode.





## 29.2.3.7 Client Transmission

When the RW bit of the incoming address byte is set and an address match occurs, the RW bit is set. The received address is loaded into the SSPxBUF register, and an ACK pulse is sent by the client on the ninth bit.

Following the  $\overline{ACK}$ , client hardware clears the CKP bit and the SCL pin is held low (see 29.2.2.5. Clock Stretching for more details). By stretching the clock, the host will be unable to assert another clock pulse until the client is done preparing the transmit data.

The transmit data must be loaded into the SSPxBUF register, which also loads the SSPSR register. Then the SCL pin will be released by setting the CKP bit. The eight data bits are shifted out on the falling edge of the SCL input. This ensures that the SDA signal is valid during the SCL high time.

The  $\overline{ACK}$  pulse from the host receiver is latched on the rising edge of the ninth SCL input pulse. This  $\overline{ACK}$  value is copied to the ACKSTAT bit. If ACKSTAT is set (NACK), then the data transfer is complete. In this case, when the NACK is latched by the client, the client goes Idle and waits for another occurrence of a Start condition. If the SDA line was low ( $\overline{ACK}$ ), the next transmit data must be loaded into the SSPxBUF register. Again, the SCL pin must be released by setting bit CKP.

An MSSP interrupt is generated for each data transfer byte. The SSPxIF bit must be cleared by software and the SSPxSTAT register is used to determine the status of the byte. The SSPxIF bit is set on the falling edge of the ninth clock pulse.

#### 29.2.3.7.1 Client Mode Bus Collision

A client receives a read request and begins shifting data out on the SDA line. If a bus collision is detected and the Client Mode Bus Collision Detect Enable (SBCDE) bit is set, the Bus Collision Interrupt Flag (BCLxIF) bit of the PIRx register is set. Once a bus collision is detected, the client goes Idle and waits to be addressed again. User software can use the BCLxIF bit to handle a client bus collision.

#### 29.2.3.7.2 7-Bit Transmission

A host device can transmit a read request to a client, and then clock data out of the clien. The list below outlines what software for a client will need to do to accomplish a standard transmission. Figure 29-22 can be used as a reference to this list.

- 1. Host sends a Start condition.
- 2. The Start (S) bit is set; SSPxIF is set if SCIE is set.
- 3. Matching address with R/W bit set is received by the Client, setting SSPxIF bit.
- 4. Client hardware generates an ACK and sets SSPxIF.
- 5. The SSPxIF bit is cleared by software.
- 6. Software reads the received address from SSPxBUF, clearing BF.
- 7. R/W is set so CKP was automatically cleared after the ACK.
- 8. The client software loads the transmit data into SSPxBUF.
- 9. CKP bit is set by software, releasing SCL, allowing the host to clock the data out of the client.
- 10. SSPxIF is set after the ACK response from the host is loaded into the ACKSTAT bit.
- 11. SSPxIF bit is cleared.
- 12. The client software checks the ACKSTAT bit to see if the host wants to clock out more data.



### Important:

- 1. If the host  $\overline{ACK}$ s then the clock will be stretched.
- 2. ACKSTAT is the only bit updated on the rising edge of the ninth SCL clock instead of the falling edge.
- 13. Steps 9-13 are repeated for each transmitted byte.
- 14. If the host sends a not ACK; the clock is not held, but SSPxIF is still set.
- 15. The host sends a Restart condition or a Stop.




Figure 29-22. I<sup>2</sup>C Client, 7-Bit Address, Transmission (AHEN = 0)

### 29.2.3.7.3 7-Bit Transmission with Address Hold Enabled

Setting the AHEN bit enables additional clock stretching and interrupt generation after the eighth falling edge of a received matching address. Once a matching address has been clocked in, CKP is cleared and the SSPxIF interrupt is set.

Figure 29-23 displays a standard waveform of a 7-bit address client transmission with AHEN enabled.

- 1. Bus starts Idle.
- 2. Host sends Start condition: the S bit is set: SSPxIF is set if SCIE is set.
- 3. Host sends matching address with the R/W bit set. After the eighth falling edge of the SCL line the CKP bit is cleared and SSPxIF interrupt is generated.
- 4. Client software clears SSPxIF.
- Client software reads the ACKTIM, R\overline{W} and D\overline{A} bits to determine the source of the interrupt.
- 6. Client reads the address value from the SSPxBUF register, clearing the BF bit.
- 7. Client software decides from this information if it wishes to ACK or NACK and sets the ACKDT bit accordingly.
- Client software sets the CKP bit, releasing SCL.
- Host clocks in the ACK value from the client.
- 10. Client hardware automatically clears the CKP bit and sets SSPxIF after  $\overline{ACK}$  if the R/W bit is set.
- 11. Client software clears SSPxIF.
- 12. Client loads value to transmit to the host into SSPxBUF, setting the BF bit.




**Important:** SSPxBUF cannot be loaded until after the ACK.

- 13. Client software sets the CKP bit, releasing the clock.
- 14. Host clocks out the data from the client and sends an ACK value on the ninth SCL pulse.
- 15. Client hardware copies the ACK value into the ACKSTAT bit.
- 16. Steps 10-15 are repeated for each byte transmitted to the host from the client.
- 17. If the host sends a not ACK, the client releases the bus allowing the host to send a Stop and end the communication.



**Important:** Host must send a not  $\overline{ACK}$  on the last byte to ensure that the client releases the SCL line to receive a Stop.



### 29,2,4 I<sup>2</sup>C Host Mode

Host mode is enabled by configuring the appropriate SSPM bits and setting the SSPEN bit. In Host mode, the SDA and SCL pins must be configured as inputs. The MSSP peripheral hardware will override the output driver TRIS controls when necessary to drive the pins low.

Host mode of operation is supported by interrupt generation on the detection of the Start and Stop conditions. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I<sup>2</sup>C bus may be taken when the P bit is set, or the bus is Idle.

In Firmware Controlled Host mode, user code conducts all I<sup>2</sup>C bus operations based on Start and Stop condition detection. Start and Stop condition detection is the only active circuitry in this mode. All other communication is done by the user software directly manipulating the SDA and SCL lines.

The following events will cause the MSSP Interrupt Flag (SSPxIF) bit to be set (MSSP interrupt, if enabled):

- · Start condition detected
- · Stop condition detected
- Data transfer byte transmitted/received
- · Acknowledge transmitted/received
- · Repeated Start generated



#### Important:

- The MSSP module, when configured in I<sup>2</sup>C Host mode, does not allow queuing of events. For
  instance, the user is not allowed to initiate a Start condition and immediately write the SSPxBUF
  register to initiate transmission before the Start condition is complete. In this case, SSPxBUF will
  not be written to and the Write Collision Detect (WCOL) bit will be set, indicating that a write to
  SSPxBUF did not occur.
- Host mode suspends Start/Stop detection when sending the Start/Stop condition by means of the SEN/PEN control bits. The SSPxIF bit is set at the end of the Start/Stop generation when hardware clears the control bit.

## 29.2.4.1 I<sup>2</sup>C Host Mode Operation

The host device generates all of the serial clock pulses and the Start and Stop conditions. A transfer is ended with a Stop condition or with a Repeated Start condition. Since the Repeated Start condition is also the beginning of the next serial transfer, the  $I^2C$  bus will not be released.

In Host Transmitter mode, serial data is output through SDA, while SCL outputs the serial clock. The first byte transmitted contains the client address of the receiving device (seven bits) and the  $R\overline{W}$  bit. In this case, the  $R\overline{W}$  bit will be logic '0'. Serial data is transmitted eight bits at a time. After each byte is transmitted, an Acknowledge bit is received. Start and Stop conditions are output to indicate the beginning and the end of a serial transfer.


In Host Receive mode, the first byte transmitted contains the client address of the transmitting device (seven bits) and the  $R/\overline{W}$  bit. In this case, the  $R/\overline{W}$  bit will be logic '1'. Thus, the first byte transmitted is a 7-bit client address followed by a '1' to indicate the receive bit. Serial data is received via SDA, while SCL outputs the serial clock. Serial data is received eight bits at a time. After each byte is received, an Acknowledge sequence is transmitted. Start and Stop conditions indicate the beginning and end of transmission.

A Baud Rate Generator is used to set the clock frequency output on SCL. See 29.3. Baud Rate Generator for more details.

## 29.2.4.1.1 Clock Arbitration

Clock arbitration occurs when the host, during any receive, transmit or Repeated Start/Stop condition, releases the SCL pin (SCL allowed to float high). When the SCL pin is allowed to float high, the Baud Rate Generator (BRG) is suspended from counting until the SCL pin is actually sampled high. When the SCL pin is sampled high, the Baud Rate Generator is reloaded with the contents of SSPxADD and begins counting. This ensures that the SCL high time will always be at least one BRG rollover count in the event that the clock is held low by an external device as shown in Figure 29-24.

Figure 29-24. Baud Rate Generator Timing with Clock Arbitration



## 29.2.4.1.2 WCOL Status Flag

If the user writes the SSPxBUF when a Start, Restart, Stop, Receive or Transmit sequence is in progress, the Write Collision Detect (WCOL) bit is set and the contents of the buffer are unchanged (the write does not occur). Any time the WCOL bit is set it indicates that an action on SSPxBUF was attempted while the module was not Idle.



**Important:** Because queuing of events is not allowed, writing to the lower five bits of SSPxCON2 is disabled until the Start condition is complete.

## 29.2.4.1.3 I<sup>2</sup>C Host Mode Start Condition Timing


To initiate a Start condition (see Figure 29-25), the user sets the Start Condition Enable (SEN) bit. If the SDA and SCL pins are sampled high, the Baud Rate Generator is reloaded with the contents of SSPxADD and starts its count. If SCL and SDA are both sampled high when the Baud Rate Generator times out ( $T_{BRG}$ ), the SDA pin is driven low. The action of the SDA being driven low while SCL is high is the Start condition and causes the Start (S) bit to be set. Following this, the Baud Rate Generator is reloaded with the contents of SSPxADD and resumes its count. When the Baud Rate Generator times out ( $T_{BRG}$ ), the SEN bit will be automatically cleared by hardware; the Baud Rate Generator is suspended, leaving the SDA line held low and the Start condition is complete.



### Important:

- 1. If at the beginning of the Start condition, the SDA and SCL pins are already sampled low, or if during the Start condition, the SCL line is sampled low before the SDA line is driven low, a bus collision occurs, the Bus Collision Interrupt Flag (BCLxIF) is set, the Start condition is aborted and the I<sup>2</sup>C module is reset into its Idle state.
- 2. The Philips I<sup>2</sup>C Specification states that a bus collision cannot occur on a Start.

Figure 29-25. First Start Bit Timing



# 29.2.4.1.4 I<sup>2</sup>C Host Mode Repeated Start Condition Timing


A Repeated Start condition (see Figure 29-26) occurs when the Repeated Start Condition Enable (RSEN) bit is programmed high and the host state machine is Idle. When the RSEN bit is set, the SCL pin is asserted low. When the SCL pin is sampled low, the Baud Rate Generator is loaded and begins counting. The SDA pin is released (brought high) for one Baud Rate Generator count ( $T_{BRG}$ ). When the Baud Rate Generator times out, if SDA is sampled high, the SCL pin will be deasserted (brought high). When SCL is sampled high, the Baud Rate Generator is reloaded and begins counting. SDA and SCL must remain high for one  $T_{BRG}$ . Module hardware then pulls the SDA line low (while SCL remains high) for one  $T_{BRG}$ , and then pulls the SCL line low. Following this, the RSEN bit will be automatically cleared and the Baud Rate Generator will not be reloaded, leaving the SDA pin held low. As soon as a Start condition is detected on the SDA and SCL pins, the S bit will be set. The SSPxIF bit will not be set until the Baud Rate Generator has timed out.



#### Important:

- 1. If RSEN is programmed while any other event is in progress, it will not take effect.
- 2. A bus collision during the Repeated Start condition occurs if:
  - SDA is sampled low when SCL goes from low-to-high.
  - SCL goes low before SDA is asserted low. This may indicate that another host is attempting to transmit a data '1'.


Figure 29-26. Repeated Start Condition Waveform



### 29.2.4.1.5 Acknowledge Sequence Timing

An Acknowledge sequence (see Figure 29-27) is enabled by setting the Acknowledge Sequence Enable (ACKEN) bit. When this bit is set, the SCL pin is pulled low and the contents of the Acknowledge Data (ACKDT) bit are presented on the SDA pin. If the user wishes to generate an Acknowledge, then the ACKDT bit must be cleared. If not, the user must set the ACKDT bit before starting an Acknowledge sequence. The Baud Rate Generator then counts for one rollover period ( $T_{BRG}$ ) and the SCL pin is deasserted (pulled high). When the SCL pin is sampled high (clock arbitration), the Baud Rate Generator counts for  $T_{BRG}$ . The SCL pin is then pulled low. Following this, the ACKEN bit is automatically cleared, the Baud Rate Generator is turned off and the MSSP module then goes into Idle mode.

Figure 29-27. Acknowledge Sequence Waveform



Note: TBRG = one Baud Rate Generator period.


### Acknowledge Write Collision

If the user writes the SSPxBUF when an Acknowledge sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).

# 29.2.4.1.6 Stop Condition Timing

A Stop condition (see Figure 29-28) is asserted on the SDA pin at the end of a receive/transmit by setting the Stop Condition Enable (PEN) bit. At the end of a receive/transmit, the SCL line is held low after the falling edge of the ninth clock. When the PEN bit is set, the host will assert the SDA line low. When the SDA line is sampled low, the Baud Rate Generator is reloaded and counts down to '0'. When the Baud Rate Generator times out, the SCL pin will be brought high and one  $T_{BRG}$  (Baud Rate Generator rollover count) later, the SDA pin will be deasserted. When the SDA pin is sampled high while SCL is high, the P bit is set. One  $T_{BRG}$  later, the PEN bit is cleared and the SSPxIF bit is set.

Figure 29-28. Stop Condition in Receive or Transmit Mode



### Write Collision on Stop

If the user writes the SSPxBUF when a Stop sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).

#### 29.2.4.1.7 Sleep Operation

While in Sleep mode, the I<sup>2</sup>C client module can receive addresses or data and when an address match or complete byte transfer occurs, wake the processor from Sleep (if the MSSP interrupt is enabled).

#### 29.2.4.1.8 Effects of a Reset

A Reset disables the MSSP module and terminates the current transfer.

#### 29.2.4.2 I<sup>2</sup>C Host Mode Transmission

Transmission of a data byte, a 7-bit address or the other half of a 10-bit address is accomplished by simply writing a value to the SSPxBUF register. This action will set the Buffer Full Status (BF) bit and allow the Baud Rate Generator to begin counting and start the next transmission.

Each bit of address/data will be shifted out onto the SDA pin after the falling edge of SCL is asserted. SCL is held low for one Baud Rate Generator rollover count ( $T_{BRG}$ ). Data must be valid before SCL is released high. When the SCL pin is released high, it is held that way for  $T_{BRG}$ . The data on the SDA pin must remain stable for that duration and some hold time after the next falling edge of SCL. After the eighth bit is shifted out (the falling edge of the eighth clock), the BF flag is cleared and the host releases SDA. This allows the client device being addressed to respond with an  $\overline{ACK}$  sequence during the ninth bit time if an address match occurred, or if data was received properly. The status of  $\overline{ACK}$  is written into the Acknowledge Status (ACKSTAT) bit on the rising edge of the ninth clock. If the host receives an  $\overline{ACK}$ , the ACKSTAT bit is cleared. If a NACK is received, ACKSTAT is set. After the ninth clock, the SSPxIF bit is set and the host clock (Baud Rate Generator) is suspended until the next data byte is loaded into the SSPxBUF, leaving SCL low and SDA unchanged (see Figure 29-29).

After the write to the SSPxBUF, each bit of the address will be shifted out on the falling edge of SCL until all seven address bits and the  $R/\overline{W}$  bit are completed. On the falling edge of the eighth clock, the host will release the SDA pin, allowing the client to respond with an  $\overline{ACK}$ . On the falling edge of the ninth clock, the host will sample the SDA pin to see if the address was recognized by a client. The status of the  $\overline{ACK}$  bit is loaded into the ACKSTAT bit.

Following the falling edge of the ninth clock transmission of the address, the SSPxIF is set, the BF flag is cleared and the Baud Rate Generator is turned off until another write to the SSPxBUF takes place, holding SCL low and allowing SDA to float.

#### 29.2.4.2.1 BF Status Flag

In Transmit mode, the Buffer Full Status (BF) bit is set when the CPU writes to SSPxBUF, and is cleared when all eight bits are shifted out.

#### 29.2.4.2.2 WCOL Status Flag

If the user writes the SSPxBUF when a transmit is already in progress (i.e., SSPSR is still shifting out a data byte), the Write Collision Detect (WCOL) bit is set and the contents of the buffer are unchanged (the write does not occur).

The WCOL bit must be cleared by software before the next transmission.

#### 29.2.4.2.3 ACKSTAT Status Flag

In Transmit mode, the Acknowledge Status (ACKSTAT) bit is cleared when the client has sent an Acknowledge (ACK = 0), and is set when the client issues a NACK. A client sends an ACK when it has recognized its address (including a General Call), or when the client has properly received its data.

#### 29.2.4.2.4 Typical Transmit Sequence

- 1. The Host generates a Start condition by setting the SEN bit.
- 2. SSPxIF is set by hardware on completion of the Start.
- 3. SSPxIF is cleared by software.
- 4. The MSSP module will wait the required start time before any other operation takes place.
- 5. Software loads the SSPxBUF with the client address and the R/W bit. In Host Transmit mode, the R/W value is zero.
- Address is shifted out the SDA pin until all eight bits are transmitted. Transmission begins as soon as SSPxBUF is written to.
- 7. The MSSP module shifts in the ACK value from the client device and writes its into the ACKSTAT bit.
- 8. The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPxIF bit.
- 9. Software loads the SSPxBUF with eight bits of data.
- 10. Data is shifted out the SDA pin until all eight bits are transmitted.
- 11. The MSSP module shifts in the ACK bit from the client device and writes its value into the ACKSTAT bit.
- 12. Steps 8-11 are repeated for all transmitted data bytes.
- 13. The user generates a Stop or Restart condition by setting the PEN or RSEN bits, respectively. An Interrupt is generated once the Stop/Restart condition is complete.

Figure 29-29. I<sup>2</sup>C Host Mode Waveform (Transmission, 7-Bit Address)





Figure 29-30. I<sup>2</sup>C Host Mode Waveform (Transmission, 10-Bit Address)



# 29.2.4.3 I<sup>2</sup>C Host Mode Reception

Host mode reception (see Figure 29-31) is enabled by setting the Receive Enable (RCEN) bit.



**Important:** The MSSP module must be in an Idle state before the RCEN bit is set or the RCEN bit will be disregarded.

The Baud Rate Generator begins counting and on each rollover, the state of the SCL pin changes (high-to-low/low-to-high) and data is shifted into the SSPxSR. After the falling edge of the eighth clock all the following events occur:

- · RCEN is automatically cleared by hardware.
- The contents of the SSPxSR are loaded into the SSPxBUF.
- · The BF flag bit is set.
- The SSPxIF flag bit is set.
- The Baud Rate Generator is suspended from counting.
- · The SCL pin is held low.

The MSSP is now in Idle state awaiting the next command. When the buffer is read by the CPU, the BF flag bit is automatically cleared. The Host can then send an Acknowledge sequence at the end of reception by setting the Acknowledge Sequence Enable (ACKEN) bit.

### 29.2.4.3.1 BF Status Flag

In receive operation, the BF bit is set when an address or data byte is loaded into SSPxBUF from SSPSR. It is cleared when the SSPxBUF register is read.

### 29.2.4.3.2 SSPOV Status Flag

In receive operation, the SSPOV bit is set when eight bits are received into SSPxSR while the BF flag bit is already set from a previous reception.

## 29.2.4.3.3 WCOL Status Flag

If the user writes the SSPxBUF when a receive is already in progress (i.e., SSPxSR is still shifting in a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write does not occur).

### 29.2.4.3.4 Typical Receive Sequence

- 1. The Host generates a Start condition by setting the SEN bit.
- 2. SSPxIF is set by hardware on completion of the Start.
- 3. SSPxIF is cleared by software.
- 4. Software writes SSPxBUF with the client address to transmit and the R/W bit set.
- Address is shifted out the SDA pin until all eight bits are transmitted. Transmission begins as soon as SSPxBUF is written to.
- 6. The MSSP module shifts in the ACK value from the client device and writes it into the ACKSTAT bit.
- 7. The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPxIF bit.
- 8. Software sets the RCEN bit and the host clocks in a byte from the client.
- 9. After the eighth falling edge of SCL, SSPxIF and BF are set.
- 10. Host clears SSPxIF and reads the received byte from SSPxBUF, which clears BF.
- 11. Host clears the ACKDT bit and initiates the ACK sequence by setting the ACKEN bit.
- 12. Host's ACK is clocked out to the client and SSPxIF is set.
- 13. User clears SSPxIF.
- 14. Steps 8-13 are repeated for each received byte from the client.
- 15. Host sends a NACK or Stop to end communication.





Figure 29-31. I<sup>2</sup>C Host Mode Waveform (Reception, 7-Bit Address)

Figure 29-32. I<sup>2</sup>C Host Mode Waveform (Reception, 10-Bit Address)



### 29.2.5 Multi-Host Mode

In Multi-Host mode, the interrupt generation on the detection of the Start and Stop conditions allows the determination of when the bus is free. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the  $I^2C$  bus may be taken when the P bit is set, or the bus is Idle, with both the S and P bits cleared. When the bus is busy, enabling the MSSP interrupt will generate an interrupt when the Stop condition occurs.

In Multi-Host operation, the SDA line must be monitored for arbitration to see if the signal level is the expected output level. This check is performed by hardware with the result placed in the BCLxIF bit.

The states where arbitration can be lost are:

- · Address Transfer
- Data Transfer
- A Start Condition
- A Repeated Start Condition
- · An Acknowledge Condition

#### 29.2.5.1 Multi-Host Communication. Bus Collision and Bus Arbitration

Multi-Host mode support is achieved by bus arbitration. When the host outputs address/data bits onto the SDA pin, arbitration takes place when the host outputs a '1' on SDA, by letting SDA float high and another host asserts a '0'. When the SCL pin floats high, data may be stable. If the expected data on SDA is a '1' and the data sampled on the SDA pin is '0', then a bus collision has taken place. The host will set the Bus Collision Interrupt Flag (BCLxIF) and reset the I<sup>2</sup>C port to its Idle state (see Figure 29-33).

If a transmit was in progress when the bus collision occurred, the transmission is halted, the BF flag is cleared, the SDA and SCL lines are deasserted, and the SSPxBUF can be written to. When software services the bus collision Interrupt Service Routine, and if the  $I^2C$  bus is free, software can resume communication by asserting a Start condition.


If a Start, Repeated Start, Stop or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDA and SCL lines are deasserted, and the respective control bits in the SSPxCON2 register are cleared. When software services the bus collision Interrupt Service Routine, and if the I<sup>2</sup>C bus is free, software can resume communication by asserting a Start condition.

The host will continue to monitor the SDA and SCL pins. If a Stop condition occurs, the SSPxIF bit will be set.

A write to the SSPxBUF will start the transmission of data at the first data bit, regardless of where the transmitter left off when the bus collision occurred.

In Multi-Host mode, the interrupt generation on the detection of Start and Stop conditions allows the determination of when the bus is free. Control of the I<sup>2</sup>C bus can be taken when the P bit is set, or the bus is Idle and the S and P bits are cleared.

Figure 29-33. Bus Collision Timing for Transmit and Acknowledge



# 29.2.5.1.1 Bus Collision During a Start Condition


During a Start condition, a bus collision occurs if:


- 1. SDA or SCL are sampled low at the beginning of the Start condition (see Figure 29-34).
- 2. SCL is sampled low before SDA is asserted low (see Figure 29-35).

During a Start condition, both the SDA and the SCL pins are monitored.

If the SDA pin is already low, or the SCL pin is already low, then all of the following occur:


- the Start condition is aborted,
- the BCLxIF flag is set and
- the MSSP module is reset to its Idle state (see Figure 29-34).





The Start condition begins with the SDA and SCL pins deasserted. When the SDA pin is sampled high, the Baud Rate Generator is loaded and counts down. If the SCL pin is sampled low while SDA is high, a bus collision occurs because it is assumed that another host is attempting to drive a data '1' during the Start condition.


Figure 29-35. Bus Collision During Start Condition (SCL = 0)



If the SDA pin is sampled low during this count, the BRG is reset and the SDA line is asserted early (see Figure 29-36). If, however, a '1' is sampled on the SDA pin, the SDA pin is asserted low at the end of the BRG count. The

Baud Rate Generator is then reloaded and counts down to zero; if the SCL pin is sampled as '0' during this time, a bus collision does not occur. At the end of the BRG count, the SCL pin is asserted low.

Figure 29-36. BRG Reset Due to SDA Arbitration During Start Condition





**Important:** The reason that a bus collision is not a factor during a Start condition is that no two bus hosts can assert a Start condition at the exact same time. Therefore, one host will always assert SDA before the other. This condition does not cause a bus collision because the two hosts must be allowed to arbitrate the first address following the Start condition. If the address is the same, arbitration must be allowed to continue into the data portion, Repeated Start or Stop conditions.

# 29.2.5.1.2 Bus Collision During a Repeated Start Condition

During a Repeated Start condition, a bus collision occurs if:

- 1. A low level is sampled on SDA when SCL goes from low level to high level (see Figure 29-37).
- 2. SCL goes low before SDA is asserted low, indicating that another host is attempting to transmit a data '1' (see Figure 29-38).

When the user releases SDA and the pin is allowed to float high, the BRG is loaded with SSPxADD and counts down to zero. The SCL pin is then deasserted and when sampled high, the SDA pin is sampled.

If SDA is low, a bus collision has occurred (i.e., another host is attempting to transmit a data '0', see Figure 29-37). If SDA is sampled high, the BRG is reloaded and begins counting. If SDA goes from high-to-low before the BRG times out, no bus collision occurs because no two hosts can assert SDA at exactly the same time.





Figure 29-37. Bus Collision During a Repeated Start Condition (Case 1)

If SCL goes from high-to-low before the BRG times out and SDA has not already been asserted, a bus collision occurs. In this case, another host is attempting to transmit a data '1' during the Repeated Start condition (see Figure 29-38).

If, at the end of the BRG time-out, both SCL and SDA are still high, the SDA pin is driven low and the BRG is reloaded and begins counting. At the end of the count, regardless of the status of the SCL pin, the SCL pin is driven low and the Repeated Start condition is complete.

Figure 29-38. Bus Collision During Repeated Start Condition (Case 2)



#### 29.2.5.1.3 Bus Collision During a Stop Condition

Bus collision occurs during a Stop condition if:


- After the SDA pin has been deasserted and allowed to float high, SDA is sampled low after the BRG has timed out (see Figure 29-39).
- 2. After the SCL pin is deasserted, SCL is sampled low before SDA goes high (see Figure 29-40).

The Stop condition begins with SDA asserted low. When SDA is sampled low, the SCL pin is allowed to float. When the pin is sampled high (clock arbitration), the Baud Rate Generator is loaded with SSPxADD and counts down to zero. After the BRG times out, SDA is sampled. If SDA is sampled low, a bus collision has occurred. This is due to another host attempting to drive a data '0' (see Figure 29-39). If the SCL pin is sampled low before SDA is allowed to float high, a bus collision occurs. This is another case of another host attempting to drive a data '0' (Figure 29-40).

Figure 29-39. Bus Collision During a Stop Condition (Case 1)



Figure 29-40. Bus Collision During a Stop Condition (Case 2)



## 29.3 Baud Rate Generator

The MSSP module has a Baud Rate Generator (BRG) available for clock generation in both I<sup>2</sup>C and SPI Host modes. The BRG reload value is placed in the SSPxADD register. When a write occurs to SSPxBUF, the BRG will automatically begin counting down. Example 29-1 shows how the value for SSPxADD is calculated.

Once the given operation is complete, the internal clock will automatically stop counting and the clock pin will remain in its last state.

An internal Reload signal, shown in Figure 29-41, triggers the value from SSPxADD to be loaded into the BRG counter. This occurs twice for each oscillation of the module clock line.

Table 29-2 illustrates clock rates based on instruction cycles and the BRG value loaded into SSPxADD.

Example 29-1. MSSP Baud Rate Generator Frequency Equation 
$$F_{CLOCK} = \frac{F_{OSC}}{4 \times (SSPxADD + 1)}$$

Figure 29-41. Baud Rate Generator Block Diagram

SSPM[3:0] SSPxADD[7:0]

SSPM[3:0] Reload Reload Control

SSPCLK BRG Down Counter Fosc/2



**Important:** Values of  $0 \times 00$ ,  $0 \times 01$  and  $0 \times 02$  are not valid for SSPxADD when used as a Baud Rate Generator for  $I^2C$ . This is an implementation limitation.

Table 29-2. MSSP Clock Rate w/BRG

Fosc	F <sub>CY</sub>	BRG Value	F <sub>CLOCK</sub> (2 Rollovers of BRG)
32 MHz	8 MHz	13h	400 kHz
32 MHz	8 MHz	19h	308 kHz
32 MHz	8 MHz	4Fh	100 kHz
16 MHz	4 MHz	09h	400 kHz
16 MHz	4 MHz	0Ch	308 kHz
16 MHz	4 MHz	27h	100 kHz
4 MHz	1 MHz	09h	100 kHz

**Note:** Refer to the I/O port electrical specifications in the "**Electrical Specifications**" chapter, Internal Oscillator Parameters, to ensure the system is designed to support all requirements.

# 29.4 Register Definitions: MSSP Control

# 29.4.1 SSPxBUF

Name: SSPxBUF Offset: 0x068C,0x0696

MSSP Data Buffer Register

Bit	7	6	5	4	3	2	1	0
[				BUF	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	X	x	x	x	X	x	X	X

Bits 7:0 - BUF[7:0] MSSP Input and Output Data Buffer bits

# 29.4.2 SSPxADD

Name: SSPxADD Offset: 0x068D,0x0697

MSSP Baud Rate Divider and Address Register

Bit	7	6	5	4	3	2	1	0
				ADD	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bits 7:0 - ADD[7:0]

- SPI and I<sup>2</sup>C Host: Baud rate divider
- I<sup>2</sup>C Client: Address bits

Value	Mode	Description
11111111	SPI and I <sup>2</sup> C Host	Baud rate divider. SCK/SCL pin clock period = ((n + 1) * 4)/F <sub>OSC</sub> . Values
_		less than 3 are not valid.
00000011		
xxxxx11x	I <sup>2</sup> C 10-bit Client MS	Bits [7:3] and Bit 0 are not used and are don't care. Bits [2:1] are bits [9:8]
-	Address	of the 10-bit Client Most Significant Address.
xxxxx00x		
11111111	I <sup>2</sup> C 10-bit Client LS	Bits [7:0] of 10-bit Client Least Significant Address
_	Address	
00000000		
11111111x	I <sup>2</sup> C 7-bit Client	Bit 0 is not used and is don't care. Bits [7:1] are the 7-bit Client Address.
-		
0000000x		

# 29.4.3 SSPxMSK

Name: SSPxMSK Offset: 0x068E,0x0698

MSSP Address Mask Register

Bit	7	6	5	4	3	2	1	0
				MSK[6:0]				MSK0
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1

# Bits 7:1 - MSK[6:0] Mask bits

Value		Description
1	I <sup>2</sup> C Client	The received address bit n is compared to SSPxADD bit n to detect I <sup>2</sup> C address match
0	I <sup>2</sup> C Client	The received address bit n is not used to detect I <sup>2</sup> C address match

#### Bit 0 - MSK0

Mask bit for I<sup>2</sup>C 10-bit Client mode

Value	Mode	Description
X	SPI or I <sup>2</sup> C 7-bit	This bit is not used
1	I <sup>2</sup> C 10-bit Client	The received address bit 0 is compared to SSPxADD bit 0 to detect I <sup>2</sup> C address match
0	I <sup>2</sup> C 10-bit Client	The received address bit 0 is not used to detect I <sup>2</sup> C address match

# 29.4.4 SSPxSTAT

Name: SSPxSTAT 0x068F,0x0699

MSSP Status Register

Bit	7	6	5	4	3	2	1	0
	SMP	CKE	D/Ā	Р	S	R/W	UA	BF
Access	R/W	R/W	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0

# Bit 7 - SMP Slew Rate Control bit

Value	Mode	Description
1	SPI Host	Input data is sampled at the end of data output time
0	SPI Host	Input data is sampled at the middle of data output time
0	SPI Client	Bit must be cleared in SPI Client mode
1	I <sup>2</sup> C	Slew rate control is disabled for Standard Speed mode (100 kHz and 1 MHz)
0	I <sup>2</sup> C	Slew rate control is enabled for High Speed mode (400 kHz)

# Bit 6 - CKE SPI: Clock Select bit<sup>(4)</sup>; I<sup>2</sup>C: SMBus Select bit

Value	Mode	Description
1	SPI	Transmit occurs on the transition from Active to Idle clock state
0	SPI	Transmit occurs on the transition from Idle to Active clock state
1	I <sup>2</sup> C	Enables SMBus-specific inputs
0	I <sup>2</sup> C	Disables SMBus-specific inputs

# Bit 5 - D/A Data/Address bit

Value	Mode	Description
Х	SPI or I <sup>2</sup> C Host	This bit is not used
1	I <sup>2</sup> C Client	Indicates that the last byte received or transmitted was data
0	I <sup>2</sup> C Client	Indicates that the last byte received or transmitted was address

# Bit 4 - P Stop bit(1)

Value	Mode	Description
X	SPI	This bit is not used
1	I <sup>2</sup> C	Stop bit was detected last
0	I <sup>2</sup> C	Stop bit was not detected last

# Bit 3 - S Start bit(1)

Value	Mode	Description
X	SPI	This bit is not used
1	I <sup>2</sup> C	Start bit was detected last
0	I <sup>2</sup> C	Start bit was not detected last

# Bit 2 - R/W Read/Write Information bit(2,3)

Value	Mode	Description
Х	SPI	This bit is not used
1	I <sup>2</sup> C Client	Read
0	I <sup>2</sup> C Client	Write
1	I <sup>2</sup> C Host	Transmit is in progress
0	I <sup>2</sup> C Host	Transmit is not in progress

# Bit 1 – UA Update Address bit (10-bit I<sup>2</sup>C Client mode only)

Value	Mode	Description	
X	All other modes	This bit is not used	

Value	Mode	Description
1	I <sup>2</sup> C 10-bit Client	Indicates that the user needs to update the address in the SSPxADD register
0	I <sup>2</sup> C 10-bit Client	Address does not need to be updated

# Bit 0 - BF Buffer Full Status bit(5)

Value	Mode	Description
1	I <sup>2</sup> C Transmit	Transmit in progress, SSPxBUF is full
0	I <sup>2</sup> C Transmit	Transmit complete; SSPxBUF is empty
1	SPI and I <sup>2</sup> C Receive	Receive complete, SSPxBUF is full
0	SPI and I <sup>2</sup> C Receive	Receive not complete, SSPxBUF is empty

#### Notes:

- 1. This bit is cleared on Reset and when SSPEN is cleared.
- 2. In I<sup>2</sup>C Client mode, this bit holds the R/W bit information following the last address match. This bit is only valid from the address match to the next Start bit, Stop bit or not ACK bit.
- 3. ORing this bit with SEN, RSEN, PEN, RCEN or ACKEN will indicate if the MSSP is in Active mode.
- 4. Polarity of clock state is set by the CKP bit.
- 5. I<sup>2</sup>C receive status does not include ACK and Stop bits.

# 29.4.5 SSPxCON1

**Name:** SSPxCON1 **Offset:** 0x0690,0x069A

MSSP Control Register 1

Bit	7	6	5	4	3	2	1	0
	WCOL	SSPOV	SSPEN	CKP		SSPN	<b>Л</b> [3:0]	
Access	R/W/HS	R/W/HS	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

### Bit 7 - WCOL

Write Collision Detect bit

Value	Mode	Description
X	Host or Client receive	This bit is not used
1	SPI or I <sup>2</sup> C Host or Client transmit	The SSPxBUF register is written while it is still transmitting the
		previous word (must be cleared in software)
0	SPI or I <sup>2</sup> C Host or Client transmit	No collision

# Bit 6 - SSPOV

Receive Overflow Indicator bit(1)

Value	Mode	Description
Х	SPI Host or I <sup>2</sup> C Host transmit	This bit is not used
1	SPI Client	A byte is received while the SSPxBUF register is still holding the previous byte. Data contained in the shift register will be discarded. The user must read SSPxBUF, even if only transmitting data, to avoid setting overflow (must be cleared in software).
1	I <sup>2</sup> C Receive	A byte is received while the SSPxBUF register is still holding the previous byte (must be cleared in software)
0	SPI Client or I <sup>2</sup> C Receive	No overflow

#### Bit 5 - SSPEN

Host Synchronous Serial Port Enable bit.(2)

Valu	ıe	Description
1		Enables the serial port
0		Disables serial port and configures these pins as I/O PORT pins

### Bit 4 - CKP

SCK Release Control bit

Value	Mode	Description
X	I <sup>2</sup> C Host	This bit is not used
1	SPI	Idle state for the clock is a high level
0	SPI	Idle state for the clock is a low level
1	I <sup>2</sup> C Client	Releases clock
0	I <sup>2</sup> C Client	Holds clock low (clock stretch), used to ensure data setup time

# Bits 3:0 - SSPM[3:0]

Host Synchronous Serial Port Mode Select bits<sup>(4)</sup>

Value	Description
1111	I <sup>2</sup> C Client mode: 10-bit address with Start and Stop bit interrupts enabled
1110	I <sup>2</sup> C Client mode: 7-bit address with Start and Stop bit interrupts enabled
1101	Reserved - do not use
1100	Reserved - do not use
1011	I <sup>2</sup> C Firmware Controlled Host mode (client Idle)

Value	Description
1010	SPI Host mode: Clock = F <sub>OSC</sub> /(4*(SSPxADD+1)). SSPxADD must be greater than 0. <sup>(3)</sup>
1001	Reserved - do not use
1000	I <sup>2</sup> C Host mode: Clock = F <sub>OSC</sub> /(4 * (SSPxADD + 1))
0111	I <sup>2</sup> C Client mode: 10-bit address
0110	I <sup>2</sup> C Client mode: 7-bit address
0101	SPI Client mode: Clock = SCKx pin. SSx pin control is disabled
0100	SPI Client mode: Clock = SCKx pin. SSx pin control is enabled
0011	SPI Host mode: Clock = TMR2 output/2
0010	SPI Host mode: Clock = F <sub>OSC</sub> /64
0001	SPI Host mode: Clock = F <sub>OSC</sub> /16
0000	SPI Host mode: Clock = F <sub>OSC</sub> /4

### Notes:

- 1. In Host mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPxBUF register.
- 2. When enabled, these pins must be properly configured as inputs or outputs.
- 3. SSPxADD = 0 is not supported.
- 4. Bit combinations not specifically listed here are either reserved or implemented in I<sup>2</sup>C mode only.

### 29,4,6 SSPxCON2

 Name:
 SSPxCON2

 Offset:
 0x0691,0x069B

MSSP Control Register 2

Control Register for I<sup>2</sup>C Operation Only

Bit	7	6	5	4	3	2	1	0
	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN
Access	R/W	R/W/HC	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - GCEN

General Call Enable bit (Client mode only)

Value	Mode	Description
X	Host mode	Don't care
1	Client mode	General Call is enabled
0	Client mode	General Call is not enabled

### Bit 6 – ACKSTAT Acknowledge Status bit (Host Transmit mode only)

Value	Description
1	Acknowledge was not received from client
0	Acknowledge was received from client

### Bit 5 - ACKDT

Acknowledge Data bit (Host Receive mode only)(1)

Value	Description		
1	Not Acknowledge		
0	Acknowledge		

### Bit 4 - ACKEN

Acknowledge Sequence Enable bit(2)

ACKITOWIC	Acknowledge dequence Enable bit.				
Value	Description				
1	Initiates Acknowledge sequence on SDAx and SCLx pins and transmits ACKDT data bit;				
	automatically cleared by hardware				
0	Acknowledge sequence is Idle				

### Bit 3 - RCEN

Receive Enable bit (Host Receive mode only)(2)

Value	Description
1	Enables Receive mode for I <sup>2</sup> C
0	Receive is Idle

# Bit 2 – PEN

Stop Condition Enable bit (Host mode only)(2)

	Value	Description
	1	Initiates Stop condition on SDAx and SCLx pins; automatically cleared by hardware
Ì	0	Stop condition is Idle

### Bit 1 - RSEN

Repeated Start Condition Enable bit (Host mode only)(2)

Value	Description
1	Initiates Repeated Start condition on SDAx and SCLx pins; automatically cleared by hardware
0	Repeated Start condition is Idle

# **MSSP - Host Synchronous Serial Port Module**

# Bit 0 - SEN

Start Condition Enable bit(2)

Value	Mode	Description
1	Host	Initiates Start condition on SDAx and SCLx pins; automatically cleared by hardware
0	Host	Start condition is Idle
1	Client	Clock stretching is enabled
0	Client	Clock stretching is disabled

#### Notes:

- 1. The value that will be transmitted when the user initiates an Acknowledge sequence at the end of a receive.
- 2. If the I<sup>2</sup>C module is active, these bits may not be set (no spooling) and the SSPxBUF may not be written (or writes to the SSPxBUF are disabled).

# 29.4.7 SSPxCON3

 Name:
 SSPxCON3

 Offset:
 0x0692,0x069C

MSSP Control Register 3

Bit	7	6	5	4	3	2	1	0
	ACKTIM	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN
Access	R/HS/HC	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

# Bit 7 - ACKTIM

Acknowledge Time Status bit

	neumentouge rime etaitae an					
Value	Mode	Description				
X	SPI or I <sup>2</sup> C Host	This bit is not used				
1	I <sup>2</sup> C Client and AHEN = 1 or DHEN = 1	Eighth falling edge of SCL has occurred and the ACK/NACK state is Active				
0	I <sup>2</sup> C Client	ACK/NACK state is not Active. Transitions low on ninth rising edge of SCL.				

### Bit 6 - PCIE

Stop Condition Interrupt Enable bit

Value	Mode	Description
X	SPI or SSPM = 1111 or 1110	This bit is not used
1	SSPM ≠ 1111 and SSPM ≠ 1110	Enable interrupt on detection of Stop condition
0	SSPM ≠ 1111 and SSPM ≠ 1110	Stop detection interrupts are disabled

### Bit 5 - SCIE Start Condition Interrupt Enable bit

Value	Mode	Description
X	SPI or SSPM = 1111 or 1110	This bit is not used
1	SSPM ≠ 1111 and SSPM ≠ 1110	Enable interrupt on detection of Start condition
0	SSPM ≠ 1111 and SSPM ≠ 1110	Start detection interrupts are disabled

### Bit 4 – BOEN

Buffer Overwrite Enable bit(1)

Value	Mode	Description
1	SPI	SSPxBUF is updated every time a new data byte is available, ignoring the BF bit
0	SPI	If a new byte is receive with BF set then SSPOV is set and SSPxBUF is not updated
1	I <sup>2</sup> C	SSPxBUF is updated every time a new data byte is available, ignoring the SSPOV effect on updating the buffer
0	I <sup>2</sup> C	SSPxBUF is only updated when SSPOV is clear

# Bit 3 - SDAHT SDA Hold Time Selection bit

Value	Mode	Description
X	SPI	Not used in SPI mode
1	I <sup>2</sup> C	Minimum of 300 ns hold time on SDA after the falling edge of SCL
0	I <sup>2</sup> C	Minimum of 100 ns hold time on SDA after the falling edge of SCL

# Bit 2 - SBCDE Client Mode Bus Collision Detect Enable bit

Unused in Host mode.

011400411		
Value	Mode	Description
X	SPI or I <sup>2</sup> C Host	This bit is not used
1	I <sup>2</sup> C Client	Bus Collision detection is enabled
0	I <sup>2</sup> C Client	Bus Collision detection is not enabled

# **MSSP - Host Synchronous Serial Port Module**

# Bit 1 - AHEN Address Hold Enable bit

Value	Mode	Description
Х	SPI or I <sup>2</sup> C Host	This bit is not used
1	I <sup>2</sup> C Client	Address hold is enabled. As a result, CKP is cleared after the eighth falling SCL edge of an address byte reception. Software must set the CKP bit to resume operation.
0	I <sup>2</sup> C Client	Address hold is not enabled

### Bit 0 - DHEN Data Hold Enable bit

Value	Mode	Description
x	SPI or I <sup>2</sup> C Host	This bit is not used
1	I <sup>2</sup> C Client	Data hold is enabled. As a result, CKP is cleared after the eighth falling SCL edge of a data byte reception. Software must set the CKP bit to resume operation.
0	I <sup>2</sup> C Client	Data hold is not enabled

#### Note:

1. For daisy-chained SPI operation; allows the user to ignore all except the last received byte. SSPOV is still set when a new byte is received and BF = 1, but hardware continues to write the most recent byte to SSPxBUF.

# 29.5 Register Summary - MSSP Control

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
 0x068B	Reserved									
0x068C	SSP1BUF	7:0				BUF	[7:0]			
0x068D	SSP1ADD	7:0					0[7:0]			
0x068E	SSP1MSK	7:0				MSK[6:0]				MSK0
0x068F	SSP1STAT	7:0	SMP	CKE	D/Ā	Р	s	R/W	UA	BF
0x0690	SSP1CON1	7:0	WCOL	SSPOV	SSPEN	CKP		SSPI	M[3:0]	Į.
0x0691	SSP1CON2	7:0	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN
0x0692	SSP1CON3	7:0	ACKTIM	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN
0x0693										
	Reserved									
0x0695										
0x0696	SSP2BUF	7:0				BUF	[7:0]			
0x0697	SSP2ADD	7:0				ADD	[7:0]			
0x0698	SSP2MSK	7:0				MSK[6:0]				MSK0
0x0699	SSP2STAT	7:0	SMP	CKE	D/Ā	Р	S	R/W	UA	BF
0x069A	SSP2CON1	7:0	WCOL	SSPOV	SSPEN	CKP		SSPI	M[3:0]	
0x069B	SSP2CON2	7:0	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN
0x069C	SSP2CON3	7:0	ACKTIM	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN

# 30. EUSART - Enhanced Universal Synchronous Asynchronous Receiver Transmitter

The Enhanced Universal Synchronous Asynchronous Receiver Transmitter (EUSART) module is a serial I/O communications peripheral. It contains all the clock generators, shift registers and data buffers necessary to perform an input or output serial data transfer independent of device program execution. The EUSART, also known as a Serial Communications Interface (SCI), can be configured as a full-duplex asynchronous system or half-duplex synchronous system.

Full Duplex mode is useful for communications with peripheral systems, such as CRT terminals and personal computers. Half Duplex Synchronous mode is intended for communications with peripheral devices, such as A/D or D/A integrated circuits, serial EEPROMs or other microcontrollers. These devices typically do not have internal clocks for baud rate generation and require the external clock signal provided by a host synchronous device.

The EUSART module includes the following capabilities:

- Full-duplex asynchronous transmit and receive
- · Two-character input buffer
- · One-character output buffer
- Programmable 8-bit or 9-bit character length
- · Address detection in 9-bit mode
- · Input buffer overrun error detection
- · Received character framing error detection
- Half-duplex synchronous host
- Half-duplex synchronous client
- · Programmable clock polarity in Synchronous modes
- Sleep operation

The EUSART module implements the following additional features, making it ideally suited for use in Local Interconnect Network (LIN) bus systems:

- · Automatic detection and calibration of the baud rate
- Wake-up on Break reception
- · 13-bit Break character transmit

Block diagrams of the EUSART transmitter and receiver are shown in Figure 30-1 and Figure 30-2.


The operation of the EUSART module consists of six registers:

- · Transmit Status and Control (TXxSTA)
- · Receive Status and Control (RCxSTA)
- Baud Rate Control (BAUDxCON)
- · Baud Rate Value (SPxBRG)
- Receive Data Register (RCxREG)
- Transmit Data Register (TXxREG)

The RXx/DTx and TXx/CKx input pins are selected with the RXxPPS and TXxPPS registers, respectively. TXx, CKx, and DTx output pins are selected with each pin's RxyPPS register. Since the RX input is coupled with the DT output in Synchronous mode, it is the user's responsibility to select the same pin for both of these functions when operating in Synchronous mode. The EUSART control logic will control the data direction drivers automatically.

Figure 30-1. EUSART Transmit Block Diagram


Rev. 10-000 113C 2/15/201 7



**Notes:** 1. In Synchronous mode, the DT output and RX input PPS selections will enable the same pin.

<sup>2.</sup> In Host Synchronous mode, the TX output and CK input PPS selections will enable the same pin.

Figure 30-2. EUSART Receive Block Diagram



Notes: 1. In Synchronous mode, the DT output and RX input PPS selections will enable the same pin.

2. In Host Synchronous mode, the TX output and CK input PPS selections will enable the same pin.

# 30.1 EUSART Asynchronous Mode

The EUSART transmits and receives data using the standard non-return-to-zero (NRZ) format. NRZ is implemented with two levels: a  $V_{OH}$  Mark state which represents a '1' data bit, and a  $V_{OL}$  Space state which represents a '0' data bit. NRZ refers to the fact that consecutively transmitted data bits of the same value stay at the output level of that bit without returning to a neutral level between each bit transmission. An NRZ transmission port idles in the Mark state. Each character transmission consists of one Start bit followed by eight or nine data bits and is always terminated by one or more Stop bits. The Start bit is always a space and the Stop bits are always marks. The most common data format is eight bits. Each transmitted bit persists for a period of 1/(Baud Rate). An on-chip dedicated 8-bit/16-bit Baud Rate Generator is used to derive standard baud rate frequencies from the system oscillator. See Table 30-2 for examples of baud rate configurations.

The EUSART transmits and receives the LSb first. The EUSART's transmitter and receiver are functionally independent, but share the same data format and baud rate. Parity is not supported by the hardware, but can be implemented in software and stored as the ninth data bit.

# 30.1.1 EUSART Asynchronous Transmitter

Figure 30-1 is a simplified representation of the transmitter. The heart of the transmitter is the serial Transmit Shift Register (TSR), which is not directly accessible by software. The TSR obtains its data from the transmit buffer, which is the TXxREG register.

### 30.1.1.1 Enabling the Transmitter

The EUSART transmitter is enabled for asynchronous operations by configuring the following three control bits:

- The Transmit Enable (TXEN) bit is set to '1' to enable the transmitter circuitry of the EUSART
- The EUSART Mode Select (SYNC) bit is set to '0' to configure the EUSART for asynchronous operation

• The Serial Port Enable (SPEN) bit is set to '1' to enable the EUSART interface and to enable automatically the output drivers for the RxyPPS selected as the TXx/CKx output

All other EUSART control bits are assumed to be in their default state.

If the TXx/CKx pin is shared with an analog peripheral, the analog I/O function must be disabled by clearing the corresponding ANSEL bit.



**Important:** The TXxIF Transmitter Interrupt Flag in the PIRx register is set when the TXEN enable bit is set and the Transmit Shift Register (TSR) is Idle.

### 30.1.1.2 Transmitting Data

A transmission is initiated by writing a character to the TXxREG register. If this is the first character, or the previous character has been completely flushed from the TSR, the data in the TXxREG is immediately transferred to the TSR register. If the TSR still contains all or part of a previous character, the new character data is held in the TXxREG until the Stop bit of the previous character has been transmitted. The pending character in the TXxREG is then transferred to the TSR in one  $T_{CY}$  immediately following the Stop bit transmission. The transmission of the Start bit, data bits and Stop bit sequence commences immediately following the transfer of the data to the TSR from the TXxREG.

### 30.1.1.3 Transmit Data Polarity

The polarity of the transmit data can be controlled with the Clock/Transmit Polarity Select (SCKP) bit. The default state of this bit is '0', which selects high true transmit Idle and data bits. Setting the SCKP bit to '1' will invert the transmit data resulting in low true Idle and data bits. The SCKP bit controls transmit data polarity in Asynchronous mode only. In Synchronous mode, the SCKP bit has a different function. See 30.4.1.2. Clock Polarity for more details.

# 30.1.1.4 Transmit Interrupt Flag

The EUSART Transmit Interrupt Flag (TXxIF) bit of the PIRx register is set whenever the EUSART transmitter is enabled and no character is being held for transmission in the TXxREG. In other words, the TXxIF bit is only cleared when the TSR is busy with a character and a new character has been queued for transmission in the TXxREG. The TXxIF flag bit is not cleared immediately upon writing TXxREG. TXxIF becomes valid in the second instruction cycle following the write execution. Polling TXxIF immediately following the TXxREG write will return invalid results. The TXxIF bit is read-only, it cannot be set or cleared by software.

The TXxIF interrupt can be enabled by setting the EUSART Transmit Interrupt Enable (TXxIE) bit of the PIEx register. However, the TXxIF flag bit will be set whenever the TXxREG is empty, regardless of the state of TXxIE enable bit.

To use interrupts when transmitting data, set the TXxIE bit only when there is more data to send. Clear the TXxIE interrupt enable bit upon writing the last character of the transmission to the TXxREG.

# 30.1.1.5 TSR Status

The Transmit Shift Register Status (TRMT) bit indicates the status of the TSR register. This is a read-only bit. The TRMT bit is set when the TSR register is empty and is cleared when a character is transferred to the TSR register from the TXxREG. The TRMT bit remains clear until all bits have been shifted out of the TSR register. No interrupt logic is tied to this bit, so the user needs to poll this bit to determine the TSR status.



Important: The TSR register is not mapped in data memory, so it is not available to the user.

### 30.1.1.6 Transmitting 9-Bit Characters

The EUSART supports 9-bit character transmissions. When the 9-Bit Transmit Enable (TX9) bit is set, the EUSART will shift nine bits out for each character transmitted. The TX9D bit is the ninth and Most Significant data bit. When transmitting 9-bit data, the TX9D data bit must be written before writing the eight Least Significant bits into the TXxREG. All nine bits of data will be transferred to the TSR register immediately after the TXxREG is written.

A special 9-bit Address mode is available for use with multiple receivers. See 30.1.2.7. Address Detection for more information on the Address mode.

#### 30.1.1.7 Asynchronous Transmission Setup

- 1. Initialize the SPxBRGH:SPxBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see 30.3. EUSART Baud Rate Generator (BRG)).
- 2. Select the transmit output pin by writing the appropriate value to the RxyPPS register.
- 3. Enable the asynchronous serial port by clearing the SYNC bit and setting the SPEN bit.
- 4. If 9-bit transmission is desired, set the TX9 control bit. That will indicate that the eight Least Significant data bits are an address when the receiver is set for address detection.
- Set SCKP bit if inverted transmit is desired.
- 6. Enable the transmission by setting the TXEN control bit. This will cause the TXxIF interrupt bit to be set.
- 7. If interrupts are desired, set the TXxIE interrupt enable bit of the PIEx register.
- 8. An interrupt will occur immediately provided that the GIE and PEIE bits of the INTCON register are also set.
- 9. If 9-bit transmission is selected, the ninth bit will be loaded into the TX9D data bit.
- 10. Load 8-bit data into the TXxREG register. This will start the transmission.

Figure 30-3. Asynchronous Transmission





Figure 30-4. Asynchronous Transmission (Back-to-Back)



### 30.1.2 EUSART Asynchronous Receiver

The Asynchronous mode is typically used in RS-232 systems. A simplified representation of the receiver is shown in Figure 30-2. The data is received on the RXx/DTx pin and drives the data recovery block. The data recovery block is actually a high-speed shifter operating at 16 times the baud rate, whereas the serial Receive Shift Register (RSR) operates at the bit rate. When all eight or nine bits of the character have been shifted in, they are immediately transferred to a two character First-In-First-Out (FIFO) memory. The FIFO buffering allows reception of two complete

characters and the start of a third character before software must start servicing the EUSART receiver. The FIFO and RSR registers are not directly accessible by software. Access to the received data is via the RCxREG register.

#### 30.1.2.1 Enabling the Receiver

The EUSART receiver is enabled for asynchronous operation by configuring the following three control bits:

- The Continuous Receive Enable (CREN) bit is set to '1' to enables the receiver circuitry of the EUSART
- The EUSART Mode Select (SYNC) bit is set to '0' to configure the EUSART for asynchronous operation
- The Serial Port Enable (SPEN) bit is set to '1' to enable the EUSART interface

All other EUSART control bits are assumed to be in their default state.

The user must set the RXxPPS register to select the RXx/DTx I/O pin and set the corresponding TRIS bit to configure the pin as an input.



**Important:** If the RX/DT function is on an analog pin, the corresponding ANSEL bit must be cleared for the receiver to function.

### 30.1.2.2 Receiving Data

The receiver data recovery circuit initiates character reception on the falling edge of the first bit. The first bit, also known as the Start bit, is always a zero. The data recovery circuit counts one-half bit time to the center of the Start bit and verifies that the bit is still a zero. If it is not a zero, then the data recovery circuit aborts character reception without generating an error, and resumes looking for the falling edge of the Start bit. If the Start bit zero verification succeeds, then the data recovery circuit counts a full bit time to the center of the next bit. The bit is then sampled by a majority detect circuit and the resulting '0' or '1' is shifted into the RSR. This repeats until all data bits have been sampled and shifted into the RSR. One final bit time is measured and the level sampled. This is the Stop bit, which is always a '1'. If the data recovery circuit samples a '0' in the Stop bit position, then a framing error is set for this character, otherwise the framing error is cleared for this character. See 30.1.2.4. Receive Framing Error for more information on framing errors.

Immediately after all data bits and the Stop bit have been received, the character in the RSR is transferred to the EUSART receive FIFO, and the EUSART Receive Interrupt Flag (RCxIF) bit of the PIRx register is set. The top character in the FIFO is transferred out of the FIFO by reading the RCxREG register.



**Important:** If the receive FIFO is overrun, no additional characters will be received until the Overrun condition is cleared. See 30.1.2.4. Receive Framing Error for more information.

# 30.1.2.3 Receive Interrupts

The EUSART Receive Interrupt Flag (RCxIF) bit of the PIRx register is set whenever the EUSART receiver is enabled and there is an unread character in the receive FIFO. The RCxIF Interrupt Flag bit is read-only, it cannot be set or cleared by software.

RCxIF interrupts are enabled by setting all of the following bits:

- · RCxIE, Interrupt Enable bit of the PIEx register
- · PEIE, Peripheral Interrupt Enable bit of the INTCON register
- · GIE, Global Interrupt Enable bit of the INTCON register

The RCxIF Interrupt Flag bit will be set when there is an unread character in the FIFO, regardless of the state of interrupt enable bits.

### 30.1.2.4 Receive Framing Error

Each character in the receive FIFO buffer has a corresponding framing error Status bit. A framing error indicates that a Stop bit was not seen at the expected time. The framing error status is accessed via the Framing Error (FERR) bit. The FERR bit represents the status of the top unread character in the receive FIFO. Therefore, the FERR bit must be read before reading the RCxREG register.

The FERR bit is read-only and only applies to the top unread character in the receive FIFO. A framing error (FERR = 1) does not preclude reception of additional characters. It is not necessary to clear the FERR bit. Reading the next character from the FIFO buffer will advance the FIFO to the next character and the next corresponding framing error.

The FERR bit can be forced clear by clearing the SPEN bit, which resets the EUSART. Clearing the CREN bit does not affect the FERR bit. A framing error by itself does not generate an interrupt.



**Important:** If all receive characters in the receive FIFO have framing errors, repeated reads of the RCxREG register will not clear the FERR bit.

#### 30.1.2.5 Receive Overrun Error

The receive FIFO buffer can hold two characters. An overrun error will be generated if a third character, in its entirety, is received before the FIFO is accessed. When this happens the Overrun Error (OERR) bit is set. The characters already in the FIFO buffer can be read but no additional characters will be received until the error is cleared. The error must be cleared by either clearing the CREN bit or by resetting the EUSART by clearing the SPEN bit.

# 30.1.2.6 Receiving 9-Bit Characters

The EUSART supports 9-bit character reception. When the 9-Bit Receive Enable (RX9) bit is set, the EUSART will shift nine bits into the RSR for each character received. The RX9D bit is the ninth and Most Significant data bit of the top unread character in the receive FIFO. When reading 9-bit data from the receive FIFO buffer, the RX9D data bit must be read before reading the eight Least Significant bits from the RCxREG register.

#### 30.1.2.7 Address Detection

A special Address Detection mode is available for use when multiple receivers share the same transmission line, such as in RS-485 systems. Address detection is enabled by setting the Address Detect Enable (ADDEN) bit.

Address detection requires 9-bit character reception. When address detection is enabled, only characters with the ninth data bit set will be transferred to the receive FIFO buffer, thereby setting the RCxIF interrupt bit. All other characters will be ignored.

Upon receiving an address character, user software determines if the address matches its own. Upon address match, user software must disable address detection by clearing the ADDEN bit before the next Stop bit occurs. When user software detects the end of the message, determined by the message protocol used, software places the receiver back into the Address Detection mode by setting the ADDEN bit.

### 30.1.2.8 Asynchronous Reception Setup

- 1. Initialize the SPxBRGH:SPxBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see 30.3. EUSART Baud Rate Generator (BRG)).
- 2. Set the RXxPPS register to select the RXx/DTx input pin.
- 3. Clear the ANSEL bit for the RXx pin (if applicable).
- 4. Enable the serial port by setting the SPEN bit. The SYNC bit must be cleared for asynchronous operation.
- 5. If interrupts are desired, set the RCxIE bit of the PIEx register and the GIE and PEIE bits of the INTCON register.
- 6. If 9-bit reception is desired, set the RX9 bit.
- 7. Enable reception by setting the CREN bit.
- 8. The RCxIF Interrupt Flag bit will be set when a character is transferred from the RSR to the receive buffer. An interrupt will be generated if the RCxIE interrupt enable bit was also set.
- 9. Read the RCxSTA register to get the Error flags and, if 9-bit data reception is enabled, the ninth data bit.
- 10. Get the received eight Least Significant data bits from the receive buffer by reading the RCxREG register.
- 11. If an overrun occurred, clear the OERR flag by clearing the CREN receiver enable bit.


# 30.1.2.9 9-Bit Address Detection Mode Setup

This mode is typically used in RS-485 systems. To set up an Asynchronous Reception with Address Detect Enable, follow these steps:

1. Initialize the SPxBRGH:SPxBRGL register pair and the BRGH and BRG16 bits to achieve the desired baud rate (see 30.3. EUSART Baud Rate Generator (BRG)).

- 2. Set the RXxPPS register to select the RXx input pin.
- 3. Clear the ANSEL bit for the RXx pin (if applicable).
- 4. Enable the serial port by setting the SPEN bit. The SYNC bit must be cleared for asynchronous operation.
- If interrupts are desired, set the RCxIE bit of the PIEx register and the GIE and PEIE bits of the INTCON register.
- 6. Enable 9-bit reception by setting the RX9 bit.
- 7. Enable address detection by setting the ADDEN bit.
- 8. Enable reception by setting the CREN bit.
- 9. The RCxIF Interrupt Flag bit will be set when a character with the ninth bit set is transferred from the RSR to the receive buffer. An interrupt will be generated if the RCxIE interrupt enable bit is also set.
- 10. Read the RCxSTA register to get the Error flags. The ninth data bit will always be set.
- 11. Get the received eight Least Significant data bits from the receive buffer by reading the RCxREG register. Software determines if this is the device's address.
- 12. If an overrun occurred, clear the OERR flag by clearing the CREN receiver enable bit.
- 13. If the device has been addressed, clear the ADDEN bit to allow all received data into the receive buffer and generate interrupts.

Figure 30-5. Asynchronous Reception



**Note:** This timing diagram shows three bytes appearing on the RXx input. The OERR flag is set because the RCxREG register is not read before the third word is received.

# 30.2 Clock Accuracy with Asynchronous Operation

The factory calibrates the internal oscillator block output (INTOSC). However, the INTOSC frequency may drift as  $V_{DD}$  or temperature changes, and this directly affects the asynchronous baud rate. Two methods may be used to adjust the baud rate clock, but both require a reference clock source of some kind.

The first (preferred) method uses the OSCTUNE register to adjust the INTOSC output. Adjusting the value in the OSCTUNE register allows for fine resolution changes to the system clock source.

The other method adjusts the value in the Baud Rate Generator. This can be done automatically with the Auto-Baud Detect feature (see 30.3.1. Auto-Baud Detect). There may not be fine enough resolution when adjusting the Baud Rate Generator to compensate for a gradual change in the peripheral clock frequency.

# 30.3 EUSART Baud Rate Generator (BRG)

The Baud Rate Generator (BRG) is an 8-bit or 16-bit timer that is dedicated to the support of both the asynchronous and synchronous EUSART operations. By default, the BRG operates in 8-bit mode. Setting the BRG16 bit selects 16-bit mode.

The SPxBRGH:SPxBRGL register pair determines the period of the free-running baud rate timer. In Asynchronous mode, the multiplier of the baud rate period is determined by both the BRGH and the BRG16 bits. In Synchronous mode, the BRGH bit is ignored.

Table 30-1 contains the formulas for determining the baud rate. Equation 30-1 provides a sample calculation for determining the baud rate and baud rate error.

Typical baud rates and error values for various Asynchronous modes have been computed and are shown in the table below. It may be advantageous to use the high baud rate (BRGH = 1), or the 16-bit BRG (BRG16 = 1) to reduce the baud rate error. The 16-bit BRG mode is used to achieve slow baud rates for fast oscillator frequencies. The BRGH bit is used to achieve very high baud rates.

Writing a new value to the SPxBRGH:SPxBRGL register pair causes the BRG timer to be reset (or cleared). This ensures that the BRG does not wait for a timer overflow before outputting the new baud rate.

If the system clock is changed during an active receive operation, a receive error or data loss may result. To avoid this, check the status of the Receive Idle Flag (RCIDL) bit to make sure the receive operation is idle before changing the system clock.

#### Equation 30-1. Calculating Baud Rate Error

For a device with F<sub>OSC</sub> of 16 MHz, desired baud rate of 9600, Asynchronous mode, 8-bit BRG:

$$DesiredBaudrate = \frac{F_{OSC}}{64 \times (SPxBRG + 1)}$$

Solving for SPxBRG:

$$SPxBRG = \frac{F_{OSC}}{64 \times DesiredBaudrate} - 1$$

$$SPxBRG = \frac{16000000}{64 \times 9600} - 1$$

$$SPxBRG = 25.042 \approx 25$$

$$CalculatedBaudrate = \frac{16000000}{64 \times (25 + 1)}$$

CalculatedBaudrate = 9615

$$Error = \frac{CalculatedBaudrate - DesiredBaudrate}{DesiredBaudrate}$$

$$Error = \frac{9615 - 9600}{9600}$$

*Error* = 0.16 %

### Table 30-1. Baud Rate Formulas

С	onfiguration B	its	BRG/EUSART Mode	Baud Rate Formula				
SYNC	BRG16	BRGH	BRG/EGSART Wode	Daud Nate i Officia				
0	0	0	8-bit/Asynchronous	F <sub>OSC</sub> /[64 (n+1)]				
0	0	1	8-bit/Asynchronous	F /[16 (p+1)]				
0	1	0	16-bit/Asynchronous	F <sub>OSC</sub> /[16 (n+1)]				

contir	nued								
С	onfiguration B	its	BRG/EUSART Mode	Based Bata Farmania					
SYNC	BRG16	BRGH	BRG/EUSART Moue	Baud Rate Formula					
0	1	1	16-bit/Asynchronous						
1	0	х	8-bit/Synchronous	F <sub>OSC</sub> /[4 (n+1)]					
1	1	х	16-bit/Synchronous						
Note: x = Don't care, n = value of SPxBRGH:SPxBRGL register pair.									

Table 30-2. Sample Baud Rates for Asynchronous Modes

		<b>SYNC</b> = 0, <b>BRGH</b> = 0, <b>BRG16</b> = 0											
Baud Rate	F <sub>OSC</sub> = 32.000 MHz			Fosc	F <sub>OSC</sub> = 20.000 MHz			F <sub>OSC</sub> = 18.432 MHz			F <sub>OSC</sub> = 11.0592 MHz		
	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	
300	_	_	_	_	_	_	_	_	_	_	_	_	
1200	_	_	_	1221	1.73	255	1200	0.00	239	1200	0.00	143	
2400	2404	0.16	207	2404	0.16	129	2400	0.00	119	2400	0.00	71	
9600	9615	0.16	51	9470	-1.36	32	9600	0.00	29	9600	0.00	17	
10417	10417	0.00	47	10417	0.00	29	10286	-1.26	27	10165	-2.42	16	
19.2k	19.23k	0.16	25	19.53k	1.73	15	19.20k	0.00	14	19.20k	0.00	8	
57.6k	55.55k	-3.55	3	_	_	_	57.60k	0.00	7	57.60k	0.00	2	
115.2k	_	_	_	_	_	_	_	_	_	_	_	_	

					SYNC	C = 0, BRGI	<b>⊣</b> = 0, <b>B</b> F	RG16 =	0				
Baud Rate	Foso	<sub>C</sub> = 8.0	00 MHz	Foso	F <sub>OSC</sub> = 4.000 MHz			F <sub>OSC</sub> = 3.6864 MHz			F <sub>OSC</sub> = 1.000 MHz		
	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	
300	_	_	_	300	0.16	207	300	0.00	191	300	0.16	51	
1200	1202	0.16	103	1202	0.16	51	1200	0.00	47	1202	0.16	12	
2400	2404	0.16	51	2404	0.16	25	2400	0.00	23	_	_	_	
9600	9615	0.16	12	_	_	_	9600	0.00	5	_	_	_	
10417	10417	0.00	11	10417	0.00	5	_	_	_	_	_	_	
19.2k	_	_	_	_	_	_	19.20k	0.00	2	_	_	_	
57.6k	_	_	_	_		_	57.60k	0.00	0	_	_	_	
115.2k	_	_	_	_	_	_	_	_	_	_	_	_	

		SYNC = 0, BRGH = 1, BRG16 = 0											
Baud	F <sub>OSC</sub> = 32.000 MHz			F <sub>OSC</sub> = 20.000 MHz			F <sub>OSC</sub> = 18.432 MHz			F <sub>OSC</sub> = 11.0592 MHz			
Rate	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	
300	_	_	_	_	_	_	_	_	_	_	_	<del>-</del>	
1200	_	_	_	_	_	_	_	_	_	_	_	_	
2400	_	_	_	_	_	_	_	_	_	_	_	_	
9600	9615	0.16	207	9615	0.16	129	9600	0.00	119	9600	0.00	71	
10417	10417	0.00	191	10417	0.00	119	10378	-0.37	110	10473	0.53	65	
19.2k	19.23k	0.16	103	19.23k	0.16	64	19.20k	0.00	59	19.20k	0.00	35	
57.6k	57.14k	-0.79	34	56.82k	-1.36	21	57.60k	0.00	19	57.60k	0.00	11	
115.2k	117.64k	2.12	16	113.64k	-1.36	10	115.2k	0.00	9	115.2k	0.00	5	

					SYNC	= 0, BRGH	H = 1, BF	RG16 =	0			
	Foso	F <sub>OSC</sub> = 8.000 MHz			= 4.00	00 MHz	Fosc	= 3.68	64 MHz	F <sub>OSC</sub> = 1.000 MHz		
Baud Rate	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)
300	_	_	_	_	_	_	_	_	_	300	0.16	207
1200	_	_	_	1202	0.16	207	1200	0.00	191	1202	0.16	51
2400	2404	0.16	207	2404	0.16	103	2400	0.00	95	2404	0.16	25
9600	9615	0.16	51	9615	0.16	25	9600	0.00	23	_	_	_
10417	10417	0.00	47	10417	0.00	23	10473	0.53	21	10417	0.00	5
19.2k	19231	0.16	25	19.23k	0.16	12	19.2k	0.00	11	_	_	_
57.6k	55556	-3.55	8	_	_	_	57.60k	0.00	3	_	_	_
115.2k	_	_	_		_	_	115.2k	0.00	1		_	_

					SYNC	= 0, BRGH	= 0, BR	G16 =	1			
Baud	Fosc	= 32.0	00 MHz	F <sub>OSC</sub> = 20.000 MHz			Fosc	= 18.4	32 MHz	F <sub>OSC</sub> = 11.0592 MHz		
Rate	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)
300	300.0	0.00	6666	300.0	-0.01	4166	300.0	0.00	3839	300.0	0.00	2303
1200	1200	-0.02	3332	1200	-0.03	1041	1200	0.00	959	1200	0.00	575
2400	2401	-0.04	832	2399	-0.03	520	2400	0.00	479	2400	0.00	287
9600	9615	0.16	207	9615	0.16	129	9600	0.00	119	9600	0.00	71
10417	10417	0.00	191	10417	0.00	119	10378	-0.37	110	10473	0.53	65
19.2k	19.23k	0.16	103	19.23k	0.16	64	19.20k	0.00	59	19.20k	0.00	35

# PIC16F18015/25/44/45

# **EUSART - Enhanced Universal Synchronous Asyn...**

57.6k	57.14k	-0.79	34	56.818	-1.36	21	57.60k	0.00	19	57.60k	0.00	11
115.2k	117.6k	2.12	16	113.636	-1.36	10	115.2k	0.00	9	115.2k	0.00	5

	SYNC = 0, BRGH = 0, BRG16 = 1											
D 10 (	Foso	= 8.00	00 MHz	Foso	= 4.00	00 MHz	Fosc	= 3.68	64 MHz	F <sub>OSC</sub> = 1.000 MHz		
Baud Rate	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)
300	299.9	-0.02	1666	300.1	0.04	832	300.0	0.00	767	300.5	0.16	207
1200	1199	-0.08	416	1202	0.16	207	1200	0.00	191	1202	0.16	51
2400	2404	0.16	207	2404	0.16	103	2400	0.00	95	2404	0.16	25
9600	9615	0.16	51	9615	0.16	25	9600	0.00	23	_	_	_
10417	10417	0.00	47	10417	0.00	23	10473	0.53	21	10417	0.00	5
19.2k	19.23k	0.16	25	19.23k	0.16	12	19.20k	0.00	11	_	_	_
57.6k	55556	-3.55	8		_	_	57.60k	0.00	3			_
115.2k	_	_	_	_	_	_	115.2k	0.00	1	_	_	_

		SYNC = 0, BRGH = 1, BRG16 = 1 or SYNC = 1, BRG16 = 1										
DI D-4-	Fosc	= 32.0	00 MHz	Fosc	= 20.0	00 MHz	Fosc	= 18.4	32 MHz	F <sub>OSC</sub> = 11.0592 MHz		
Baud Rate	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)
300	300.0	0.00	26666	300.0	0.00	16665	300.0	0.00	15359	300.0	0.00	9215
1200	1200	0.00	6666	1200	-0.01	4166	1200	0.00	3839	1200	0.00	2303
2400	2400	0.01	3332	2400	0.02	2082	2400	0.00	1919	2400	0.00	1151
9600	9604	0.04	832	9597	-0.03	520	9600	0.00	479	9600	0.00	287
10417	10417	0.00	767	10417	0.00	479	10425	0.08	441	10433	0.16	264
19.2k	19.18k	-0.08	416	19.23k	0.16	259	19.20k	0.00	239	19.20k	0.00	143
57.6k	57.55k	-0.08	138	57.47k	-0.22	86	57.60k	0.00	79	57.60k	0.00	47
115.2k	115.9k	0.64	68	116.3k	0.94	42	115.2k	0.00	39	115.2k	0.00	23

		SYNC = 0, BRGH = 1, BRG16 = 1 or SYNC = 1, BRG16 = 1												
David Data	F <sub>OSC</sub> = 8.000 MHz		F <sub>OSC</sub> = 4.000 MHz		F <sub>OSC</sub> = 3.6864 MHz			F <sub>OSC</sub> = 1.000 MHz						
Baud Rate	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)	Actual Rate	% Error	SPBRG value (decimal)		
300	300.0	0.00	6666	300.0	0.01	3332	300.0	0.00	3071	300.1	0.04	832		
1200	1200	-0.02	1666	1200	0.04	832	1200	0.00	767	1202	0.16	207		
2400	2401	0.04	832	2398	0.08	416	2400	0.00	383	2404	0.16	103		

-													
	9600	9615	0.16	207	9615	0.16	103	9600	0.00	95	9615	0.16	25
	10417	10417	0	191	10417	0.00	95	10473	0.53	87	10417	0.00	23
	19.2k	19.23k	0.16	103	19.23k	0.16	51	19.20k	0.00	47	19.23k	0.16	12
	57.6k	57.14k	-0.79	34	58.82k	2.12	16	57.60k	0.00	15	_		_
	115.2k	117.6k	2.12	16	111.1k	-3.55	8	115.2k	0.00	7	_	_	_

#### 30.3.1 Auto-Baud Detect

The EUSART module supports automatic detection and calibration of the baud rate.

In the Auto-Baud Detect (ABD) mode, the clock to the BRG is reversed. Rather than the BRG clocking the incoming RX signal, the RX signal is timing the BRG. The Baud Rate Generator is used to time the period of a received 55h (ASCII "U") which is the Sync character for the LIN bus. The unique feature of this character is that it has five rising edges, including the Stop bit edge.

Setting the Auto-Baud Detect Enable (ABDEN) bit starts the auto-baud calibration sequence. While the ABD sequence takes place, the EUSART state machine is held in Idle. On the first rising edge of the receive line, after the Start bit, the SPxBRG register begins counting up using the BRG counter clock as shown in Figure 30-6. The fifth rising edge will occur on the RXx pin at the end of the eighth bit period. At that time, an accumulated value totaling the proper BRG period is left in the SPxBRGH:SPxBRGL register pair, the ABDEN bit is automatically cleared, and the RCxIF interrupt flag is set. The value in the RCxREG register needs to be read to clear the RCxIF interrupt. RCxREG content may be discarded. When calibrating for modes that do not use the SPxBRGH register, the user can verify that the SPxBRGL register did not overflow by checking for 00h in the SPxBRGH register.

The BRG auto-baud clock is determined by the BRG16 and BRGH bits, as shown in Table 30-3. During ABD, both the SPxBRGH and SPxBRGL registers are used as a 16-bit counter, independent of the BRG16 bit setting. While calibrating the baud rate period, the SPxBRGH and SPxBRGL registers are clocked at 1/8<sup>th</sup> the BRG base clock rate. The resulting byte measurement is the average bit time when clocked at full speed.

#### Notes:

- 1. If the Wake-Up Enable (WUE) bit is set with the ABDEN bit, auto-baud detection will occur on the byte following the Break character (see 30.3.3. Auto-Wake-Up on Break).
- It is up to the user to determine that the incoming character baud rate is within the range of the selected BRG clock source. Some combinations of oscillator frequency and EUSART baud rates are not possible.
- 3. During the auto-baud process, the auto-baud counter starts counting at one. Upon completion of the auto-baud sequence, to achieve maximum accuracy, subtract 1 from the SPxBRGH:SPxBRGL register pair.

Table 30-3. BRG Counter Clock Rates

BRG16	BRGH	BRG Base Clock	BRG ABD Clock
1	1	F <sub>OSC</sub> /4	F <sub>OSC</sub> /32
1	0	F <sub>OSC</sub> /16	F <sub>OSC</sub> /128
0	1	F <sub>OSC</sub> /16	F <sub>OSC</sub> /128
0	0	F <sub>OSC</sub> /64	F <sub>OSC</sub> /512

**Note:** During the ABD sequence, the SPxBRGL and SPxBRGH registers are both used as a 16-bit counter, independent of the BRG16 setting.




Figure 30-6. Automatic Baud Rate Calibration

#### 30.3.2 Auto-Baud Overflow

During the course of automatic baud detection, the Auto-Baud Detect Overflow (ABDOVF) bit will be set if the baud rate counter overflows before the fifth rising edge is detected on the RXx pin. The ABDOVF bit indicates that the counter has exceeded the maximum count that can fit in the 16 bits of the SPxBRGH:SPxBRGL register pair. After the ABDOVF bit has been set, the counter continues to count until the fifth rising edge is detected on the RXx pin. Upon detecting the fifth RX edge, the hardware will set the RCxIF interrupt flag and clear the ABDEN bit. The RCxIF flag can be subsequently cleared by reading the RCxREG register. The ABDOVF bit can be cleared by software directly.

To terminate the auto-baud process before the RCxIF flag is set, clear the ABDEN bit then clear the ABDOVF bit. The ABDOVF bit will remain set if the ABDEN bit is not cleared first.

### 30.3.3 Auto-Wake-Up on Break

During Sleep mode, all clocks to the EUSART are suspended. Because of this, the Baud Rate Generator is inactive and a proper character reception cannot be performed. The Auto-Wake-Up feature allows the controller to wake up due to activity on the RX/DT line. This feature is available only in Asynchronous mode.

The Auto-Wake-Up feature is enabled by setting the WUE bit. Once set, the normal receive sequence on RX/DT is disabled, and the EUSART remains in an Idle state, monitoring for a wake-up event independent of the CPU mode. A wake-up event consists of a high-to-low transition on the RX/DT line. This coincides with the start of a Sync Break or a wake-up signal character for the LIN protocol.

The EUSART module generates an RCxIF interrupt coincident with the wake-up event. The interrupt is generated synchronously to the Q clocks in normal CPU operating modes as shown in Figure 30-7, and asynchronously if the device is in Sleep mode, as shown in Figure 30-8. The Interrupt condition is cleared by reading the RCxREG register.

The WUE bit is automatically cleared by the low-to-high transition on the RX line at the end of the Break. This signals to the user that the Break event is over. At this point, the EUSART module is in Idle mode waiting to receive the next character.

### 30.3.3.1 Special Considerations

### **Break Character**

To avoid character errors or character fragments during a wake-up event, the wake-up character must be all zeros.

When the wake-up is enabled, the function works independent of the low time on the data stream. If the WUE bit is set and a valid nonzero character is received, the low time from the Start bit to the first rising edge will be interpreted

as the wake-up event. The remaining bits in the character will be received as a fragmented character and subsequent characters can result in framing or overrun errors.


Therefore, the initial character in the transmission must be all '0's. This must be 10 or more bit times, 13-bit times recommended for LIN bus, or any number of bit times for standard RS-232 devices.

#### **WUE Bit**

The wake-up event causes a receive interrupt by setting the RCxIF bit. The WUE bit is cleared in hardware by a rising edge on RX/DT. The Interrupt condition is then cleared in software by reading the RCxREG register and discarding its contents.


To ensure that no actual data is lost, check the RCIDL bit to verify that a receive operation is not in process before setting the WUE bit. If a receive operation is not occurring, the WUE bit may then be set just prior to entering the Sleep mode.

Figure 30-7. Auto-Wake-Up (WUE) Bit Timing During Normal Operation



Note: The EUSART remains in Idle while the WUE bit is set.

Figure 30-8. Auto-Wake-Up (WUE) Bit Timings During Sleep



Note: The EUSART remains in Idle while the WUE bit is set.

### 30.3.4 Break Character Sequence

The EUSART module has the capability of sending the special Break character sequences that are required by the LIN bus standard. A Break character consists of a Start bit, followed by 12 '0' bits and a Stop bit.

To send a Break character, set the Send Break Character (SENDB) and Transmit Enable (TXEN) bits. The Break character transmission is then initiated by a write to the TXxREG. The value of data written to TXxREG will be ignored and all '0's will be transmitted.

The SENDB bit is automatically reset by hardware after the corresponding Stop bit is sent. This allows the user to preload the transmit FIFO with the next transmit byte following the Break character (typically, the Sync character in the LIN specification).

The Transmit Shift Register Status (TRMT) bit indicates when the transmit operation is Active or Idle, just as it does during normal transmission. See Figure 30-9 for more details.

#### 30.3.4.1 Break and Sync Transmit Sequence

The following sequence will start a message frame header made up of a Break, followed by an auto-baud Sync byte. This sequence is typical of a LIN bus host.

- 1. Configure the EUSART for the desired mode.
- 2. Set the TXEN and SENDB bits to enable the Break sequence.
- 3. Load the TXxREG with a dummy character to initiate transmission (the value is ignored).
- 4. Write '55h' to TXxREG to load the Sync character into the transmit FIFO buffer.
- 5. After the Break has been sent, the SENDB bit is reset by hardware and the Sync character is then transmitted.

When the TXxREG becomes empty, as indicated by TXxIF, the next data byte can be written to TXxREG.

### 30.3.5 Receiving a Break Character

The EUSART module can receive a Break character in two ways.

The first method to detect a Break character uses the Framing Error (FERR) bit and the received data as indicated by RCxREG. The Baud Rate Generator is assumed to have been initialized to the expected baud rate.


A Break character has been received when all three of the following conditions are true:

- RCxIF bit is set
- FERR bit is set
- RCxREG = 00h

The second method uses the Auto-Wake-Up feature described in 30.3.3. Auto-Wake-Up on Break. By enabling this feature, the EUSART will sample the next two transitions on RX/DT, cause an RCxIF interrupt, and receive the next data byte followed by another interrupt.

Note that following a Break character, the user will typically want to enable the Auto-Baud Detect feature. For both methods, the user can set the ABDEN bit before placing the EUSART in Sleep mode.

Figure 30-9. Send Break Character Sequence



# 30.4 EUSART Synchronous Mode

Synchronous serial communications are typically used in systems with a single host and one or more clients. The host device contains the necessary circuitry for baud rate generation and supplies the clock for all devices in the system. Client devices can take advantage of the host clock by eliminating the internal clock generation circuitry.

There are two signal lines in Synchronous mode: A bidirectional data line (DT) and a clock line (CK). The clients use the external clock supplied by the host to shift the serial data into and out of their respective receive and transmit shift registers. Since the data line is bidirectional, synchronous operation is half-duplex only. Half-duplex refers to the fact that host and client devices can receive and transmit data but not both simultaneously. The EUSART can operate as either a host or client device.

Start and Stop bits are not used in synchronous transmissions.

#### 30.4.1 **Synchronous Host Mode**

The following bits are used to configure the EUSART for synchronous host operation:

- The SYNC bit is set to '1' to configure the EUSART for synchronous operation
- The Clock Source Select (CSRC) bit is set to '1' to configure the EUSART as the host
- The Single Receive Enable (SREN) bit is set to '0' for transmit; SREN = 1 for receive (recommended setting to receive 1 byte)
- The Continuous Receive Enable (CREN) bit is set to '0' for transmit; CREN = 1 to receive continuously
- The SPEN bit is set to '1' to enable the EUSART interface



Important: Clearing the SREN and CREN bits ensure that the device is in the Transmit mode, otherwise the device will be configured to receive.

#### 30.4.1.1 Host Clock

Synchronous data transfers use a separate clock line, which is synchronous with the data. A device configured as a host transmits the clock on the TX/CK line. The TXx/CKx pin output driver is automatically enabled when the EUSART is configured for synchronous transmit or receive operation. Serial data bits change on the leading edge to ensure they are valid at the trailing edge of each clock. One clock cycle is generated for each data bit. Only as many clock cycles are generated as there are data bits.

### 30.4.1.2 Clock Polarity

A clock polarity option is provided for Microwire compatibility. Clock polarity is selected with the Clock/Transmit Polarity Select (SCKP) bit. Setting the SCKP bit sets the clock Idle state as high. When the SCKP bit is set, the data changes on the falling edge of each clock. Clearing the SCKP bit sets the Idle state as low. When the SCKP bit is cleared, the data changes on the rising edge of each clock.

### 30.4.1.3 Synchronous Host Transmission

Data is transferred out of the device on the RXx/DTx pin. The RXx/DTx and TXx/CKx pin output drivers are automatically enabled when the EUSART is configured for synchronous host transmit operation.

A transmission is initiated by writing a character to the TXxREG register. If the TSR still contains all or part of a previous character the new character data is held in the TXxREG until the last bit of the previous character has been transmitted. If this is the first character, or the previous character has been completely flushed from the TSR, the data in the TXxREG is immediately transferred to the TSR. The transmission of the character commences immediately following the transfer of the data to the TSR from the TXxREG.

Each data bit changes on the leading edge of the host clock and remains valid until the subsequent leading clock edge.


Note: The TSR register is not mapped in data memory, so it is not available to the user.

### 30.4.1.4 Synchronous Host Transmission Setup

- 1. Initialize the SPxBRGH;SPxBRGL register pair and the BRG16 bit to achieve the desired baud rate (see 30.3. EUSART Baud Rate Generator (BRG)).
- Select the transmit output pin by writing the appropriate values to the RxyPPS register and RXxPPS register. Both selections may enable the same pin.
- Select the clock output pin by writing the appropriate values to the RxyPPS register and TXxPPS register. Both selections may enable the same pin.

- 4. Enable the synchronous host serial port by setting bits SYNC, SPEN and CSRC.
- 5. Disable Receive mode by clearing the SREN and CREN bits.
- 6. Enable Transmit mode by setting the TXEN bit.
- 7. If 9-bit transmission is desired, set the TX9 bit.
- If interrupts are desired, set the TXxIE bit of the PIEx register and the GIE and PEIE bits of the INTCON register.
- 9. If 9-bit transmission is selected, the ninth bit will be loaded in the TX9D bit.
- 10. Start transmission by loading data to the TXxREG register.

### Figure 30-10. Synchronous Transmission



### 30.4.1.5 Synchronous Host Reception

Data is received at the RXx/DTx pin. The RXx/DTx pin output driver is automatically disabled when the EUSART is configured for synchronous host receive operation.

In Synchronous mode, reception is enabled by setting either the Single Receive Enable (SREN) bit or the Continuous Receive Enable (CREN) bit.

When SREN is set and CREN is clear, only as many clock cycles are generated as there are data bits in a single character. The SREN bit is automatically cleared at the completion of one character. When CREN is set, clocks are continuously generated until CREN is cleared. If CREN is cleared in the middle of a character the CK clock stops immediately and the partial character is discarded. If SREN and CREN are both set, then SREN is cleared at the completion of the first character and CREN takes precedence.

To initiate reception, set either SREN or CREN. Data is sampled at the RXx/DTx pin on the trailing edge of the TX/CK clock pin and is shifted into the Receive Shift Register (RSR). When a complete character is received into the RSR, the RCxIF bit is set and the character is automatically transferred to the two character receive FIFO. The eight Least Significant bits of the top character in the receive FIFO are available in RCxREG. The RCxIF bit remains set as long as there are unread characters in the receive FIFO.

**Note:** If the RX/DT function is on an analog pin, the corresponding ANSEL bit must be cleared for the receiver to function.

#### 30.4.1.6 Client Clock

Synchronous data transfers use a separate clock line, which is synchronous with the data. A device configured as a client receives the clock on the TX/CK line. The TXx/CKx pin output driver is automatically disabled when the device is configured for synchronous client transmit or receive operation. Serial data bits change on the leading edge to ensure they are valid at the trailing edge of each clock. One data bit is transferred for each clock cycle. Only as many clock cycles may be received as there are data bits.



**Important:** If the device is configured as a client and the TX/CK function is on an analog pin, the corresponding ANSEL bit must be cleared.

#### 30.4.1.7 Receive Overrun Error

The receive FIFO buffer can hold two characters. An overrun error will be generated if a third character, in its entirety, is received before the FIFO is accessed. When this happens the Overrun Error (OERR) bit is set. The characters already in the FIFO buffer can be read but no additional characters will be received until the error is cleared. The error must be cleared by either clearing the CREN bit or by resetting the EUSART by clearing the SPEN bit.


### 30.4.1.8 Receiving 9-Bit Characters

The EUSART supports 9-bit character reception. When the 9-Bit Receive Enable (RX9) bit is set, the EUSART will shift nine bits into the RSR for each character received. The RX9D bit is the ninth and Most Significant data bit of the top unread character in the receive FIFO. When reading 9-bit data from the receive FIFO buffer, the RX9D data bit must be read before reading the eight Least Significant bits from the RCxREG register.

### 30.4.1.9 Synchronous Host Reception Setup

- Initialize the SPxBRGH:SPxBRGL register pair and set or clear the BRG16 bit, as required, to achieve the
  desired baud rate.
- 2. Select the receive input pin by writing the appropriate values to the RxyPPS and RXxPPS registers. Both selections may enable the same pin.
- 3. Select the clock output pin by writing the appropriate values to the RxyPPS and TXxPPS registers. Both selections may enable the same pin.
- 4. Clear the ANSEL bit for the RXx pin (if applicable).
- 5. Enable the synchronous host serial port by setting the SYNC, SPEN and CSRC bits.
- 6. Ensure that the CREN and SREN bits are cleared.
- 7. If interrupts are desired, set the RCxIE bit of the PIEx register and the GIE and PEIE bits of the INTCON register.
- 8. If 9-bit reception is desired, set the RX9 bit.
- 9. Start reception by setting the SREN bit, or for continuous reception set the CREN bit.
- 10. The RCxIF Interrupt Flag bit will be set when reception of a character is complete. An interrupt will be generated if the RCxIE enable bit was set.
- 11. Read the RCxSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- 12. Read the 8-bit received data by reading the RCxREG register.
- 13. If an overrun error occurs, clear the error by either clearing the CREN bit or by clearing the SPEN bit which resets the EUSART.

Figure 30-11. Synchronous Reception (Host Mode, SREN)



### 30.4.2 Synchronous Client Mode

The following bits are used to configure the EUSART for synchronous client operation:

- SYNC = 1 (configures the EUSART for synchronous operation)
- CSRC = 0 (configures the EUSART as a client)
- SREN = 0 (for transmit); SREN = 1 (for single byte receive)
- CREN = 0 (for transmit); CREN = 1 (recommended setting for continuous receive)
- SPEN = 1 (enables the EUSART)



**Important:** Clearing the SREN and CREN bits ensure that the device is in Transmit mode, otherwise the device will be configured to receive.

### 30.4.2.1 EUSART Synchronous Client Transmit

The operation of the Synchronous Host and Client modes are identical (see 30.4.1.3. Synchronous Host Transmission), except in the case of the Sleep mode.

If two words are written to the TXxREG and then the SLEEP instruction is executed, the following will occur:

- 1. The first character will immediately transfer to the TSR register and transmit.
- The second word will remain in the TXxREG register.
- 3. The TXxIF bit will not be set.
- 4. After the first character has been shifted out of TSR, the TXxREG register will transfer the second character to the TSR and the TXxIF bit will now be set.
- 5. If the PEIE and TXxIE bits are set, the interrupt will wake the device from Sleep and execute the next instruction. If the GIE bit is also set, the program will call the Interrupt Service Routine.

### 30.4.2.2 Synchronous Client Transmission Setup

- 1. Set the SYNC and SPEN bits and clear the CSRC bit.
- 2. Select the transmit output pin by writing the appropriate values to the RxyPPS register and RXxPPS register. Both selections may enable the same pin.
- 3. Select the clock input pin by writing the appropriate value to the TXxPPS register.
- 4. Clear the ANSEL bit for the CKx pin (if applicable).
- 5. Clear the CREN and SREN bits.
- 6. If interrupts are desired, set the TXxIE bit of the PIEx register and the GIE and PEIE bits of the INTCON register.
- 7. If 9-bit transmission is desired, set the TX9 bit.
- Enable transmission by setting the TXEN bit.
- If 9-bit transmission is selected, insert the Most Significant bit into the TX9D bit.
- 10. Prepare for transmission by writing the eight Least Significant bits to the TXxREG register. The word will be transmitted in response to the Host clocks at the CKx pin.

#### 30.4.2.3 EUSART Synchronous Client Reception

The operation of the Synchronous Host and Client modes is identical (see 30.4.1.5. Synchronous Host Reception), with the following exceptions:

- Sleep
- CREN bit is always set, therefore the receiver is never Idle
- · SREN bit, which is a "don't care" in Client mode

A character may be received while in Sleep mode by setting the CREN bit prior to entering Sleep. Once the word is received, the RSR register will transfer the data to the RCxREG register. If the RCxIE enable bit is set, the interrupt generated will wake the device from Sleep and execute the next instruction. If the GIE bit is also set, the program will branch to the interrupt vector.

### 30.4.2.4 Synchronous Client Reception Setup

- 1. Set the SYNC and SPEN bits and clear the CSRC bit.
- Select the receive input pin by writing the appropriate value to the RXxPPS register.
- 3. Select the clock input pin by writing the appropriate values to the TXxPPS register.
- 4. Clear the ANSEL bit for both the TXx/CKx and RXx/DTx pins (if applicable).
- If interrupts are desired, set the RCxIE bit of the PIEx register and the GIE and PEIE bits of the INTCON register.
- 6. If 9-bit reception is desired, set the RX9 bit.
- 7. Set the CREN bit to enable reception.
- 8. The RCxIF bit will be set when reception is complete. An interrupt will be generated if the RCxIE bit was set.
- 9. If 9-bit mode is enabled, retrieve the Most Significant bit from the RX9D bit.
- 10. Retrieve the eight Least Significant bits from the receive FIFO by reading the RCxREG register.
- 11. If an overrun error occurs, clear the error by either clearing the CREN bit or by clearing the SPEN bit which resets the EUSART.

# 30.5 EUSART Operation During Sleep

The EUSART will remain active during Sleep only in the Synchronous Client mode. All other modes require the system clock and therefore cannot generate the necessary signals to run the Transmit or Receive Shift registers during Sleep.

Synchronous Client mode uses an externally generated clock to run the Transmit and Receive Shift registers.

# 30.5.1 Synchronous Receive During Sleep

To receive during Sleep, all the following conditions must be met before entering Sleep mode:

- RCxSTA and TXxSTA Control registers must be configured for Synchronous Client Reception (see 30.4.2.4. Synchronous Client Reception Setup).
- If interrupts are desired, set the RCxIE bit of the PIEx register and the GIE and PEIE bits of the INTCON register.
- The RCxIF interrupt flag must be cleared by reading RCxREG to unload any pending characters in the receive buffer.

Upon entering Sleep mode, the device will be ready to accept data and clocks on the RXx/DTx and TXx/CKx pins, respectively. When the data word has been completely clocked in by the external device, the RCxIF Interrupt Flag bit of the PIRx register will be set. Thereby, waking the processor from Sleep.

Upon waking from Sleep, the instruction following the SLEEP instruction will be executed. If the Global Interrupt Enable (GIE) bit of the INTCON register is also set, then the Interrupt Service Routine (ISR) will be called.

#### 30.5.2 Synchronous Transmit During Sleep

To transmit during Sleep, all the following conditions must be met before entering Sleep mode:

- The RCxSTA and TXxSTA Control registers must be configured for synchronous client transmission (see 30.4.2.2. Synchronous Client Transmission Setup).
- The TXxIF interrupt flag must be cleared by writing the output data to the TXxREG, thereby filling the TSR and transmit buffer.
- The TXxIE interrupt enable bits of the PIEx register and PEIE of the INTCON register must be written to '1'.
- If interrupts are desired, set the GIE bit of the INTCON register.

Upon entering Sleep mode, the device will be ready to accept clocks on the TXx/CKx pin and transmit data on the RXx/DTx pin. When the data word in the TSR register has been completely clocked out by the external device, the pending byte in the TXxREG will transfer to the TSR and the TXxIF flag will be set. Thereby, waking the processor from Sleep. At this point, the TXxREG is available to accept another character for transmission. Writing TXxREG will clear the TXxIF flag.

Upon waking from Sleep, the instruction following the SLEEP instruction will be executed. If the Global Interrupt Enable (GIE) bit is also set then the Interrupt Service Routine (ISR) will be called.

# PIC16F18015/25/44/45

**EUSART - Enhanced Universal Synchronous Asyn...** 

30.6	Register	<b>Definitions:</b>	<b>EUSART</b>	<b>Control</b>
------	----------	---------------------	---------------	----------------

### 30.6.1 TXxSTA

Name: TXxSTA
Offset: 0x0611,0x061B

Transmit Status and Control Register

Bit	7	6	5	4	3	2	1	0
[	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D
Access	R/W	R/W	R/W	R/W	R/W	R/W	R	R/W
Reset	0	0	0	0	0	0	1	0

# Bit 7 - CSRC Clock Source Select

Value	Condition	Description
1	SYNC = 1	Host mode (clock generated internally from BRG)
0	SYNC = 1	Client mode (clock from external source)
X	SYNC = 0	Don't care

# Bit 6 - TX9 9-Bit Transmit Enable

Value	Description
1	Selects 9-bit transmission
0	Selects 8-bit transmission

# Bit 5 - TXEN Transmit Enable

Enables transmitter<sup>(1)</sup>

Value	Description		
1	Transmit enabled		
0	Transmit disabled		

#### Bit 4 - SYNC EUSART Mode Select

Value	alue Description		
1	Synchronous mode		
0	Asynchronous mode		

# Bit 3 - SENDB Send Break Character

Value	Condition	Description
1	SYNC = 0	Send Sync Break on next transmission (cleared by hardware upon completion)
0	SYNC = 0	Sync Break transmission disabled or completed
X	SYNC = 1	Don't care

### Bit 2 - BRGH High Baud Rate Select

Value	Condition	Description
1	SYNC = 0	High speed, if BRG16 = 1, baud rate is baudclk/4; else baudclk/16
0	SYNC = 0	Low speed
X	SYNC = 1	Don't care

#### Bit 1 - TRMT Transmit Shift Register (TSR) Status

	The first transfer of the great ( ) or y existing		
Value	Description		
1	TSR is empty		
0	TSR is not empty		

# Bit 0 - TX9D Ninth Bit of Transmit Data

Can be address/data bit or a parity bit.

Note: 1. The SREN and CREN bits override TXEN in Sync mode.

### 30,6,2 RCxSTA

Name: RCxSTA Offset: 0x0610,0x061A

Receive Status and Control Register

Bit	7	6	5	4	3	2	1	0
	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
Access	R/W	R/W	R/W/HC	R/W	R/W	R	R/HC	R/HC
Reset	0	0	0	0	0	0	0	0

# Bit 7 - SPEN Serial Port Enable

Value	Description	
1	Serial port enabled	
0	Serial port disabled (held in Reset)	

#### Bit 6 - RX9 9-Bit Receive Enable

Value	Description	
1	Selects 9-bit reception	
0	Selects 8-bit reception	

# Bit 5 - SREN Single Receive Enable

Controls reception. This bit is cleared by hardware when reception is complete

Value	lue Condition Description		
1	SYNC = 1 AND CSRC = 1	Start single receive	
0	SYNC = 1 AND CSRC = 1	Single receive is complete	
X	SYNC = 0 OR CSRC = 0	Don't care	

# Bit 4 - CREN Continuous Receive Enable

Value	Condition	Description
1	SYNC = 1	Enables continuous receive until enable bit CREN is cleared (CREN overrides SREN)
0	SYNC = 1	Disables continuous receive
1	SYNC = 0	Enables receiver
0	SYNC = 0	Disables receiver

### Bit 3 - ADDEN Address Detect Enable

Value	Condition	Description
1	SYNC = 0 AND RX9 = 1	The receive buffer is loaded and the interrupt occurs only when the ninth
		received bit is set
0	<b>SYNC = </b> 0 <b>AND RX9 =</b> 1	All bytes are received and interrupt always occurs. Ninth bit can be used as
		parity bit
X	<b>RX9</b> = 0 <b>OR SYNC</b> = 1	Don't care

# Bit 2 - FERR Framing Error

Value	Description
1	Unread byte in RCxREG has a framing error
0	Unread byte in RCxREG does not have a framing error

#### Bit 1 - OERR Overrun Error

1	/alue	Description
-	_	Overrun error (can be cleared by clearing either SPEN or CREN bit)
(	)	No overrun error

# Bit 0 - RX9D Ninth bit of Received Data

This can be address/data bit or a parity bit which is determined by user firmware.

# 30.6.3 BAUDxCON

Name: BAUDxCON
Offset: 0x0612,0x061C

# **Baud Rate Control Register**

Bit	7	6	5	4	3	2	1	0
	ABDOVF	RCIDL		SCKP	BRG16		WUE	ABDEN
Access	R	R		R/W	R/W		R/W	R/W
Reset	0	0		0	0		0	0

# Bit 7 - ABDOVF Auto-Baud Detect Overflow

Value	Condition	Description
1	SYNC = 0	Auto-baud timer overflowed
0	SYNC = 0	Auto-baud timer did not overflow
X	SYNC = 1	Don't care

### Bit 6 - RCIDL Receive Idle Flag

Value	Condition	Description
1	SYNC = 0	Receiver is Idle
0	SYNC = 0	Start bit has been received and the receiver is receiving
X	SYNC = 1	Don't care

### Bit 4 – SCKP Clock/Transmit Polarity Select

Value	Condition	Description
1	SYNC = 0	Idle state for transmit (TX) is a low level (transmit data inverted)
0	SYNC = 0	Idle state for transmit (TX) is a high level (transmit data is noninverted)
1	SYNC = 1	Data is clocked on rising edge of the clock
0	SYNC = 1	Data is clocked on falling edge of the clock

# Bit 3 - BRG16 16-bit Baud Rate Generator Select

Value	Description
1	16-bit Baud Rate Generator is used
0	8-bit Baud Rate Generator is used

# Bit 1 - WUE Wake-Up Enable

Value	Condition	Description
1	SYNC = 0	Receiver is waiting for a falling edge. Upon falling edge, no character will be received and
		the RCxIF flag will be set. WUE will automatically clear after RCxIF is set.
0	SYNC = 0	Receiver is operating normally
X	SYNC = 1	Don't care

#### Bit 0 - ABDEN Auto-Baud Detect Enable

Value	Condition	Description								
1	SYNC = 0	Auto-Baud Detect mode is enabled (clears when auto-baud is complete)								
0	SYNC = 0	Auto-Baud Detect is complete or mode is disabled								
X	SYNC = 1	Don't care								

# 30.6.4 RCxREG

Name: RCxREG Offset: 0x060C,0x0616

Receive Data Register

Bit	7	6	5	4	3	2	1	0		
	RCREG[7:0]									
Access	R	R	R	R	R	R	R	R		
Reset	0	0	0	0	0	0	0	0		

Bits 7:0 - RCREG[7:0] Receive data

# 30.6.5 TXxREG

Name: TXxREG Offset: 0x060D,0x0617

Transmit Data Register

Bit	7	6	5	4	3	2	1	0		
[	TXREG[7:0]									
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W		
Reset	0	0	0	0	0	0	0	0		

Bits 7:0 - TXREG[7:0] Transmit Data

# 30.6.6 SPxBRG

Name: SPxBRG Offset: 0x060E,0x0618

**EUSART Baud Rate Generator** 

Bit	15	14	13	12	11	10	9	8				
		SPBRG[15:8]										
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W R/W R/W 0 0 0 0 0 0					
Reset	0	0	0	0	0	0	0	0				
Bit	7	6	5	4	3	2	1	0				
				SPBR	G[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W				
Reset	0	0	0	0	0	0	0	0				

Bits 15:0 - SPBRG[15:0] Baud Rate Register

Notes: The individual bytes in this multibyte register can be accessed with the following register names:

- SPxBRGH: Accesses the high byte SPBRG[15:8]
- SPxBRGL: Accesses the low byte SPBRG[7:0]

# 30.7 Register Summary - EUSART

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
 0x060B	Reserved									
0x060C	RC1REG	7:0			:	RCRE	G[7:0]	•		-
0x060D	TX1REG	7:0				TXRE	:G[7:0]			
0x060E	SD1DDC	7:0		SPBRG[7:0]						
UXUOUE	SP1BRG	15:8				SPBR	G[15:8]			
0x0610	RC1STA	7:0	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
0x0611	TX1STA	7:0	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D
0x0612	BAUD1CON	7:0	ABDOVF	RCIDL		SCKP	BRG16		WUE	ABDEN
0x0613	Reserved									
 0x0615	Neserveu									
0x0616	RC2REG	7:0				RCRE	G[7:0]			
0x0617	TX2REG	7:0				TXRE	:G[7:0]			
0x0618	SP2BRG	7:0				SPBR	RG[7:0]			
030018	SFZBRG	15:8				SPBR	G[15:8]			
0x061A	RC2STA	7:0	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
0x061B	TX2STA	7:0	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D
0x061C	BAUD2CON	7:0	ABDOVF	RCIDL		SCKP	BRG16		WUE	ABDEN

# 31. ADC - Analog-to-Digital Converter with Computation Module

The Analog-to-Digital Converter with Computation module allows conversion of single-ended analog input signals to a 10-bit binary representation of that signal. This device uses analog inputs that are multiplexed into a single Sample-and-Hold circuit. The output of the Sample-and-Hold (S/H) circuit is connected to the input of the converter. The converter generates a 10-bit binary result via successive approximation and stores the conversion result into the ADC result registers. In single-ended conversions, the ADC measures the voltage between the selected analog input and  $V_{SS}$  (0V). The selected ADC input channels can either be from an internal source, such as the Fixed Voltage Reference (FVR), or from external analog input pins. Additionally, the following features are provided within the ADC module:


- Acquisition Timer
- · Hardware Capacitive Voltage Divider (CVD) support:
  - Precharge timer
  - Adjustable Sample-and-Hold capacitor array
  - Guard ring digital output drive
- · Automatic Repeat and Sequencing:
  - Automated double sample conversion for CVD
  - Two sets of Result registers (Current Result and Previous Result)
  - Auto-conversion trigger
  - Internal retrigger
- Channel Grouping:
  - Allows multiple input channels to be grouped together into a single input channel
- Computation Features:
  - Averaging and low-pass filter functions
  - Reference comparison
  - 2-level threshold comparison
  - Selectable interrupts

Figure 43-1 shows the block diagram of the ADC.


The ADC positive voltage reference is software selectable to be either internally generated or externally supplied. The ADC negative voltage reference is internally connected to V<sub>SS</sub>.

The ADC can generate an interrupt upon completion of a conversion and upon threshold comparison. These interrupts can be used to wake up the device from Sleep.

Figure 31-1. ADC Block Diagram



#### **Positive Input Selection Multiplexers**



**Note 1:** The internal input channel selections vary. The inputs shown are all possible input selections. Refer to the "**ADC Positive Input Channel Selection**" table for device-specific selection options.

### 31.1 ADC Configuration

When configuring the ADC the following functions must be considered:

- · Port Configuration
- · Channel Selection
- ADC Voltage Reference Selection
- ADC Conversion Clock Source
- Interrupt Control
- · Result Formatting
- · Conversion Trigger Selection
- · ADC Acquisition Time
- · ADC Precharge Time
- · Additional Sample-and-Hold Capacitor
- · Single/Double Sample Conversion
- · Guard Ring Outputs

### 31.1.1 Port Configuration

The ADC will convert the voltage level on a pin, whether or not the ANSEL bit is set. When converting analog signals, the I/O pin may be configured for analog by setting the associated TRIS and ANSEL bits. Refer to the "I/O Ports" chapter for more information.



**Important:** Analog voltages on any pin defined as a digital input may cause the input buffer to conduct excess current.

#### 31.1.2 Channel Selection

The ADPCH register determines which input channels are connected to the Sample-and-Hold circuit for conversion. When switching channels, it is recommended to have some acquisition time (ADACQ register) before starting the next conversion. Refer to the ADC Operation section for more information.




**Important:** To reduce the chance of measurement error, it is recommended to discharge the Sample-and-Hold capacitor when switching between ADC channels by starting a conversion on a channel connected to  $V_{SS}$  and terminating the conversion after the acquisition time has elapsed. If the ADC does not have a dedicated  $V_{SS}$  input channel, the  $V_{SS}$  selection through the DAC output channel can be used. If the DAC is in use (or the device does not have a DAC), a free input channel can be connected to  $V_{SS}$ , and can be used in place of the DAC.

### 31.1.2.1 Channel Grouping

Channel grouping allows multiple, simultaneous input connections to the ADC. The ADC Channel Group Selection (ADCGxp, x = Group number, p = PORT) registers are used to enable each I/O port's analog input channels. A channel group includes all enabled inputs from each of the group's selection registers. All of the group's input signals are wire-OR'd into a single ADC positive input channel, ADCGx, which can be selected by the ADC Positive Input Channel Selection (PCH) bits.

The example below illustrates the configuration of one channel group.



#### 31.1.3 ADC Voltage Reference

The PREF bits provide control of the positive voltage reference. Refer to the ADREF register for the list of available positive sources.

#### 31.1.4 Conversion Clock

The conversion clock source is selected with the CS bit. When CS = 1, the ADC clock source is an internal fixed-frequency clock referred to as ADCRC. When CS = 0, the ADC clock source is derived from  $F_{OSC}$ .

# ADC - Analog-to-Digital Converter with ...



**Important:** When CS = 0, the clock can be divided using the ADCLK register to meet the ADC clock period requirements.

The time to complete one bit conversion is defined as the  $T_{AD}$ . Refer to Figure 31-2 for the complete timing details of the ADC conversion.

For correct conversion, the appropriate T<sub>AD</sub> specification must be met. Refer to the ADC Timing Specifications table in the "**Electrical Specifications**" chapter of the device data sheet for more details. The table below gives examples of appropriate ADC clock selections.

Table 31-1. ADC Clock Period (T<sub>AD</sub>) vs. Device Operating Frequencies<sup>(1,3)</sup>

ADC Clock	ADCLK		ADC Clock Per	riod (T <sub>AD</sub> ) for Dif	ferent Device Fr	equency (F <sub>OSC</sub> )	
Source	ADCLK	32 MHz	20 MHz	16 MHz	8 MHz	4 MHz	1 MHz
F <sub>OSC</sub> /2	<b>'</b> b0000000	62.5 ns <sup>(2)</sup>	100 ns <sup>(2)</sup>	125 ns <sup>(2)</sup>	250 ns <sup>(2)</sup>	500 ns	2.0 µs
F <sub>OSC</sub> /4	<b>'</b> b000001	125 ns <sup>(2)</sup>	200 ns <sup>(2)</sup>	250 ns <sup>(2)</sup>	500 ns	1.0 µs	4.0 µs
F <sub>OSC</sub> /6	<b>'</b> b000010	187.5 ns <sup>(2)</sup>	300 ns <sup>(2)</sup>	375 ns <sup>(2)</sup>	750 ns	1.5 µs	6.0 µs
F <sub>OSC</sub> /8	<b>'</b> b000011	250 ns <sup>(2)</sup>	400 ns <sup>(2)</sup>	500 ns	1.0 µs	2.0 µs	8.0 µs
F <sub>OSC</sub> /16	<b>'</b> b000111	500 ns	800 ns	1.0 µs	2.0 µs	4.0 µs	16.0 µs <sup>(2)</sup>
F <sub>OSC</sub> /32	<b>'</b> b001111	1.0 µs	1.6 µs	2.0 µs	4.0 µs	8.0 µs	32.0 μs <sup>(2)</sup>
F <sub>OSC</sub> /64	<b>'</b> b0111111	2.0 µs	3.2 µs	4.0 µs	8.0 µs	16.0 µs <sup>(2)</sup>	64.0 µs <sup>(2)</sup>
F <sub>OSC</sub> /128	<b>'</b> b111111	4.0 µs	6.4 µs	8.0 µs	16.0 μs <sup>(2)</sup>	32.0 µs <sup>(2)</sup>	128.0 µs <sup>(2)</sup>
ADCRC	<b>CS</b> = 1	1.0-6.0 µs	1.0-6.0 µs	1.0-6.0 µs	1.0-6.0 µs	1.0-6.0 µs	1.0-6.0 µs

#### Notes:


- Refer to the "Electrical Specifications" chapter of the device data sheet to see the T<sub>AD</sub> parameter for the ADCRC source typical T<sub>AD</sub> value.
- 2. These values violate the required T<sub>AD</sub> time.
- 3. The ADC clock period (T<sub>AD</sub>) and total ADC conversion time can be minimized when the ADC clock is derived from the system clock F<sub>OSC</sub>. However, the ADCRC oscillator source must be used when conversions are to be performed with the device in Sleep mode.



#### Important:

- Except for the ADCRC clock source, any changes in the system clock frequency will change the ADC clock frequency, which may adversely affect the ADC result.
- The internal control logic of the ADC runs off of the clock selected by the CS bit. When the CS bit is set to '1' (ADC runs on ADCRC), there may be unexpected delays in operation when setting the ADC control bits.

Figure 31-2. Analog-to-Digital Conversion Cycles



#### Notes:

- 1. Refer to the ADC Conversion Timing Specifications table in the "Electrical Specifications" chapter of the device data sheet for more details.
- 2. Refer to the ADPRE register for more details.
- 3. Refer to the ADACQ register for more details.

### 31.1.5 Interrupts

The ADC module allows for the ability to generate an interrupt upon completion of an Analog-to-Digital Conversion. The ADC interrupt flag is the ADIF bit in the PIRx register. The ADC interrupt enable is the ADIE bit in the PIEx register. The ADIF bit must be cleared by software.



#### Important:

- The ADIF bit is set at the completion of every conversion, regardless of whether or not the ADC interrupt is enabled.
- The ADC operates during Sleep only when the ADCRC oscillator is selected.


The ADC Interrupt can be generated while the device is operating or while in Sleep. While the device is operating in Sleep mode:

- If ADIE = 1, PEIE = 1, and GIE = 0: An interrupt will wake the device from Sleep. Upon waking from Sleep, the instructions following the SLEEP instruction are executed. The Interrupt Service Routine is not executed.
- If ADIE = 1, PEIE = 1, and GIE = 1: An interrupt will wake the device from Sleep. Upon waking from Sleep, the instruction following the SLEEP instruction is always executed. Then the execution will switch to the Interrupt Service Routine.

#### 31.1.6 Result Formatting

The ADC conversion result can be supplied in two formats: Left justified or right justified. The FM bit controls the output format as shown in the figure below.

Figure 31-3. 10-Bit ADC Conversion Result Format





**Important:** Writes to the ADRES register pair are always right justified, regardless of the selected format mode. Therefore, a data read after writing to ADRES when FM = 0 will be shifted left five places.

### 31.2 ADC Operation

#### 31.2.1 Starting a Conversion

To enable the ADC module, the ON bit must be set to '1'. A conversion may be started by any of the following:

- · Software setting the GO bit to '1'
- An external trigger (source selected by ADACT)
- A Continuous-mode retrigger (see the Continuous Sampling Mode section for more details)



**Important:** The GO bit must not be set in the same instruction that turns on the ADC. Refer to the ADC Conversion Procedure (Basic Mode) section for more details.

### 31.2.2 Completion of a Conversion

When any individual conversion is complete, the existing value in ADRES is written into ADPREV (if PSIS = 0) and the new conversion results appear in ADRES. When the conversion completes, the ADC module will:

- · Clear the GO bit (unless the CONT bit is set)
- · Set the ADIF Interrupt Flag bit
- · Set the MATH bit
- Update ADACC

After every conversion when DSEN = 0, or after every other conversion when DSEN = 1, the following events occur:

- · ADERR is calculated
- ADC Channel Threshold Interrupt (ADCHxIF) is set if ADERR calculation meets threshold comparison

### 31.2.3 ADC Operation During Sleep

The ADC module can operate during Sleep. This requires the ADC clock source to be set to the ADCRC option. When the ADCRC oscillator source is selected, the ADC waits one additional instruction before starting the

## ADC - Analog-to-Digital Converter with ...

conversion. This allows the SLEEP instruction to be executed, which can reduce system noise during the conversion. If the ADC interrupt is enabled, the device will wake up from Sleep when the conversion completes. If the ADC interrupt is disabled, the device remains in Sleep and the ADC module is turned off after the conversion completes, although the ON bit remains set.

#### 31.2.4 **External Trigger During Sleep**

If the external trigger is received during Sleep while the ADC clock source is set to the ADCRC, the ADC module will perform the conversion and set the ADIF bit upon completion.

If an external trigger is received when the ADC clock source is something other than ADCRC, the trigger will be recorded, but the conversion will not begin until the device exits Sleep.

#### 31.2.5 **Auto-Conversion Trigger**

The auto-conversion trigger allows periodic ADC measurements without software intervention. When a rising edge of the selected source occurs, the GO bit is set by hardware.

The auto-conversion trigger source is selected with the ACT bits.

Using the auto-conversion trigger does not ensure proper ADC timing. It is the user's responsibility to ensure that the ADC timing requirements are met.

#### 31,2,6 **ADC Conversion Procedure (Basic Mode)**

This is an example procedure for using the ADC to perform an Analog-to-Digital Conversion:

- Configure Port:
  - Disable pin output driver (refer to the TRISx register)
  - Configure pin as analog (refer to the ANSELx register)
- Configure the ADC module:
  - a. Select ADC conversion clock
  - b. Configure voltage reference
  - Select ADC input channel C.
  - d. Configure precharge (ADPRE) and acquisition (ADACQ) time period
  - Turn on ADC module
- Configure ADC interrupt (optional):
  - a. Clear ADC interrupt flag
  - b. Enable ADC interrupt
  - Enable global interrupt (GIE bit)(1)
- If ADACQ != 0, software must wait the required acquisition time<sup>(2)</sup>.
- Start conversion by setting the GO bit.
- Wait for ADC conversion to complete by one of the following:
  - Polling the GO bit
  - Waiting for the ADC interrupt (if interrupt is enabled)
- Read ADC Result.
- Clear the ADC interrupt flag (if interrupt is enabled). 8.

### Notes:

- With global interrupts disabled (GIE = 0), the device will wake from Sleep, but will not enter an Interrupt Service Routine.
- Refer to the ADC Acquisition Requirements section for more details.

```
Example 31-2. ADC Conversion (Single-Ended Input)
  /*This code block configures the ADC
 for polling, V_{DD} and V_{SS} references,
 ADCRC oscillator
 Conversion start & polling for completion
 are included.
```

```
void main()
initializeSystem();
                        //System Initialize
//Setup ADC
ADCONObits.FM = 1;
                        //Right justify
ADCONObits.CS = 1;
                        //ADCRC Clock
ADPCH = 0x00;
                       //RAO is positive input
TRISAbits.TRISA0 = 1;
                       //Set RAO to input
ANSELAbits.ANSELA0 = 1; //Set RA0 to analog
ADACQ = 32;
                        //Set acquitisition time
ADCONObits.ON = 1;
                        //Turn ADC On
while (1)
   ADCONObits.GO = 1;
                          //Start conversion
   while (ADCONObits.GO); //Wait for conversion done
   resultHigh = ADRESH;
                          //Read result
   resultLow = ADRESL;
                          //Read result
```

## 31.3 ADC Acquisition Requirements

For the ADC to meet its specified accuracy, the charge holding capacitor ( $C_{HOLD}$ ) must be allowed to fully charge to the input channel voltage level. The analog input model is shown in Figure 31-4. The source impedance ( $R_S$ ) and the internal sampling switch ( $R_{SS}$ ) impedance directly affect the time required to charge the capacitor  $C_{HOLD}$ . The sampling switch ( $R_{SS}$ ) impedance varies over the device voltage ( $V_{DD}$ ). The maximum recommended impedance for analog sources is 10 k $\Omega$ . As the source impedance is decreased, the acquisition time may be decreased. After the analog input channel is selected (or changed), an ADC acquisition time must be completed before the conversion can be started. To calculate the minimum acquisition time, Equation 31-1 may be used. This equation assumes an error of 1/2 LSb. The 1/2 LSb error is the maximum error allowed for the ADC to meet its specified resolution.

#### **Equation 31-1. Acquisition Time Example**

Assumptions: Temperature =  $50^{\circ}$ C; External impedance =  $10 \text{ k}\Omega$ ;  $V_{DD}$  = 5.0V

T<sub>ACQ</sub> = Amplifier Settling Time + Hold Capacitor Charging Time + Temperature Coefficient

$$T_{ACO} = T_{AMP} + T_C + T_{COFF}$$

$$T_{ACQ} = 2 \mu s + T_C + \left[ \left( Temperature - 25^{\circ}C \right) \left( 0.05 \mu s / ^{\circ}C \right) \right]$$

The value for T<sub>C</sub> can be approximated with the following equations:

$$V_{APPLIED} \left( 1 - \frac{1}{\left(2^{n+1}\right) - 1} \right) = V_{CHOLD}$$
; [1]  $V_{CHOLD}$  charged to within ½ LSb

$$V_{APPLIED} \left(1 - e^{\frac{-T_C}{RC}}\right) = V_{CHOLD}$$
; [2]  $V_{CHOLD}$  charge response to  $V_{APPLIED}$ 

$$V_{APPLIED} \left(1 - e^{\frac{-T_C}{RC}}\right) = V_{APPLIED} \left(1 - \frac{1}{\left(2^{n+1}\right) - 1}\right)$$
; Combining [1] and [2]

Note: Where n = ADC resolution in bits

Solving for T<sub>C</sub>:

$$T_C = -C_{HOLD}(R_{IC} + R_{SS} + R_S) \ln (1/2047)$$

$$T_C = -10 \, pF(1 \, k\Omega + 7 \, k\Omega + 10 \, k\Omega) \, ln \, (0.0004885)$$

$$T_C = 1.37 \, \mu s$$

Therefore:

$$T_{ACQ} = 2 \mu s + 1.37 \mu s + [(50^{\circ}C - 25^{\circ}C) (0.05 \mu s/^{\circ}C)]$$
  
 $T_{ACQ} = 4.62 \mu s$ 




#### Important:

- The reference voltage ( $V_{\text{REF}}$ ) has no effect on the equation, since it cancels itself out
- The charge holding capacitor (C<sub>HOLD</sub>) is not discharged after each conversion
- The maximum recommended impedance for analog sources is 10 k $\Omega$ . This is required to meet the pin leakage specification.

Figure 31-4. Analog Input Model

Note:



Legend: CPIN = Input Capacitance

ILEAKAGE = Leakage Current at the pin due to various junctions


= Interconnect Resistance Rs = Source Impedance VA

Vт SS

Rss CHOLD

Sampling Switch Rss = Analog Voltage  $(K\Omega)$ = Diode Forward Voltage = Sampling Switch = Resistance of the Sampling Switch = Sample/Hold Capacitance 3 4 5 6 VDD (V) 1. Refer to the "Electrical Specifications" chapter of the device data sheet for more details.


Figure 31-5. ADC Transfer Function



# 31.4 Computation Operation

The ADC module hardware is equipped with post-conversion computation features. These features provide post-processing functions such as digital filtering/averaging and threshold comparison. Based on computation results, the module can be configured to take additional samples or stop conversions and an interrupt may be asserted.

Figure 31-6. Computational Features Simplified Block Diagram



The operation of the ADC computational features is controlled by the MD bits.

The module can be operated in one of five modes:

- **Basic:** This is a Legacy mode. In this mode, ADC conversion occurs on single (DSEN = 0) or double (DSEN = 1) samples. ADIF is set after each conversion is complete. ADCHxIF is set according to the Calculation mode.
- Accumulate: With each trigger, the ADC conversion result is added to the accumulator and ADCNT increments.
   ADIF is set after each conversion. ADCHxIF is set according to the Calculation mode.

# PIC16F18015/25/44/45

## ADC - Analog-to-Digital Converter with ...

- Average: With each trigger, the ADC conversion result is added to the accumulator. When the RPT number of samples have been accumulated, a threshold test is performed. Upon the next trigger, the accumulator is cleared. For the subsequent tests, additional RPT samples are required to be accumulated.
- Burst Average: At the trigger, the accumulator is cleared. The ADC conversion results are then collected repetitively until RPT samples are accumulated and finally the threshold is tested.
- Low-Pass Filter (LPF): With each trigger, the ADC conversion result is sent through a filter. When RPT samples have occurred, a threshold test is performed. Every trigger after that, the ADC conversion result is sent through the filter and another threshold test is performed.

The five modes are summarized in the following table.

Table 31-2. Computation Modes

	:	Register Clear Event	Value after Cycle <sup>(1)</sup>	e <sup>(1)</sup> Completion	T.	Threshold Operations	Su	Value at	Value at ADCHmIF Interrupt	rupt
Miode	2	ADACC and CNT	ADACC	ADCNT	Retrigger	Threshold Test	Interrupt	AOV	ADFLTR	ADCNT
Basic	0	ACLR = 1	Unchanged	Unchanged	N <sub>O</sub>	Every Sample	If threshold=true	N/A	N/A	count
Accumulate	-	<b>ACLR</b> = 1	S1 + ADACC or (S2-S1) <sup>(2)</sup> + ADACC	If (ADCNT = 0xFF): ADCNT, otherwise: ADCNT+1	o Z	Every Sample	If threshold=true	ADACC	ADACC/2 <sup>CRS</sup>	count
Average	2	ACLR = 1 or ADCNT ≥ ADRPT at GO set or retrigger	S1 + ADACC or (S2-S1) + ADACC	If (ADCNT = 0×FF): ADCNT, otherwise: ADCNT+1	o Z	If ADCNT ≥ ADRPT	If threshold=true	ADACC Overflow	ADACC/2 <sup>CRS</sup>	count
Burst Average	က	ACLR = 1 or at GO set or retrigger	Each repetition: same as Average End with sum of all samples	Each repetition: same as Average End with ADCNT = ADRPT	Repeat while ADCNT < ADRPT	If ADCNT ≥ ADRPT	If threshold=true	ADACC Overflow	ADACC/2 <sup>CRS</sup> ADRPT	ADRPT
Low-pass Filter	4	ACLR = 1	S1 + ADACC- ADACC/ 2 <sup>CRS</sup> or (S2-S1) + ADACC-ADACC/ 2 <sup>CRS</sup>	If (ADCNT = 0xFF): ADCNT, otherwise: ADCNT+1	o Z	If ADCNT ≥ ADRPT	If threshold=true	ADACC	ADACC/2 <sup>CRS</sup> (Filtered Value)	count
Notes:										

When DSEN = 0, Cycle means one conversion. When DSEN = 1, Cycle means two conversions. -: 2

S1 and S2 are abbreviations for Sample 1 and Sample 2, respectively. When DSEN = 0, S1 = ADRES; when DSEN = 1, S1 = ADPREV and S2 = ADRES.

### 31.4.1 Digital Filter/Average

The digital filter/average module consists of an accumulator with data feedback options, and control logic to determine when threshold tests need to be applied. The accumulator can be accessed through the ADACC register.

Upon each trigger event (the GO bit set or external event trigger), the ADC conversion result is added to or subtracted from the accumulator. If the accumulated value exceeds 2<sup>(accumulator\_width)</sup> - 1 = 2<sup>18</sup> - 1 = 262143, the AOV overflow bit is set.

The number of samples to be accumulated is determined by the ADRPT (ADC Repeat Setting) register. Each time a sample is added to the accumulator, the ADCNT register is incremented. Once the ADRPT samples are accumulated (ADCNT = ADRPT), the accumulator may be cleared automatically depending on ADC Operation mode. An accumulator clear command can be issued in software by setting the ACLR bit. Setting the ACLR bit will also clear the AOV (Accumulator Overflow) bit, as well as the ADCNT register. The ACLR bit is cleared by the hardware when accumulator clearing action is complete.



**Important:** When ADC is operating from ADCRC, up to five ADCRC clock cycles are required to execute the ADACC clearing operation.

The CRS bits control the data shift on the accumulator result, which effectively divides the value in the accumulator registers. For the Accumulate mode of the digital filter, the shift provides a simple scaling operation. For the Average/Burst Average mode, the calculated average is only accurate when the number of samples agrees with the number of bits shifted. For the Low-Pass Filter mode, the shift is an integral part of the filter, and determines the cutoff frequency of the filter. Table 31-3 shows the -3 dB cutoff frequency in  $\omega T$  (radians) and the highest signal attenuation obtained by this filter at Nyquist frequency ( $\omega T = \pi$ ).

Table 31-3. Low-Pass Filter -3 dB Cutoff Frequency

CRS	ωT (radians) @ -3 dB Frequency	dB @ F <sub>Nyquist</sub> = 1/(2T)
1	0.72	-9.5
2	0.284	-16.9
3	0.134	-23.5
4	0.065	-29.8
5	0.032	-36.0
6	0.016	-42.0

#### 31.4.2 Basic Mode

Basic mode (MD = 'b000) disables all additional computation features. In this mode, no accumulation occurs but threshold error comparison is performed. Double sampling, Continuous mode, and all CVD features are still available, but no digital filter/average calculations are performed.

#### 31.4.3 Accumulate Mode

In Accumulate mode (MD = `b001), after every conversion, the ADC result is added to the ADACC register. The ADACC register is right-shifted by the value of the CRS bits. This right-shifted value is copied into the ADFLTR register. The Formatting mode does not affect the right-justification of the ADACC or ADFLTR values. Upon each sample, ADCNT is incremented, counting the number of samples accumulated. After each sample and accumulation, the ADFLTR value has a threshold comparison performed on it (see the Threshold Comparison section) and the ADCHxIF interrupt may trigger.

#### 31.4.4 Average Mode

In Average mode (MD = `b010), the ADACC registers accumulate with each ADC sample, much as in Accumulate mode, and the ADCNT register increments with each sample. The ADFLTR register is also updated with the right-shifted value of the ADACC register. The value of the CRS bits governs the number of right shifts. However, in Average mode, the threshold comparison is performed upon ADCNT being greater than or equal to a user-defined

## ADC - Analog-to-Digital Converter with ...

ADRPT value. In this mode, when ADRPT =  $2^{CRS}$ , the final accumulated value will be divided by the number of samples, allowing for a threshold comparison operation on the average of all gathered samples.

#### 31.4.5 Burst Average Mode

The Burst Average mode (MD = `b011) acts the same as the Average mode in most respects. The one way it differs is that it continuously retriggers ADC sampling until the CNT value is equal to RPT, even if Continuous Sampling mode (see Continuous Sampling Mode) is not enabled. This provides a threshold comparison on the average of a short burst of ADC samples.

#### 31.4.6 Low-Pass Filter Mode

The Low-Pass Filter mode (MD = 'b100) acts similarly to the Average mode in how it handles samples; it accumulates samples until the CNT value is greater than or equal to RPT, then triggers a threshold comparison. But, instead of a simple average, it performs a low-pass filter operation on all of the samples, reducing the effect of high-frequency noise on the total, then performs a threshold comparison on the results. In this mode, the CRS bits determine the cutoff frequency of the low-pass filter (as demonstrated by Digital Filter/Average). Refer to the Computation Operation section for a more detailed description of the mathematical operation.

For more information about Low-Pass Filter mode, refer to the following Microchip application note, available in the corporate website (www.microchip.com):

• AN2749, "PIC18 12-bit ADCC in Low-Pass Filter Mode"

#### 31.4.7 Threshold Comparison

At the end of each computation:

- The conversion results are captured at the end-of-conversion.
- The error (ADERR) is calculated based on a difference calculation which is selected by the CALC bits. The value can be one of the following calculations:
  - The first derivative of single measurements
  - The CVD result when double sampling is enabled
  - The current result vs. setpoint value in the ADSTPT register
  - The current result vs. the filtered/average result
  - The first derivative of the filtered/average value
  - Filtered/average value vs. setpoint value in the ADSTPT register
- The result of the calculation (ADERR) is compared to the upper and lower thresholds, ADUTH and ADLTH
  registers, to set the UTHR and LTHR Status bits. The threshold logic is selected by the TMD bits. The threshold
  trigger option can be one of the following:
  - Never interrupt
  - Error is less than lower threshold
  - Error is greater than or equal to lower threshold
  - Error is between thresholds (inclusive)
  - Error is outside of thresholds
  - Error is less than or equal to upper threshold
  - Error is greater than upper threshold
  - Always interrupt regardless of threshold test results
  - If the Threshold condition is met, the channel threshold interrupt flag ADCHxIF is set.



#### Important:

- · The threshold tests are signed operations.
- If the AOV bit is set, a threshold interrupt is signaled. It is good practice for threshold interrupt handlers to verify the validity of the threshold by checking the AOV bit.

### 31.4.8 Repetition and Sampling Options

#### 31.4.8.1 Continuous Sampling Mode

Setting the CONT bit automatically retriggers a new conversion cycle after updating the ADACC register. That means the GO bit remains set to generate automatic retriggering. If SOI = 1, a Threshold Interrupt condition will clear the GO bit and the conversion will stop.


#### 31.4.8.2 Double Sample Conversion

Double sampling is enabled by setting the DSEN bit. When this bit is set, two conversions are required before the module calculates the threshold error. Each conversion must be triggered separately when CONT = 0, but will repeat automatically form a single trigger when CONT = 1. The first conversion will set the MATH bit and update the ADACC register, but will not calculate ADERR or trigger ADCHnIF. When the second conversion completes, the first value is transferred to ADPREV (depending on the setting of PSIS) and the value of the second conversion is placed into ADRES. Only upon the completion of the second conversion is ADERR calculated and ADCHnIF triggered (depending on the value of CALC).

#### 31.4.9 Capacitive Voltage Divider (CVD) Features

The ADC module contains several features that allow the user to perform a relative capacitance measurement on any ADC channel using the internal ADC Sample-and-Hold capacitance as a reference. This relative capacitance measurement can be used to implement capacitive touch or proximity sensing applications. The following figure shows the basic block diagram of the CVD portion of the ADC module.

Figure 31-7. Hardware Capacitive Voltage Divider Block Diagram



This is an example to configure ADC for CVD operation:

- 1. Configure Port:
  - a. Disable pin output driver (refer to the TRISx register)
  - b. Configure pin as analog (refer to the ANSELx register)
- 2. Configure the ADC module:
  - a. Select ADC conversion clock
  - b. Configure voltage reference
  - c. Select ADC input channel
  - d. Configure precharge (ADPRE) and acquisition (ADACQ) time period
  - e. Select precharge polarity (PPOL)
  - f. Enable Double Sampling (DSEN)

# PIC16F18015/25/44/45

## ADC - Analog-to-Digital Converter with ...

- g. Turn on ADC module
- Configure ADC interrupt (optional):
  - a. Clear ADC interrupt flag
  - b. Enable ADC interrupt
  - c. Enable global interrupt (GIE bit)<sup>(1)</sup>
- 4. Start double sample conversion by setting the GO bit.
- 5. Wait for ADC conversion to complete by one of the following:
  - Polling the GO bit
  - Waiting for the ADC interrupt (if interrupt is enabled)
- 6. Second ADC conversion depends on the state of CONT:
  - a. If CONT = 1, both conversion will repeat automatically form a single trigger.
  - If CONT = 0, each conversion must be triggered separately.
- The ADERR register contains the CVD result.
- Clear the ADC interrupt flag (if interrupt is enabled).

#### Note:

1. With global interrupts disabled (GIE = 0), the device will wake from Sleep, but will not enter an Interrupt Service Routine.

#### 31.4.9.1 CVD Operation

A CVD operation begins with the ADC's internal Sample-and-Hold capacitor ( $C_{HOLD}$ ) being disconnected from the path, which connects it to the external capacitive sensor node. While disconnected,  $C_{HOLD}$  is precharged to  $V_{DD}$  or discharged to  $V_{SS}$ . If the PCSC bit is clear, the sensor node is either discharged or charged to  $V_{SS}$  or  $V_{DD}$ , respectively to the opposite level of  $C_{HOLD}$ . If PCSC is set, the external capacitive sensor node receives no precharge. When the precharge phase is complete, the  $V_{DD}/V_{SS}$  bias paths for the two nodes are disconnected and the paths between  $C_{HOLD}$  and the external sensor node is reconnected, at which time the acquisition phase of the CVD operation begins. During acquisition, a capacitive voltage divider is formed between the precharged  $C_{HOLD}$  and sensor nodes, which results in a final voltage level setting on  $C_{HOLD}$ , which is determined by the capacitances and precharge levels of the two nodes. After acquisition, the ADC converts the voltage level on  $C_{HOLD}$ . This process is then repeated with the selected precharge levels inverted for both the  $C_{HOLD}$  and the sensor nodes. The waveform for two CVD measurements, which is known as differential CVD measurement, is shown in the following figure.




Figure 31-8. Differential CVD Measurement Waveform

**Note 1:** External Capacitive Sensor voltage during the conversion phase may vary as per the configuration of the corresponding pin.

#### 31.4.9.2 Precharge Control

The precharge stage is the period of time that brings the external channel and internal Sample-and-Hold capacitor to known voltage levels. Precharge is enabled by writing a nonzero value to the ADPRE register. This stage is initiated when an ADC conversion begins, either from setting the GO bit, a Special Event Trigger, or a conversion restart from the computation functionality. If the ADPRE register is cleared when an ADC conversion begins, this stage is skipped.

The Precharge Sample Capacitor Only (PCSC) bit can be used to disable the precharge stage to the external channel.

During the precharge time,  $C_{HOLD}$  is disconnected from the outer portion of the sample path that leads to the external capacitive sensor and is connected to either  $V_{DD}$  or  $V_{SS}$ , depending on the value of the PPOL bit. At the same time, when PCSC is clear (PCSC = 0), the port pin logic of the selected analog channel is overridden to drive a digital high or low out, to precharge the outer portion of the ADC's sample path, which includes the external sensor. The output polarity of this override is determined by the PPOL bit such that the external sensor cap is charged opposite that of the internal  $C_{HOLD}$  cap. If PCSC is set (PCSC = 1), the outer portion of the ADC's sample path is disconnected, preventing the precharge from occurring on the external channel. The amount of time for precharge is controlled by the ADPRE register.



**Important:** The external charging overrides the TRIS/LAT/Guard outputs setting of the respective I/O pin. If there is a device attached to this pin, the PCSC bit will be set, or precharge will not be used.

#### 31.4.9.3 Acquisition Control for CVD (ADPRE > 0)

The acquisition stage allows time for the voltage on the internal Sample-and-Hold capacitor to charge or discharge from the selected analog channel. This acquisition time is controlled by the ADACQ register. The acquisition stage begins when precharge stage ends.

At the start of the acquisition stage, the port pin logic of the selected analog channel is overridden to turn off the digital high/low output drivers so they do not affect the final result of the charge averaging. Also, the selected ADC channel is connected to  $C_{HOLD}$ . This allows charge averaging to proceed between the precharged channel and the  $C_{HOLD}$  capacitor.



**Important:** When ADPRE > 0, setting ADACQ to '0' will set a maximum acquisition time. When precharge is disabled, setting ADACQ to '0' will disable hardware acquisition time control.

#### 31.4.9.4 Guard Ring Outputs

Figure 31-9 shows a typical guard ring circuit.  $C_{GUARD}$  represents the capacitance of the guard ring trace placed on the PCB. The user selects values for  $R_A$  and  $R_B$  that will create a voltage profile on  $C_{GUARD}$ , which will match the selected acquisition channel.


The purpose of the guard ring is to generate a signal in phase with the CVD sensing signal to minimize the effects of the parasitic capacitance on sensing electrodes. It also can be used as a mutual drive for mutual capacitive sensing. For more information about active guard and mutual drive, refer to the following Microchip application note, available on the corporate website (www.microchip.com):

• AN1478, "mTouch<sup>TM</sup> Sensing Solution Acquisition Methods Capacitive Voltage Divider"

The ADC has two guard ring drive outputs, ADGRDA and ADGRDB. These outputs are routed through PPS controls to I/O pins. Refer to the "Peripheral Pin Select (PPS) Module" chapter for more details. The polarity of these outputs is controlled by the GPOL and IPEN bits.

At the start of the first precharge stage, both outputs are set to match the GPOL bit. Once the acquisition stage begins, ADGRDA changes polarity, while ADGRDB remains unchanged. When performing a double sample conversion, setting the IPEN bit causes both guard ring outputs to transition to the opposite polarity of GPOL at the start of the second precharge stage, and ADGRDA toggles again for the second acquisition. For more information on the timing of the guard ring output, refer to Figure 31-10.

Figure 31-9. Guard Ring Circuit






Figure 31-10. Differential CVD with Guard Ring Output Waveform

Note 1: External Capacitive Sensor voltage during the conversion phase may vary as per the configuration of the corresponding pin.

#### 31.4.9.5 Additional Sample-and-Hold Capacitance

Additional capacitance can be added in parallel with the internal Sample-and-Hold capacitor (C<sub>HOLD</sub>) by using the ADCAP register. This register selects a digitally programmable capacitance that is added to the ADC conversion bus, increasing the effective internal capacitance of the Sample-and-Hold capacitor in the ADC module. This is used to improve the match between internal and external capacitance for a better sensing performance. The additional capacitance does not affect analog performance of the ADC because it is not connected during conversion.

# 31.5 Register Definitions: ADC Control

Long bit name prefixes for the ADC peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 31-4. ADC Long Bit Name Prefixes

Peripheral	Bit Name Prefix
ADC	AD

#### 31.5.1 ADCON0

Name: ADCON0 Offset: 0x1D26

### ADC Control Register 0

Bit	7	6	5	4	3	2	1	0
	ON	CONT		cs		FM		GO
Access	R/W	R/W	•	R/W	•	R/W		R/W/HC/HS
Reset	0	0		0		0		0

### Bit 7 - ON ADC Enable

Value	Description
1	ADC is enabled
0	ADC is disabled

#### Bit 6 - CONT ADC Continuous Operation Enable

Value	Description
1	GO is retriggered upon completion of each conversion trigger until ADTIF is set (if SOI is set) or until
	GO is cleared (regardless of the value of SOI)
0	ADC is cleared upon completion of each conversion trigger

#### Bit 4 - CS ADC Clock Selection

1	/alue	Description
[1		Clock supplied from ADCRC dedicated oscillator
(	)	Clock supplied by F <sub>OSC</sub> , divided according to the ADCLK register

### Bit 2 - FM ADC Results Format/Alignment Selection

Value	Description
1	ADRES and ADPREV data are right justified
0	ADRES and ADPREV data are left justified

#### Bit 0 - GO ADC Conversion Status<sup>(1,2)</sup>

	7.2.5.5.11.11.11.11.11.11.11.11.11.11.11.11
Value	Description
1	ADC conversion cycle in progress. Setting this bit starts an ADC conversion cycle. The bit is cleared by
	hardware as determined by the CONT bit.
0	ADC conversion completed/not in progress

#### Notes:

- 1. This bit requires the ON bit to be set.
- If cleared by software while a conversion is in progress, the results of the conversion up to this point will be transferred to ADRES and the state machine will be reset, but the ADIF Interrupt Flag bit will not be set; filter and threshold operations will not be performed.

### 31.5.2 ADCON1

Name: ADCON1 Offset: 0x1D27

ADC Control Register 1

Bit	7	6	5	4	3	2	1	0
	PPOL	IPEN	GPOL				PCSC	DSEN
Access	R/W	R/W	R/W				R/W	R/W
Reset	0	0	0				0	0

### Bit 7 - PPOL Precharge Polarity

Action During 1st Precharge Stage

Value	Condition	Description
Х	ADPRE = 0	Bit has no effect
1	ADPRE > 0	External analog I/O pin is connected to $V_{DD}$ Internal AD sampling capacitor ( $C_{HOLD}$ ) is connected to $V_{SS}$
0	ADPRE > 0	External analog I/O pin is connected to $V_{SS}$ Internal AD sampling capacitor ( $C_{HOLD}$ ) is connected to $V_{DD}$

### Bit 6 - IPEN A/D Inverted Precharge Enable

Va	lue	Condition	Description
X		DSEN = 0	Bit has no effect
1		DSEN = 1	The precharge and guard signals in the second conversion cycle are the opposite polarity of the first cycle
0		DSEN = 1	Both Conversion cycles use the precharge and guards specified by PPOL and GPOL

### Bit 5 - GPOL Guard Ring Polarity Selection

Value	Description
1	ADC guard Ring outputs start as digital high during Precharge stage
0	ADC guard Ring outputs start as digital low during Precharge stage

#### Bit 1 - PCSC Precharge Sample Capacitor Only

	Bit 1 1 900 Fredharge dampie dapacitor only				
Value	Description				
1	Precharge only applies to the internal sampling capacitor				
0	Precharge applies to both the internal sampling capacitor and the external I/O pin				

### Bit 0 - DSEN Double-Sample Enable

Value	Description	
1	Two conversions are processed as a pair. The selected computation is performed after every second	
	conversion.	
0	Selected computation is performed after every conversion	

#### 31.5.3 ADCON2

Name: ADCON2 Offset: 0x1D28

ADC Control Register 2

Bit	7	6	5	4	3	2	1	0
	PSIS		CRS[2:0]		ACLR		MD[2:0]	
Access	R/W	R/W	R/W	R/W	R/W/HC	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

#### Bit 7 - PSIS ADC Previous Sample Input Select

Value	Description
1	ADFLTR is transferred to ADPREV at the start of conversion
0	ADRES is transferred to ADPREV at the start of conversion

#### Bits 6:4 - CRS[2:0] ADC Accumulated Calculation Right Shift Select

Value	Condition	Description
1 to 6	MD = 'b100	Low-pass filter time constant is 2 <sup>CRS</sup> , filter gain is 1:1 <sup>(2)</sup>
1 to 6	MD = 'b011 to 'b001	The accumulated value is right-shifted by CRS (divided by 2 <sup>CRS</sup> ) <sup>(1,2)</sup>
X	MD = 'b0000 or 'b111	These bits are ignored

### Bit 3 - ACLR A/D Accumulator Clear Command<sup>(3)</sup>

Value	Description
1	Registers ADACC and ADCNT and the AOV bit are cleared
0	Clearing action is complete (or not started)

### Bits 2:0 - MD[2:0] ADC Operating Mode Selection<sup>(4)</sup>

Value	Description
111-101	Reserved
100	Low-Pass Filter mode
011	Burst Average mode
010	Average mode
001	Accumulate mode
000	Basic (Legacy) mode


### Notes:

- To correctly calculate an average, the number of samples (set in ADRPT) must be 2<sup>CRS</sup>.
- 2. CRS = 'b111 and 'b000 are reserved.
- 3. This bit is cleared by hardware when the accumulator operation is complete; depending on oscillator selections, the delay may be many instructions.
- 4. See the "Computation Operation" section for full mode descriptions.

### 31.5.4 ADCON3

Name: ADCON3 Offset: 0x1D29

ADC Control Register 3



Bits 6:4 - CALC[2:0] ADC Error Calculation Mode Select

### Table 31-5. ADC Error Calculation Mode

		ADERR		
CALC	DSEN = 0 Single-Sample Mode	DSEN = 1 CVD Double-Sample Mode <sup>(1)</sup>	Application	
111	Reserved	Reserved	Reserved	
110	Reserved	Reserved	Reserved	
101	ADFLTR-ADSTPT	ADFLTR-ADSTPT	Average/filtered value vs. setpoint	
100	ADPREV-ADFLTR	ADPREV-ADFLTR	First derivative of filtered value <sup>(3)</sup> (negative)	
011	Reserved	Reserved	Reserved	
010	ADRES-ADFLTR	(ADRES-ADPREV)-ADFLTR	Actual result vs. averaged/filtered value	
001	ADRES-ADSTPT	(ADRES-ADPREV)-ADSTPT	Actual result vs. setpoint	
000	ADRES-ADPREV	ADRES-ADPREV	First derivative of single measurement <sup>(2)</sup> Actual CVD result <sup>(2)</sup>	

## Notes:

- 1. When DSEN = 1 and PSIS = 0, ADERR is computed only after every second sample.
- 2. When PSIS = 0.
- 3. When PSIS = 1.

### Bit 3 - SOI ADC Stop-on-Interrupt

Value	Condition	Description
value		
X	CONT = 0	This bit is not used
1	CONT = 1	GO is cleared when the Threshold conditions are met, otherwise the conversion is
		retriggered
0	CONT = 1	GO is not cleared by hardware, must be cleared by software to stop retriggers

### Bits 2:0 - TMD[2:0] Threshold Interrupt Mode Select

Value	Description
111	Interrupt regardless of threshold test results
110	Interrupt if ADERR > ADUTH
101	Interrupt if ADERR ≤ ADUTH
100	Interrupt if ADERR < ADLTH or ADERR > ADUTH
011	Interrupt if ADERR > ADLTH and ADERR < ADUTH
010	Interrupt if ADERR ≥ ADLTH
001	Interrupt if ADERR < ADLTH
000	Never interrupt

### 31.5.5 ADSTAT

Name: ADSTAT Offset: 0x1D2A

**ADC Status Register** 

Bit	7	6	5	4	3	2	1	0
[	AOV	UTHR	LTHR	MATH			STAT[2:0]	
Access	R/C/HS/HC	R	R	R/W/HS		R	R	R
Reset	0	0	0	0		0	0	0

### Bit 7 - AOV ADC Accumulator Overflow

	Value	Description
ſ	1	ADACC or ADFLTR or ADERR registers have overflowed
	0	ADACC, ADFLTR and ADERR registers have not overflowed

#### Bit 6 - UTHR ADC Module Greater-than Upper Threshold Flag

Value	Description
1	ADERR > ADUTH
0	ADERR ≤ ADUTH

#### Bit 5 - LTHR ADC Module Less-than Lower Threshold Flag

	<b>U</b>
Value	Description
1	ADERR < ADLTH
0	ADERR ≥ ADLTH

#### Bit 4 - MATH ADC Module Computation Status

ADC Module Computation Status(1)

Value	e Description
1	Registers ADACC, ADFLTR, ADUTH, ADLTH and the AOV bit are updating or have already updated
0	Associated registers/bits have not changed since this bit was last cleared

### Bits 2:0 - STAT[2:0] ADC Module Cycle Multi-Stage Status

Value	Description
111	ADC module is in 2 <sup>nd</sup> conversion stage
110	ADC module is in 2 <sup>nd</sup> acquisition stage
101	ADC module is in 2 <sup>nd</sup> precharge stage
100	ADC computation is suspended between 1st and 2nd sample; the computation results are incomplete
	and awaiting data from the 2nd sample <sup>(2,3)</sup>
011	ADC module is in 1 <sup>st</sup> conversion stage
010	ADC module is in 1 <sup>st</sup> acquisition stage
001	ADC module is in 1st precharge stage
000	ADC module is not converting


#### Notes:

- 1. MATH bit cannot be cleared by software while STAT = 'b100.
- If ADC clock source is ADCRC, and F<sub>OSC</sub> < ADCRC, the indicated status may not be valid.</li>
- 3. STAT = b100 appears between the two triggers when DSEN = 1 and CONT = 0.

### 31.5.6 ADCLK

Name: ADCLK Offset: 0x1D2D

ADC Clock divider Register



Bits 5:0 - CS[5:0] ADC Clock divider Select


	object in the object and object
Value	Description
n	ADC Clock frequency = $F_{OSC}/(2*(n+1))$

**Note:** ADC Clock divider is only available if  $F_{OSC}$  is selected as the ADC clock source (CS = 0).

### 31.5.7 ADREF

Name: ADREF Offset: 0x1D2B

ADC Reference Selection Register




Bits 1:0 - PREF[1:0] ADC Positive Voltage Reference Selection

Value	Description
11	V <sub>REF</sub> + is connected to internal Fixed Voltage Reference (FVR) module
10	V <sub>REF</sub> + is connected to external V <sub>REF</sub> +
01	Reserved
00	V <sub>REF</sub> + is connected to V <sub>DD</sub>

### 31.5.8 ADPCH

Name: ADPCH Offset: 0x1D1F

ADC Positive Channel Selection Register



Bits 5:0 - PCH[5:0] ADC Positive Input Channel Selection

### Table 31-6. ADC Positive Input Channel Selections

PCH	ADC Positive Channel Input
111111	Fixed Voltage Reference (FVR) Buffer 2 <sup>(1)</sup>
111110	Fixed Voltage Reference (FVR) Buffer 1 <sup>(1)</sup>
111101-111100	Reserved
111011	Temperature Indicator <sup>(2)</sup>
111010	V <sub>SS</sub> (Analog Ground)
111001-011000	Reserved
010111	RC7/ANC7 <sup>(3)</sup>
010110	RC6/ANC6 <sup>(3)</sup>
010101	RC5/ANC5 <sup>(4)</sup>
010100	RC4/ANC4 <sup>(4)</sup>
010011	RC3/ANC3 <sup>(4)</sup>
010010	RC2/ANC2 <sup>(4)</sup>
010001	RC1/ANC1 <sup>(4)</sup>
010000	RC0/ANC0 <sup>(4)</sup>
001111	RB7/ANB7 <sup>(3)</sup>
001110	RB6/ANB6 <sup>(3)</sup>
001101	RB5/ANB5 <sup>(3)</sup>
001100	RB4/ANB4 <sup>(3)</sup>
001011-000110	Reserved
000101	RA5/ANA5
000100	RA4/ANA4
000011	ADCG1
000010	RA2/ANA2
000001	RA1/ANA1
000000	RA0/ANA0


#### Notes:

- 1. Refer to the "Fixed Voltage Reference Module" chapter for more details.
- 2. Refer to the "Temperature Indicator Module" chapter for more details.
- 3. 20-pin devices only.
- 4. 14/20-pin devices only.

### 31.5.9 ADPRE

Name: ADPRE Offset: 0x1D24

ADC Precharge Time Control Register



Bits 12:0 - PRE[12:0] Precharge Time Select

Table 31-7. Precharge Time

ADPRE	Precharge Time		
ADFRE	CS != ADCRC	CS = ADCRC	
1 1111 1111 1111	8191 clocks of F <sub>OSC</sub>	8191 clocks of ADCRC	
1 1111 1111 1110	8190 clocks of F <sub>OSC</sub>	8190 clocks of ADCRC	
1 1111 1111 1101	8189 clocks of F <sub>OSC</sub>	8189 clocks of ADCRC	
0 0000 0000 0010	2 clocks of F <sub>OSC</sub>	2 clocks of ADCRC	
0 0000 0000 0001	1 clocks of F <sub>OSC</sub>	1 clocks of ADCRC	
0 0000 0000 0000	Not included in the	e data conversion cycle	


**Notes:** The individual bytes in this multibyte register can be accessed with the following register names:

- ADPREH: Accesses the high byte ADPRE[12:8]
- ADPREL: Accesses the low byte ADPRE[7:0]

### 31.5.10 ADACQ

Name: ADACQ Offset: 0x1D21

ADC Acquisition Time Control Register



Bits 12:0 - ACQ[12:0] Acquisition (charge share time) Select

Table 31-8. Acquisition Time

ADACQ	Acquisition Time		
ADACQ	CS != ADCRC	CS = ADCRC	
1 1111 1111 1111	8191 clocks of F <sub>OSC</sub>	8191 clocks of ADCRC	
1 1111 1111 1110	8190 clocks of F <sub>OSC</sub>	8190 clocks of ADCRC	
1 1111 1111 1101	8189 clocks of F <sub>OSC</sub>	8189 clocks of ADCRC	
0 0000 0000 0010	2 clocks of F <sub>OSC</sub>	2 clocks of ADCRC	
0 0000 0000 0001	1 clocks of F <sub>OSC</sub>	1 clocks of ADCRC	
0 0000 0000 0000	Not included in the	data conversion cycle <sup>(1)</sup>	
Note:			
1. If ADPRE is not equal to '0', the	n ACQ = 0 means Acquisition Time is	8192 clocks of F <sub>OSC</sub> or ADCRC.	

Notes: The individual bytes in this multibyte register can be accessed with the following register names:


- ADACQH: Accesses the high byte ADACQ[12:8]
- ADACQL: Accesses the low byte ADACQ[7:0]

# ADC - Analog-to-Digital Converter with ...

### 31.5.11 ADCAP

Name: ADCAP Offset: 0x1D23

ADC Additional Sample Capacitor Selection Register



Bits 4:0 - CAP[4:0] ADC Additional Sample Capacitor Selection

Value	Description	
1 to 31	Number of pF in the additional capacitance	
0	No additional capacitance	


# PIC16F18015/25/44/45

# ADC - Analog-to-Digital Converter with ...

### 31.5.12 ADRPT

Name: ADRPT Offset: 0x1D1A

**ADC Repeat Setting Register** 



### Bits 7:0 - RPT[7:0] ADC Repeat Threshold

Determines the number of times that the ADC is triggered for a threshold check. When CNT reaches this value, the error threshold is checked. Used when the computation mode is Low-Pass Filter, Burst Average, or Average. See the "Computation Operation" section for more details.


# PIC16F18015/25/44/45

# ADC - Analog-to-Digital Converter with ...

### 31.5.13 ADCNT

Name: ADCNT Offset: 0x1D19

**ADC Repeat Counter Register** 



### Bits 7:0 - CNT[7:0] ADC Repeat Count

Counts the number of times that the ADC is triggered before the threshold is checked. When this value reaches RPT, the threshold is checked. Used when the computation mode is Low-Pass Filter, Burst Average, or Average. See the "Computation Operation" section for more details.

### 31.5.14 ADFLTR

Name: ADFLTR Offset: 0x1D14

ADC Filter Register

Bit	15	14	13	12	11	10	9	8	
	FLTR[15:8]								
Access	R	R	R	R	R	R	R	R	
Reset	x	X	x	x	X	x	x	X	
Bit	7	6	5	4	3	2	1	0	
	FLTR[7:0]								
Access	R	R	R	R	R	R	R	R	
Reset	x	X	x	x	X	x	x	x	

Bits 15:0 - FLTR[15:0] ADC Filter Output - Signed two's complement

In Accumulate, Average, and Burst Average mode, this is equal to ACC right shifted by the CRS bits. In LPF mode, this is the output of the Low-Pass Filter.


Notes: The individual bytes in this multibyte register can be accessed with the following register names:

- ADFLTRH: Accesses the high byte ADFLTR[15:8]
- ADFLTRL: Accesses the low byte ADFLTR[7:0]

### 31,5,15 ADRES

Name: ADRES Offset: 0x1D1D

**ADC Result Register** 



Bits 15:0 - RES[15:0] ADC Sample Result

Notes: The individual bytes in this multibyte register can be accessed with the following register names:

- ADRESH: Accesses the high byte ADRES[15:18]
- ADRESL: Accesses the low byte ADRES[7:0]

### 31.5.16 ADPREV

Name: ADPREV Offset: 0x1D1B

### ADC Previous Result Register

Bit	15	14	13	12	11	10	9	8
	PREV[15:8]							
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
	PREV[7:0]							
Access	R	R	R	R	R	R	R	R
Reset	0	0	0	0	0	0	0	0

#### Bits 15:0 - PREV[15:0] Previous ADC Result

Value	Condition	Description
n	PSIS = 1	n = ADFLTR value at the start of current ADC conversion
n	PSIS = 0	n = ADRES at the start of current ADC conversion <sup>(1)</sup>

#### Notes:

- 1. If PSIS = 0, ADPREV is formatted the same way as ADRES is, depending on the FM bits.
- 2. The individual bytes in this multibyte register can be accessed with the following register names:
  - ADPREVH: Accesses ADPREV[15:8]
  - ADPREVL: Accesses ADPREV[7:0].

### 31,5,17 ADACC


Name: ADACC Offset: 0x1D16

ADC Accumulator Register(1)

See the "Computation Operation" section for more details.



**Important:** This register contains signed two's complement accumulator value and the upper unused bits contain copies of the sign bit.



Bits 17:0 - ACC[17:0] ADC Accumulator - Signed two's complement

#### Notes:

- 1. This register can only be written when GO = 0.
- 2. The individual bytes in this multibyte register can be accessed with the following register names:
  - ADACCU: Accesses the upper byte ADACC[17:16]
  - ADACCH: Accesses the high byte ADACC[15:8]
  - ADACCL: Accesses the low byte ADACC[7:0].

### 31.5.18 ADSTPT

Name: ADSTPT Offset: 0x1D12

ADC Threshold Setpoint Register

Depending on CALC, it may be used to determine ADERR.

Bit	15	14	13	12	11	10	9	8
	STPT[15:8]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
	STPT[7:0]							
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 15:0 - STPT[15:0] ADC Threshold Setpoint - Signed two's complement

**Notes:** The individual bytes in this multibyte register can be accessed with the following register names:

- ADSTPTH: Accesses the high byte ADSTPT[15:8]
- ADSTPTH: Accesses the low byte ADSTPT[7:0]

### 31,5,19 ADERR

Name: ADERR Offset: 0x1D10

ADC Setpoint Error Register

ADC Setpoint Error calculation is determined by the CALC bits.

Bit	15	14	13	12	11	10	9	8
				ERR	[15:8]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	X	x	X	x	x	X
Bit	7	6	5	4	3	2	1	0
				ERR	[7:0]			
Access	R	R	R	R	R	R	R	R
Reset	X	X	x	x	X	x	x	x

Bits 15:0 - ERR[15:0] ADC Setpoint Error - Signed two's complement

**Notes:** The individual bytes in this multibyte register can be accessed with the following register names:

- ADERRH: Accesses the high byte ADERR[15:8]
- ADERRL: Accesses the low byte ADERR[7:0]

### 31,5,20 ADLTH

Name: ADLTH Offset: 0x1D0C

ADC Lower Threshold Register

ADLTH and ADUTH are compared with ADERR to set the UTHR and LTHR bits. Depending on the setting of the TMD bits, an interrupt may be triggered by the results of this comparison.

Bit	15	14	13	12	11	10	9	8
				LTH[	15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				LTH	[7:0]	,		
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 15:0 - LTH[15:0] ADC Lower Threshold - Signed two's complement

Notes: The individual bytes in this multibyte register can be accessed with the following register names:

- ADLTHH: Accesses the high byte ADLTH[15:8]
- ADLTHL: Accesses the low byte ADLTH[7:0]

### 31,5,21 ADUTH

Name: ADUTH Offset: 0x1D0E

## ADC Upper Threshold Register

ADLTH and ADUTH are compared with ADERR to set the UTHR and LTHR bits. Depending on the setting of the TMD bits, an interrupt may be triggered by the results of this comparison.

Bit	15	14	13	12	11	10	9	8
				UTH	[15:8]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0
Bit	7	6	5	4	3	2	1	0
				UTH	[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 15:0 - UTH[15:0] ADC Upper Threshold - Signed two's complement


Notes: The individual bytes in this multibyte register can be accessed with the following register names:

- ADUTHH: Accesses the high byte ADUTH[15:8]
- ADUTHL: Accesses the low byte ADUTH[7:0]

### 31,5,22 ADACT

Name: ADACT Offset: 0x1D2C

ADC Auto-Conversion Trigger Source Selection Register




Bits 5:0 – ACT[5:0] Auto-Conversion Trigger Select Table 31-9. ADC Auto-Conversion Trigger Sources

ACT	Auto-Conversion Trigger Source
11111-10111	Reserved
10110	Software write to ADPCH
10101	Software read of ADRESH
10100	Software read of ADERRH
10011	CLC4_OUT
10010	CLC3_OUT
10001	CLC2_OUT
10000	CLC1_OUT
01111	Interrupt-on-change Interrupt Flag
01110	C1_OUT
01101	NCO1_OUT
01100	PWM5_OUT
01011	PWM4_OUT
01010	PWM3_OUT
01001	CCP2_OUT
01000	CCP1_OUT
00111	TMR6_postscaled_OUT
00110	TMR4_postscaled_OUT
00101	TMR3_overflow
00100	TMR2_postscaled_OUT
00011	TMR1_overflow
00010	TMR0_overflow
00001	Pin selected by ADACTPPS
00000	External Trigger Disabled

### 31.5.23 ADCGxA

Name: ADCGxA Offset: 0x1D2E

ADC Channel Group Selection Port A



Bits 4, 5 - CGAn Channel Group Selection Enable on RA Pins

Bits 0, 1, 2 - CGAn Channel Group Selection Enable on RA Pins

Note: Refer to the "Pin Allocation Table" for details about available pins per port.

### 31.5.24 ADCGxB

Name: ADCGxB Offset: 0x1D2F

ADC Channel Group Selection Port B



Bits 4, 5, 6, 7 - CGBn Channel Group Selection Enable on RB Pins

Note: Refer to the "Pin Allocation Table" for details about available pins per port.

### 31.5.25 ADCGxC

Name: ADCGxC Offset: 0x1D30

ADC Channel Group Selection Port C

Bit	7	6	5	4	3	2	1	0
	CGC7	CGC6	CGC5	CGC4	CGC3	CGC2	CGC1	CGC0
Access	R/W							
Reset	0	0	0	0	0	0	0	0

Bits 0, 1, 2, 3, 4, 5 - CGCn Channel Group Selection Enable on RC Pins

Bits 0, 1, 2, 3, 4, 5, 6, 7 - CGCn Channel Group Selection Enable on RC Pins

Note: Refer to the "Pin Allocation Table" for details about available pins per port.

# 31.6 Register Summary - ADC

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x1D0B		7.0				LTU	17.01			
0x1D0C	ADLTH	7:0 15:8					[7:0]			
		7:0					[15:8] I[7:0]			
0x1D0E	ADUTH	15:8					[15:8]			
		7:0					R[7:0]			
0x1D10	ADERR	15:8					[15:8]			
		7:0					T[7:0]			
0x1D12	ADSTPT	15:8					[15:8]			
		7:0					R[7:0]			
0x1D14	ADFLTR	15:8					1[15:8]			
		7:0					[7:0]			
0x1D16	ADACC	15:8					[15:8]			
0.0.0	7127100	23:16				7.00	[]		ACC	[17:16]
0x1D19	ADCNT	7:0				CNT	[7:0]			
0x1D1A	ADRPT	7:0					[7:0]			
		7:0				PRE				
0x1D1B	ADPREV	15:8					/[15:8]			
		7:0					[7:0]			
0x1D1D	ADRES	15:8					[15:8]			
0x1D1F	ADPCH	7:0						H[5:0]		
0x1D20	Reserved									
0.4004	ADACQ	7:0		•		ACC	Q[7:0]			
0x1D21	ADACQ	15:8						ACQ[12:8]		
0x1D23	ADCAP	7:0						CAP[4:0]		
0x1D24	ADPRE	7:0		•		PRE	[7:0]			
0.0024	ADPRE	15:8						PRE[12:8]		
0x1D26	ADCON0	7:0	ON	CONT		CS		FM		GO
0x1D27	ADCON1	7:0	PPOL	IPEN	GPOL				PCSC	DSEN
0x1D28	ADCON2	7:0	PSIS		CRS[2:0]		ACLR		MD[2:0]	
0x1D29	ADCON3	7:0			CALC[2:0]		SOI		TMD[2:0]	
0x1D2A	ADSTAT	7:0	AOV	UTHR	LTHR	MATH			STAT[2:0]	
0x1D2B	ADREF	7:0							PRE	F[1:0]
0x1D2C	ADACT	7:0						Γ[5:0]		
0x1D2D	ADCLK	7:0					CS	[5:0]		
0x1D2E	ADCG1A	7:0			CGA5	CGA4		CGA2	CGA1	CGA0
0x1D2F	ADCG1B	7:0	CGB7	CGB6	CGB5	CGB4				
0x1D30	ADCG1C	7:0	CGC7	CGC6	CGC5	CGC4	CGC3	CGC2	CGC1	CGC0

# 32. DAC - Digital-to-Analog Converter Module

The Digital-to-Analog Converter (DAC) supplies a variable voltage reference, ratiometric with the input source, with programmable selectable output levels.

The positive and negative input references (DACxREF+ and DACxREF-) can each be selected from several sources.


The output of the DAC (DAC10UT1) can be selected as a reference voltage to several other peripherals or routed to output pins.

The Digital-to-Analog Converter (DAC) is enabled by setting the EN bit.



**Important:** This family of devices has one DAC module. The DAC1 module has a buffered output that can be connected to any of the designated DAC output pins. DAC1 is also connected internally to the ADC and CMP modules.

Figure 32-1. Digital-to-Analog Converter Block Diagram



Note 1: The output enable bits are configured so that they act as a 'one-hot' system, meaning only one DAC output can be enabled at a time.

## 32.1 Output Voltage Selection

The DAC has 2<sup>n</sup> voltage level ranges, where n is the number of bits in DACR. Each level is determined by the DACxR bits. The DAC output voltage can be determined by using Equation 32-1.

#### **Equation 32-1. DAC Output Equation**

$$DACx\_output = \left( \left( V_{REF+} - V_{REF-} \right) \times \frac{DACR}{2^n} \right) + V_{REF-}$$

## 32.2 Ratiometric Output Level

The DAC output value is derived using a resistor ladder with each end of the ladder tied to a positive and negative voltage reference input source. If the voltage of either input source fluctuates, a similar fluctuation will result in the DAC output value. The value of the individual resistors within the ladder can be found in the "Electrical Specifications" chapter for each respective device.

# 32.3 Buffered DAC Output Range Selection

The DAC offers selectable output ranges that improve the output performance of the buffered DAC output (DAC1OUT1). Range selection allows module hardware to optimize the DAC buffer output by biasing the reference voltages towards either DACxREF+ (high range) or DACxREF- (low range). Range selection can be done automatically or through software control.

The DAC Buffer Automatic Range Select Enable (DACAUTOEN) bit of the Configuration Words is used to select either user software-controlled ranging or automatic ranging via hardware control.

When  $\overline{DACAUTOEN}$  is set ( $\overline{DACAUTOEN}$  = 1), the range is determined by the Buffer Reference Range Selection (REFRNG) bit in user software. When REFRNG is set (REFRNG = 1), the high range (( $V_{SS}$  + 1.0V) through  $V_{DD}$ ) is selected as the voltage reference range. When REFRNG is clear (REFRNG = 0), the low range ( $V_{SS}$  through ( $V_{DD}$  - 1.0V) is selected as the reference range.

When DACAUTOEN is clear (DACAUTOEN = 0), module hardware monitors the DACxDATL register and automatically selects the appropriate range based on the DACxDAT value.



**Important:** To ensure the most accurate results, it is highly recommended to do the following:

- Enable the DAC Auto-Ranging feature in the Configuration Words (DACAUTOEN = 0)
- Set the Charge Pump to Auto mode (CPCONbits.CPON = \b10)
- Wait the required settling time when changing the DACxDATL values (see the "Electrical Specifications" section)

This allows module hardware to continuously monitor the DAC output and  $V_{DD}$  levels to ensure a stable, accurate result with little software overhead.

# 32.4 Operation During Sleep

When the device wakes from Sleep through an interrupt or a WWDT Time-out Reset, the contents of the DACxCON and DACxDATL registers are not affected. To minimize current consumption in Sleep mode, the voltage reference will be disabled.

## 32.5 Effects of a Reset

A device Reset affects the following:

# **DAC - Digital-to-Analog Converter Module**

- · The DAC module is disabled
- The DAC output voltage is removed from the DACxOUTn pin(s)
- · The DACxR bits are cleared

# 32.6 Register Definitions: DAC Control

Long bit name prefixes for the DAC are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 32-1. DAC Long Bit Name Prefixes

Peripheral	Bit Name Prefix
DAC1	DAC1

### 32.6.1 DACxCON

Name: DACxCON Offset: 0x110C

Digital-to-Analog Converter Control Register

Bit	7	6	5	4	3	2	1	0
	EN	REFRNG	OE[	1:0]	PSS	[1:0]		NSS
Access	R/W	R/W	R/W	R/W	R/W	R/W		R/W
Reset	0	0	0	0	0	0		0

### Bit 7 - EN DAC Enable

V	alue	Description
1		DAC is enabled
0		DAC is disabled

# Bit 6 – REFRNG Buffer Reference Range Selection<sup>(1)</sup>

Value	Condition	Description
Х	DACAUTOEN = 0	Automatic ranging enabled; the REFRNG bit is ignored
1	DACAUTOEN = 1	Range optimized for voltages from (V <sub>SS</sub> + 1.0V) through V <sub>DD</sub>
0	DACAUTOEN = 1	Range optimized for voltages from V <sub>SS</sub> through (V <sub>DD</sub> - 1.0V)

## Bits 5:4 - OE[1:0] DAC Output Enable

OE	DAC1
11	DAC1OUT1 is disabled
10	DAC1OUT1 is disabled
01	DAC1OUT1 is enabled on pin RA0 only
00	DAC1OUT1 is disabled

## Bits 3:2 - PSS[1:0] DAC Positive Reference Selection

PSS	DAC Positive Reference
11	Reserved, do not use
10	FVR Buffer 2
01	V <sub>REF</sub> +
00	$V_{DD}$

## Bit 0 - NSS DAC Negative Reference Selection

NSS	DAC Negative Reference
1	V <sub>REF</sub> -
0	$V_{SS}$

#### Note:

1. The REFRNG bit only applies to DAC1OUT1.

## 32.6.2 DACxDATL

Name: DACxDATL Offset: 0x110D

Digital-to-Analog Converter Data Register

Bit	7	6	5	4	3	2	1	0
[				DACx	R[7:0]			
Access	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bits 7:0 - DACxR[7:0] Data Input Bits for DAC Value

# 32.7 Register Summary - DAC

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x110B										
0x110C	DAC1CON	7:0	EN	REFRNG	OE	[1:0]	PSS	[1:0]		NSS
0x110D	DAC1DATL	7:0	DAC1R[7:0]							

# 33. CMP - Comparator Module

Comparators are used to interface analog circuits to a digital circuit by comparing two analog voltages and providing a digital indication of their relative magnitudes. Comparators are very useful mixed signal building blocks because they provide analog functionality independent of program execution.


The analog comparator module includes the following features:

- · Programmable input selection
- · Programmable output polarity
- · Rising/falling output edge interrupts
- · Wake-up from Sleep
- · Selectable voltage reference
- · ADC auto-trigger
- Inter-connections with other available modules (e.g., timer clocks)

# 33.1 Comparator Overview

A single comparator is shown in Figure 33-1 along with the relationship between the analog input levels and the digital output. When the analog voltage at  $V_{IN}$ + is less than the analog voltage at  $V_{IN}$ -, the output of the comparator is a digital low level. When the analog voltage at  $V_{IN}$ + is greater than the analog voltage at  $V_{IN}$ -, the output of the comparator is a digital high level.


Figure 33-1. Single Comparator



#### Note:

1. The black areas of the output of the comparator represent the uncertainty due to input offsets and response time.

Figure 33-2. Comparator Module Simplified Block Diagram



Note 1: When EN = 0, all multiplexer inputs are disconnected and the Comparator will produce a '0' at the output.

# 33.2 Comparator Control

Each comparator has two control registers: CMxCON0 and CMxCON1.

The CMxCON0 register contains Control and Status bits for the following:

- Enable
- Output
- Output Polarity
- · Hysteresis Enable
- · Timer1 Output Synchronization

The CMxCON1 register contains Control bits for the following:

Interrupt on Positive/Negative Edge Enables

The CMxPCH and CMxNCH registers are used to select the positive and negative input channels, respectively.

## 33.2.1 Comparator Enable

Setting the EN bit enables the comparator for operation. Clearing the EN bit disables the comparator, resulting in minimum current consumption.

#### 33.2.2 Comparator Output

The output of the comparator can be monitored in two different registers. Each output can be read individually by reading the OUT bit. Outputs of all the comparators can be collectively accessed by reading the CMOUT register.

## **CMP - Comparator Module**

The comparator output can also be routed to an external pin through the RxyPPS register. Refer to the "PPS - Peripheral Pin Select Module" chapter for more details. The corresponding TRIS bit must be clear to enable the pin as an output.



**Important:** The internal output of the comparator is latched with each instruction cycle. Unless otherwise specified, external outputs are not latched.

#### 33.2.3 Comparator Output Polarity

Inverting the output of the comparator is functionally equivalent to swapping the comparator inputs. The polarity of the comparator output can be inverted by setting the POL bit. Clearing the POL bit results in a noninverted output. Table 33-1 shows the Output state versus Input conditions, including polarity control.

Table 33-1. Comparator Output State vs. Input Conditions

Input Condition	POL	OUT
CxVn > CxVp	0	0
CxVn < CxVp	0	1
CxVn > CxVp	1	1
CxVn < CxVp	1	0

## 33.3 Comparator Output Synchronization

The output from a comparator can be synchronized with Timer1 by setting the SYNC bit.

Once enabled, the comparator output is latched on the falling edge of the Timer1 source clock. If a prescaler is used with Timer1, the comparator output is latched after the prescaling function. To prevent a Race condition, the comparator output is latched on the falling edge of the Timer1 clock source and Timer1 increments on the rising edge of its clock source. A simplified block diagram of the comparator module is shown in Figure 33-2. Refer to the "TMR1 - Timer1 Module with Gate Control" chapter for more details.

# 33.4 Comparator Hysteresis

A selectable amount of separation voltage can be added to the input pins of each comparator to provide a hysteresis function to the overall operation. Hysteresis is enabled by setting the HYS bit.

See the "Comparator Specifications" section for more information.

## 33.5 Comparator Interrupt

An interrupt can be generated for every rising or falling edge of the comparator output.

When either edge detector is triggered and its associated enable bit is set (INTP and/or INTN bits), the Corresponding Interrupt Flag bit (CxIF bit of the respective PIR register) will be set.

To enable the interrupt, the following bits must be set:

- EN bit
- INTP bit (for a rising edge detection)
- INTN bit (for a falling edge detection)
- CxIE bit of the respective PIE register
- GIE bit of the INTCON0 register

**CMP - Comparator Module** 

The associated interrupt flag bit, CxIF bit of the respective PIR register, must be cleared in software to successfully detect another edge.



**Important:** Although a comparator is disabled, an interrupt will be generated by changing the output polarity with the POL bit.

## 33.6 Comparator Positive Input Selection

Configuring the PCH bits direct an internal voltage reference or an analog pin to the noninverting input of the comparator.

Any time the comparator is disabled (EN = 0), all comparator inputs are disabled.

## 33.7 Comparator Negative Input Selection

The NCH bits direct an analog input pin, internal reference voltage or analog ground to the inverting input of the comparator.



**Important:** To use CxINy+ and CxINy- pins as analog input, the appropriate bits must be set in the ANSEL register and the corresponding TRIS bits must also be set to disable the output drivers.

# 33.8 Comparator Response Time

The comparator output is indeterminate for a period of time after the change of an input source or the selection of a new reference voltage. This period is referred to as the response time. The response time of the comparator differs from the settling time of the voltage reference. Therefore, both of these times must be considered when determining the total response time to a comparator input change. See the Comparator and Voltage Reference Specifications in the "Comparator Specifications" and "Fixed Voltage Reference (FVR) Specifications" sections for more details.

## 33.9 Analog Input Connection Considerations


A simplified circuit for an analog input is shown in Figure 33-3. Since the analog input pins share their connection with a digital input, they have reverse biased ESD protection diodes to  $V_{DD}$  and  $V_{SS}$ . The analog input, therefore, must be between  $V_{SS}$  and  $V_{DD}$ . If the input voltage deviates from this range by more than 0.6V in either direction, one of the diodes is forward biased and abnormal behavior may occur.

A maximum source impedance of 10 k $\Omega$  is recommended for the analog sources. Also, any external component connected to an analog input pin, such as a capacitor or a Zener diode, will have very little leakage current to minimize corrupting the result.

#### Notes:

- 1. When reading a PORT register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert as an analog input, according to the input specification.
- 2. Analog levels on any pin defined as a digital input may cause the input buffer to consume more current than specified.

Figure 33-3. Analog Input Model



Legend: CPIN = Input Capacitance

ILEAKAGE = Leakage Current at the pin due to various junctions

Ric = Interconnect Resistance
Rs = Source Impedance
VA = Analog Voltage
VT = Diode Forward Voltage

#### Note:

1. See the "Electrical Specifications" chapter.

# 33.10 Operation in Sleep Mode

The comparator module can operate during Sleep. A comparator interrupt will wake the device from Sleep. The CxIE bits of the respective PIE register must be set to enable comparator interrupts.

The comparator clock source is based on the Timer1 clock source. If the Timer1 clock source is either the system clock ( $F_{OSC}$ ) or the instruction clock ( $F_{OSC}$ /4), Timer1 will not operate during Sleep, and synchronized comparator outputs will not operate.

# 33.11 ADC Auto-Trigger Source

The output of the comparator module can be used to trigger an ADC conversion. When the ADACT register is set to trigger on a comparator output, an ADC conversion will trigger when the comparator output goes high.

# 33.12 Register Definitions: Comparator Control

Long bit name prefixes for the Comparator peripherals are shown in the table below. Refer to the "Long Bit Names" section in the "Register and Bit Naming Conventions" chapter for more information.

Table 33-2. Comparator Long Bit Name Prefixes

Peripheral	Bit Name Prefix
C1	C1

### 33.12.1 CMxCON0

Name: CMxCON0 Offset: 0x108C

Comparator Control Register 0

Bit	7	6	5	4	3	2	1	0
	EN	OUT		POL			HYS	SYNC
Access	R/W	R		R/W			R/W	R/W
Reset	0	0		0			0	0

### Bit 7 - EN Comparator Enable

Value	Description
1	Comparator is enabled
0	Comparator is disabled and consumes no active power

#### Bit 6 - OUT Comparator Output

Value	Condition	Description
1	If POL = 0 (noninverted polarity):	CxVP > CxVN
0	If POL = 0 (noninverted polarity):	CxVP < CxVN
1	If POL = 1 (inverted polarity):	CxVP < CxVN
0	If POL = 1 (inverted polarity):	CxVP > CxVN

## Bit 4 – POL Comparator Output Polarity Select

Value Description		Description
	1	Comparator output is inverted
	0	Comparator output is not inverted

#### Bit 1 - HYS Comparator Hysteresis Enable

Value	Description
1	Comparator hysteresis enabled
0	Comparator hysteresis disabled


# Bit 0 - SYNC Comparator Output Synchronous Mode

Value	Description
1	Comparator output to Timer1 and I/O pin is synchronous to changes on Timer1 clock source. Output
	updated on the falling edge of Timer1 clock source.
0	Comparator output to Timer1 and I/O pin is asynchronous

### 33.12.2 CMxCON1

Name: CMxCON1 Offset: 0x108D

Comparator Control Register 1



Bit 1 - INTP Comparator Interrupt on Positive-Going Edge Enable

Value	Description
1	The CxIF interrupt flag will be set upon a positive-going edge of the CxOUT bit
0	No interrupt flag will be set on a positive-going edge of the CxOUT bit

### Bit 0 - INTN Comparator Interrupt on Negative-Going Edge Enable

	√alue	Description
	1	The CxIF interrupt flag will be set upon a negative-going edge of the CxOUT bit
(	)	No interrupt flag will be set on a negative-going edge of the CxOUT bit

### 33.12.3 CMxNCH

Name: **CMxNCH** Offset: 0x108E

Comparator Inverting Channel Select Register




Bits 2:0 - NCH[2:0] Comparator Inverting Input Channel Select

V <sub>SS</sub> FVR_Buffer2 NCH not connected NCH not connected CxIN3- <sup>(1)</sup>
NCH not connected  NCH not connected
NCH not connected
CVINI3_(1)
ONINO- ,
CxIN2- <sup>(1)</sup>
CxIN1-
CxIN0-

# 33.12.4 CMxPCH

Name: CMxPCH Offset: 0x108F

Comparator Noninverting Channel Select Register



Bits 2:0 - PCH[2:0] Comparator Noninverting Input Channel Select

PCH	Positive Input Sources
111	$V_{SS}$
110	FVR_Buffer2
101	PCH not connected
100	DAC1_OUT
011	PCH not connected
010	PCH not connected
001	PCH not connected
000	CxIN0+

# 33.12.5 CMOUT

Name: CMOUT Offset: 0x109F

Comparator Output Register



Bit 0 - CxOUT Mirror copy of the CMxCON0.OUT

# 33.13 Register Summary - Comparator

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x108B										
0x108C	CM1CON0	7:0	EN	OUT		POL			HYS	SYNC
0x108D	CM1CON1	7:0							INTP	INTN
0x108E	CM1NCH	7:0							NCH[2:0]	
0x108F	CM1PCH	7:0							PCH[2:0]	
0x1090										
	Reserved									
0x109E										
0x109F	CMOUT	7:0								C1OUT

# 34. FVR - Fixed Voltage Reference

The Fixed Voltage Reference (FVR) is a stable voltage reference, independent of V<sub>DD</sub>, with 1.024V, 2.048V or 4.096V selectable output levels. The output of the FVR can be configured to supply a reference voltage to analog peripherals such as those listed below.

- · ADC input channel
- · ADC positive reference
- · Comparator input
- Digital-to-Analog Converter (DAC)

The FVR can be enabled by setting the EN bit to '1'.

**Note:** Fixed Voltage Reference output cannot exceed V<sub>DD</sub>.

## 34.1 Independent Gain Amplifiers


The output of the FVR is routed through two independent programmable gain amplifiers. Each amplifier can be programmed for a gain of 1x, 2x or 4x, to produce the three possible voltage levels.

The ADFVR bits are used to enable and configure the gain amplifier settings for the reference supplied to the ADC module. Refer to the "ADCC - Analog-to-Digital Converter with Computation Module" chapter for additional information.

The CDAFVR bits are used to enable and configure the gain amplifier settings for the reference supplied to the DAC and comparator modules. Refer to the "DAC - Digital-to-Analog Converter Module" and "CMP - Comparator Module" chapters for additional information.

Refer to the figure below for the block diagram of the FVR module.

Figure 34-1. Fixed Voltage Reference Block Diagram



#### 34.2 FVR Stabilization Period

When the Fixed Voltage Reference module is enabled, it requires time for the reference and amplifier circuits to stabilize. Once the circuits stabilize and are ready for use, the RDY bit will be set.

## 34.3 Register Definitions: FVR

Long bit name prefixes for the FVR peripherals are shown in the following table. Refer to the "Long Bit Names" section in the "Register and Bits Naming Conventions" chapter for more information.

# PIC16F18015/25/44/45

**FVR - Fixed Voltage Reference** 

# Table 34-1. FVR Long Bit Name Prefixes

Peripheral	Bit Name Prefix
FVR	FVR

#### 34,3,1 FVRCON

Name: FVRCON Offset: 0x100C

**FVR Control Register** 



**Important:** This register is shared between the Fixed Voltage Reference (FVR) module and the temperature indicator module.

Bit	7	6	5	4	3	2	1	0
	EN	RDY	TSEN	TSRNG	CDAF\	/R[1:0]	ADFV	R[1:0]
Access	R/W	R	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	q	0	0	0	0	0	0

#### Bit 7 - EN Fixed Voltage Reference Enable

Value	Description
1	Enables module
0	Disables module

#### Bit 6 - RDY Fixed Voltage Reference Ready Flag

Value	Description
1	Fixed Voltage Reference output is ready for use
0	Fixed Voltage Reference output is not ready for use or not enabled

#### Bit 5 - TSEN Temperature Indicator Enable

Value	Description
1	Temperature Indicator is enabled
0	Temperature Indicator is disabled

## Bit 4 - TSRNG Temperature Indicator Range Selection

DIC + 101	Dit 4 TOTATO Temperature indicator range defection				
Value	Description				
1	$V_{OUT} = 3V_{T}$ (High Range)				
0	$V_{OUT} = 2V_T$ (Low Range)				

### Bits 3:2 - CDAFVR[1:0] FVR Buffer 2 Gain Selection<sup>(1)</sup>

Value	Description
11	FVR Buffer 2 Gain is 4x, (4.096V) <sup>(3)</sup>
10	FVR Buffer 2 Gain is 2x, (2.048V) <sup>(3)</sup>
01	FVR Buffer 2 Gain is 1x, (1.024V)
00	FVR Buffer 2 is OFF

#### Bits 1:0 - ADFVR[1:0] FVR Buffer 1 Gain Selection<sup>(2)</sup>

	· · · · · · · · · · · · · · · · · · ·
Value	Description
11	FVR Buffer 1 Gain is 4x, (4.096V) <sup>(3)</sup>
10	FVR Buffer 1 Gain is 2x, (2.048V) <sup>(3)</sup>
01	FVR Buffer 1 Gain is 1x, (1.024V)
00	FVR Buffer 1 is OFF

## Notes:

- 1. This output goes to the DAC and comparator modules, and to the ADC module as an input channel only.
- 2. This output goes to the ADC module as a reference and an input channel.
- 3. Fixed Voltage Reference output cannot exceed V<sub>DD</sub>.

# 34.4 Register Summary - FVR

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x100B										
0x100C	FVRCON	7:0	EN	RDY	TSEN	TSRNG	CDAF	VR[1:0]	ADFV	'R[1:0]

# 35. Temperature Indicator Module

This family of devices is equipped with a temperature circuit designed to measure the operating temperature of the silicon die. The temperature indicator module provides a temperature-dependent voltage that can be measured by the internal Analog-to-Digital Converter.

The circuit's range of operating temperature falls between -40°C and +125°C. The circuit may be used as a temperature threshold detector or a more accurate temperature indicator, depending on the level of calibration performed. A one-point calibration allows the circuit to indicate a temperature closely surrounding that point. A two-point calibration allows the circuit to sense the entire range of temperature more accurately.


Microchip tests each device during manufacturing and provides the gain, offset, and Temperature Indicator ADC values at 90°C, for both High and Low Range operation.

## 35.1 Module Operation

The temperature indicator module consists of a temperature-sensing circuit that provides a voltage to the device ADC. The analog voltage output varies inversely to the device temperature. The output of the temperature indicator is referred to as  $V_{\text{MEAS}}$ .

The following figure shows a simplified block diagram of the temperature indicator module.

Figure 35-1. Temperature Indicator Module Block Diagram



The output of the circuit is measured using the internal Analog-to-Digital Converter. A channel is reserved for the temperature circuit output. Refer to the "ADCC - Analog-to-Digital Converter with Computation Module" chapter for more details.

The ON/OFF bit for the module is located in the FVRCON register. The circuit is enabled by setting the TSEN bit. When the module is disabled, the circuit draws no current. Refer to the "FVR - Fixed Reference Voltage" chapter for more details.

#### 35.1.1 Temperature Indicator Range

The temperature indicator circuit operates in either high or low range. The high range, selected by setting the TSRNG bit, provides a wider output voltage. This provides more resolution over the temperature range. High range requires a higher bias voltage to operate and thus, a higher  $V_{DD}$  is needed. The low range is selected by clearing the TSRNG bit. The low range generates a lower sensor voltage and thus, a lower  $V_{DD}$  voltage is needed to operate the circuit.

The output voltage of the sensor is the highest value at -40°C and the lowest value at +125°C.

- High Range: The high range is used in applications with the reference for the ADC, V<sub>REF</sub> = 2.048V. This range
  may not be suitable for battery-powered applications.
- Low Range: This mode is useful in applications in which the V<sub>DD</sub> is too low for high-range operation. The V<sub>DD</sub> in this mode can be as low as 1.8V. However, V<sub>DD</sub> must be at least 0.5V higher than the maximum sensor voltage depending on the expected low operating temperature.



**Important:** The standard parameters for the Temperature Indicator for both high range and low range are stored in the DIA table. Refer to the DIA table in the "**Memory Organization**" chapter for more details. Additionally, the Temperature Indicator sensitivity parameter ( $M_V$ ) for both high range and low range is located in the "**Electrical Specifications**" section.

## 35.1.2 Minimum Operating V<sub>DD</sub>

When the temperature circuit is operated in low range, the device may be operated at any operating voltage that is within the device specifications. When the temperature circuit is operated in high range, the device operating voltage,  $V_{DD}$ , must be high enough to ensure that the temperature circuit is correctly biased.

The following table shows the recommended minimum V<sub>DD</sub> vs. Range setting.

Table 35-1. Recommended V<sub>DD</sub> vs. Range

Min. V <sub>DD</sub> , TSRNG = 1 (High Range)	Min. V <sub>DD</sub> , TSRNG = 0 (Low Range)				
≥ 2.5	≥ 1.8				

# 35.2 Temperature Calculation

This section describes the steps involved in calculating the die temperature, T<sub>MEAS</sub>:

- Obtain the ADC count value of the measured analog voltage: The analog output voltage, V<sub>MEAS</sub>, is converted
  to a digital count value by the Analog-to-Digital Converter (ADC) and is referred to as ADC<sub>MEAS</sub>.
- Obtain the Gain value from the DIA table. This parameter is TSLR1 for the low range setting or TSHR1 for the high range setting of the temperature indicator module. Refer to the DIA table in the "Memory Organization" chapter for more details.
- 3. Obtain the Offset value from the DIA table. This parameter is TSLR3 for the low range setting or TSHR3 for the high range setting of the temperature indicator module. Refer to the DIA table in the "Memory Organization" chapter for more details.

The following equation provides an estimate for the die temperature based on the above parameters:

#### Equation 35-1. Sensor Temperature (in °C)

$$T_{MEAS} = \frac{\frac{\left(ADC_{MEAS} \times Gain\right)}{256} + Offset}{10}$$

Where:

ADC<sub>MEAS</sub> = ADC reading at temperature being estimated

Gain = Gain value stored in the DIA table

Offset = Offset value stored in the DIA table

**Note:** It is recommended to take the average of ten measurements of  $ADC_{MEAS}$  to reduce noise and improve accuracy.

```
Example 35-1. Temperature Calculation (C)

// offset is int16_t data type
// gain is int16_t data type
// ADC_MEAS is uint16_t data type
// Temp_in_C is int24_t data type

ADC_MEAS = ((ADRESH << 8) + ADRESL);
Temp_in_C = (int24_t) (ADC_MEAS) * gain;
// Store the ADC Result
// Gain and store the result in a
// signed variable

Temp_in_C = Temp_in_C / 256;
Temp_in_C = Temp_in_C + offset;
// Add (Offset) to the result</pre>
```

# PIC16F18015/25/44/45

# **Temperature Indicator Module**



**Important:** If the application requires more precise temperature measurement, additional calibrations steps will be necessary. For these applications, two-point or three-point calibration is recommended. For additional information on two-point calibration method, refer to the following Microchip application note, available at the corporate website (www.microchip.com):

• AN2798, "Using the PIC16F/PIC18F Ground Referenced Temperature Indicator Module"

# 35.3 ADC Acquisition Time

To ensure accurate temperature measurements, the user must wait a certain minimum acquisition time (parameter TS01) after the temperature indicator output is selected as ADC input. This is required for the ADC sampling circuit to settle before the conversion is performed.

**Note**: Parameter TS01 can be found in the Temperature Indicator Requirements table of the "**Electrical Specifications**" chapter.

# 35.4 Register Definitions: Temperature Indicator

#### 35.4.1 FVRCON

Name: FVRCON Offset: 0x100C

**FVR Control Register** 



**Important:** This register is shared between the Fixed Voltage Reference (FVR) module and the temperature indicator module.

Bit	7	7 6 5		4 3		2	1	0
	EN	RDY	TSEN	TSRNG	CDAFVR[1:0]		ADFVR[1:0]	
Access	R/W	R	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	q	0	0	0	0	0	0

#### Bit 7 - EN Fixed Voltage Reference Enable

Value	Description
1	Enables module
0	Disables module

### Bit 6 - RDY Fixed Voltage Reference Ready Flag

Value	Description
1	Fixed Voltage Reference output is ready for use
0	Fixed Voltage Reference output is not ready for use or not enabled

#### Bit 5 - TSEN Temperature Indicator Enable

Value	Description
1	Temperature Indicator is enabled
0	Temperature Indicator is disabled

#### Bit 4 - TSRNG Temperature Indicator Range Selection

D.C - 1011	NO Temperature indicator runge colocion
Value	Description
1	$V_{OUT} = 3V_T$ (High Range)
0	V <sub>OUT</sub> = 2V <sub>T</sub> (Low Range)

#### Bits 3:2 - CDAFVR[1:0] FVR Buffer 2 Gain Selection(1)

Value	Description
11	FVR Buffer 2 Gain is 4x, (4.096V) <sup>(3)</sup>
10	FVR Buffer 2 Gain is 2x, (2.048V) <sup>(3)</sup>
01	FVR Buffer 2 Gain is 1x, (1.024V)
00	FVR Buffer 2 is OFF

#### Bits 1:0 - ADFVR[1:0] FVR Buffer 1 Gain Selection<sup>(2)</sup>

	· · · · · · · · · · · · · · · · · · ·
Value	Description
11	FVR Buffer 1 Gain is 4x, (4.096V) <sup>(3)</sup>
10	FVR Buffer 1 Gain is 2x, (2.048V) <sup>(3)</sup>
01	FVR Buffer 1 Gain is 1x, (1.024V)
00	FVR Buffer 1 is OFF

## Notes:

- 1. This output goes to the DAC and comparator modules, and to the ADC module as an input channel only.
- 2. This output goes to the ADC module as a reference and an input channel.
- 3. Fixed Voltage Reference output cannot exceed V<sub>DD</sub>.

# 35.5 Register Summary - Temperature Indicator


Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x100B										
0x100C	FVRCON	7:0	EN	RDY	TSEN	TSRNG	CDAF	VR[1:0]	ADFV	'R[1:0]

## 36. ZCD - Zero-Cross Detection Module

The ZCD module detects when an A/C signal crosses through the ground potential. The actual zero-crossing threshold is the zero-crossing reference voltage,  $Z_{CPINV}$ , which is typically 0.75V above ground.

The connection to the signal to be detected is through a series current-limiting resistor. The module applies a current source or sink to the ZCD pin to maintain a constant voltage on the pin, thereby preventing the pin voltage from forward biasing the ESD protection diodes. When the applied voltage is greater than the reference voltage, the module sinks current. When the applied voltage is less than the reference voltage, the module sources current. The current source and sink action keeps the pin voltage constant over the full range of the applied voltage. The ZCD module is shown in the following simplified block diagram.

Figure 36-1. Simplified ZCD Block Diagram



The ZCD module is useful when monitoring an A/C waveform for, but not limited to, the following purposes:

- · A/C period measurement
- Accurate long term time measurement

- · Dimmer phase delayed drive
- · Low EMI cycle switching


#### 36.1 External Resistor Selection

The ZCD module requires a current-limiting resistor in series with the external voltage source. The impedance and rating of this resistor depends on the external source peak voltage. Select a resistor value that will drop all of the peak voltage when the current through the resistor is less than the maximum input current (ZC02). Refer to the "Electrical Specifications" chapter for more details. Make sure that the ZCD I/O pin internal weak pull-up is disabled so it does not interfere with the current source and sink.

#### Equation 36-1. External Resistor

$$R_{SERIES} = \frac{V_{PEAK}}{I_{ZCD}}$$

Figure 36-2. External Voltage Source



# 36.2 ZCD Logic Output

The ZCD module includes a Status bit, which can be read to determine whether the current source or sink is active. The OUT bit is set when the current sink is active, and cleared when the current source is active. The OUT bit is affected by the polarity bit.

The OUT signal can also be used as input to other modules. This is controlled by the registers of the corresponding module.

## 36.3 ZCD Logic Polarity

The POL bit inverts the OUT bit relative to the current source and sink output. When the POL bit is set, a OUT high indicates that the current source is active, and a low output indicates that the current sink is active. The POL bit affects the ZCD interrupts.

### 36.4 ZCD Interrupts

An interrupt will be generated upon a change in the ZCD logic output when the appropriate interrupt enables are set. The ZCD module has a rising edge detector and a falling edge detector.

The ZCDIF bit of the PIRx register will be set when either edge detector is triggered and its associated enable bit is set. The INTP enables rising edge interrupts and the INTN bit enables falling edge interrupts.

To fully enable the interrupt, the following bits must be set:

- · ZCDIE bit of the PIEx register
- · INTP bit for rising edge detection
- · INTN bit for falling edge detection
- · GIEL and GIE bits of the INTCON0 register

Changing the POL bit will cause an interrupt, regardless of the level of the SEN bit.

The ZCDIF bit of the PIRx register must be cleared in software as part of the interrupt service. If another edge is detected while this flag is being cleared, the flag will still be set at the end of the sequence.

## 36.5 Correction for Z<sub>CPINV</sub> Offset

The actual voltage at which the ZCD switches is the reference voltage at the noninverting input of the ZCD op amp. For external voltage source waveforms other than square waves, this voltage offset from zero causes the zero-cross event to occur either too early or too late.

#### 36.5.1 Correction by AC Coupling

When the external voltage source is sinusoidal, the effects of the  $Z_{CPINV}$  offset can be eliminated by isolating the external voltage source from the ZCD pin with a capacitor, in addition to the voltage reducing resistor. The capacitor will cause a phase shift resulting in the ZCD output switch in advance of the actual zero-crossing event. The phase shift will be the same for both rising and falling zero-crossings, which can be compensated for by either delaying the CPU response to the ZCD switch by a timer or other means, or selecting a capacitor value large enough that the phase shift is negligible.

To determine the series resistor and capacitor values for this configuration, start by computing the impedance, Z, to obtain a peak current less than the maximum input current (ZC02). Refer to the "Electrical Specifications" chapter for more details. Next, arbitrarily select a suitably large nonpolar capacitor and compute its reactance, Xc, at the external voltage source frequency. Finally, compute the series resistor, capacitor peak voltage, and phase shift using the formulas shown below.

When this technique is used and the input signal is not present, the ZCD will tend to oscillate. To avoid this oscillation, connect the ZCD pin to  $V_{DD}$  or GND with a high-impedance resistor.

Note: In this example, the impedance value is calculated for a peak current of 300 µA.

#### Equation 36-2. R-C Equations

V<sub>PEAK</sub> = external voltage source peak voltage

f = external voltage source frequency

C = series capacitor

R = series resistor

V<sub>C</sub> = peak capacitor voltage

 $\Phi$  = capacitor induced zero-crossing phase advance in radians

 $T_{\Phi}$  = time ZC event occurs before actual zero-crossing

$$Z = \frac{V_{PEAK}}{3 \times 10^{-4}}$$

$$X_C = \frac{1}{2\pi f C}$$

$$R = \sqrt{Z^2 - X_C^2}$$

$$V_C = X_C \left(3 \times 10^{-4}\right)$$

$$\Phi = \tan^{-1} \left( \frac{X_C}{R} \right)$$

$$T_{\Phi} = \frac{\Phi}{2\pi f}$$

### Equation 36-3. R-C Calculation Example

$$V_{rms}=120\,$$

$$V_{PEAK} = V_{rms} \times \sqrt{2} = 169.7$$

$$f = 60 Hz$$

$$C = 0.1 \,\mu F$$

$$Z = \frac{V_{PEAK}}{3 \times 10^{-4}} = \frac{169.7}{3 \times 10^{-4}} = 565.7 \,k\Omega$$

$$X_C = \frac{1}{2\pi f C} = \frac{1}{2\pi \times 60 \times 10^{-7}} = 26.53 \,k\Omega$$

$$R = \sqrt{Z^2 - X_C^2} = 565.1 \,k\Omega \,(computed)$$

$$R_a = 560 \,k\Omega \,(used)$$

$$Z_R = \sqrt{R_a^2 + X_C^2} = 560.6 \,k\Omega$$

$$I_{PEAK} = \frac{V_{PEAK}}{Z_R} = 302.7 \times 10^{-6} A$$

$$V_C = X_C \times I_{PEAK} = 8.0 \,V$$

$$\Phi = \tan^{-1}\left(\frac{X_C}{R}\right) = 0.047 \, radians$$

$$T_{\Phi} = \frac{\Phi}{2\pi f} = 125.6 \,\mu s$$

## 36.5.2 Correction by Offset Current

When the waveform is varying relative to  $V_{SS}$ , the zero-cross is detected too early as the waveform falls and too late as the waveform rises. When the waveform is varying relative to  $V_{DD}$ , the zero-cross is detected too late as the waveform rises and too early as the waveform falls. The actual offset time can be determined for sinusoidal waveforms with the corresponding equations shown below.

## Equation 36-4. ZCD Event Offset

When External Voltage source is relative to VSS:

$$T_{offset} = \frac{\sin^{-1}\left(\frac{Z_{CPINV}}{V_{PEAK}}\right)}{2\pi f}$$

When External Voltage source is relative to  $V_{\text{DD}}$ :

$$T_{offset} = \frac{\sin^{-1}\left(\frac{V_{DD} - Z_{CPINV}}{V_{PEAK}}\right)}{2\pi f}$$

This offset time can be compensated for by adding a pull-up or pull-down biasing resistor to the ZCD pin. A pull-up resistor is used when the external voltage source is varying relative to  $V_{SS}$ . A pull-down resistor is used when the voltage is varying relative to  $V_{DD}$ . The resistor adds a bias to the ZCD pin so that the target external voltage source must go to zero to pull the pin voltage to the  $Z_{CPINV}$  switching voltage. The pull-up or pull-down value can be determined with the equations shown below.

#### Equation 36-5. ZCD Pull-up/Pull-down Resistor

When External Voltage source is relative to V<sub>SS</sub>:

$$R_{pullup} = \frac{R_{SERIES} \left( V_{pullup} - Z_{CPINV} \right)}{Z_{CPINV}}$$

When External Voltage source is relative to V<sub>DD</sub>:

$$R_{pulldown} = \frac{R_{SERIES}(Z_{CPINV})}{(V_{DD} - Z_{CPINV})}$$

## 36.6 Handling V<sub>PEAK</sub> Variations

If the peak amplitude of the external voltage is expected to vary, the series resistor must be selected to keep the ZCD current source, and sink below the design maximum range specified by ZC02 and above a reasonable minimum range depending on the application. The compensating pull-up for this series resistance can be determined with the equations shown in Equation 36-5 because the pull-up value is independent from the peak voltage.



**Tip:** It is recommended that the maximum peak voltage be no more than six times the minimum peak voltage.

## 36.7 Operation During Sleep

The ZCD current sources and interrupts are unaffected by Sleep.

#### 36.8 Effects of a Reset

The ZCD circuit can be configured to default to the Active or Inactive state on Power-on Reset (POR). When the  $\overline{\text{ZCD}}$  Configuration bit is cleared, the ZCD circuit will be active at POR. When the  $\overline{\text{ZCD}}$  Configuration bit is set, the SEN bit must be set to enable the ZCD module.

## 36.9 Disabling the ZCD Module

The ZCD module can be disabled in two ways:

- The ZCD Configuration bit disables the ZCD module when set. When this is the case, then the ZCD module
  will be enabled by setting the SEN bit. When the ZCD bit is clear, the ZCD is always enabled and the SEN bit
  has no effect.
- 2. The ZCD can also be disabled using the ZCDMD bit of the PMDx register. This is subject to the status of the ZCD bit.

## 36.10 Register Definitions: ZCD Control

Long bit name prefixes for the ZCD peripherals are shown in the table below. Refer to the "Long Bit Names" section of the "Register and Bit Naming Conventions" chapter for more information.

Table 36-1. ZCD Long Bit Name Prefixes

Peripheral	Bit Name Prefix
ZCD	ZCD

#### 36.10.1 ZCDCON

Name: ZCDCON Offset: 0x101F

Zero-Cross Detect Control Register

Bit	7	6	5	4	3	2	1	0
	SEN		OUT	POL			INTP	INTN
Access	R/W		R	R/W		•	R/W	R/W
Reset	0		x	0			0	0

#### Bit 7 - SEN Zero-Cross Detect Software Enable

This bit is ignored when the ZCD fuse is cleared.

Value	Condition	Description
X	ZCD Config fuse = 0	Zero-cross detect is always enabled. This bit is ignored.
1	ZCD Config fuse = 1	Zero-cross detect is enabled. ZCD pin is forced to output to source and sink current.
0	ZCD Config fuse = 1	Zero-cross detect is disabled. ZCD pin operates according to PPS and TRIS controls.

#### Bit 5 - OUT Zero-Cross Detect Data Output

Value	Condition	Description
1	POL = 0	ZCD pin is sinking current
0	POL = 0	ZCD pin is sourcing current
1	POL = 1	ZCD pin is sourcing current
0	POL = 1	ZCD pin is sinking current

#### Bit 4 - POL Zero-Cross Detect Polarity

Value	Description
1	ZCD logic output is inverted
0	ZCD logic output is not inverted

## Bit 1 – INTP Zero-Cross Detect Positive-Going Edge Interrupt Enable

V	/alue	Description
1	•	The ZCDIF bit is set on low-to-high ZCD_output transition
C	)	The ZCDIF bit is unaffected by low-to-high ZCD_output transition

#### Bit 0 - INTN Zero-Cross Detect Negative-Going Edge Interrupt Enable

Value	escription
1	he ZCDIF bit is set on high-to-low ZCD_output transition
0	he ZCDIF bit is unaffected by high-to-low ZCD_output transition

# 36.11 Register Summary - ZCD

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x101E										
0x101F	ZCDCON	7:0	SEN		OUT	POL			INTP	INTN

# 37. Charge Pump

This family of devices offers a dedicated charge pump, which is controlled through the Charge Pump Control (CPCON) register. The primary purpose of the charge pump is to supply a constant voltage to the gates of transistor devices contained in analog peripherals, signal and reference input pass-gates, and to prevent degradation of transistor performance at low operating voltages.

The charge pump offers the following modes:

- Manually Enabled
- · Automatically Enabled
- Disabled

## 37.1 Manually Enabled

The charge pump can be manually enabled via the Charge Pump Enable (CPON) bits. When the CPON bits are configured as '11', the charge pump is enabled. In this case, the charge pump provides additional voltage to all analog systems, regardless of  $V_{DD}$  levels, but also consumes additional current.

## 37.2 Automatically Enabled

The charge pump can also be enabled automatically. This allows the application to determine when to enable the charge pump. If the charge pump is enabled while  $V_{DD}$  levels are above a sufficient threshold, the charge pump does not improve analog performance, but also consumes additional current. Allowing hardware to monitor  $V_{DD}$  and determine when to enable the charge pump prevents unnecessary current consumption.

When the CPON bits are configured as '10', charge pump hardware monitors  $V_{DD}$  and compares the  $V_{DD}$  levels to a reference voltage threshold ( $V_{AUTO}$ ), which is set to 4.096V. When hardware detects a  $V_{DD}$  level lower than the threshold, the charge pump is automatically enabled. If  $V_{DD}$  returns to a level above the threshold, hardware automatically disables the charge pump.

When the CPON bits are configured as '01', charge pump hardware waits for an analog peripheral, such as the ADC, to be enabled before monitoring  $V_{DD}$ . In this case, charge pump hardware monitors all analog peripherals, and once an analog peripheral is enabled, hardware begins to compare  $V_{DD}$  to  $V_{AUTO}$ . When hardware detects a  $V_{DD}$  level lower than the threshold, hardware enables the charge pump. If  $V_{DD}$  returns to a level above the threshold, or if the analog peripheral is disabled, the charge pump is automatically disabled.

### 37.3 Disabled

The charge pump is disabled by default (CPON = 00). Clearing the CPON bits will disable the charge pump.

### 37.4 Charge Pump Oscillator

The Charge Pump Oscillator Selection (CPOS) bit selects the charge pump oscillator source. The CPOS bit allows the user to select between the charge pump's internal oscillator or the oscillator driving the ADC.

When CPOS is set (CPOS = 1), the charge pump utilizes its internal oscillator. The charge pump's internal oscillator provides a very steady output voltage, but at the expense of higher operating current.

When CPOS is clear (CPOS = 0), and the ADGO bit is clear (GO = 0), the charge pump is clock by the ADCRC. When ADGO is set (GO = 1), the charge pump is clocked by a derivative of the F<sub>OSC</sub> (as determined by the ADCLK register). This allows the charge pump to operate at a lower current when the ADC is not converting, while offering higher performance when the ADC is converting.

## 37.5 Charge Pump Threshold

The Charge Pump Threshold (CPT) bit indicates whether or not  $V_{DD}$  is at an acceptable operating level. Charge pump hardware compares  $V_{DD}$  to the threshold voltage ( $V_{AUTO}$ ), which is set at 4.096V. If  $V_{DD}$  is above  $V_{AUTO}$ , the CPT bit is set (CPT = 1). If  $V_{DD}$  is below  $V_{AUTO}$ , CPT is clear (CPT = 0).

## 37.6 Charge Pump Ready

The Charge Pump Ready Status (CPRDY) bit indicates whether or not the charge pump is ready for use. When CPRDY is set (CPRDY = 1), the charge pump has reached a steady-state operation and is ready for use. When CPRDY is clear (CPRDY = 0), the charge pump is either in the OFF state or has not reached a steady-state operation.

## 37.7 Register Definitions: Charge Pump

#### 37.7.1 CPCON

Name: CPCON Offset: 0x100D

Charge Pump Control Register

Bit	7	6	5	4	3	2	1	0
	CPO	N[1:0]	CPOS			CPREQ	CPT	CPRDY
Access	R/W	R/W	R/W	•	•	R	R	R
Reset	0	0	0			0	0	0

## Bits 7:6 - CPON[1:0]

Charge Pump Enable

s enabled
s automatically enabled when V <sub>DD</sub> < V <sub>AUTO</sub> (V <sub>AUTO</sub> = 4.096V)
s automatically enabled when an analog peripheral is enabled (ADCON0.ON = 1) and
s disabled

#### Bit 5 - CPOS

Charge Pump Oscillator Selection

Value	Condition	Description
1		Charge pump clock is the internal charge pump oscillator
0	When ADC GO bit = 1	Charge pump clock is FOSC (oscillator frequency determined by ADCLK)
0	When ADC GO bit = 0	Charge pump clock is the ADCRC

#### Bit 2 - CPREQ

Charge Pump Request Status

Value	Description
1	Charge pump has been requested by an analog peripheral
0	Charge pump has not been requested by an analog peripheral

## Bit 1 - CPT

Charge Pump Threshold

Sharge Famp Threehold			
Value	Description		
1	V <sub>DD</sub> is above the charge pump auto-enable threshold (V <sub>AUTO</sub> )		
0	V <sub>DD</sub> is below the charge pump auto-enable threshold (V <sub>AUTO</sub> )		

### Bit 0 - CPRDY

Charge Pump Ready Status

1	/alue	Description	
1	L	Charge pump has reached a steady-state operation	
(	)	Charge pump is off or has not reached a steady-state operation	

# 37.8 Register Summary - Charge Pump

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x00										
	Reserved									
0x100C										
0x100D	CPCON	7:0	CPO	N[1:0]	CPOS			CPREQ	CPT	CPRDY

# 38. Instruction Set Summary

The PIC16F180 devices incorporate the standard set of 50 PIC16 core instructions. Each instruction is a 14-bit word containing the operation code (opcode) and all required operands. The opcodes are broken into three broad categories:

- · Byte-Oriented
- · Bit-Oriented
- · Literal and Control

The literal and control category contains the most varied instruction word format.

Table 38-3 lists the instructions recognized by the XC8 assembler.

All instructions are executed within a single instruction cycle, with the following exceptions, which may take two or three cycles:

- Subroutine entry takes two cycles (CALL, CALLW)
- Returns from interrupts or subroutines take two cycles (RETURN, RETLW, RETFIE)
- Program branching takes two cycles (GOTO, BRA, BRW, BTFSS, BTFSC, DECFSZ, INCSFZ)
- One additional instruction cycle will be used when any instruction references an indirect file register, and the file select register is pointing to program memory

One instruction cycle consists of four oscillator cycles; for an oscillator frequency of 4 MHz, this gives a nominal instruction execution rate of 1 MHz.

All instruction examples use the format '0xhh' to represent a hexadecimal number, where 'h' signifies a hexadecimal digit.

## 38.1 Read-Modify-Write Operations

Any instruction that specifies a file register as part of the instruction performs a Read-Modify-Write (RMW) operation. The register is read, the data is modified, and the result is stored according to either the Working (W) register, or the originating file register, depending on the state of the destination designator 'd' (see Table 38-1 for more information). A read operation is performed on a register even if the instruction writes to that register.

Table 38-1. Opcode Field Descriptions

Field	Description
f	Register file address (0x00 to 0x7F)
W	Working register (accumulator)
b	Bit address within an 8-bit file register
k	Literal field, constant data or label
x	"Don't care" location (= $0$ or $1$ ).  The assembler will generate code with $x = 0$ .  It is the recommended form of use for compatibility with all Microchip software tools.
d	Destination select; d = 0: store result in W, d = 1: store result in file register f.
n	FSR or INDF number. (0-1)
mm	Pre/post increment/decrement mode selection

Table 38-2. Abbreviation Descriptions

Field	Description
PC	Program Counter

continued							
Field	Description						
TO	Time-Out bit						
С	Carry bit						
DC	Digit Carry bit						
Z	Zero bit						
PD	Power-Down bit						

# 38.2 Standard Instruction Set

Table 38-3. Instruction Set

Mnemo		Description	Cycles		14-Bit (	Opcode		Status	Notes
Operar	nds	Description	Cycles	MSb			LSb	Affected	notes
		BYTE-ORIENTED OPER	ATIONS						
ADDWF	f, d	Add WREG and f	1	00	0111	dfff	ffff	C, DC, Z	2
ADDWFC	f, d	Add WREG and Carry bit to f	1	11	1101	dfff	ffff	C, DC, Z	2
ANDWF	f, d	AND WREG with f	1	00	0101	dfff	ffff	Z	2
ASRF	f, d	Arithmetic Right Shift	1	11	0111	dfff	ffff	C, Z	2
LSLF	f, d	Logical Left Shift	1	11	0101	dfff	ffff	C, Z	2
LSRF	f, d	Logical Right Shift	1	11	0110	dfff	ffff	C, Z	2
CLRF	f	Clear f	1	00	0001	lfff	ffff	Z	2
CLRW	_	Clear WREG	1	00	0001	0000	00xx	Z	
COMF	f, d	Complement f	1	00	1001	dfff	ffff	Z	2
DECF	f, d	Decrement f	1	00	0011	dfff	ffff	Z	2
INCF	f, d	Increment f	1	00	1010	dfff	ffff	Z	2
IORWF	f, d	Inclusive OR WREG with f	1	00	0100	dfff	ffff	Z	2
MOVF	f, d	Move f	1	00	1000	dfff	ffff	Z	2
MOVWF	f	Move WREG to f	1	00	0000	1fff	ffff	None	2
RLF	f, d	Rotate Left f through Carry	1	00	1101	dfff	ffff	С	2
RRF	f, d	Rotate Right f through Carry	1	00	1100	dfff	ffff	С	2

con									
<b>Mnemo</b> Operar		Description	Cycles	MSb	14-Bit (	Opcode	LSb	Status Affected	Notes
SUBWF	f, d	Subtract WREG from f	1	00	0010	dfff	ffff	C, DC, Z	2
SUBWFB	f, d	Subtract WREG from f with Borrow	1	11	1011	dfff	ffff	C, DC, Z	2
SWAPF	f, d	Swap nibbles in f	1	00	1110	dfff	ffff	None	2
XORWF	f, d	Exclusive OR WREG with f	1	00	0110	dfff	ffff	Z	2
	,	BYTE-ORIENTED SKIP OP	ERATION	NS					
DECFSZ	f, d	Decrement f, Skip if 0	1(2)	00	1011	dfff	ffff	None	1, 2
INCFSZ	f, d	Increment f, Skip if 0	1(2)	00	1111	dfff	ffff	None	1, 2
		BIT-ORIENTED FILE REGISTER	OPERA	TIONS					
BCF	f, b	Bit Clear f	1	01	00bb	bfff	ffff	None	2
BSF	f, b	Bit Set f	1	01	01bb	bfff	ffff	None	2
	'	BIT-ORIENTED SKIP OPE	RATION	S					
BTFSC	f, b	Bit Test f, Skip if Clear	1(2)	01	10bb	bfff	ffff	None	1, 2
BTFSS	f, b	Bit Test f, Skip if Set	1(2)	1010	11bb	bfff	ffff	None	1, 2
·	'	LITERAL OPERATION	NS						
ADDLW	k	Add literal and WREG	1	11	1110	kkkk	kkkk	C, DC, Z	
ANDLW	k	AND literal with WREG	1	11	1001	kkkk	kkkk	Z	
IORLW	k	Inclusive OR literal with WREG	1	11	1000	kkkk	kkkk	Z	
MOVLB	k	Move literal to BSR	1	00	000	0 k	kkkk	None	
MOVLP	k	Move literal to PCLATH	1	11	0001	1kkk	kkkk	None	
MOVLW	k	Move literal to W	1	11	0000	kkkk	kkkk	None	
SUBLW	k	Subtract W from literal	1	11	1100	kkkk	kkkk	C, DC, Z	
XORLW	k	Exclusive OR literal with W	1	11	1010	kkkk	kkkk	Z	
		CONTROL OPERATION	ONS						

cor									
<b>Mnemo</b> Operar		Description	Cycles		14-Bit	Opcode		Status Affected	Note
			<u> </u>	MSb			LSb		
BRA	k	Relative Branch	2	11	001k	kkkk	kkkk	None	
BRW	_	Relative Branch with WREG	2	00	0000	0000	1011	None	-
CALL	k	Call Subroutine	2	10	0kkk	kkkk	kkkk	None	-
CALLW	_	Call Subroutine with WREG	2	00	0000	0000	1010	None	
GOTO	k	Go to address	2	10	1kkk	kkkk	kkkk	None	-
RETFIE	k	Return from interrupt	2	00	0000	0000	1001	None	-
RETLW	k	Return with literal in WREG	2	11	0100	kkkk	kkkk	None	
RETURN	_	Return from Subroutine	2	00	0000	0000	1000	None	-
		INHERENT OPERATION	S						1
CLRWDT	_	Clear Watchdog Timer	1	00	0000	0110	0100	TO, PD	
NOP	_	No Operation	1	00	0000	0000	0000	None	
RESET	_	Software device Reset	1	00	0000	0000	0001	None	
SLEEP	_	Go into Standby mode	1	00	0000	0110	0011	TO, PD	
TRIS	f	Load TRIS register with WREG	1	00	0000	0110	Offf	None	
		C-COMPILER OPTIM	IZED			-			-
ADDFSR	n, k	Add Literal k to FSRn	1	11	0001	0nkk	kkkk	None	
	n, mm	Move Indirect FSRn to WREG with pre/post inc/dec modifier, mm	1	00	0000	0001	Onmm	Z	2, 3
MOVIW	k[n]	Move INDFn to WREG, Indexed Indirect.	1	11	1111	0nkk	kkkk	Z	2
	n, mm	Move WREG to Indirect FSRn with pre/post inc/dec modifier, mm	1	00	0000	0001	1nmm	None	2, 3
MOVWI	k[n]	Move WREG to INDFn, Indexed Indirect.	1	11	1111	1nkk	kkkk	None	2

#### Notes:

- 1. If the Program Counter (PC) is modified, or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.
- 2. If this instruction addresses an INDF register and the MSb of the corresponding FSR is set, this instruction will require one additional instruction cycle.
- 3. Details on MOVIW and MOVWI instruction descriptions are available in the next section.

## 38.2.1 Standard Instruction Set

ADDFSR	Add Literal to FSRn
Syntax:	[ label ] ADDFSR FSRn, k
Operands:	$-32 \le k \le 31;$ $n \in [0, 1]$
Operation:	$FSR(n) + k \rightarrow FSR(n)$
Status Affected:	None
Description:	The signed 6-bit literal 'k' is added to the contents of the FSRnH:FSRnL register pair. FSRn is limited to the range 0000h-FFFFh. Moving beyond these bounds will cause the FSR to wrap-around.

ADDLW	Add Literal to W
Syntax:	[ label ] ADDLW k
Operands:	0 ≤ k ≤ 255
Operation:	(W) + k → (W)
Status Affected:	C, DC, Z
Description:	The contents of W are added to the 8-bit literal 'k' and the result is placed in W.

ADDWF	Add W to f
Syntax:	[ label ] ADDWF f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(W) + (f) \rightarrow dest$
Status Affected:	C, DC, Z
Description:	Add the contents of the W register with register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'.

ADDWFC	Add W and Carry Bit to f
Syntax:	[ label ] ADDWFC f {,d}
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(W) + (f) + (C) \rightarrow dest$
Status Affected:	C, DC, Z
Description:	Add W, the Carry flag and data memory location 'f'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed in data memory location 'f'.

ANDLW	AND Literal with W
Syntax:	[ label ] ANDLW k
Operands:	0 ≤ k ≤ 255
Operation:	(W) .AND. $k \rightarrow (W)$

continued	
ANDLW	AND Literal with W
Status Affected:	Z
Description:	The contents of W are AND'ed with the 8-bit literal 'k'. The result is placed in W.

ANDWF	AND W with f
Syntax:	[ label ] ANDWF f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(W) .AND. (f) $\rightarrow$ dest
Status Affected:	Z
Description:	AND the W register with register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f'.

ASRF	Arithmetic Right Shift
Syntax:	[ label ] ASRF f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
	$(f[7]) \rightarrow dest[7]$
Operation:	$(f[7:1]) \rightarrow dest[6:0]$
	$(f[0]) \rightarrow C$
Status Affected:	C, Z
Description:	The contents of register 'f' are shifted one bit to the right through the Carry flag. The MSb remains unchanged. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f'. Register $f \rightarrow C$

BCF	Bit Clear f
Syntax:	[ label ] BCF f, b
Operands:	$0 \le f \le 127$ $0 \le b \le 7$
Operation:	$0 \rightarrow f[b]$
Status Affected:	None
Description:	Bit 'b' in register 'f' is cleared.

BRA	Relative Branch
Syntax:	[ label ] BRA label [ label ] BRA \$+k
Operands:	-256 ≤ label - PC + ≤ 255 -256 ≤ k ≤ 255

continued	
BRA	Relative Branch
Operation:	(PC) + 1 + k → PC
Status Affected:	None
Description:	Add the signed 9-bit literal 'k' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 1 + k. This instruction is a two-cycle instruction. This branch has a limited range.

BRW	Relative Branch with W
Syntax:	[ label ] BRW
Operands:	None
Operation:	(PC) + (W) → PC
Status Affected:	None
Description:	Add the contents of W (unsigned) to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 1 + (W). This instruction is a two-cycle instruction.

BSF	Bit Set f
Syntax:	[ label ] BSF f, b
Operands:	$0 \le f \le 127$ $0 \le b \le 7$
Operation:	$1 \to (f[b])$
Status Affected:	None
Description:	Bit 'b' in register 'f' is set.

BTFSC	Bit Test File, Skip If Clear
Syntax:	[ label ] BTFSC f, b
Operands:	0 ≤ f ≤ 127 0 ≤ b ≤ 7
Operation:	skip if (f[b]) = 0
Status Affected:	None
Description:	If bit 'b' in register 'f' is '1', the next instruction is executed.  If bit 'b', in register 'f', is '0', the next instruction is discarded, and a NOP is executed instead, making this a two-cycle instruction.

BTFSS	Bit Test File, Skip If Set
Syntax:	[ label ] BTFSS f, b
Operands:	0 ≤ f ≤ 127 0 ≤ b < 7
Operation:	skip if (f[b]) = 1

continued	
BTFSS	Bit Test File, Skip If Set
Status Affected:	None
Description:	If bit 'b' in register 'f' is '0', the next instruction is executed.  If bit 'b' is '1', then the next instruction is discarded, and a NOP is executed instead, making this a two-cycle instruction.

CALL	Subroutine Call
Syntax:	[ label ] CALL k
Operands:	0 ≤ k ≤ 2047
Operation:	$(PC) + 1 \rightarrow TOS,$ $k \rightarrow PC[10:0],$ $(PCLATH[6:3]) \rightarrow PC[14:11]$
Status Affected:	None
Description:	Call Subroutine. First, return address (PC + 1) is pushed onto the stack. The 11-bit immediate address is loaded into PC bits [10:0]. The upper bits of the PC are loaded from PCLATH. CALL is a two-cycle instruction.

CALLW	Subroutine Call with W	
Syntax:	[ label ] CALLW	
Operands:	None	
Operation:	$(PC) + 1 \rightarrow TOS,$ $(W) \rightarrow PC[7:0],$ $(PCLATH[6:0]) \rightarrow PC[14:8]$	
Status Affected:	None	
Description:	Subroutine call with W. First, the return address (PC + 1) is pushed onto the return stack. Then, the contents of W is loaded into PC[7:0], and the contents of PCLATH into PC[14:8]. CALLW is a two-cycle instruction.	

CLRF	Clear f
Syntax:	[ label ] CLRF f
Operands:	0 ≤ f ≤ 127
Operation:	$\begin{array}{c} 000h \rightarrow f \\ 1 \rightarrow Z \end{array}$
Status Affected:	Z
Description:	The contents of register 'f' are cleared and the Z bit is set.

CLRW	Clear W
Syntax:	[ label ] CLRW
Operands:	None

continued	
CLRW	Clear W
Operation:	$00h \rightarrow (W)$ $1 \rightarrow Z$
Status Affected:	Z
Description:	W register is cleared. Zero (Z) bit is set.

CLRWDT	Clear Watchdog Timer
Syntax:	[ label ] CLRWDT
Operands:	None
Operation:	00h → WDT, 00h → WDT prescaler, 1 → $\overline{\text{TO}}$ , 1 → $\overline{\text{PD}}$
Status Affected:	TO, PD
Description:	The CLRWDT instruction resets the Watchdog Timer. It also resets the prescaler of the WDT. Status bits, TO and PD, are set.

COMF	Complement f
Syntax:	[ label ] COMF f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(\overline{\mathfrak{f}})  o dest$
Status Affected:	Z
Description:	The contents of register 'f' are complemented.  If 'd' is '0', the result is stored in W.  If 'd' is '1', the result is stored back in register 'f'.

DECF	Decrement f
Syntax:	[ label ] DECF f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) – 1 → dest
Status Affected:	Z
Description:	Decrement register 'f'.  If 'd' is '0', the result is stored in the W register.  If 'd' is '1', the result is stored back in register 'f'.

DECFSZ	Decrement f, Skip If 0
Syntax:	[ label ] DECFSZ f, d

continued	
DECFSZ	Decrement f, Skip If 0
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) − 1 → dest, skip if result = 0
Description:	The contents of register 'f' are decremented.  If 'd' is '0', the result is placed in the W register.  If 'd' is '1', the result is placed back in register 'f'.  If the result is '1', the next instruction is executed.  If the result is '0', then a NOP is executed instead,  making it a two-cycle instruction.

GOTO	Unconditional Branch
Syntax:	[ label ] GOTO k
Operands:	0 ≤ k ≤ 2047
Operation:	k → PC[10:0] PCLATH[6:3] → PC[14:11]
Status Affected:	None
Description:	GOTO is an unconditional branch. The 11-bit immediate value is loaded into PC bits [10:0]. The upper bits of PC are loaded from PCLATH[4:3]. GOTO is a two-cycle instruction.

INCF	Increment f	
Syntax:	[ label ] INCF f, d	
Operands:	$0 \le f \le 127$ $d \in [0,1]$	
Operation:	(f) + 1 → dest	
Status Affected:	Z	
Description:	The contents of register 'f' are incremented.  If 'd' is '0', the result is placed in the W register.  If 'd' is '1', the result is placed back in register 'f'.	

INCFSZ	Increment f, Skip If 0
Syntax:	[ label ] INCFSZ f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(f) + 1 → dest, skip if result = 0
Status Affected:	None

continued				
INCFSZ	Increment f, Skip If 0			
Description:	The contents of register 'f' are incremented.  If 'd' is '0', the result is placed in the W register.  If 'd' is '1', the result is placed back in register 'f'.  If the result is '1', the next instruction is executed.  If the result is '0', a NOP is executed instead,  making it a two-cycle instruction.			

IORLW	Inclusive OR Literal with W		
Syntax:	[ label ] IORLW k		
Operands:	0 ≤ k ≤ 255		
Operation:	(W) .OR. $k \rightarrow (W)$		
Status Affected:	Z		
Description:	The contents of W are ORed with the 8-bit literal 'k'. The result is placed in W.		

IORWF	Inclusive OR W with f	
Syntax:	IORWF f, d	
Operands:	$0 \le f \le 127$ $d \in [0,1]$	
Operation:	(W) .OR. (f) $\rightarrow$ dest	
Status Affected:	Z	
Description:	Inclusive OR the W register with register 'f'.  If 'd' is '0', the result is placed in the W register.  If 'd' is '1', the result is placed back in register 'f'.	

LSLF	Logical Left Shift
Syntax:	[ label ] LSLF f {,d}
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$ \begin{array}{l} (f[7]) \rightarrow C \\ (f[6:0]) \rightarrow dest[7:1] \\ 0 \rightarrow dest[0] \end{array} $
Status Affected:	C, Z
Description:	The contents of register 'f' are shifted one bit to the left through the Carry flag. A '0' is shifted into the LSb. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f'. $C \leftarrow Register\ f \leftarrow 0$

LSRF	Logical Right Shift
Syntax:	[ label ] LSRF f {,d}

continued		
LSRF	Logical Right Shift	
Operands:	$0 \le f \le 127$ $d \in [0,1]$	
Operation:	$0 \rightarrow \text{dest}[7]$ $(f[7:1]) \rightarrow \text{dest}[6:0],$ $(f[0]) \rightarrow C$	
Status Affected:	C, Z	
Description:	The contents of register 'f' are shifted one bit to the right through the Carry flag. A '0' is shifted into the MSb. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f'. $0 \to \mathbf{Register} \ \mathbf{f} \to \mathbf{C}$	

MOVF	Move f			
Syntax:	[ label ] MOVF f, d	[ label ] MOVF f, d		
Operands:	$0 \le f \le 127$ $d \in [0,1]$			
Operation:	$f \rightarrow dest$			
Status Affected:	Z			
Description:	The contents of register f is moved to a destination dependent upon the status of d. If $d = 0$ , destination is W register. If $d = 1$ , the destination is file register f itself. $d = 1$ is useful to test a file register since status flag Z is affected.			
Words:	1			
Cycles:	1			

Example:	MOVF F	SR, 0
After Instruction W = value in FSR register Z = 1		

MOVIW	Move INDFn to W
Syntax:	[ label ] MOVIW ++FSRn [ label ] MOVIWFSRn
	[ label ] MOVIW FSRn++
	[ label ] MOVIW FSRn
	[ label ] MOVIW k[FSRn]
Operands:	$n \in [0,1]$ $mm \in [00,01,10,11]$ $-32 \le k \le 31$

continued				
MOVIW	Move INDFn to W			
Operation:	INDFn → (W)  Effective address is determined by  • FSR + 1 (preincrement)  • FSR - 1 (predecrement)  • FSR + k (relative offset)  After the Move, the FSR value will be either:  • FSR + 1 (all increments)  • FSR - 1 (all decrements)  • Unchanged			
	Z			
	MODE	SYNTAX	mm	
Status	Preincrement	++FSRn	00	
Affected:	Predecrement	FSRn	01	
	Postincrement	FSRn++	10	
	Postdecrement	FSRn	11	
Description:	This instruction is used to move data between W and one of the indirect registers (INDFn).  Before/after this move, the pointer (FSRn) is updated by pre/post incrementing/decrementing it.  The INDFn registers are not physical registers.  Any instruction that accesses an INDFn register actually accesses the register at the address specified by the FSRn.  FSRn is limited to the range 0000h - FFFFh.  Incrementing/decrementing it beyond these bounds will cause it to wrap-around.			

MOVLB	Move Literal to BSR
Syntax:	[ label ] MOVLB k
Operands:	0 ≤ k ≤ 127
Operation:	$k \rightarrow BSR$
Status Affected:	None
Description:	The 6-bit literal 'k' is loaded into the Bank Select Register (BSR).

MOVLP	Move Literal to PCLATH
Syntax:	[ label ] MOVLP k
Operands:	0 ≤ k ≤ 127
Operation:	$k \rightarrow PCLATH$
Status Affected:	None
Description:	The 7-bit literal 'k' is loaded into the PCLATH register.

MOVLW	Move Literal to W
Syntax:	[ label ] MOVLW k
Operands:	0 ≤ k ≤ 255

continued				
MOVLW	Move Literal to W	<i>I</i>		
Operation:	$k \rightarrow (VV)$			
Status Affected:	None			
Description:	The 8-bit literal 'k' is loaded into W register. The "don't cares" will assemble as '0's.			
Words:	1			
Cycles:	1			

Example:	MOVLW	5Ah
After Instruction W = 5Ah		

MOVWF	Move W to f			
Syntax:	[ label ] MOVWF f			
Operands:	0 ≤ f ≤ 127			
Operation:	$(VV) \rightarrow f$			
Status Affected:	None			
Description:	Move data from W to register 'f'.			
Words:	1			
Cycles:	1			

Example:	MOVWF	LATA
Before Instruction LATA = FFh		
<b>W</b> = 4 Fh		
After Instruction		
LATA = 4Fh		
<b>W</b> = 4 Fh		

MOVWI	Move W to INDFn
Syntax:	[ label ] MOVWI ++FSRn [ label ] MOVWIFSRn
	[ label ] MOVWI FSRn++
	[ label ] MOVWI FSRn
	[ label ] MOVWI k[FSRn]
Operands:	$n \in [0,1]$ $mm \in [00,01,10,11]$ $-32 \le k \le 31$

continued				
MOVWI	Move W to INDFn			
Operation:	<ul> <li>(W) → INDFn</li> <li>Effective address is determined by</li> <li>FSR + 1 (preincrement)</li> <li>FSR - 1 (predecrement)</li> <li>FSR + k (relative offset)</li> </ul> After the Move, the FSR value will be either: <ul> <li>FSR + 1 (all increments)</li> <li>FSR - 1 (all decrements)</li> <li>Unchanged</li> </ul>			
	None			
	MODE	SYNTAX	mm	
Status	Preincrement	++FSRn	00	
Affected:	Predecrement	FSRn	01	
	Postincrement	FSRn++	10	
	Postdecrement	FSRn	11	
Description:	This instruction is used to move data between W and one of the indirect registers (INDFn).  Before/after this move, the pointer (FSRn) is updated by pre/post incrementing/decrementing it.  The INDFn registers are not physical registers.  Any instruction that accesses an INDFn register actually accesses the register at the address specified by the FSRn.  FSRn is limited to the range 0000h-FFFFh.  Incrementing/decrementing it beyond these bounds will cause it to wrap-around.  The increment/decrement operation on FSRn will not affect any Status bits.			

NOP	No Operation
Syntax:	[ label ] NOP
Operands:	None
Operation:	No operation
Status Affected:	None
Description:	No operation.
Words:	1
Cycles:	1

Example:	NOP
None.	

RESET	Software Reset
Syntax:	[ label ] RESET
Operands:	None
Operation:	Execute a device Reset. Resets the RI flag of the PCON register.

continued	
RESET	Software Reset
Status Affected:	None
Description:	This instruction provides a way to execute a hardware Reset by software.

RETFIE	Return from Interrupt		
Syntax:	[ label ] RETFIE k		
Operands:	None		
Operation:	(TOS) → PC, 1 → GIE		
Status Affected:	None		
Description:	Return from Interrupt. Stack is POPed and Top-of-Stack (TOS) is loaded in the PC. Interrupts are enabled by setting the Global Interrupt Enable bit, GIE (INTCON[7]). This is a two-cycle instruction.		
Words:	1		
Cycles:	2		

Example:	RETFIE
After Interrupt PC = TOS	
GIE = 1	

RETLW	Return Literal to W	
Syntax:	[ label ] RETLW k	
Operands:	0 ≤ k ≤ 255	
Operation:	$k \rightarrow (W),$ (TOS) $\rightarrow$ PC,	
Status Affected:	None	
Description:	The W register is loaded with the 8-bit literal 'k'. The program counter is loaded from the top of the stack (the return address). This is a two-cycle instruction.	
Words:	1	
Cycles:	2	

```
Example:

CALL TABLE ; W contains table
; offset value
; W now has
; table value
:
TABLE
ADDWF PC ; W = offset
RETLW k1 ; Begin table
RETLW k2 ;
:
RETLW kn ; End of table

Before Instruction
W = 07h
After Instruction
W = value of k8
```

RETURN	Return from Subroutine			
Syntax:	[ label ] RETURN	[ label ] RETURN		
Operands:	None	None		
Operation:	$(TOS) \rightarrow PC$ ,			
Status Affected:	None			
Encoding:	0000	0000 0000 0001 001s		
Description:	Return from subroutine. The stack is POPped and the top of the stack (TOS) is loaded into the Program Counter. This is a two-cycle instruction.			

RLF	Rotate Left f through Carry			
Syntax:	[ label ] RLF f, d			
Operands:	0 ≤ f ≤ 127 d ∈ [0,1]	- ' '='		
Operation:	$(f[n]) \rightarrow dest[n + 1],$ $(f[7]) \rightarrow C,$ $(C) \rightarrow dest[0]$			
Status Affected:	С			
Encoding:	0011	01da	ffff	ffff
Description:	If 'd' is '0', the result is pl	ored back in register 'f' (de		flag.
Words:	1			
Cycles:	1			

Example:	RLF	REG1, 0
Before Instruction REG1 = 1110 0110		
C = 0		
After Instruction		
REG = 1110 0110		
W = 1100 1100		
C = 1		

RRF	Rotate Right f through Carry
Syntax:	[label] RRF f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(f[n]) \rightarrow dest[n-1],$ $(f[0]) \rightarrow C,$ $(C) \rightarrow dest[7]$
Status Affected:	С
Description:	The contents of register 'f' are rotated one bit to the right through the Carry flag. If 'd' is '0', the result is placed in W.  If 'd' is '1', the result is placed back in register 'f' (default).  C register f

SLEEP	Enter Sleep Mode
Syntax:	[ label ] SLEEP
Operands:	None
Operation:	00h → WDT, 0 → WDT prescaler, 1 → $\overline{TO}$ , 0 → $\overline{PD}$
Status Affected:	TO, PD
Description:	The Power-Down (PD) Status bit is cleared. The Time-Out (TO) Status bit is set. Watchdog Timer and its prescaler are cleared.

SUBLW	Subtract W from Literal
Syntax:	[ label ] SUBLW k
Operands:	0 ≤ k ≤ 255
Operation:	$k - (W) \rightarrow (W)$
Status Affected:	C, DC, Z

continued	
SUBLW	Subtract W from Literal
	The W register is subtracted (two's complement method) from the 8-bit literal 'k'. The result is placed in the W register. $C = 0$ , W > k
Description	$C = 1, W \le k$
	DC = 0, $W[3:0] > k[3:0]$
	$DC = 1, W[3:0] \le k[3:0]$

SUBWF	Subtract W from f
Syntax:	[ label ] SUBWF f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(f) - (W) \rightarrow (dest)$
Status Affected:	C, DC, Z
Description	Subtract (two's complement method) W register from register 'f'. If 'd' is '0', the result is stored in the W register. If 'd' is '1', the result is stored back in register 'f. $C = 0$ , $W > f$ $C = 1$ , $W \le f$ $DC = 0$ , $W[3:0] > f[3:0]$ $DC = 1$ , $W[3:0] \le f[3:0]$

SUBWFB	Subtract W from f with Borrow
Syntax:	[ label ] SUBFWB f {,d}
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(W) - (f) - (\overline{B}) \rightarrow dest$
Status Affected:	C, DC, Z
Description:	Subtract W and the Borrow flag (Carry) from register 'f' (two's complement method). If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f'.

SWAPF	Swap Nibbles in f
Syntax:	[ label ] SWAPF f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	$(f[3:0]) \rightarrow dest[7:4],$ $(f[7:4]) \rightarrow dest[3:0]$
Status Affected:	None

continued							
SWAPF	Swap Nibbles in f						
Description:	The upper and lower nibbles of register 'f' are exchanged.  If 'd' is '0', the result is placed in W.  If 'd' is '1', the result is placed in register 'f' (default).						

TRIS	Load TRIS Register with W
Syntax:	[ label ] TRIS f
Operands:	5 ≤ f ≤ 7
Operation:	(W) → TRIS register 'f'
Status Affected:	None
Description:	Move data from W register to TRIS register. When 'f' = 5, TRISA is loaded. When 'f' = 6, TRISB is loaded. When 'f' = 7, TRISC is loaded.

XORLW	Exclusive OR Literal with W
Syntax:	[ label ] XORLW k
Operands:	0 ≤ k ≤ 255
Operation:	(W) .XOR. $k \rightarrow (W)$
Status Affected:	Z
Description:	The contents of W are XORed with the 8-bit literal 'k'. The result is placed in W.

XORWF	Exclusive OR W with f
Syntax:	[ label ] XORWF f, d
Operands:	$0 \le f \le 127$ $d \in [0,1]$
Operation:	(W) .XOR. (f) $\rightarrow$ dest
Status Affected:	Z
Description:	Exclusive OR the contents of the W register with register 'f'.  If 'd' is '0', the result is stored in the W register.  If 'd' is '1', the result is stored back in register 'f'.

# 39. ICSP<sup>™</sup> - In-Circuit Serial Programming<sup>™</sup>

ICSP programming allows customers to manufacture circuit boards with unprogrammed devices. Programming can be done after the assembly process, allowing the device to be programmed with the most recent firmware or a custom firmware. Five pins are needed for ICSP programming:

- ICSPCLK
- ICSPDAT
- MCLR/V<sub>PP</sub>
- V<sub>DD</sub>
- V<sub>SS</sub>

In Program/Verify mode, the program memory, User IDs and the Configuration bits are programmed through serial communications. The ICSPDAT pin is a bidirectional I/O used for transferring the serial data and the ICSPCLK pin is the clock input. For more information on ICSP, refer to the "Family Programming Specification".

## 39.1 High-Voltage Programming Entry Mode

The device is placed into High-Voltage Programming Entry mode by holding the ICSPCLK and ICSPDAT pins low, then raising the voltage on  $\overline{MCLR}/V_{PP}$  to  $V_{IH}$ .

## 39.2 Low-Voltage Programming Entry Mode

The Low-Voltage Programming Entry mode allows the  $PIC^{\otimes}$  Flash MCUs to be programmed using  $V_{DD}$  only, without high voltage. When the LVP Configuration bit is set to '1', the low-voltage ICSP programming entry is enabled. To disable the Low-Voltage ICSP mode, the LVP bit must be programmed to '0'.

Entry into the Low-Voltage Programming Entry mode requires the following steps:

- 1.  $\overline{\mathsf{MCLR}}$  is brought to  $\mathsf{V}_\mathsf{H}$  .
- 2. A 32-bit key sequence is presented on ICSPDAT, while clocking ICSPCLK.

Once the key sequence is complete,  $\overline{MCLR}$  must be held at  $V_{IL}$  for as long as Program/Verify mode is to be maintained.


If low-voltage programming is enabled (LVP = 1), the  $\overline{MCLR}$  Reset function is automatically enabled and cannot be disabled. See the  $\overline{MCLR}$  section for more information.

The LVP bit can only be reprogrammed to '0' by using the High-Voltage Programming mode.

## 39.3 Common Programming Interfaces

Connection to a target device is typically done through an ICSP header. A commonly found connector on development tools is the RJ-11 in the 6P6C (6-pin, 6-connector) configuration. See Figure 39-1.

Figure 39-1. ICD RJ-11 Style Connector Interface



Pin Description


- $1 = V_{PP} / \overline{MCLR}$
- 2 = V<sub>DD</sub> Target
- $3 = V_{SS}$  (ground)
- 4 = ICSPDAT
- 5 = ICSPCLK
- 6 = No Connect

Another connector often found in use with the PICkit<sup>™</sup> programmers is a standard 6-pin header with 0.1 inch spacing. Refer to Figure 39-2.

For additional interface recommendations, refer to the specific device programmer manual prior to PCB design.

It is recommended that isolation devices be used to separate the programming pins from other circuitry. The type of isolation is highly dependent on the specific application and may include devices such as resistors, diodes, or even jumpers. See Figure 39-3 for more information.

Figure 39-2. PICkit™ Programmer Style Connector Interface



Pin Description<sup>(1)</sup>:

 $1 = V_{PP} / \overline{MCLR}$ 

 $2 = V_{DD}$  Target

 $3 = V_{SS}$  (ground)

4 = ICSPDAT


5 = ICSPCLK

6 = No Connect

#### Note:

1. The 6-pin header (0.100" spacing) accepts 0.025" square pins.

Figure 39-3. Typical Connection for ICSP™ Programming



\* Isolation devices (as required).

# 40. Register Summary

Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0	
0x00	INDF0	7:0			l .	INDF	0[7:0]				
0x01	INDF1	7:0				INDF					
0x02	PCL	7:0					[7:0]				
0x03	STATUS	7:0				TO	PD	Z	DC	С	
		7:0		!	!	FSR			Į.		
0x04	FSR0	15:8		FSR0[15:8]							
0.00	E0D4	7:0				FSR <sup>-</sup>					
0x06	FSR1	15:8				FSR1					
0x08	BSR	7:0					BSR	[5:0]			
0x09	WREG	7:0				WRE	G[7:0]				
0x0A	PCLATH	7:0					PCLATH[6:0]				
0x0B	INTCON	7:0	GIE	PEIE						INTEDG	
0x0C	PORTA	7:0			RA5	RA4	RA3	RA2	RA1	RA0	
0x0D	PORTB	7:0	RB7	RB6	RB5	RB4					
0x0E	PORTC	7:0	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0	
0x0F											
	Reserved										
0x11											
0x12	TRISA	7:0			TRISA5	TRISA4	Reserved	TRISA2	TRISA1	TRISA0	
0x13	TRISB	7:0	TRISB7	TRISB6	TRISB5	TRISB4					
0x14	TRISC	7:0	TRISC7	TRISC6	TRISC5	TRISC4	TRISC3	TRISC2	TRISC1	TRISC0	
0x15											
	Reserved										
0x17											
0x18	LATA	7:0			LATA5	LATA4		LATA2	LATA1	LATA0	
0x19	LATB	7:0	LATB7	LATB6	LATB5	LATB4					
0x1A	LATC	7:0	LATC7	LATC6	LATC5	LATC4	LATC3	LATC2	LATC1	LATC0	
0x1B											
	Reserved										
0x8B											
0x8C	PIR0	7:0			TMR0IF	IOCIF				INTF	
0x8D	PIR1	7:0	TMR2IF	TMR3GIF	TMR3IF	TMR1GIF	TMR1IF	ACTIF		NVMIF	
0x8E	PIR2	7:0	CLC2IF	CLC1IF	CWG1IF	NCO1IF	CCP2IF	CCP1 <b>I</b> F	TMR6IF	TMR4IF	
0x8F	PIR3	7:0	BCL1 <b>I</b> F	SSP1IF	RC2IF	TX2IF	RC1IF	TX1IF	CLC4IF	CLC3IF	
0x90	PIR4	7:0			ZCDIF	ADTIF	ADIF	CM1 <b>I</b> F	BCL2IF	SSP2IF	
0x91											
	Reserved										
0x95	DIEO	7.0			TMDOLE	IOOIE				INITE	
0x96	PIE0 PIE1	7:0 7:0	TMDOLE	TMD2CIE	TMR0IE	IOCIE	TMD4IF	ACTIC		INTE	
0x97			TMR2IE	TMR3GIE CLC1IE	TMR3IE	TMR1GIE	TMR1IE	ACTIE	TMDelF	NVMIE	
0x98	PIE2	7:0	CLC2IE		CWG1IE RC2IE	NCO1IE	CCP2IE	CCP1IE	TMR6IE	TMR4IE	
0x99 0x9A	PIE3 PIE4	7:0 7:0	BCL1IE	SSP1IE	ZCDIE	TX2IE ADTIE	RC1IE ADIE	TX1IE CM1IE	CLC4IE BCL2IE	CLC3IE SSP2IE	
0x9A 0x9B	FIE4	7.0			ZODIE	ADITE	ADIC	CIVITIE	BULZIE	JOFZIE	
	Reserved										
 0x018B	r coei veu										
0x018C	WDTCON	7:0	CS				PS[4:0]			SEN	
0x018D	BORCON	7:0	SBOREN				1 0[4.0]			BORRDY	
0x018E	PCON0	7:0	STKOVF	STKUNF		RWDT	RMCLR	RI	POR	BOR	
0x018F	PCON1	7:0	511.0 VI	311(0)(1)		111101	TUNGER	- 11	MEMV	2310	
0x0190	1 33111	7.0							171.E1VI V		
	Reserved										
0x019B	500, 700										
0x019C	TMR0L	7:0				TMRC	L[7:0]				
0x019D	TMR0H	7:0					H[7:0]				
0x019E	TOCONO	7:0	EN		OUT	MD16	[ ]	OUT	PS[3:0]		
OVOIRE	1000110	7.0	L14			INIDIO		0011	<u> </u>		

conti	inued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x019F	T0CON1	7:0		CS[2:0]		ASYNC		CKP	S[3:0]	
0x01A0										
	Reserved									
0x020D										
0x020E	OSCCON2	7:0			COSC[2:0]					
0x020F	OSCCON3	7:0		SOSCPWR						
0x0210	OSCSTAT	7:0		HFOR	MFOR	LFOR	SOR	ADOR	SFOR	
0x0211	OSCEN	7:0		HFOEN	MFOEN	LFOEN	SOSCEN	ADOEN		
0x0212	OSCTUNE	7:0					TUN	[5:0]		
0x0213	OSCFRQ	7:0							FRQ[2:0]	
0x0214	ACTCON	7:0	ACTEN	ACTUD			ACTLOCK		ACTORS	
0x0215	Danamand									
 0x028B	Reserved									
0X020B		7:0				TMD	1[7:0]			
0x028C	TMR1	15:8					1[7:0] 1[15:8]			
0x028E	T1CON	7:0			CKPS		. [ . 0.0]	SYNC	RD16	ON
0x028F	T1GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL	1.510	514
0x0290	T1GATE	7:0	J	5. 52	57101		300.00112	GSS[4:0]		
0x0291	T1CLK	7:0						CS[4:0]		
		7:0				TMR	3[7:0]			
0x0292	TMR3	15:8					B[15:8]			
0x0294	T3CON	7:0			CKPS			SYNC	RD16	ON
0x0295	T3GCON	7:0	GE	GPOL	GTM	GSPM	GGO/DONE	GVAL		
0x0296	T3GATE	7:0						GSS[4:0]		
0x0297	T3CLK	7:0						CS[4:0]		
0x0298										
	Reserved									
0x030B										
0x030C	T2TMR	7:0					IR[7:0]			
0x030D	T2PR	7:0				T2PI	R[7:0]			
0x030E	T2CON	7:0	ON		CKPS[2:0]				PS[3:0]	
0x030F	T2HLT	7:0	PSYNC	CPOL	CSYNC			MODE[4:0]	-	
0x0310	T2CLKCON	7:0							[3:0]	
0x0311	T2RST	7:0						RSE	L[3:0]	
0x0312	T4TMR	7:0					IR[7:0]			
0x0313 0x0314	T4PR T4CON	7:0	ON	I	CKDCI2-01	1491	R[7:0]	OUTE	10.01	
0x0314 0x0315	T4CON T4HLT	7:0 7:0	ON PSYNC	CPOL	CKPS[2:0]			MODE[4:0]	PS[3:0]	
			POTING	CFOL	CSTNC				.3·U]	
0x0316 0x0317	T4CLKCON T4RST	7:0 7:0							[3:0] L[3:0]	
0x0317 0x0318	T6TMR	7:0				TATM	  R[7:0]	INGE	_[0.0]	
0x0310	T6PR	7:0					R[7:0]			
0x0313	T6CON	7:0	ON		CKPS[2:0]	1011		OUTE	PS[3:0]	
0x031A	T6HLT	7:0	PSYNC	CPOL	CSYNC			MODE[4:0]	<u> </u>	
0x031C	T6CLKCON	7:0		5. 52	200				[3:0]	
0x031D	T6RST	7:0							L[3:0]	
0x031E										
	Reserved									
0x038B										
	CCDD4	7:0				CCP	R[7:0]			
0x038C	CCPR1	15:8					R[15:8]			
0x038E	CCP1CON	7:0	EN		OUT	FMT		MOD	E[3:0]	
0x038F	CCP1CAP	7:0							[3:0]	
0x0390	CCPR2	7:0				ССР	R[7:0]			
UXU39U	COPKZ	15:8				CCPF	R[15:8]			
0x0392	CCP2CON	7:0	EN		OUT	FMT		MOD	E[3:0]	

conti	nued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x0394										
 0x039E	Reserved									
0x039F	CCPTMRS0	7:0					C2TSE	=I [1·0]	C1TSI	=I [1·0]
0x03A0	001 11111100	7.0					02101	[,,0]	0110.	[,,,,]
 0x040B	Reserved									
		7:0	DCL	[1:0]						
0x040C	PWM3DC	15:8					I[7:0]			
0x040E	PWM3CON	7:0	EN		OUT	POL				
0x040F	PWM4DC	7:0 15:8	DCL	[1:0]		DCH	l[7:0]			
0x0411	PWM4CON	7:0	EN		OUT	POL				
0x0412	PWM5DC	7:0	DCL	[1:0]						
030412	FVIVISDC	15:8				DCF	H[7:0]			
0x0414	PWM5CON	7:0	EN		OUT	POL				
0x0415 	Reserved									
0x041E										
0x041F	PWMTMRS0	7:0			P5TS	EL[1:0]	P4TSE	EL[1:0]	P3TSE	EL[1:0]
0x0420										
 0x048B	Reserved									
		7:0				ACC	[7:0]			
0x048C	NCO1ACC	15:8				ACC	[15:8]			
		23:16						ACC[	19:16]	
		7:0				INC	[7:0]			
0x048F	NCO1INC	15:8				INC[	[15:8]			
		23:16						INC[1	19:16]	
0x0492	NCO1CON	7:0	EN		OUT	POL				PFM
0x0493	NCO1CLK	7:0		PWS[2:0]	1			CKS	S[3:0]	
0x0494 	Reserved									
0x050B										
0x050C	CWG1CLK	7:0								CS
0x050D	CWG1ISM	7:0							[3:0]	
0x050E	CWG1DBR	7:0					DBR			
0x050F	CWG1DBF	7:0	- FN	1.0			DBF	[5:0]	MODEIO	
0x0510 0x0511	CWG1CON0 CWG1CON1	7:0 7:0	EN	LD	IN		POLD	POLC	MODE[2:0] POLB	POLA
0x0511	CWG1AS0	7:0	SHUTDOWN	REN		 D[1:0]	LSAC		I OLD	I OLA
0x0512	CWG1AS1	7:0	AS7E	AS6E	AS5E	AS4E	AS3E	AS2E	AS1E	AS0E
0x0514	CWG1STR	7:0	OVRD	OVRC	OVRB	OVRA	STRD	STRC	STRB	STRA
0x0515		111	2.1.1.2				2.1.1.2			
 0v0E0D	Reserved									
0x058B	01.00011	7.0	EN.		OUT	INITO	INITAL		MODER	
0x058C 0x058D	CLCnCON	7:0	EN POL		OUT	INTP	INTN G4POL	Caboi	MODE[2:0]	CAROL
0x058D 0x058E	CLCnSEL0	7:0 7:0	PUL				G4POL D1S	G3POL	G2POL	G1POL
0x058E	CLCnSEL1	7:0					D1S			
0x0590	CLCnSEL2	7:0					D23			
0x0590	CLCnSEL3	7:0					D3S			
0x0591	CLCnGLS0	7:0	G1D4T	G1D4N	G1D3T	G1D3N	G1D2T	G1D2N	G1D1T	G1D1N
0x0593	CLCnGLS1	7:0	G2D4T	G2D4N	G2D3T	G2D3N	G2D2T	G2D2N	G2D1T	G2D1N
0x0594	CLCnGLS2	7:0	G3D4T	G3D4N	G3D3T	G3D3N	G3D2T	G3D2N	G3D1T	G3D1N
		-	G4D4T	G4D4N	G4D3T	G4D3N	G4D2T	G4D2N	G4D1T	G4D1N
	CLCnGLS3	7:0	G4D41	CTDTI						
0x0595 0x0596	CLCnGLS3 CLCSELECT	7:0	G4D41	OTDTI	0.001	- 1 - 1 1	¥ = .			
0x0595			G4D41	OFBFIN	0.20.		CLC4OUT	CLC3OUT	SLCT[2:0] CLC2OUT	CLC1OUT

conti	inuad									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x0598										
	Reserved									
0x060B	DOADEO	7.0				DODE	0.7.01			
0x060C	RC1REG	7:0 7:0				RCRE				
0x060D	TX1REG	7:0				TXRE				
0x060E	SP1BRG	15:8				SPBR SPBR				
0x0610	RC1STA	7:0	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
0x0611	TX1STA	7:0	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D
0x0612	BAUD1CON	7:0	ABDOVF	RCIDL	TALI	SCKP	BRG16	BIXOIT	WUE	ABDEN
0x0613	2710210011	7.0	7,850 11	TOBE		00111	Britaria		1102	, abben
	Reserved									
0x0615										
0x0616	RC2REG	7:0				RCRE	G[7:0]		ļ.	
0x0617	TX2REG	7:0				TXRE	G[7:0]			
0x0618	SP2BRG	7:0				SPBR				
UXU010	3FZBRG	15:8				SPBR	G[15:8]			
0x061A	RC2STA	7:0	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
0x061B	TX2STA	7:0	CSRC	TX9	TXEN	SYNC	SENDB	BRGH	TRMT	TX9D
0x061C	BAUD2CON	7:0	ABDOVF	RCIDL		SCKP	BRG16		WUE	ABDEN
0x061D										
<u>.</u>	Reserved									
0x068B	00040115	7.0				DUE	17.01			
0x068C	SSP1BUF	7:0					[7:0]			
0x068D	SSP1ADD	7:0				ADD	0[7:0]			1401/0
0x068E	SSP1MSK	7:0	CMD	OKE	D/Ā	MSK[6:0]		R/W	110	MSK0
0x068F	SSP1STAT	7:0	SMP	CKE			S		UA	BF
0x0690	SSP1CON1	7:0	WCOL	SSPOV	SSPEN	CKP	DOEN		M[3:0]	CEN
0x0691	SSP1CON2	7:0	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN
0x0692 0x0693	SSP1CON3	7:0	ACKTIM	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN
	Reserved									
0x0695	reserved									
0x0696	SSP2BUF	7:0				BUF	:[7·0]			
0x0697	SSP2ADD	7:0				ADD				
0x0698	SSP2MSK	7:0				MSK[6:0]				MSK0
0x0699	SSP2STAT	7:0	SMP	CKE	D/Ā	P	s	R/W	UA	BF
0x069A	SSP2CON1	7:0	WCOL	SSPOV	SSPEN	CKP		SSPI	M[3:0]	
0x069B	SSP2CON2	7:0	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN
0x069C	SSP2CON3	7:0	ACKTIM	PCIE	SCIE	BOEN	SDAHT	SBCDE	AHEN	DHEN
0x069D										
	Reserved									
0x100B										
0x100C	FVRCON	7:0	EN	RDY	TSEN	TSRNG	CDAF	VR[1:0]		'R[1:0]
0x100D	CPCON	7:0	СРО	N[1:0]	CPOS			CPREQ	CPT	CPRDY
0x100E										
	Reserved									
0x101E	7000011	7.0	051		OUT	DOL			INITE	IA ITA I
0x101F	ZCDCON	7:0	SEN		OUT	POL			INTP	INTN
0x1020	Doggrand									
 0x108B	Reserved									
	CM1CON0	7:0	ENI	OUT		POL			HYS	SYNC
0x108C 0x108D	CM1CON0 CM1CON1	7:0 7:0	EN	001		FUL			INTP	INTN
0x108D 0x108E	CM1NCH	7:0							NCH[2:0]	INTIN
0x108E 0x108F	CM1PCH	7:0							PCH[2:0]	
0x108F 0x1090	CWITCH	7.0							гоп[2:0]	
	Reserved									
 0x109E	r Coci veu									
CATOOL										

contii	nued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x109F	CMOUT	7:0		<u> </u>					<u> </u>	C1OUT
0x1091	CIVIOUT	7.0								01001
	Reserved									
0x110B	110001100									
0x110C	DAC1CON	7:0	EN	REFRNG	OE	[1:0]	PSS	[1:0]		NSS
0x110D	DAC1DATL	7:0					IR[7:0]			
0x110E										
	Reserved									
0x1C8B										
04000	NI MAADD	7:0				NVMA	DR[7:0]			!
0x1C8C	NVMADR	15:8					NVMADR[14:8	]		
0v1C9E	NVMDAT	7:0		-		NVMD	AT[7:0]			
0x1C8E	NVMDAT	15:8					NVMD	AT[13:8]		
0x1C90	NVMCON1	7:0		NVMREGS	LWLO	FREE	WRERR	WREN	WR	RD
0x1C91	NVMCON2	7:0				NVMC	ON2[7:0]			
0x1C92										
	Reserved									
0x1D0B										
0x1D0C	ADLTH	7:0					I[7:0]			
5X1200	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	15:8					[15:8]			
0x1D0E	ADUTH	7:0					1[7:0]			
		15:8					[15:8]			
0x1D10	ADERR	7:0					R[7:0]			
		15:8					[15:8]			
0x1D12	ADSTPT	7:0					T[7:0]			
		15:8					Γ[15:8]			
0x1D14	ADFLTR	7:0					R[7:0]			
		15:8					R[15:8]			
		7:0					C[7:0]			
0x1D16	ADACC	15:8				ACC	[15:8]			
0.4040	ADONT	23:16				011	F17.01		ACC	17:16]
0x1D19	ADDRT	7:0					Γ[7:0]			
0x1D1A	ADRPT	7:0					Γ[7:0] \(17:0)			
0x1D1B	ADPREV	7:0 15:8					V[7:0]			
		7:0					/[15:8] S[7:0]			
0x1D1D	ADRES	15:8					[15:8]			
0x1D1F	ADPCH	7:0				INLO		H[5:0]		
0x1D11	Reserved	7.0					FOI	1[3.0]		
		7:0				ACC	Q[7:0]			<u> </u>
0x1D21	ADACQ	15:8				/.00	~[∨]	ACQ[12:8]		
0x1D23	ADCAP	7:0						CAP[4:0]		
		7:0				PRE	E[7:0]	S [1.0]		
0x1D24	ADPRE	15:8						PRE[12:8]		
0x1D26	ADCON0	7:0	ON	CONT		CS		FM		GO
0x1D27	ADCON1	7:0	PPOL	IPEN	GPOL				PCSC	DSEN
0x1D28	ADCON2	7:0	PSIS	1 = 1	CRS[2:0]		ACLR		MD[2:0]	
0x1D29	ADCON3	7:0			CALC[2:0]		SOI		TMD[2:0]	
0x1D2A	ADSTAT	7:0	AOV	UTHR	LTHR	MATH			STAT[2:0]	
0x1D2B	ADREF	7:0								F[1:0]
0x1D2C	ADACT	7:0					ACT	[5:0]		
0x1D2D	ADCLK	7:0						[5:0]		
0x1D2E	ADCG1A	7:0			CGA5	CGA4		CGA2	CGA1	CGA0
0x1D2F	ADCG1B	7:0	CGB7	CGB6	CGB5	CGB4				
0x1D30	ADCG1C	7:0	CGC7	CGC6	CGC5	CGC4	CGC3	CGC2	CGC1	CGC0
0x1D31										
	Reserved									
0x1D8B										
0x1D8C	RA0PPS	7:0					RA0P	PS[5:0]		

contin	ued									
Offect										
Oliser	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x1D8D	RA1PPS	7:0					RA1PI	PS[5:0]		
0x1D8E	RA2PPS	7:0					RA2PI	PS[5:0]		
0x1D8F	Reserved									
0x1D90	RA4PPS	7:0					RA4PI	PS[5:0]		
0x1D91	RA5PPS	7:0					RA5PI	PS[5:0]		
0x1D92										
	Reserved									
0x1D97										
0x1D98	RB4PPS	7:0					RB4PI	PS[5:0]		
0x1D99	RB5PPS	7:0						PS[5:0]		
0x1D9A	RB6PPS	7:0					RB6PI	PS[5:0]		
0x1D9B	RB7PPS	7:0					RB7PI	PS[5:0]		
0x1D9C	RC0PPS	7:0					RC0P	PS[5:0]		
0x1D9D	RC1PPS	7:0						PS[5:0]		
0x1D9E	RC2PPS	7:0					RC2P	PS[5:0]		
0x1D9F	RC3PPS	7:0					RC3P	PS[5:0]		
0x1DA0	RC4PPS	7:0						PS[5:0]		
0x1DA1	RC5PPS	7:0						PS[5:0]		
0x1DA2	RC6PPS	7:0						PS[5:0]		
0x1DA3	RC7PPS	7:0					RC7P	PS[5:0]		
0x1DA4										
	Reserved									
0x1E0B										
0x1E0C	PPSLOCK	7:0								PPSLOCKED
0x1E0D	INTPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E0E	T0CKIPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E0F	T1CKIPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E10	T1GPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E11	T3CKIPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E12	T3GPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E13										
	Reserved									
0x1E18										
0x1E19	T2INPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E1A	T4INPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E1B	T6INPPS	7:0				PORT[2:0]	ı		PIN[2:0]	
0x1E1C	December									
	Reserved									
0x1E1D	0004000	7.0				DODTIO 01			DINIO	
0x1E1E	CCP1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E1F	CCP2PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E20	Reserved									
 0x1E38	Reserveu									
0x1E36	CWG1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E39	CVVGTFF3	7.0				PORT[2.0]			FIN[Z.U]	
	Reserved									
 0x1E3C	r coci veu									
0x1E3D	CLCIN0PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E3E	CLCIN1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E3E	CLCIN2PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E31	CLCIN3PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E40	RX1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E41	CK1PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E42 0x1E43	RX2PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E43	CK2PPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E44	UNZFFO	7.0				1 (111[2.0]			1 114[2.0]	
	Reserved									
 0x1E46	1 COOL VEG									

conti	inued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
		ļ	,					2		
0x1E47	SSP1CLKPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E48	SSP1DATPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E49	SSP1SSPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E4A	SSP2CLKPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E4B	SSP2DATPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E4C	SSP2SSPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E4D										
	Reserved									
0x1E4F	ADAOTEDO	7.0				DODTIO O			DINIO 01	
0x1E50	ADACTPPS	7:0				PORT[2:0]			PIN[2:0]	
0x1E51	Decembed									
 0v4F0D	Reserved									
0x1E8B	ANCELA	7:0			ANCELAE	ANCELAA	ANCELAS	ANCELAS	ANCELAA	ANCELAG
0x1E8C	ANSELA	7:0			ANSELA5	ANSELA4	ANSELA3	ANSELA2	ANSELA1	ANSELA0
0x1E8D	WPUA	7:0			WPUA5	WPUA4	WPUA3	WPUA2	WPUA1	WPUA0
0x1E8E	ODCONA	7:0			ODCA5	ODCA4		ODCA2	ODCA1	ODCA0
0x1E8F	SLRCONA	7:0			SLRA5	SLRA4	INITYTEAC	SLRA2	SLRA1	SLRA0
0x1E90	INLVLA	7:0			INLVLA5	INLVLA4	INLVLA3	INLVLA2	INLVLA1	INLVLA0
0x1E91	IOCAP	7:0			IOCAP5	IOCAP4	IOCAP3	IOCAP2	IOCAP1	IOCAP0
0x1E92	IOCAN	7:0			IOCAN5	IOCAN4	IOCAN3	IOCAN2	IOCAN1	IOCAN0
0x1E93	IOCAF	7:0			IOCAF5	IOCAF4	IOCAF3	IOCAF2	IOCAF1	IOCAF0
0x1E94										
	Reserved									
0x1E95	441051.5		ANIOE! DE	11105150	411051.05	41105157				
0x1E96	ANSELB	7:0	ANSELB7	ANSELB6	ANSELB5	ANSELB4				
0x1E97	WPUB	7:0	WPUB7	WPUB6	WPUB5	WPUB4				
0x1E98	ODCONB	7:0	ODCB7	ODCB6	ODCB5	ODCB4				
0x1E99	SLRCONB	7:0	SLRB7	SLRB6	SLRB5	SLRB4				
0x1E9A	INLVLB	7:0	INLVLB7	INLVLB6	INLVLB5	INLVLB4				
0x1E9B	IOCBP	7:0	IOCBP7	IOCBP6	IOCBP5	IOCBP4				
0x1E9C	IOCBN	7:0	IOCBN7	IOCBN6	IOCBN5	IOCBN4				
0x1E9D	IOCBF	7:0	IOCBF7	IOCBF6	IOCBF5	IOCBF4				
0x1E9E										
	Reserved									
0x1E9F										
0x1EA0	ANSELC	7:0	ANSELC7	ANSELC6	ANSELC5	ANSELC4	ANSELC3	ANSELC2	ANSELC1	ANSELC0
0x1EA1	WPUC	7:0	WPUC7	WPUC6	WPUC5	WPUC4	WPUC3	WPUC2	WPUC1	WPUC0
0x1EA2	ODCONC	7:0	ODCC7	ODCC6	ODCC5	ODCC4	ODCC3	ODCC2	ODCC1	ODCC0
0x1EA3	SLRCONC	7:0	SLRC7	SLRC6	SLRC5	SLRC4	SLRC3	SLRC2	SLRC1	SLRC0
0x1EA4	INLVLC	7:0	INLVLC7	INLVLC6	INLVLC5	INLVLC4	INLVLC3	INLVLC2	INLVLC1	INLVLC0
0x1EA5	IOCCP	7:0	IOCCP7	IOCCP6	IOCCP5	IOCCP4	IOCCP3	IOCCP2	IOCCP1	IOCCP0
0x1EA6	IOCCN	7:0	IOCCN7	IOCCN6	IOCCN5	IOCCN4	IOCCN3	IOCCN2	IOCCN1	IOCCN0
0x1EA7	IOCCF	7:0	IOCCF7	IOCCF6	IOCCF5	IOCCF4	IOCCF3	IOCCF2	IOCCF1	IOCCF0
0x1EA8										
	Reserved									
0x1EE0										
0x1EE1	RA1I2C	7:0		SLEW	PU[					1:0]
0x1EE2	RA2I2C	7:0		SLEW	PU[	1:0]			THI	1:0]
0x1EE3										
	Reserved									
0x1EE4										
0x1EE5	RB4I2C	7:0		SLEW	PU[					1:0]
0x1EE6	RB5I2C	7:0		SLEW	PU[					1:0]
0x1EE7	RB6I2C	7:0		SLEW	PU[	1:0]				1:0]
0x1EE7	RB7I2C	7:0		SLEW	PU[	1:0]			THI	1:0]
0x1EE8	Reserved									
0x1EE9	RC0I2C	7:0		SLEW	PU[	1:0]			THI	1:0]
0x1EEA	RC1I2C	7:0		SLEW	PU[	1:0]			THI	1:0]
0x1EEB	Reserved									
J.A										

# PIC16F18015/25/44/45

# **Register Summary**

conti	nued									
Offset	Name	Bit Pos.	7	6	5	4	3	2	1	0
0x1EEC	RC4I2C	7:0		SLEW	PU	1:0]			TH	[1:0]
0x1EED	RC5I2C	7:0		SLEW	PU	PU[1:0]			TH	[1:0]
0x1EEE  0x8004	Reserved									
0,,000	REVISIONID	7:0	MJRRI	EV[1:0]			MNRR	EV[5:0]		
0x8005	KENISIONID	15:8			Reserved	Reserved		MJRR	EV[5:2]	
0x8006	DEVICEID	7:0				DEV	/[7:0]			
000000	DEVICEID	15:8			Reserved	Reserved		DEV	[11:8]	
0x8007	CONFIG1	7:0			RSTOSC[2:0]				FEXTO	OSC[1:0]
0.0007	CONFIG	15:8				VDDAR				CLKOUTEN
0x8008	CONFIG2	7:0	BORE	N[1:0]		WDT	E[1:0]	PWR	ΓS[1:0]	MCLRE
000000	CONFIG2	15:8			DEBUG	STVREN	PPS1WAY	ZCD	BORV	DACAUTOEN
0x8009	CONFIG3	7:0								
0x6009	CONFIGS	15:8								
0x800A	CONFIG4	7:0	WRTAPP			SAFEN	BBEN		BBSIZE[2:0]	
OXOUUA	CONFIG4	15:8			LVP		WRTSAF	WRTD	WRTC	WRTB
0x800B	CONFIG5	7:0							CPD	CP
OXOUUD	CONFIGS	15:8								

## 41. Electrical Specifications

## 41.1 Absolute Maximum Ratings(†)

Parameter		Rating
Ambient temperature under bias		-40°C to +125°C
Storage temperature		-65°C to +150°C
Volta	ge on pins with respect to V <sub>SS</sub>	
• on V <sub>DD</sub> pin:		-0.3V to +6.5V
• on MCLR pin:		-0.3V to +9.0V
• on all other pins:		$-0.3V$ to $(V_{DD} + 0.3V)$
	Maximum current <sup>(1)</sup>	
• on V <sub>SS</sub> pin	-40°C ≤ T <sub>A</sub> ≤ $+85$ °C	300 mA
	$85^{\circ}\text{C} < \text{T}_{A} \le +125^{\circ}\text{C}$	120 mA
• on V <sub>DD</sub> pin	$-40$ °C $\leq$ T <sub>A</sub> $\leq$ $+85$ °C	250 mA
	$85^{\circ}\text{C} < \text{T}_{A} \le +125^{\circ}\text{C}$	85 mA
on any standard I/O pin		±25 mA
Clamp current, I <sub>K</sub> (V <sub>PIN</sub> < 0 or V <sub>PIN</sub> > V <sub>DD</sub> )		±20 mA
Total power dissipation <sup>(2)</sup>		800 mW

#### Notes:

- Maximum current rating requires even load distribution across I/O pins. Maximum current rating may be limited
  by the device package power dissipation characterizations, see the "Thermal Characteristics" section to
  calculate device specifications.
- 2. Power dissipation is calculated as follows:  $P_{DIS} = V_{DD} x \{I_{DD} \Sigma I_{OH}\} + \Sigma \{(V_{DD} V_{OH}) \times I_{OH}\} + \Sigma (V_{OI} \times I_{OL})$ 
  - Internal Power Dissipation is calculated as follows:

 $P_{INTERNAL} = I_{DD} \times V_{DD}$ 

where I<sub>DD</sub> is current to run the chip alone without driving any load on the output pins.

4. I/O Power Dissipation is calculated as follows:

$$P_{I/O} = \Sigma(I_{OL}*V_{OL}) + \Sigma(I_{OH}*(V_{DD}-V_{OH}))$$

5. Derated Power is calculated as follows:

$$P_{DER} = PD_{MAX}(T_J-T_A)/\theta_{JA}$$

where  $T_A$  = Ambient Temperature,  $T_J$  = Junction Temperature.



**Notice:** Stresses above those listed under the "**Absolute Maximum Ratings**" section may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure above maximum rating conditions for extended periods may affect device reliability.


## 41.2 Standard Operating Conditions

The standard operating conditions for any device are defined as:

Parameter	Condition
Operating Voltage:	$V_{DDMIN} \le V_{DD} \le V_{DDMAX}$
Operating Temperature:	$T_{AMIN} \le T_A \le T_{AMAX}$

Parameter		Ratings
V <sub>DD</sub> — Operating Supply Voltage <sup>(1)</sup>		
	V <sub>DDMIN</sub> (F <sub>OSC</sub> ≤ 16 MHz)	+1.8V
	V <sub>DDMIN</sub> (F <sub>OSC</sub> ≤ 32 MHz)	+2.5V
	$V_{DDMAX}$	+5.5V
T <sub>A</sub> — Operating Ambient Temperature Ra	nge	
Industrial Temperature	T <sub>A_MIN</sub>	<b>-4</b> 0°C
industrial remperature	T <sub>A_MAX</sub>	+85°C
Extended Temperature	T <sub>A_MIN</sub>	<b>-4</b> 0°C
Extended remperature	T <sub>A_MAX</sub>	+125°C
Note:		
1. See Parameter <b>D002</b> , DC Characteris	tics: Supply Voltage.	

Figure 41-1. Voltage Frequency Graph, -40°C  $\leq T_A \leq +125$ °C



- 1. The shaded region indicates the permissible combinations of voltage and frequency.
- 2. Refer to the "External Clock/Oscillator Timing Requirements" section for each Oscillator mode's supported frequencies.

## 41.3 DC Characteristics

## 41.3.1 Supply Voltage


Table 41-1.

Standard Op	perating Cond	ditions (unless other	wise stated	d)			
Param. No.	Sym.	Characteristic	Min.	Typ.†	Max.	Units	Conditions
Supply Volta	ige						
D002	V		1.8	_	5.5	V	F <sub>OSC</sub> ≤ 16 MHz
D002	V <sub>DD</sub>		2.5	_	5.5	V	F <sub>OSC</sub> > 16 MHz
RAM Data R	etention <sup>(1)</sup>						
D003	V <sub>DR</sub>		1.7	_	_	V	Device in Sleep mode
Power-on Re	eset Release	Voltage <sup>(2)</sup>					
D004	V <sub>POR</sub>		_	1.6	_	V	BOR disabled <sup>(3)</sup>
Power-on Re	eset Rearm V	oltage <sup>(2)</sup>	:			•	
D005	V <sub>PORR</sub>		_	1	_	V	BOR disabled <sup>(3)</sup>
V <sub>DD</sub> Rise Ra	te to ensure i	internal Power-on Re	eset signal	(2)		•	-
D006	S <sub>VDD</sub>		0.05	_	_	V/ms	BOR disabled <sup>(3)</sup>

 $<sup>\</sup>dagger$  Data in "Typ." column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

- 1. This is the limit to which  $V_{DD}$  can be lowered in Sleep mode without losing RAM data.
- 2. See the POR and POR Rearm with Slow Rising  $V_{DD}$  figure below.
- 3. See the Reset, WDT, Power-up Timer, and Brown-Out Reset Specifications section for BOR trip point information.

Figure 41-2. POR and POR Rearm with Slow Rising V<sub>DD</sub>



#### Note:

1. When N<sub>POR</sub> is low, the device is held in Reset.

## 41.3.2 Supply Current $(I_{DD})^{(1,2)}$

Table 41-2.

Standard O	Standard Operating Conditions (unless otherwise stated)											
Param. No.	Sym.	Device	Min.	Тур.†	Max.	Units	Conditions					
		Characteristics					V <sub>DD</sub>	Note				
D101	I <sub>DDHFO16</sub>	HFINTOSC = 16 MHz	_	2.4	2.6	mA	3.0V					
D102	I <sub>DDHFOPLL</sub>	HFINTOSC = 32 MHz	_	4.5	5	mA	3.0V					

† Data in "Typ." column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

- 1. The test conditions for all  $I_{DD}$  measurements in Active Operation mode are: OSC1 = external square wave, from rail-to-rail; all I/O pins are outputs driven low;  $\overline{MCLR} = V_{DD}$ ; WDT disabled.
- The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O
  pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an
  impact on the current consumption.

## 41.3.3 Power-Down Current (I<sub>PD</sub>)<sup>(1,2,3)</sup>

#### Table 41-3.

Standard	Operating Cor	nditions (unless oth	erwise s	stated)					
Param.	Sym.	Device	Min.	Typ.†	Max.	Max.	Units	Co	onditions
No.		Characteristics			+85°C	+125°C		V <sub>DD</sub>	Note
D200	I <sub>PD</sub>	I <sub>PD</sub> Base	_	0.4	4	7	μA	3.0V	
D201	I <sub>PD_WDT</sub>	Low-Frequency Internal Oscillator/WDT	_	0.5	5	13	μΑ	3.0V	
D202	I <sub>PD_SOSC</sub>	Secondary Oscillator (S <sub>OSC</sub> )	_	_	8.5	20	μА	3.0V	
D204	I <sub>PD_FVR_BUF1</sub>	FVR Buffer 1 (ADC)	_	40	64	76	μΑ	3.0V	
D204A	I <sub>PD_FVR_BUF2</sub>	FVR Buffer 2 (DAC/CMP)	_	40	64	76	μΑ	3.0V	
D205	I <sub>PD_BOR</sub>	Brown-out Reset (BOR)	_	27	38	50	μΑ	3.0V	
D207	I <sub>PD_ADCA</sub>	ADC - Active	_	_	5	13	μΑ	3.0V	ADC is not converting (Note 4)
D208	I <sub>PD_CMP</sub>	Comparator	_	27	45	70	μA	3.0V	

<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ." column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Notes:

- 1. The peripheral current is the sum of the base  $I_{DD}$  and the additional current consumed when this peripheral is enabled. The peripheral  $\Delta$  current can be determined by subtracting the base  $I_{DD}$  or  $I_{PD}$ current from this limit. Max. values will be used when calculating total current consumption.
- 2. The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode with all I/O pins in High-Impedance state and tied to V<sub>SS</sub>.
- All peripheral currents listed are on a per-peripheral basis if more than one instance of a peripheral is available.
- 4. ADC clock source is ADCRC.

#### 41.3.4 I/O Ports

#### Table 41-4.

Standard Op	erating Co	onditions (unless other	wise stated	d)			
Param. No.	Sym.	Device Characteristics	Min.	Typ.†	Max.	Units	Conditions
Input Low Vo	oltage						

cont							
Standard C	Operating C	onditions (unless othe	rwise stated	)			
Param. No	Sym.	Device Characteristics	Min.	Typ.†	Max.	Units	Conditions
	$V_{IL}$	I/O PORT:					_
D300		with TTL buffer	_	_	0.8	V	$4.5V \le V_{DD} \le 5.5V$
D301			_	_	0.15 V <sub>DD</sub>	V	1.8V ≤ V <sub>DD</sub> < 4.5V
D302		with Schmitt     Trigger buffer	_	_	0.2 V <sub>DD</sub>	V	2.0V ≤ V <sub>DD</sub> ≤ 5.5V
D303		with I <sup>2</sup> C levels	_	_	0.3 V <sub>DD</sub>	V	2.0V ≤ V <sub>DD</sub> ≤ 5.5V
D304		with SMBus 2.0	_	_	0.8	V	$2.7V \le V_{DD} \le 5.5V$
D305		with SMBus 3.0	_	_	0.8	V	
D306		MCLR	_		0.2 V <sub>DD</sub>	V	
High Low \							
	V <sub>IH</sub>	I/O PORT:					
D320		with TTL buffer	2.0		_	V	$4.5V \le V_{DD} \le 5.5V$
D321			0.25 V <sub>DD</sub> + 0.8	_	_	V	1.8V ≤ V <sub>DD</sub> < 4.5V
D322		with Schmitt     Trigger buffer	0.8 V <sub>DD</sub>	_	_	V	2.0V ≤ V <sub>DD</sub> ≤ 5.5V
D323		with I <sup>2</sup> C levels	0.7 V <sub>DD</sub>	_	_	V	
D324		with SMBus 2.0	2.1		_	V	$2.7V \le V_{DD} \le 5.5V$
D325		• with SMBus 3.0	1.35	_	_	V	
D326		MCLR	0.7 V <sub>DD</sub>	_	_	V	
	age Curren						
D340	I <sub>IL</sub>	I/O PORTS	_	±5	_	nA	V <sub>SS</sub> ≤ V <sub>PIN</sub> ≤ V <sub>DD</sub> , Pin at high- impedance, 85°C
D341			_	±5	_	nA	V <sub>SS</sub> ≤ V <sub>PIN</sub> ≤ V <sub>DD</sub> , Pin at high- impedance, 125°C
D342		MCLR <sup>(2)</sup>	_	±50	_	nA	V <sub>SS</sub> ≤ V <sub>PIN</sub> ≤ V <sub>DD</sub> , Pin at high- impedance, 85°C
Weak Pull-	up Current						
D350	I <sub>PUR</sub>		_	_	_	μΑ	$V_{DD} = 3.0V,$ $V_{PIN} = V_{SS}$
Output Lov	w Voltage						
D360	V <sub>OL</sub>	I/O PORTS	_	_	0.6	V	I <sub>OL</sub> = 10.0 mA, V <sub>PIN</sub> = 3.0V
Output Hig	h Voltage						
D370	V <sub>OH</sub>	I/O PORTS	V <sub>DD</sub> - 0.7	_	_	V	I <sub>OH</sub> = 6.0 mA, V <sub>PIN</sub> = 3.0V
All I/O Pins	3						
D380	C <sub>IO</sub>			5	50	pF	

continued									
Standard Operating Conditions (unless otherwise stated)									
Param. No.	Sym.	Device Characteristics	Min.	Typ.†	Max.	Units	Conditions		

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Notes:

- 1. Negative current is defined as current sourced by the pin.
- 2. The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

## 41.3.5 Memory Programming Specifications

#### Table 41-5.

Standard O	perating	Conditions (unless otherwise s	tated)				
Param. No.	Sym.	Device Characteristics	Min.	Typ. †	Max.	Units	Conditions
Data EEPRO	OM Memo	ory Specifications					
MEM20	E <sub>D</sub>	DataEE Byte Endurance	100k	_	_	E/W	-40°C ≤ T <sub>A</sub> ≤ +85°C
MEM21	T <sub>D_RET</sub>	Characteristic Retention	_	40	_	Year	Provided no other specifications are violated
MEM23	V <sub>D_RW</sub>	V <sub>DD</sub> for Read or Erase/Write operation	V <sub>DDMIN</sub>	_	V <sub>DDMAX</sub>	٧	
MEM24	T <sub>D_BEW</sub>	Byte Erase and Write Cycle Time	_	_	11	ms	
Program Fla	ash Mem	ory Specifications					
МЕМ30	E <sub>P</sub>	Flash Memory Cell Endurance	10k	_	_	E/W	-40°C ≤ T <sub>A</sub> ≤ +85°C (Note 1)
MEM32	T <sub>P_RET</sub>	Characteristic Retention	_	40	_	Year	Provided no other specifications are violated
MEM33	V <sub>P_RD</sub>	V <sub>DD</sub> for Read operation	V <sub>DDMIN</sub>	_	V <sub>DDMAX</sub>	V	
MEM34	V <sub>P_REW</sub>	V <sub>DD</sub> for Row Erase or Write operation	V <sub>DDMIN</sub>	_	$V_{\text{DDMAX}}$	V	
MEM35	T <sub>P_REW</sub>	Self-Timed Page Write	_	_	_	ms	
МЕМ36	T <sub>SE</sub>	Self-Timed Page Erase	_	_	_	ms	
MEM37	T <sub>P_WRD</sub>	Self-Timed Word Write	_	_	_	μs	
+ D-4- :- "T-	,,		4-41			-	

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Note:

 Flash Memory Cell Endurance for the Flash memory is defined as: One Row Erase operation and one Self-Timed Write.

## 41.3.6 Thermal Characteristics


## Table 41-6.

Standard O	perating Co	onditions (unless otherwise stated)			
Param. No.	Sym.	Characteristic	Тур.	Units	Conditions
TH01	$\theta_{JA}$	Thermal Resistance Junction to	_	°C/W	8-pin PDIP package
		Ambient	_	°C/W	8-pin SOIC package
			_	°C/W	8-pin DFN package
				°C/W	14-pin PDIP package
			_	°C/W	14-pin SOIC package
			_	°C/W	14-pin TSSOP package
			_	°C/W	16-pin VQFN package
			_	°C/W	20-pin PDIP package
			_	°C/W	20-pin SOIC package
			_	°C/W	20-pin SSOP package
			_	°C/W	20-pin QFN package
TH02	T <sub>JMAX</sub>	Maximum Junction Temperature	150	°C	
TH03	PD	Power Dissipation	_	W	PD = P <sub>INTERNAL</sub> +P <sub>I/O</sub>
TH04	P <sub>INTERNAL</sub>	Internal Power Dissipation	_	W	$P_{INTERNAL} = I_{DD} \times V_{DD}^{(1)}$
TH05	P <sub>I/O</sub>	I/O Power Dissipation		W	$P_{I/O} = \Sigma(I_{OL}^*V_{OL}) + \Sigma(I_{OH}^*(V_{DD}^-V_{OH}))$
TH06	P <sub>DER</sub>	Derated Power	_	W	$P_{DER} = PD_{MAX} (T_J - T_A) / \theta_{JA}^{(2)}$

- 1. I<sub>DD</sub> is current to run the chip alone without driving any load on the output pins.
- 2.  $T_A$  = Ambient Temperature,  $T_J$  = Junction Temperature.

## 41.4 AC Characteristics

Figure 41-3. Load Conditions



## 41.4.1 External Clock/Oscillator Timing Requirements

Figure 41-4. Clock Timing




Table 41-7.

Standard Op	Standard Operating Conditions (unless otherwise stated)										
Param. No.	Sym.	Characteristic	Min.	Тур. †	Units	Conditions					
ECL Oscillator											
OS1	F <sub>ECL</sub>	Clock Frequency	_	_	1	MHz					
OS2	T <sub>ECL_DC</sub>	Clock Duty Cycle	40	_	60	%					
ECH Oscilla	tor										
OS5	F <sub>ECH</sub>	Clock Frequency	_	_	32	MHz	V <sub>DD</sub> ≥ 2.7V				
			_	_	16	MHz	V <sub>DD</sub> < 2.7V				

contin	ued									
Standard Operating Conditions (unless otherwise stated)										
Param. No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions			
OS6	T <sub>ECH_DC</sub>	Clock Duty Cycle	40	_	60	%				
Secondary (	Oscillator		'	-						
OS10	F <sub>SEC</sub>	Clock Frequency	_	32.768	_	kHz	(Note 4)			
System Osc	illator		'	-						
OS20	Fosc	System Clock Frequency	_	_	32	MHz	(Note 2, Note 3)			
OS21	F <sub>CY</sub>	Instruction Frequency	_	F <sub>OSC</sub> /4	_	MHz				
OS22	T <sub>CY</sub>	Instruction Period	125	1/F <sub>CY</sub>	_	ns				

#### Notes:

- Instruction cycle period (T<sub>CY</sub>) equals four times the input oscillator time base period. All specified values are
  based on characterization data for that particular oscillator type under standard operating conditions with the
  device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or
  higher than expected current consumption. All devices are tested to operate at "min" values with an external
  clock applied to OSC1 pin. When an external clock input is used, the "max" cycle time limit is "DC" (no clock)
  for all devices.
- 2. The system clock frequency (F<sub>OSC</sub>) is selected by the "main clock switch controls" as described in the "Power Saving Operation Modes" section.
- 3. The system clock frequency (F<sub>OSC</sub>) must meet the voltage requirements defined in the "Standard Operating Conditions" section.

#### 41.4.2 Internal Oscillator Parameters<sup>(1)</sup>

#### Table 41-8.

Standard Op	perating Condi	tions (unless otherwis	se stated)				
Param. No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions
OS50	F <sub>HFOSC</sub>	Precision Calibrated HFINTOSC Frequency	_	4 8 16 32	_	MHz	(Note 2)
OS51	F <sub>HFOSCLP</sub>	Low-Power Optimized HFINTOSC Frequency	_ _ _ _	1 2 1 2	_ _ _ _ _	MHz MHz MHz MHz	-40°C to 85°C -40°C to 85°C -40°C to 125 °C -40°C to 125 °C
OS52	F <sub>MFOSC</sub>	Internal Calibrated MFINTOSC Frequency	_	500	_	kHz	
OS53*	F <sub>LFOSC</sub>	Internal LFINTOSC Frequency	_	31	_	kHz	


	Standard Operating Conditions (unless otherwise stated)										
Param. No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions				
OS54*	T <sub>HFOSCST</sub>	HFINTOSC Wake-up from Sleep Start-up Time	_	_	_	μs					
OS56	T <sub>LFOSCST</sub>	LFINTOSC Wake-up from Sleep Start-up Time	_	_	_	ms					

<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

- 1. To ensure these oscillator frequency tolerances,  $V_{DD}$  and  $V_{SS}$  must be capacitively decoupled as close to the device as possible. 0.1  $\mu F$  and 0.01  $\mu F$  values in parallel are recommended.
- 2. See the figure below.

Figure 41-5. Precision Calibrated HFINTOSC Frequency Accuracy Over Device V<sub>DD</sub> and Temperature



## 41.4.3 I/O and CLKOUT Timing Specifications

Figure 41-6. CLKOUT and I/O Timing




Table 41-9. I/O and CLKOUT Timing Specifications

Param. No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions
IO1*	T <sub>CLKOUTH</sub>	CLKOUT rising edge delay (rising edge F <sub>OSC</sub> (Q1 cycle) to falling edge CLKOUT	_	_	_	ns	
IO2*	T <sub>CLKOUTL</sub>	CLKOUT falling edge delay (rising edge F <sub>OSC</sub> (Q3 cycle) to rising edge CLKOUT	_	_	_	ns	
IO3*	T <sub>IO_VALID</sub>	Port output valid time (rising edge F <sub>OSC</sub> (Q1 cycle) to port valid)	_	_	_	ns	
IO4*	T <sub>IO_SETUP</sub>	Port input setup time (Setup time before rising edge F <sub>OSC</sub> – Q2 cycle)	_	_	_	ns	
IO5*	T <sub>IO_HOLD</sub>	Port input hold time (Hold time after rising edge F <sub>OSC</sub> – Q2 cycle)	_	_	_	ns	
IO6*	T <sub>IOR_SLREN</sub>	Port I/O rise time, slew rate enabled	_	_	_	ns	V <sub>DD</sub> = 3.0V
IO7*	T <sub>IOR_SLRDIS</sub>	Port I/O rise time, slew rate disabled	_	_	_	ns	V <sub>DD</sub> = 3.0V
IO8*	T <sub>IOF_SLREN</sub>	Port I/O fall time, slew rate enabled	_	_	_	ns	V <sub>DD</sub> = 3.0V
IO9*	T <sub>IOF_SLRDIS</sub>	Port I/O fall time, slew rate disabled	_	_	_	ns	V <sub>DD</sub> = 3.0V
IO10*	T <sub>INT</sub>	INT pin high or low time to trigger an interrupt	_	_	_	ns	
IO11*	T <sub>IOC</sub>	Interrupt-on-Change minimum high or low time to trigger interrupt	_	_	_	ns	

# 41.4.4 Timer0 and Timer1 External Clock Requirements Table 41-10.

Standard Operating Conditions (unless otherwise stated)


Operating Temperature:  $-40^{\circ}C \le T_A \le +125^{\circ}C$ 

Param.	Sym.	Cha	racteristic	Min.	Тур. †	Max.	Units	Conditions
No.								
40*	T <sub>T</sub> 0H	T0CKI High	No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
		Pulse Width	With Prescaler	10	_	_	ns	
41*	T <sub>T</sub> 0L	T0CKI Low	No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
		Pulse Width	With Prescaler	10	_	_	ns	
42*	T <sub>T</sub> 0P	T0CKI Perio	d	Greater of: 20 or (T <sub>CY</sub> +40)/N	_	_	ns	N = Prescale value
45*	T <sub>T</sub> 1H	T1CKI High Time	Synchronous, No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
			Synchronous, with Prescaler	15	_	_	ns	
			Asynchronous	30	_	_	ns	
46*	T <sub>T</sub> 1L	T1CKI Low Time	Synchronous, No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
			Synchronous, with Prescaler	15	_	_	ns	
			Asynchronous	30	_	_	ns	
47*	T <sub>T</sub> 1P	T1CKI Input	Synchronous	Greater of: 30 or (T <sub>CY</sub> +40)/N	_	_	ns	N = Prescale value
		Period	Asynchronous	60	_	_	ns	
49*	TCKEZ <sub>TMR</sub> 1	Delay from E to Timer Incr	External Clock Edge ement	2 T <sub>OSC</sub>	_	7 T <sub>OSC</sub>	_	Timers in Sync

<sup>\*</sup> These parameters are characterized but not tested.


<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Figure 41-7. Timer0 and Timing1 External Clock Timings



## 41.4.5 Reset, WDT, Power-up Timer, and Brown-Out Reset Specifications


Figure 41-8. Reset, Watchdog Timer, and Power-up Timer Timing



#### Note:

1. Asserted low.

Figure 41-9. Brown-out Reset Timing and Characteristics



#### Note:

1. Delay period is determined by the PWRTS bits in the Configuration Word register.

Table 41-11

Standard Op	Standard Operating Conditions (unless otherwise stated)										
Param. No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions				
RST01*	T <sub>MCLR</sub>	MCLR Pulse Width Low to ensure Reset	_	_	_	μs					
RST02*	T <sub>IOZ</sub>	I/O high-impedance from Reset detection	_	_	_	μs					
RST03	T <sub>WDT</sub>	Watchdog Timer Time- out Period	_	_	_	ms	<b>WDTCPS =</b> 00100				
RST04*	T <sub>PWRT</sub>	Power-up Timer Period	_	_	64	ms					
RST05	T <sub>OST</sub>	Oscillator Start-up Timer Period <sup>(1,2)</sup>	_	1024	_	Tosc					
RST06	$V_{BOR}$	Brown-out Reset	_	2.65	_	V	BORV = 0				
		Voltage	_	1.9	_	V	BORV = 1				
RST07	V <sub>BORHYS</sub>	Brown-out Reset Hysteresis	_	_	_	mV	BORV = 00				
RST08	T <sub>BORDC</sub>	Brown-out Reset Response Time	_	_	_	μs					

<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

- 1. By design, the Oscillator Start-up Timer (OST) counts the first 1024 cycles, independent of frequency.
- 2. To ensure these voltage tolerances,  $V_{DD}$  and  $V_{SS}$  must be capacitively decoupled as close to the device as possible. 0.1  $\mu F$  and 0.01  $\mu F$  values in parallel are recommended.

# 41.4.6 Analog-to-Digital Converter (ADC) Accuracy Specifications<sup>(1,2)</sup> Table 41-12.

Standard Op	Standard Operating Conditions (unless otherwise stated)									
$V_{DD} = 3.0 V,$	Γ <sub>A</sub> = 25°C	c, T <sub>AD</sub> = 500 ns								
Param. No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions			
AD01	N <sub>R</sub>	Resolution	_	_	10	bit				
AD02	E <sub>IL</sub>	Integral Nonlinearity Error	_	_	±2	LSb	$ADC_{REF}$ + = 3.0V, $ADC_{REF}$ - = 0V			
AD03	E <sub>DL</sub>	Differential Nonlinearity Error	_	_	±1	LSb	$ADC_{REF}$ + = 3.0V, $ADC_{REF}$ - = 0V			
AD04	E <sub>OFF</sub>	Offset Error	_	_	±2	LSb	$ADC_{REF}$ + = 3.0V, $ADC_{REF}$ - = 0V			
AD05	E <sub>GN</sub>	Gain Error	_	_	±2.5	LSb	$ADC_{REF}$ + = 3.0V, $ADC_{REF}$ - = 0V			
AD06	V <sub>ADREF</sub>	ADC Reference Voltage (AD <sub>REF</sub> + - AD <sub>REF</sub> -)	_	_	V <sub>DD</sub>	٧				
AD07	V <sub>AIN</sub>	Full-Scale Range	AD <sub>REF</sub> -	_	AD <sub>REF</sub> +	V				
AD08	Z <sub>AIN</sub>	Recommended Impedance of Analog Voltage Source	_	1	_	kΩ				
AD09	R <sub>VREF</sub>	ADC Voltage Reference Ladder Impedance	_	50	_	kΩ	(Note 3)			

<sup>\*</sup> These parameters are characterized but not tested.

#### Notes:

- 1. Total Absolute Error is the sum of the offset, gain and integral nonlinearity (INL) errors.
- 2. The ADC conversion result never decreases with an increase in the input and has no missing codes.
- 3. This is the impedance seen by the  $V_{\mathsf{REF}}$  pads when the external reference pads are selected.

# 41.4.7 Analog-to-Digital Converter (ADC) Conversion Timing Specifications Table 41-13.

Standard O	peratin	g Conditions (unless other	wise s	stated)			
Param. No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions
AD20	T <sub>AD</sub>	ADC Clock Period	_	_	_	μs	Using F <sub>OSC</sub> as the ADC clock source ADOCS = 0
			_	2	_	μs	Using ADCRC as the ADC clock source ADOCS = 1
AD21	T <sub>CNV</sub>	Conversion Time	_	14 T <sub>AD</sub> +2T <sub>CY</sub>	_	_	Using F <sub>OSC</sub> as the ADC clock source ADOCS = 0
			_	16 T <sub>AD</sub> +2T <sub>CY</sub>	_	_	Using ADCRC as the ADC clock source ADOCS = 1

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Standard Operating Conditions (unless otherwise stated)									
Param. No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions		
AD22	T <sub>HCD</sub>	Sample-and-Hold Capacitor Disconnect Time	_	2 T <sub>AD</sub> +1T <sub>CY</sub>	_	_	Using F <sub>OSC</sub> as the ADC clock source ADOCS = 0		
			_	3 T <sub>AD</sub> +2T <sub>CY</sub>	_	_	Using ADCRC as the ADC clock source ADOCS = 1		

<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Figure 41-10. ADC Conversion Timing (ADC Clock F<sub>OSC</sub>-Based)





Figure 41-11. ADC Conversion Timing (ADC Clock from ADCRC)



#### Note:

1. If the ADC clock source is selected as ADCRC, a time of  $T_{CY}$  is added before the ADC clock starts. This allows the SLEEP instruction to be executed.

#### 41.4.8 8-Bit DAC Specifications

#### Table 41-14.

Standard Ope	rating Cond	ditions (unless otherwise	e stated)				
$V_{DD} = 3.0V, T_A$	<sub>λ</sub> = 25°C						
Param. No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions
DAC01*	C <sub>LSB</sub>	Step Size	_	(V <sub>DACREF</sub> +- V <sub>DACREF</sub> -)/256	_	V	
DAC02	C <sub>INL</sub>	Integral Error	_	_	±1	LSb	
DAC03	C <sub>DNL</sub>	Differential Error	_	_	±1	LSb	
DAC04	C <sub>OFF</sub>	Offset Error	_	_	±1	LSb	
DAC05	C <sub>GN</sub>	Gain Error	_	_	±2	LSb	
DAC06*	C <sub>R</sub>	Unit Resistor Value	_	_	_	Ω	
DAC07*	C <sub>ST</sub>	Settling Time <sup>(1)</sup>	_	_	10	μs	
DAC08*	C <sub>ACC</sub>	Absolute Accuracy	_	_	±1	LSb	

<sup>\*</sup> These parameters are characterized but not tested.

#### Note:

1. Settling time measured while DACR[7:0] transitions from 'b000000000 to 'b111111111.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

## 41.4.9 Comparator Specifications

#### Table 41-15.

Standard Opera	ating Conditi	ons (unless otherwise stated	d)				
$V_{DD}$ = 3.0V, $T_A$	= 25°C						
Param. No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions
CM01	V <sub>IOFF</sub>	Input Offset Voltage	_	_	±50	mV	$V_{ICM} = V_{DD}/2$
CM02	V <sub>ICM</sub>	Input Common Mode Range	GND	_	V <sub>DD</sub>	V	
CM03	CMRR	Common Mode Input Rejection Ratio	_	_	35	dB	
CM04	V <sub>HYST</sub>	Comparator Hysteresis	10	_	35	mV	
CM05	T <sub>RESP</sub> (1)	Response Time, Rising Edge	_	_	_	ns	
		Response Time, Falling	_	_	_	ns	

<sup>\*</sup> These parameters are characterized but not tested.

#### Note:

1. Response time measured with one comparator input at  $V_{DD}/2$ , while the other input transitions from  $V_{SS}$  to  $V_{DD}$ .

## 41.4.10 Zero-Cross Detect (ZCD) Specifications

#### Table 41-16.

$V_{DD} = 3.0V, T_A = 25^{\circ}C$										
Param. No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions			
ZC01	V <sub>PINZC</sub>	Voltage on Zero-Cross Pin	_	0.9	_	V				
ZC02	I <sub>ZCD_MAX</sub>	Maximum source or sink current	_	_	600	μA				
ZC03	T <sub>RESPH</sub>	Response Time, Rising Edge	_	1	_	μs				
	T <sub>RESPL</sub>	Response Time, Falling Edge	_	1	_	μs				

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

## 41.4.11 Fixed Voltage Reference (FVR) Specifications

Table 41-17.

Standard Ope	Standard Operating Conditions (unless otherwise stated)									
Param. No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions			
FVR01	V <sub>FVR</sub> 1	1x Gain (1.024V)	-4	_	+4	%	V <sub>DD</sub> ≥ 2.5V, -40°C to 85°C			
FVR02	V <sub>FVR</sub> 2	2x Gain (2.048V)	-4	_	+4	%	V <sub>DD</sub> ≥ 2.5V, -40°C to 85°C			
FVR03	V <sub>FVR</sub> 4	4x Gain (4.096V)	<b>-</b> 6	_	+6	%	V <sub>DD</sub> ≥ 4.75V, -40°C to 85°C			
FVR04	T <sub>FVRST</sub>	FVR Start-up Time	_	25	_	μs				

#### 41.4.12 Temperature Indicator Requirements

Table 41-18.

Standard Ope	Standard Operating Conditions (unless otherwise stated)								
Param. No.	Sym.	Characte	Characteristic			Max.	Units	Conditions	
TS01*	T <sub>ACQMIN</sub>	Minimum ADC A Time Delay	cquisition	_	25	_	μs		
TS02*	M <sub>V</sub>	Voltage	High Range	_	-3.75	_	mV/°C	TSRNG = 1	
		Sensitivity	Low Range	_	-2.75	_	mV/°C	TSRNG = 0	

<sup>\*</sup> These parameters are characterized but not tested.

## 41.4.13 Capture/Compare/PWM Requirements (CCP)

Table 41-19.

Standard Operating Conditions (unless otherwise stated) Operating Temperature: -40°C  $\leq T_A \leq +125$ °C


Param. No.	Sym.	Chara	cteristic	Min.	Тур. †	Max.	Units	Conditions
CC01*	T <sub>CC</sub> L	CCPx Input	No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
		Low Time	With Prescaler	20	_	_	ns	
CC02*	T <sub>CC</sub> H	CCPx Input	No Prescaler	0.5T <sub>CY</sub> +20	_	_	ns	
		High Time	With Prescaler	20	_	_	ns	
CC03*	T <sub>CC</sub> P	CCPx Input Period		(3T <sub>CY</sub> +40)/N	_	_	ns	N = Prescale value

<sup>\*</sup> These parameters are characterized but not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Figure 41-12. Capture/Compare/PWM Timings (CCP)




Note: Refer to the "Load Conditions" figure for load conditions.

## 41.4.14 EUSART Synchronous Transmission Requirements

Table 41-20.

Standard Ope	Standard Operating Conditions (unless otherwise stated)								
Param. No.	Sym.	Characteristic	Min.	Max.	Units	Conditions			
US120	T <sub>CK</sub> H2 <sub>DT</sub> V	SYNC XMIT (Host and Client)	_	_	ns	3.0V ≤ V <sub>DD</sub> ≤ 5.5V			
		Clock high to data-out valid	_	_	ns	1.8V ≤ V <sub>DD</sub> ≤ 5.5V			
US121	T <sub>CKRF</sub>	Clock out rise time and fall time	_	_	ns	3.0V ≤ V <sub>DD</sub> ≤ 5.5V			
		(Host mode)	_	_	ns	$1.8V \le V_{DD} \le 5.5V$			
US122	T <sub>DTRF</sub>	Data-out rise time and fall time	_	_	ns	$3.0V \le V_{DD} \le 5.5V$			
			_	_	ns	1.8V ≤ V <sub>DD</sub> ≤ 5.5V			

Figure 41-13. EUSART Synchronous Transmission (Host/Client) Timing




Note: Refer to the "Load Conditions" figure for load conditions.

## 41.4.15 EUSART Synchronous Receive Requirements

Table 41-21.

Standard Ope	Standard Operating Conditions (unless otherwise stated)							
Param. No.	Sym.	Characteristic	Min.	Max.	Units	Conditions		
US125	T <sub>DT</sub> V2 <sub>CKL</sub>	SYNC RCV (Host and Client)  Data-setup before CK ↓ (DT hold time)	_	_	ns			
US126	T <sub>CK</sub> L2 <sub>DTL</sub>	Data-hold after CK ↓ (DT hold time)		_	ns			

Figure 41-14. EUSART Synchronous Receive (Host/Client) Timing



Note: Refer to the "Load Conditions" figure for load conditions.

## 41.4.16 SPI Mode Requirements

Table 41-22. SPI Mode

Standard (	Operating Cond	litions (unless otherwis	e stated)				
Param. No.	Sym.	Characteristic	Min.	Тур. †	Max.	Units	Conditions
SP70*	T <sub>SS</sub> L2 <sub>SC</sub> H, T <sub>SS</sub> L2 <sub>SC</sub> L	SDO to SCK↓ or SCK↑ input	2.25*T <sub>CY</sub>	_	_	ns	
SP71*	T <sub>SC</sub> H	SCK output high time	T <sub>CY</sub> + 20	_	0.5 T <sub>SCK</sub> + 12	ns	
SP72*	T <sub>SC</sub> L	SCK output low time	T <sub>CY</sub> + 20	_	0.5 T <sub>SCK</sub> + 12	ns	
SP73*	T <sub>DI</sub> V2 <sub>SC</sub> H, T <sub>DI</sub> V2 <sub>SC</sub> L	Setup time of SDI data input to SCK edge	85	_	_	ns	
SP74*	T <sub>SC</sub> H2 <sub>DI</sub> L, T <sub>SC</sub> L2 <sub>DI</sub> L	Hold time of SDI data input to SCK edge	0	_	_	ns	
		Hold time of SDI data input to final SCK	0.5 T <sub>SCK</sub>			ns	CKE = 0, SMP = 1
SP75*	T <sub>DO</sub> R	SDO data output rise time	_	10	25	ns	C <sub>L</sub> = 50 pF
SP76*	T <sub>DO</sub> F	SDO data output fall time	_	10	25	ns	C <sub>L</sub> = 50 pF
SP78*	T <sub>SC</sub> R	SCK output rise time	_	10	25	ns	C <sub>L</sub> = 50 pF
SP79*	T <sub>SC</sub> F	SCK output fall time	_	10	25	ns	C <sub>L</sub> = 50 pF
SP80*	$T_{SC}H2_{DO}V$ , $T_{SC}L2_{DO}V$	SDO data output valid after SCK edge	_	_	_	ns	C <sub>L</sub> = 50 pF
SP81*	T <sub>DO</sub> V2 <sub>SC</sub> H, T <sub>DO</sub> V2 <sub>SC</sub> L	SDO data output valid to first SCK edge	1 T <sub>CY</sub>	_	_	ns	C <sub>L</sub> = 50 pF CKE = 1
SP82*	T <sub>SS</sub> L2 <sub>DO</sub> V	SDO data output valid after SS↓ edge	_	_	50	ns	C <sub>L</sub> = 20 pF
SP83*	T <sub>SC</sub> H2 <sub>SS</sub> H, T <sub>SC</sub> L2 <sub>SS</sub> H	SS ↑ after last SCK edge	1.5 T <sub>CY</sub> + 40	_	_	ns	

conti	continued								
Standard O	perating Condit	ions (unless otherwis	e stated)						
Param. No.	Sym.	Characteristic	Min.	Typ. †	Max.	Units	Conditions		


<sup>\*</sup> These parameters are characterized but not tested.

† Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

#### Note:

1. SMP bit in the SSPxSTAT register must be set and the slew rate control must be disabled on the clock and data pins (clear the corresponding bits in SLRCONx register) for SPI to operate over 4 MHz.

Figure 41-15. SPI Host Mode Timing (CKE = 0, SMP = 0)




Note: Refer to the "Load Conditions" figure for load conditions.

Rev. 30-0000844 4/6/2017

Figure 41-16. SPI Host Mode Timing (CKE = 1, SMP = 1)


SS

; SP81;



Note: Refer to the "Load Conditions" figure for load conditions.

Figure 41-17. SPI Client Mode Timing (CKE = 0)



Note: Refer to the "Load Conditions" figure for load conditions.

Rev. 30-000086A 4/6/2017 - SP82 SS SP70 SP83 SCK (CKP = 0) SP72 SCK (CKP = 1) -¦SP80 LSb SDO MSb bit 6 →; ;<del>←</del> SP75, SP76 SP77 SDI MSb In LSb In SP74

Figure 41-18. SPI Client Mode Timing (CKE = 1)


Note: Refer to the "Load Conditions" figure for load conditions.

## 41.4.17 I<sup>2</sup>C Bus Start/Stop Bits Requirements

Table 41-23.

Standard O	perating	Conditions (un	less otherwise	stated	)				
Param. No.	Sym.	Characteristic		Min.	Тур. †	Max.	Units	Conditions	
SP90*	T <sub>SU:STA</sub>	Start condition	100 kHz mode	4700	_	_	ns	Only relevant for Repeated	
		Setup time	400 kHz mode	600	_	_		Start condition	
SP91*	T <sub>HD:STA</sub>	Start condition	100 kHz mode	4000	_	_	ns	After this period, the first clock	
		Hold time	400 kHz mode	600	_	_		pulse is generated	
SP92*	T <sub>SU:STO</sub>	Stop condition	100 kHz mode	4000	_	_	ns		
		Setup time	400 kHz mode	600	_	_			
SP93*	T <sub>HD:STO</sub>	Stop condition	100 kHz mode	4700	_	_	ns		
		Hold time	400 kHz mode	1300	_	_			
* These para	* These parameters are characterized but not tested.								

Figure 41-19. I<sup>2</sup>C Bus Start/Stop Bits Timing



Note: Refer to the "Load Conditions" figure for load conditions.

## 41.4.18 I<sup>2</sup>C Bus Data Requirements

Table 41-24.

Standard Operating Conditions (unless otherwise stated)									
Param. No.	Sym.	Characteristic		Min.	Max.	Units	Conditions		
SP100*	T <sub>HIGH</sub>	Clock high time	100 kHz mode	4000	_	ns	Device must operate at a minimum of 1.5 MHz		
			400 kHz mode	600	<u> </u>	ns	Device must operate at a minimum of 10 MHz		
SP101*	T <sub>LOW</sub>	Clock low time	100 kHz mode	4700	<del>_</del>	ns	Device must operate at a minimum of 1.5 MHz		
			400 kHz mode	1300	<del>_</del>	ns	Device must operate at a minimum of 10 MHz		
SP102*	T <sub>R</sub>	SDA and SCL rise time	100 kHz mode	_	1000	ns			
			400 kHz mode	20	300	ns	C <sub>B</sub> is specified to be from 10-400 pF		
SP103*	T <sub>F</sub>	SDA and SCL fall time	100 kHz mode	_	250	ns			
			400 kHz mode	20 × (V <sub>DD</sub> / 5.5V)	250	ns	C <sub>B</sub> is specified to be from 10-400 pF		
SP106*	T <sub>HD:DAT</sub>	Data input hold time	100 kHz mode	0	_	ns			
			400 kHz mode	0	<del>_</del>	ns			


continued Standard Operating Conditions (unless otherwise stated)								
Param. No.	Sym.	Characteristic		Min.	Max.	Units	Conditions	
SP107*	T <sub>SU:DAT</sub>	Data input setup time	100 kHz mode	250	_	ns	(Note 2)	
			400 kHz mode	100	_	ns		
SP109*	T <sub>AA</sub>	Output valid from clock	100 kHz mode	_	3450	ns	(Note 1)	
			400 kHz mode	_	900	ns		
SP110*	T <sub>BUF</sub>	Bus free time	100 kHz mode	4700	_	ns	Time the bus must be free before a	
			400 kHz mode	1300	_	ns	new transmission can start	
SP111	Св	Bus capacitive loading	100 kHz mode	_	400	pF		
			400 kHz mode	_	400	pF		

<sup>\*</sup> These parameters are characterized but not tested.

#### Notes:

- 1. As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of Start or Stop conditions.
- 2. A Fast mode (400 kHz) I<sup>2</sup>C bus device can be used in a Standard mode (100 kHz) I<sup>2</sup>C bus system, but the requirement T<sub>SU:DAT</sub> ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line TR max. + T<sub>SU:DAT</sub> = 1000 + 250 = 1250 ns (according to the Standard mode I<sup>2</sup>C bus specification), before the SCL line is released.
- 3. Using internal I<sup>2</sup>C pull-ups. For greater bus capacitance use external pull-ups.

Figure 41-20. I<sup>2</sup>C Bus Data Timing



Note: Refer to the "Load Conditions" figure for load conditions.

# 41.4.19 Configurable Logic Cell (CLC) Characteristics Table 41-25.


Standard Operating Conditions (unless otherwise stated)										
Operating Temperature: -40°C≤T <sub>A</sub> ≤+125°C										
Param. No.	Sym.	Characteristic		Min.	Тур. †	Max.	Units	Conditions		
CLC01*	T <sub>CLCIN</sub>	CLC input time		_	7	IO5	ns	(Note 1)		
CLC02*	T <sub>CLC</sub>	CLC module input to output		_	24	_	ns	V <sub>DD</sub> = 1.8V		
		propagation time		_	12			V <sub>DD</sub> > 3.6V		
CLC03*	T <sub>CLCOUT</sub>	CLC output time	Rise Time	_	106	_	_	(Note 1)		
			Fall Time	_	IO8	_	_	(Note 1)		
CLC04*	F <sub>CLCMAX</sub>	CLC maximum switching frequency		_	_	OS20	_			

<sup>\*</sup> These parameters are characterized but not tested.

#### Note:

1. See the "I/O and CLKOUT Timing Specifications" section for IO5, IO6 and IO8 rise and fall times.

Figure 41-21. CLC Propagation Timing



<sup>†</sup> Data in "Typ" column is at 3.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

Graphs and tables are not available at this time.

## 43. Packaging Information

Package Marking Information

Legend: XX...X Customer-specific information or Microchip part number

Y Year code (last digit of calendar year)
YY Year code (last 2 digits of calendar year)
WW Week code (week of January 1 is week '01')

NNN Alphanumeric traceability code


e3 Pb-free JEDEC® designator for Matte Tin (Sn)

Note: In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available


characters for customer-specific information.

8-Lead Plastic Dual In-Line - 300 mil Body [PDIP]


8-Lead PDIP (300 mil)



Example



8-Lead SOIC (3.90 mm)




Example




# PIC16F18015/25/44/45


## **Packaging Information**


14-Lead TSSOP (4.4 mm)






14-Lead SOIC (3.90 mm)






14-Lead Plastic Dual In-Line – 300 mil Body [PDIP]


14-Lead PDIP (300 mil)





Example



Rev. 30-009020A 09/21/2017









20-Lead PDIP (300 mil)


Example






20-Lead SSOP (5.30 mm)











20-Lead QFN (4x4x1 mm)








## 43.1 Package Details

The following sections give the technical details of the packages.

## 8-Lead Plastic Dual In-Line (P) - 300 mil Body [PDIP]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging





Microchip Technology Drawing No. C04-018-P Rev E Sheet 1 of 2

## 8-Lead Plastic Dual In-Line (P) - 300 mil Body [PDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging







Units		INCHES		
Dimension Limits		MIN	NOM	MAX
Number of Pins	N		8	
Pitch	е		.100 BSC	
Top to Seating Plane	Α	1	-	.210
Molded Package Thickness	A2	.115	.130	.195
Base to Seating Plane	A1	.015	ı	-
Shoulder to Shoulder Width	Е	.290	.310	.325
Molded Package Width	E1	.240	.250	.280
Overall Length	D	.348	.365	.400
Tip to Seating Plane	L	.115	.130	.150
Lead Thickness	С	.008	.010	.015
Upper Lead Width	b1	.040	.060	.070
Lower Lead Width	b	.014	.018	.022
Overall Row Spacing §	eВ	-	-	.430


#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- 5. Lead design above seating plane may vary, based on assembly vendor.

Microchip Technology Drawing No. C04-018-P Rev E Sheet 2 of 2

## 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm (.150 ln.) Body [SOIC]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing No. C04-057-SN Rev G Sheet 1 of 2

## 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm (.150 ln.) Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS			
Dimension	Limits	MIN	NOM	MAX	
Number of Pins	N		8		
Pitch	е		1.27 BSC		
Overall Height	Α	-	1	1.75	
Molded Package Thickness	A2	1.25	1	-	
Standoff §	A1	0.10	1	0.25	
Overall Width	Е		6.00 BSC		
Molded Package Width	E1	3.90 BSC			
Overall Length	D	4.90 BSC			
Chamfer (Optional)	h	0.25 – 0.50			
Foot Length	L	0.40	ı	1.27	
Footprint	L1		1.04 REF		
Lead Thickness	С	0.17	-	0.25	
Lead Width	b	0.31	1	0.51	
Lead Bend Radius	R	0.07 – –			
Lead Bend Radius	R1	0.07 – –			
Foot Angle	θ	0°	_	8°	
Mold Draft Angle	θ1	5°	_	15°	
Lead Angle	θ2	0°	_	8°	


#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.15mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
  - REF: Reference Dimension, usually without tolerance, for information purposes only.
- 5. Datums A & B to be determined at Datum H.

Microchip Technology Drawing No. C04-057-SN Rev G Sheet 2 of 2  $\,$ 

## 8-Lead Plastic Small Outline (SN) - Narrow, 3.90 mm (.150 ln.) Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



#### RECOMMENDED LAND PATTERN

	Units	MILLIMETERS			
Dimension	Dimension Limits		NOM	MAX	
Contact Pitch	Е	1.27 BSC			
Contact Pad Spacing	С	5.40			
Contact Pad Width (X8)	X1			0.60	
Contact Pad Length (X8)	Y1			1.55	

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-2057-SN Rev G

## 14-Lead Plastic Dual In-Line (P) - 300 mil Body [PDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		INCHES		
	Dimension Limits		NOM	MAX	
Number of Pins	N		14		
Pitch	е		.100 BSC		
Top to Seating Plane	A	-	_	.210	
Molded Package Thickness	A2	.115	.130	.195	
Base to Seating Plane	A1	.015	_	-	
Shoulder to Shoulder Width	E	.290	.310	.325	
Molded Package Width	E1	.240	.250	.280	
Overall Length	D	.735	.750	.775	
Tip to Seating Plane	L	.115	.130	.150	
Lead Thickness	С	.008	.010	.015	
Upper Lead Width	b1	.045	.060	.070	
Lower Lead Width	b	.014	.018	.022	
Overall Row Spacing §	eB	-	_	.430	

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located with the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-005B


## 14-Lead Plastic Small Outline (SL) - Narrow, 3.90 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



## 14-Lead Plastic Small Outline (SL) - Narrow, 3.90 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	MILLIMETERS			
Dimension	Limits	MIN	NOM	MAX
Number of Pins	N		14	
Pitch	е		1.27 BSC	
Overall Height	Α	1	-	1.75
Molded Package Thickness	A2	1.25	-	-
Standoff §	A1	0.10	-	0.25
Overall Width	Е		6.00 BSC	
Molded Package Width	E1		3.90 BSC	
Overall Length	D		8.65 BSC	
Chamfer (Optional)	h	0.25	-	0.50
Foot Length	L	0.40	-	1.27
Footprint	L1		1.04 REF	
Lead Angle	Θ	0°	-	-
Foot Angle	$\varphi$	0°	-	8°
Lead Thickness	С	0.10 - 0.25		
Lead Width	b	0.31 - 0.51		
Mold Draft Angle Top	α	5° - 15°		
Mold Draft Angle Bottom	β	5°	-	15°


#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic
- Dimension D does not include mold flash, protrusions or gate burrs, which shall not exceed 0.15 mm per end. Dimension E1 does not include interlead flash or protrusion, which shall not exceed 0.25 mm per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
  - REF: Reference Dimension, usually without tolerance, for information purposes only.
- 5. Datums A & B to be determined at Datum H.

Microchip Technology Drawing No. C04-065-SL Rev D Sheet 2 of 2

## 14-Lead Plastic Small Outline (SL) - Narrow, 3.90 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



### RECOMMENDED LAND PATTERN

Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е		1.27 BSC	
Contact Pad Spacing	С		5.40	
Contact Pad Width (X14)	Х			0.60
Contact Pad Length (X14)	Υ			1.55

#### Notes:


1. Dimensioning and tolerancing per ASME Y14.5M

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing No. C04-2065-SL Rev D

## 14-Lead Thin Shrink Small Outline Package [ST] - 4.4 mm Body [TSSOP]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-087 Rev E Sheet 1 of 2

## 14-Lead Thin Shrink Small Outline Package [ST] - 4.4 mm Body [TSSOP]

For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS		
Dime	ension Limits	MIN	NOM	MAX
Number of Terminals	N		14	
Pitch	е		0.65 BSC	
Overall Height	А	-	_	1.20
Standoff	A1	0.05	_	0.15
Molded Package Thickness	A2	0.80	1.00	1.05
Overall Length	D	4.90	5.00	5.10
Overall Width	E		6.40 BSC	
Molded Package Width	E1	4.30	4.40	4.50
Terminal Width	b	0.19	_	0.30
Terminal Thickness	С	0.09	-	0.20
Terminal Length	L	0.45	0.60	0.75
Footprint	L1		1.00 REF	
Lead Bend Radius	R1	0.09	_	_
Lead Bend Radius	R2	0.09	_	_
Foot Angle	θ1	0°	_	8°
Mold Draft Angle	θ2	-	12° REF	_
Mold Draft Angle	θ3	_	12° REF	_

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Dimensioning and tolerancing per ASME Y14.5M

  BSC: Basic Dimension. Theoretically exact value shown without tolerances.
  - REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-087 Rev E Sheet 2 of 2

## 14-Lead Thin Shrink Small Outline Package [ST] - 4.4 mm Body [TSSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



### RECOMMENDED LAND PATTERN

	MILLIMETERS			
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е	0.65 BSC		
Contact Pad Spacing	С		5.90	
Contact Pad Width (Xnn)	Χ			0.45
Contact Pad Length (Xnn)	Υ			1.45
Contact Pad to Contact Pad (Xnn)	G	0.20		


#### Notes:

Dimensioning and tolerancing per ASME Y14.5M
 BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-2087 Rev E

# 16-Lead Plastic Quad Flat, No Lead Package (7N) - 4x4x1.0 mm Body [VQFN] Wettable Flanks (Stepped), 0.40 mm Terminal Length


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-403C Sheet 1 of 2

# 16-Lead Plastic Quad Flat, No Lead Package (7N) - 4x4x1.0 mm Body [VQFN] Wettable Flanks (Stepped), 0.40 mm Terminal Length

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS		
Dimension	Dimension Limits		NOM	MAX
Number of Terminals	N		16	
Pitch	е		0.65 BSC	
Overall Height	Α	0.80	0.90	1.00
Standoff	A1	0.00	0.02	0.05
Terminal Thickness	A3		0.20 REF	
Step Height	A4	0.05	0.12	0.19
Overall Width	Е		4.00 BSC	
Exposed Pad Width	E2	2.50	2.60	2.70
Overall Length	D		4.00 BSC	
Exposed Pad Length	D2	2.50	2.60	2.70
Terminal Width	b	0.25	0.30	0.35
Terminal Length	Ĺ	0.30	0.40	0.50
Step Length	L1	0.035	0.060	0.085
Terminal-to-Exposed Pad	K	0.30	-	-

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-403C Sheet 2 of 2

# 16-Lead Plastic Quad Flat, No Lead Package (7N) - 4x4x1.0 mm Body [VQFN] Wettable Flanks (Stepped), 0.40 mm Terminal Length

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



#### RECOMMENDED LAND PATTERN

	MILLIMETERS			
Dimension Limits		MIN	NOM	MAX
Contact Pitch	E		0.65 BSC	
Optional Center Pad Width	X2			2.70
Optional Center Pad Length	Y2			2.70
Contact Pad Spacing	C1		4.00	
Contact Pad Spacing	C2		4.00	
Contact Pad Width (X16)	X1			0.30
Contact Pad Length (X16)	Y1			0.80
Contact Pad to Center Pad (X16)	G1	0.20		
Contact Pad to Contact Pad (X12)	G2	0.35		
Thermal Via Diameter	V		0.30	
Thermal Via Pitch	EV		1.00	


#### Notes:

- Dimensioning and tolerancing per ASME Y14.5M
   BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- 2. For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Drawing C04-2403B

## 20-Lead Plastic Dual In-Line (P) - 300 mil Body [PDIP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		INCHES	
Dimensi	on Limits	MIN	NOM	MAX
Number of Pins	N		20	
Pitch	е		.100 BSC	
Top to Seating Plane	Α	-	_	.210
Molded Package Thickness	A2	.115	.130	.195
Base to Seating Plane	A1	.015	_	_
Shoulder to Shoulder Width	E	.300	.310	.325
Molded Package Width	E1	.240	.250	.280
Overall Length	D	.980	1.030	1.060
Tip to Seating Plane	L	.115	.130	.150
Lead Thickness	С	.008	.010	.015
Upper Lead Width	b1	.045	.060	.070
Lower Lead Width	b	.014	.018	.022
Overall Row Spacing §	eB	_	_	.430

#### Notes:


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. § Significant Characteristic.
- 3. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" per side.
- 4. Dimensioning and tolerancing per ASME Y14.5M.

BSC: Basic Dimension. Theoretically exact value shown without tolerances.

Microchip Technology Drawing C04-019B

## 20-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Erawing C04-094 Rev E Sheet 1 of 2

## 20-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units	MILLIMETERS		
	Dimension Limits	MIN	NOM	MAX
Number of Terminals	N		20	
Pitch	е		1.27 BSC	
Overall Height	А	-	-	2.65
Standoff §	A1	0.10	-	0.30
Molded Package Thickness	A2	2.05	-	-
Overall Length	D		12.80 BSC	
Overall Width	Е		10.30 BSC	
Molded Package Width	E1		7.50 BSC	
Terminal Width	b	0.31	-	0.51
Terminal Thickness	С	0.25	-	0.75
Corner Chamfer	h	0.25	-	0.75
Terminal Length	L	0.40	0.65	1.27
Footprint	L1		1.40 REF	
Lead Bend Radius	R1	0.07	-	-
Lead Bend Radius	R2	0.07	-	-
Foot Angle	θ	0°	-	8°
Lead Angle	θ1	0°	-	-
Mold Draft Angle	θ2	5°	-	15°
Mold Draft Angle	θ3	5°	-	15°

### Notes:


- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Dimensioning and tolerancing per ASME Y14.5M
  - BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- REF: Reference Dimension, usually without tolerance, for information purposes only.

  3. Dimension D does not include mold flash, protrusions or gate burrs, which shall
- not exceed 0.15 mm per end. Dimension E1 does not include interlead flash or protrusion, which shall not exceed 0.25 mm per side.
- 4. § Significant Characteristic

Microchip Technology Erawing C04-094 Rev E  $\,$  Sheet 2 of 2  $\,$ 

## 20-Lead Plastic Small Outline (SO) - Wide, 7.50 mm Body [SOIC]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



RECOMMENDED LAND PATTERN

	MILLIMETERS			
Dimension Limits		MIN	NOM	MAX
Contact Pitch E		1.27 BSC		
Contact Pad Spacing	С		9.40	
Contact Pad Width (X20)	Х			0.60
Contact Pad Length (X20)				1.95
Contact Pad to Contact Pad	G	0.67		
Contact Pad to Contact Pad	G1	7.45		


#### Notes


- Dimensioning and tolerancing per ASME Y14.5M
   BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- 2. For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Erawing C04-2094 Rev E

## 20-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging






Microchip Technology Drawing C04-072 Rev C Sheet 1 of 2

### 20-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Number of Pins	N	20		
Pitch	е		0.65 BSC	
Overall Height	Α	A 2.00		2.00
Molded Package Thickness	A2	1.65	1.75	1.85
Standoff	A1	0.05	-	-
Overall Width	Е	7.40	7.80	8.20
Molded Package Width	E1	5.00	5.30	5.60
Overall Length	D	6.90	7.20	7.50
Foot Length L		0.55	0.75	0.95
Footprint L1		1.25 REF		
Lead Thickness	С	0.09	-	0.25
Foot Angle 9		0°	4°	8°
Lead Width b		0.22	-	0.38

#### Notes:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed 0.20mm per side.
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-072 Rev C Sheet 2 of 2

## 20-Lead Plastic Shrink Small Outline (SS) - 5.30 mm Body [SSOP]

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



#### RECOMMENDED LAND PATTERN

Units		MILLIMETERS		
Dimension Limits		MIN	NOM	MAX
Contact Pitch	Е	0.65 BSC		·
Contact Pad Spacing	С		7.00	
Contact Pad Width (X20)	X1			0.45
Contact Pad Length (X20)	Y1			1.85
Contact Pad to Center Pad (X18)	G1	0.20		


#### Notes:

- Dimensioning and tolerancing per ASME Y14.5M
   BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- 2. For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Drawing C04-2072 Rev C

# 20-Lead Plastic Quad Flat, No Lead Package (ML) - 4x4 mm Body [QFN] Also called VQFN


**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Microchip Technology Drawing C04-126-ML Rev D Sheet 1 of 2

# 20-Lead Plastic Quad Flat, No Lead Package (ML) - 4x4 mm Body [QFN] Also called VQFN

For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



Units		MILLIMETERS		
Dimension	Dimension Limits		NOM	MAX
Number of Terminals	N		20	
Pitch	е		0.50 BSC	
Overall Height	Α	0.80 0.90 1.00		
Standoff	A1	0.00 0.02 0.05		0.05
Terminal Thickness	A3	0.20 REF		
Overall Length	D	4.00 BSC		
Exposed Pad Length	D2	2.60 2.70 2.80		2.80
Overall Width	Е	4.00 BSC		
Exposed Pad Width	E2	2.60 2.70 2.80		2.80
Terminal Width	b	0.18	0.25	0.30
Terminal Length	L	0.30	0.40	0.50
Terminal-to-Exposed-Pad K		0.20	-	-

#### Notes:

Note:

- 1. Pin 1 visual index feature may vary, but must be located within the hatched area.
- 2. Package is saw singulated
- 3. Dimensioning and tolerancing per ASME Y14.5M


BSC: Basic Dimension. Theoretically exact value shown without tolerances.

REF: Reference Dimension, usually without tolerance, for information purposes only.

Microchip Technology Drawing C04-126-ML Rev D Sheet 2 of 2

# 20-Lead Plastic Quad Flat, No Lead Package (ML) - 4x4 mm Body [QFN] Also called VQFN

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



### RECOMMENDED LAND PATTERN

Units		MILLIMETERS		
Dimension	Limits	MIN	NOM	MAX
Contact Pitch	E	0.50 BSC		
Optional Center Pad Width	X2			2.80
Optional Center Pad Length	Y2			2.80
Contact Pad Spacing	C1		4.00	
Contact Pad Spacing	C2		4.00	
Contact Pad Width (X20)	X1			0.30
Contact Pad Length (X20)	Y1			0.80
Contact Pad to Center Pad (X16)	G1	0.20		
Thermal Via Diameter	V		0.30	
Thermal Via Pitch	EV		1.00	

### Notes:

- Dimensioning and tolerancing per ASME Y14.5M
   BSC: Basic Dimension. Theoretically exact value shown without tolerances.
- 2. For best soldering results, thermal vias, if used, should be filled or tented to avoid solder loss during reflow process

Microchip Technology Drawing C04-2126-ML Rev D

**Appendix A: Revision History** 

# 44. Appendix A: Revision History

Doc Rev.	Date	Comments
В	4/2022	Preliminary document release
A	8/2021	Initial document release

## The Microchip Website

Microchip provides online support via our website at www.microchip.com/. This website is used to make files and information easily available to customers. Some of the content available includes:

- Product Support Data sheets and errata, application notes and sample programs, design resources, user's
  quides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQs), technical support requests, online discussion groups, Microchip design partner program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

## **Product Change Notification Service**

Microchip's product change notification service helps keep customers current on Microchip products. Subscribers will receive email notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, go to www.microchip.com/pcn and follow the registration instructions.

## **Customer Support**

Users of Microchip products can receive assistance through several channels:


- · Distributor or Representative
- · Local Sales Office
- Embedded Solutions Engineer (ESE)
- · Technical Support

Customers should contact their distributor, representative or ESE for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in this document.

Technical support is available through the website at: www.microchip.com/support

## **Product Identification System**

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.



Device:	PIC16F18015, PIC16F18025, PIC16F18044, PIC16F18045		
Tape & Reel Option:	Blank	= Tube	
	Т	= Tape & Reel	
Temperature Range:	I	= -40°C to +85°C (Industrial)	
	E	= -40°C to +125°C (Extended)	
Package:	P	= 8-lead PDIP	
	SN	= 8-lead SOIC	
	P	= 14-lead PDIP	
	SL	= 14-lead SOIC	
	ST	= 14-lead TSSOP	
	7N	= 16-lead VQFN	
	P	= 20-lead PDIP	
	SO	= 20-lead SOIC	
	SS	= 20-lead SSOP	
	ML	= 20-lead QFN	

#### Examples:

- PIC16F18015 T-E/P: Tape and Reel, Extended temperature, 8-lead PDIP
- PIC16F18045 T-I/P: Tape and Reel, Industrial temperature, 20-lead PDIP

#### Notes:

- Tape and Reel identifier only appears in the catalog part number description. This identifier is used for ordering purposes and is not printed on the device package. Check with your Microchip Sales Office for package availability with the Tape and Reel option.
- 2. Small form-factor packaging options may be available. Please check www.microchip.com/packaging for small-form factor package availability, or contact your local Sales Office.

# **Microchip Devices Code Protection Feature**

Note the following details of the code protection feature on Microchip products:

- Microchip products meet the specifications contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is secure when used in the intended manner, within operating specifications, and under normal conditions.
- Microchip values and aggressively protects its intellectual property rights. Attempts to breach the code
  protection features of Microchip product is strictly prohibited and may violate the Digital Millennium Copyright
  Act.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of its code. Code
  protection does not mean that we are guaranteeing the product is "unbreakable". Code protection is constantly
  evolving. Microchip is committed to continuously improving the code protection features of our products.

## **Legal Notice**

This publication and the information herein may be used only with Microchip products, including to design, test, and integrate Microchip products with your application. Use of this information in any other manner violates these terms. Information regarding device applications is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. Contact your local Microchip sales office for additional support or, obtain additional support at www.microchip.com/en-us/support/design-help/client-support-services.

THIS INFORMATION IS PROVIDED BY MICROCHIP "AS IS". MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION INCLUDING BUT NOT LIMITED TO ANY IMPLIED WARRANTIES OF NON-INFRINGEMENT, MERCHANTABILITY, AND FITNESS FOR A PARTICULAR PURPOSE, OR WARRANTIES RELATED TO ITS CONDITION, QUALITY, OR PERFORMANCE.

IN NO EVENT WILL MICROCHIP BE LIABLE FOR ANY INDIRECT, SPECIAL, PUNITIVE, INCIDENTAL, OR CONSEQUENTIAL LOSS, DAMAGE, COST, OR EXPENSE OF ANY KIND WHATSOEVER RELATED TO THE INFORMATION OR ITS USE, HOWEVER CAUSED, EVEN IF MICROCHIP HAS BEEN ADVISED OF THE POSSIBILITY OR THE DAMAGES ARE FORESEEABLE. TO THE FULLEST EXTENT ALLOWED BY LAW, MICROCHIP'S TOTAL LIABILITY ON ALL CLAIMS IN ANY WAY RELATED TO THE INFORMATION OR ITS USE WILL NOT EXCEED THE AMOUNT OF FEES, IF ANY, THAT YOU HAVE PAID DIRECTLY TO MICROCHIP FOR THE INFORMATION.

Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights unless otherwise stated.

### **Trademarks**

The Microchip name and logo, the Microchip logo, Adaptec, AnyRate, AVR, AVR logo, AVR Freaks, BesTime, BitCloud, CryptoMemory, CryptoRF, dsPIC, flexPWR, HELDO, IGLOO, JukeBlox, KeeLoq, Kleer, LANCheck, LinkMD, maXStylus, maXTouch, MediaLB, megaAVR, Microsemi, Microsemi logo, MOST, MOST logo, MPLAB, OptoLyzer, PIC, picoPower, PICSTART, PIC32 logo, PolarFire, Prochip Designer, QTouch, SAM-BA, SenGenuity, SpyNIC, SST, SST Logo, SuperFlash, Symmetricom, SyncServer, Tachyon, TimeSource, tinyAVR, UNI/O, Vectron, and XMEGA are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

AgileSwitch, APT, ClockWorks, The Embedded Control Solutions Company, EtherSynch, Flashtec, Hyper Speed Control, HyperLight Load, IntelliMOS, Libero, motorBench, mTouch, Powermite 3, Precision Edge, ProASIC, ProASIC Plus, ProASIC Plus logo, Quiet- Wire, SmartFusion, SyncWorld, Temux, TimeCesium, TimeHub, TimePictra, TimeProvider, TrueTime, WinPath, and ZL are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Adjacent Key Suppression, AKS, Analog-for-the-Digital Age, Any Capacitor, Anyln, AnyOut, Augmented Switching, BlueSky, BodyCom, CodeGuard, CryptoAuthentication, CryptoAutomotive, CryptoCompanion, CryptoController, dsPICDEM, dsPICDEM.net, Dynamic Average Matching, DAM, ECAN, Espresso T1S, EtherGREEN, GridTime, IdealBridge, In-Circuit Serial Programming, ICSP, INICnet, Intelligent Paralleling, Inter-Chip Connectivity, JitterBlocker, Knob-on-Display, maxCrypto, maxView, memBrain, Mindi, MiWi, MPASM, MPF, MPLAB Certified logo, MPLIB, MPLINK, MultiTRAK, NetDetach, NVM Express, NVMe, Omniscient Code Generation, PICDEM, PICDEM.net, PICkit, PICtail, PowerSmart, PureSilicon, QMatrix, REAL ICE, Ripple Blocker, RTAX, RTG4, SAM-ICE, Serial Quad I/O, simpleMAP, SimpliPHY, SmartBuffer, SmartHLS, SMART-I.S., storClad, SQI, SuperSwitcher, SuperSwitcher II, Switchtec, SynchroPHY, Total Endurance, TSHARC, USBCheck, VariSense, VectorBlox, VeriPHY, ViewSpan, WiperLock, XpressConnect, and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

SQTP is a service mark of Microchip Technology Incorporated in the U.S.A.

The Adaptec logo, Frequency on Demand, Silicon Storage Technology, Symmcom, and Trusted Time are registered trademarks of Microchip Technology Inc. in other countries.

GestIC is a registered trademark of Microchip Technology Germany II GmbH & Co. KG, a subsidiary of Microchip Technology Inc., in other countries.

All other trademarks mentioned herein are property of their respective companies.

© 2021-2022, Microchip Technology Incorporated and its subsidiaries. All Rights Reserved.

ISBN: 978-1-6683-0201-9

# **Quality Management System**

For information regarding Microchip's Quality Management Systems, please visit www.microchip.com/quality.



# **Worldwide Sales and Service**

AMERICAS	ASIA/PACIFIC	ASIA/PACIFIC	EUROPE
Corporate Office	Australia - Sydney	India - Bangalore	Austria - Wels
2355 West Chandler Blvd.	Tel: 61-2-9868-6733	Tel: 91-80-3090-4444	Tel: 43-7242-2244-39
Chandler, AZ 85224-6199	China - Beijing	India - New Delhi	Fax: 43-7242-2244-393
Tel: 480-792-7200	Tel: 86-10-8569-7000	Tel: 91-11-4160-8631	Denmark - Copenhagen
Fax: 480-792-7277	China - Chengdu	India - Pune	Tel: 45-4485-5910
Technical Support:	Tel: 86-28-8665-5511	Tel: 91-20-4121-0141	Fax: 45-4485-2829
www.microchip.com/support	China - Chongging	Japan - Osaka	Finland - Espoo
Web Address:	Tel: 86-23-8980-9588	Tel: 81-6-6152-7160	Tel: 358-9-4520-820
www.microchip.com	China - Dongguan	Japan - Tokyo	France - Paris
Atlanta	Tel: 86-769-8702-9880	Tel: 81-3-6880- 3770	Tel: 33-1-69-53-63-20
Duluth, GA	China - Guangzhou	Korea - Daegu	Fax: 33-1-69-30-90-79
Tel: 678-957-9614	Tel: 86-20-8755-8029	Tel: 82-53-744-4301	Germany - Garching
Fax: 678-957-1455	China - Hangzhou	Korea - Seoul	Tel: 49-8931-9700
Austin, TX	Tel: 86-571-8792-8115	Tel: 82-2-554-7200	Germany - Haan
Tel: 512-257-3370	China - Hong Kong SAR	Malaysia - Kuala Lumpur	Tel: 49-2129-3766400
Boston	Tel: 852-2943-5100	Tel: 60-3-7651-7906	Germany - Heilbronn
Westborough, MA	China - Nanjing	Malaysia - Penang	Tel: 49-7131-72400
Tel: 774-760-0087	Tel: 86-25-8473-2460	Tel: 60-4-227-8870	Germany - Karlsruhe
Fax: 774-760-0088	China - Qingdao	Philippines - Manila	Tel: 49-721-625370
Chicago	Tel: 86-532-8502-7355	Tel: 63-2-634-9065	Germany - Munich
Itasca, IL	China - Shanghai	Singapore	Tel: 49-89-627-144-0
Tel: 630-285-0071	Tel: 86-21-3326-8000	Tel: 65-6334-8870	Fax: 49-89-627-144-44
Fax: 630-285-0075	China - Shenyang	Taiwan - Hsin Chu	Germany - Rosenheim
Dallas	Tel: 86-24-2334-2829	Tel: 886-3-577-8366	Tel: 49-8031-354-560
Addison, TX	China - Shenzhen	Taiwan - Kaohsiung	Israel - Ra'anana
Tel: 972-818-7423	Tel: 86-755-8864-2200	Tel: 886-7-213-7830	Tel: 972-9-744-7705
Fax: 972-818-2924	China - Suzhou	Taiwan - Taipei	Italy - Milan
Detroit	Tel: 86-186-6233-1526	Tel: 886-2-2508-8600	Tel: 39-0331-742611
Novi, MI	China - Wuhan	Thailand - Bangkok	Fax: 39-0331-466781
Tel: 248-848-4000	Tel: 86-27-5980-5300	Tel: 66-2-694-1351	Italy - Padova
Houston, TX	China - Xian	Vietnam - Ho Chi Minh	Tel: 39-049-7625286
Tel: 281-894-5983	Tel: 86-29-8833-7252	Tel: 84-28-5448-2100	Netherlands - Drunen
Indianapolis	China - Xiamen		Tel: 31-416-690399
Noblesville, IN	Tel: 86-592-2388138		Fax: 31-416-690340
Tel: 317-773-8323	China - Zhuhai		Norway - Trondheim
Fax: 317-773-5453	Tel: 86-756-3210040		Tel: 47-72884388
Tel: 317-536-2380			Poland - Warsaw
Los Angeles			Tel: 48-22-3325737
Mission Viejo, CA			Romania - Bucharest
Tel: 949-462-9523			Tel: 40-21-407-87-50
Fax: 949-462-9608			Spain - Madrid
Tel: 951-273-7800			Tel: 34-91-708-08-90
Raleigh, NC			Fax: 34-91-708-08-91
Tel: 919-844-7510			Sweden - Gothenberg
New York, NY			Tel: 46-31-704-60-40
Tel: 631-435-6000			Sweden - Stockholm
San Jose, CA			Tel: 46-8-5090-4654
Tel: 408-735-9110			UK - Wokingham
Tel: 408-436-4270			Tel: 44-118-921-5800
Canada - Toronto			Fax: 44-118-921-5820
Tel: 905-695-1980			
Fax: 905-695-2078			